



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

### Usage guidelines


Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

### About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>




SB  
406  
.L88  
1865

Agnes Tichy  
15 June 1867.

A.T.



THE  
LADIES' COMPANION  
TO  
THE FLOWER-GARDEN.



225



Azalea Amoena .

THE  
LADIES' COMPANION  
TO  
THE FLOWER-GARDEN.

BEING  
AN ALPHABETICAL ARRANGEMENT OF  
ALL THE ORNAMENTAL PLANTS USUALLY GROWN IN  
GARDENS AND SHRUBBERIES ;  
WITH FULL DIRECTIONS FOR THEIR CULTURE.

BY MRS. LOUDON.

*Eighth Edition,*

CONSIDERABLY ENLARGED, AND CORRECTED TO  
THE PRESENT TIME,

BY

CHARLES EDMONDS, F.R.H.S.,  
Gardener to Her Grace the Dowager Duchess of Sutherland,  
Chiswick House.

LONDON:  
BRADBURY AND EVANS, 11, BOUVERIE STREET.

---

1865.

LONDON:  
BRADBURY AND EVANS, PRINTERS, WHITEFRIARS.

May 12, 1870

## PREFACE.

---

It is a common subject of complaint among amateur florists, that the directions for the culture of flowers given in works on Gardening, are scattered through so many different volumes, and mixed with so many other matters, as to be of comparatively little use to the possessors of small gardens. Having felt this inconvenience myself, it occurred to me that a dictionary of the English and botanic names of the most popular flowers, with directions for their culture, would be useful ; and the result is the present volume. The botanic names are accented, to show on which syllable the emphasis is to be laid ; and every syllable must be pronounced, whether accented or not. When the accent is acute, thus : á, it signifies that the consonant following the vowel is to be taken into the syllable ; and when the accent is grave, thus : à, that the vowel finishes the syllable. Thus Anthýllis is pronounced An-thyl-lis, and armàta, ar-ma-ta ; while, as a proof that every syllable is pronounced, Agàve is called A-ga-vè, and Amphième, Am-fic-o-mè.

As this was the only one of my works in which any assistance was given to me by my late deeply lamented husband, it may be interesting to my readers to know, that he wrote the whole of the articles on Borders, Climate, Conservative Walls, Draining, Edgings, Fences, Flower Gardens, Gravel Walks,

Hotbeds, Levelling, Planting, Pleasure Grounds, Reserve Ground, Rock-work, Seats, Shrubbery, Single Trees, Sowing Seeds, Tallies, Tan, Walls, and Water, and part of several other articles ; besides having read over and revised the whole of the first and second editions.

The Appendix to the work was suggested by Lord Murray, of Edinburgh ; to whom I am under very great obligations for the valuable assistance he has rendered me, both by his own letters and by those he has forwarded to me from a lady, a friend of his, and from Mr. James Mac Nab, which have been of great use to me in affording hints as to the subjects most likely to be useful in the Appendix.

Notwithstanding the large sale of the work (which has exceeded twenty-five thousand copies,) it has never been stereotyped ; but every new edition has been carefully revised, and descriptions of new plants and of new discoveries in floriculture have been added, so as to bring the whole down completely to the present day.

J. W. LOUDON.

BAYSWATER,

*January 11th, 1858.*



## PREFACE TO EIGHTH EDITION.

---

HORTICULTURE like other Arts does not stand still, and perhaps it is more progressive than most ; for not a year passes in which improvements on existing plants are not effected at home, and fresh introductions made from abroad. Six years have elapsed since the last edition of this work appeared ; and the impression, though a large one, having been completely exhausted, the publishers finding that a fresh one was urgently demanded, confided its preparation to me. Well executed in the first instance, and carefully brought up to the time as each fresh edition was required, the task has been lighter than would have otherwise been the case. Each article has been carefully revised, and such additions made as seemed necessary as far as the limits of the work would permit ; by confining some subsidiary matters within narrower limits (without however omitting anything of real importance), I have been enabled to do so without adding to the cost of the work, or, I believe, in the least impairing its usefulness. That it is free from errors I cannot affirm—

despite of every care no work is—but I trust that these will be found of so trivial a nature that they will meet with the kind indulgence of the public, in whose hands I now leave it. That it may conduce to the cultivation of all that is beautiful, and all that is good, is the earnest wish of

CHARLES EDMONDS.

CHISWICK HOUSE,  
*December, 1864.*

## The Ladies' Companion

TO

## THE FLOWER GARDEN.

### ABELIA.

**ABELIA.**—*Caprifoliaceæ*.—This genus was discovered in China as long back as 1818, by Dr. Abel, in honour of whom it was named; but it was little known in Europe, though several species were afterwards discovered, till 1844, when Mr. Fortune sent over plants of *Abelia rupestris*, which he found growing among some rocks on the Chamoo Hills. It is a pretty little plant, with fragrant flowers, somewhat resembling those of the sweet-scented Daphne, but not remarkably beautiful. Another species (*A. uniflora*) is an evergreen shrub, with whitish flowers, which appear in July. It was introduced by Messrs. Standish and Noble, in 1851, and seems hardy. There is another species of the genus, which was introduced in 1842, under the name of *Vesàlia floribunda*, from Mexico, which has long rose-coloured flowers, closely resembling those of the honeysuckle, to which, indeed, it is nearly allied, but which are produced singly. The plant itself is a pendulous shrub, and it requires a warm greenhouse. It grows freely, strikes readily from cuttings, and flowers during the greater part of the summer.

### ABUTILON.

**ABUTILON.**—*Leguminosæ*.—The Wild Liquorice (*A. precatorius*) is a pretty climbing stove plant, which requires a strong heat to throw it into flower. The seeds, which are poisonous, are scarlet and black, and are sometimes made into necklaces for children.

**ABUTILON.**—*Malvaceæ*.—There is a very beautiful greenhouse plant called *Abutilon striatum*, or *Sida picta*, that deserves a place in every collection. It is a native of Brazil, and half-shrubby, with vine-like leaves, and bell-shaped flowers of a bright yellow, strongly veined with scarlet, which hang down on long slender stalks. The plant should be grown in a pot, a quarter filled with broken potsberds to insure perfect drainage, in a light sandy loam; and it should be trained to a slight frame; or it may be planted in the open air, and trained against a wall or trellis, as it is nearly hardy, and only requires protection from frost. It is sometimes also grown in a stove, where it flowers abundantly, if allowed plenty of moisture, though the whole plant is much weaker than when grown in a cooler temperature. There are several very beautiful

species of this genus, some of which are generally found in the nurseries, under the name of *Sida*. One of the handsomest kinds is called *Abutilon vitifolium*, or *Sida vitifolia*, from its vine-shaped leaves. It is a noble-looking shrub, growing about six feet high, with a mass of large purplish or lilac flowers. It is a native of Chili, and may be grown in the open ground; with a slight protection; or in a conservatory. The flowers are much darker under glass, and sometimes become nearly white when the plant is grown in the open air. *A. pœoniæ-florea*, which has been only lately introduced from Brazil, has its flowers of a deep rose colour. The best soil for it is a mixture of heath-mould and silver sand. Another new species, called *Abutilon insigne*, has white flowers veined with crimson. All the *Abutilons* are subject to attacks from the red spider, and require frequent syringing to keep them in health.

ACACIA. — *Leguminosæ*. — Most persons understand by the word *Acacia*, tall trees with pea-flowers, which are natives of North America, and quite hardy in the open air of England. These trees, however, are the Locust trees, or false *Acacias*, and belong to the genus *Robinia*. The true *Acacias* (which were placed in the genus *Mimosa* by Linnæus) are what are called *Wattle trees* in Australia, with flowers like balls or spikes of down; and, as they require protection from the frost in England, they are generally treated, in this country, as greenhouse shrubs. Above three hundred species have been introduced, but only about thirty are in cultivation in British nurseries, and nearly all these have been figured in the botanical periodicals. By far the greater part of the *Acacias* grown in England are natives of New Holland, and most of these are nearly

hardy; but some are from the East Indies and Arabia, and most of them require a stove. Nearly all the kinds are evergreen; and the Australian species are very valuable in greenhouses, because they are in flower during winter. In the open ground they flower in March, April, May, and June. The following kinds are the most common of the Australian *Acacias* in British nurseries: — *A. armata*, a most useful plant for windows and balconies, from its hardiness, its compact, simple, dark-green leaves, or phyllodia, and the great abundance of its yellow ball-like flowers; *A. alata*, a curious species, with winged stems; *A. decipiens*, with small angular leaves; *A. diffusa*, a dwarf plant with small flowers; *A. floribunda*, flowers yellow, numerous, fragrant; *A. hybrida*, very fragrant; *A. longifolia*, with very long leaves, and the flowers not in balls, but in long close spikes; *A. pubescens*, a very elegant species with drooping branches, bipinnate leaves, and the ball-like flowers disposed in racemes; *A. pulchella major*, flowers bright golden yellow; *A. nigricans*, with blackish-green foliage; *A. verticillata*, with the leaves like spines, and disposed in whorls; *A. lophantha*, with bipinnate leaves, and long spike-like whitish flowers; *A. dealbata*, the *A. affinis* of some botanists, remarkable for the delicacy of its foliage, and the whitish bloom which covers its trunk and branches; *A. spectabilis*, remarkable for the immense number of its yellow balls of flowers, which is nearly allied to *A. dealbata*, but requires rather more heat; *A. virgata*, about three feet high, branches slender, leaves entire, flowers in February and March, and desirable on this account; and *A. melanoxylon*, the Black Wood, or Black Wattle of the Australians,

the dilated petioles or phyllodia of which look like leaves, with the real leaves, which are bipinnate, attached to their extremities. Of the other kinds of Acacia, the hardest are *A. acanthocarpa*, a native of Mexico, with pale pink flowers, and spiny pods; and *A. Julibrissin*, the Silk tree, a native of Persia, and one of the most beautiful small trees that can be imagined; the flowers are like long silk tassels, and they vary from a pale pink or rose-colour, to a delicate lilac; but they seldom attain perfection in the open air in England, for want of heat in our summers, though they are extremely beautiful in Italy. Of the stove species, the handsomest are *A. speciosa*, *A. grandiflora*, *A. Houstoni*, and *A. scandens*; and they should all be kept in the coolest and most airy part of the stove. *A. vera*, the Gum Arabic tree, *A. Catechu*, from the unripe pods of which is made the substance called Terra Japonica, and *A. Senegal*, the Gum Senegal tree, are only interesting for their products.

All the kinds of Acacia require to be grown in sandy loam, or in a mixture of sand, peat, and leaf-mould, well drained. They are generally propagated by imported seeds (though some of the species have ripened seed in this country); and the seeds are sometimes two, or even three years in the ground, before they come up. To hasten their vegetation, they may be steeped in very hot water, and left in the water for several days, or in oxalic acid and water, and sometimes even boiled for a minute or two; or a little bit may be cut or scraped off just at the scar on the seed; and when prepared by any of these modes, they will generally come up in about a week or a fortnight. Acacias may also be propagated by cuttings; but, as these are rather difficult to strike,

they should be put into a pot filled with pure white sand, covered closely with a bell-glass, and then plunged into a hotbed. The tenderer species may also be grafted on *A. dealbata*, *A. lophantha*, and *A. melanoxylon*, which appear to be the hardest kinds. These three species will generally spring up again from the root, when killed down to the ground by frost; and whenever this is the case with any plants, it indicates that the plants may be propagated by cuttings of the roots, which is frequently done with these Acacias. All the roots of the Australian species of Acacia smell like Garlic, and this smell is very perceptible on entering a room where any of these plants are kept, if it has been shut up for a few days. For this reason, when Acacias are kept in a greenhouse adjoining the living-rooms of a house, care should be taken to give the house abundance of ventilation; and this is also very conducive to the health of the plants. They all require frequent washing and syringing of the foliage, as they are very liable to be attacked by insects, particularly the mealy bug and scale. If the scales are allowed to harbour on the old wood, the young broods issue from beneath them in vast numbers towards the younger parts of the tree; the bark should therefore be always kept clear by means of a brush with soft soap and warm water.

ACACIA.—See ROBINA and MIMOSA; as plants belonging to these genera are often called Acacia, though they differ widely from the true Acacias both in the structure and appearance of their flowers, and in their habit of growth.

ACANTHUS.—*Acanthaceæ*.—Perennial plants, natives of the warm parts of Europe, two of which, *A. mollis* and *A. spinosus*, deserve a place in every collection, from their

stately appearance, and from the legend of their leaves having given the first idea of the capital of the Corinthian order of architecture. All the kinds of *Acanthus* require a sandy soil, and a good deal of room; and they are all readily increased by division of the root, and by seeds. The situations most suitable for a large plant of *Acanthus* are near a stone seat on a lawn; at the foot of a block of stone introduced among rockwork; or among classical ruins, such as those at Virginia Water, Windsor, &c.

**A'CARUS.**—A genus of small insects or mites. *A'carus telarius*, the red spider, is one of the most troublesome of all insects to gardeners, particularly in the bark stove, as it breeds in the bark. When first hatched, this little creature is scarcely perceptible, as its colour is of a yellowish green, and it spins its web on the under side of the leaves. As it gets older, it becomes of a brownish red. It has eight legs, and belongs to the spider family; but it is provided with a kind of proboscis or rostrum, with which it sucks the juices of the leaves it lives upon, and soon renders them sickly and of a yellow hue, by depriving them of their parenchyma; thus spoiling both fruit and flowers, as neither can be properly nourished by the sap without the assistance of this green colouring matter of the leaves. It is very difficult to destroy this insect, as tobacco-smoke, and the other remedies generally used against it, appear to have very little effect. Sprinkling with cold water will sometimes destroy it; but as the insect is generally produced by keeping the plants too hot, too dry at root, and not allowing them sufficient air, the best remedy appears to be to set all the hothouse plants in the open ground

during the months of July and August, plunging the pots in a bed of dung, decayed leaves, or tan, and well ventilating and cleaning the houses while they are empty.

**ACHILLE'A.**—*Compositæ*.—The plants belonging to this genus are known under their English name of Milfoil. Most of them have no great beauty, but they are of very vigorous growth, and will thrive in any soil or situation, bearing either smoke or cold without any visible change. They are also suitable plants for balconies or boxes, as they are not easily injured either by too much watering, or by being kept too dry. The most ornamental of the vigorous-growing kinds are *Achillea tomentosa*, the woolly Milfoil, with yellow flowers, and *A. tanacetifolia*, with red flowers. Of the more delicate species, *A. Clavenna*, the silvery-leaved Milfoil, with large white flowers, is a very pretty little plant for rockwork. *A. aurea*, which scarcely grows half a foot high, and has rich yellow flowers, which it produces in great profusion, is very suitable for edgings to beds and borders. All the species grow freely in any soil that is tolerably dry; and they are all readily increased by division of the root.

**ACHIMENES.**—*Scrophulariæ*.—The plants belonging to this genus are, generally speaking, highly ornamental perennials, with very showy flowers; natives of South or Central America, and require artificial heat in Europe. They have tuberous roots covered with scales, and funnel-shaped flowers; that is, their flowers have a very narrow tube, and a broad spreading limb. The first species known in British gardens was first called *Cyrtilla pulchella*, and afterwards *Trevirana coccinea*. It is a native of Jamaica, and was introduced in 1778. In 1841, tubers of some other species of the

same genus were sent to England from Guatemala, when it was discovered that the Jamaica species had originally been called *Achimenes* by Dr. Patrick Browne, who first described it; and hence that name was given to the genus. The derivation of the name is unknown, but it is supposed to signify a plant that does not like wintry weather. The first three of the following species were introduced by Mr. Hartweg, from Guatemala, in 1841 and 1842:—*A. rosea*, with flowers resembling those of *A. coccinea*, but longer and of a deep rose colour; *A. longiflora*, a very handsome species, the flowers of which have an exceedingly large rich dark-blue limb, and a very narrow pinkish tube, the back of the limb being also pinkish; and *A. pedunculata*, which has flowers with a larger tube and smaller limb than any of the other species; they are orange and scarlet, marked with rows of crimson spots. *A. grandiflora* was introduced in 1843; in shape the flowers resemble those of *A. longiflora*, but the limb is a rich purplish crimson: this plant is a native of Mexico. *A. multiflora* is a native of Brazil, introduced in 1840, and has flowers resembling in shape those of *A. pedunculata*, but of a most beautiful lilac, with a sort of fringe round the margin of the limb; and *A. hirsuta*, introduced from Guatemala in 1843, has the flowers of a deep rose-colour, with a yellow mouth spotted with crimson, and in shape between those of *A. rosea* and *A. pedunculata*. *A. patens* was first discovered by Mr. Hartweg, in Mexico, in 1838; but unfortunately none of the roots which he sent home arrived in a living state. On his return to Mexico, however, in 1845, he was so fortunate as to discover the plant again; and living plants of it reached England in the spring of

1846. The flowers are extremely ornamental, resembling those of *A. longiflora*, but being of a very dark and rich purple, with a tinge of crimson; and the edges of the petals being somewhat undulated. The roots, which resemble bundles of small scales, Mr. Gordon observes, in the *Journal of the Horticultural Society*, should be separated, "at least all those scales which will part from each other freely, and be, as it were, sown on the surface of the soil in the pots; the pots should be filled with a light fibry heath-soil, and a small portion of well-decayed dung should be mixed with the finer portions of the soil for top covering. The scales and crown-ends of the roots, which sometimes will not separate, should be covered about a quarter of an inch in depth, and then the pots containing them should be placed in a melon or cucumber pit, or any other structure where there is a moderate bottom heat and rather moist atmosphere." The young plants will begin to appear in about ten days, and when two inches high they should be transplanted. All the species require the same treatment. When the stems die down, which they do after flowering, the tubers must be kept quite dry during the winter, or till such time as it is desirable to start them into fresh growth, which may be as early as January, and successionally till the end of May. Previously to their being placed in heat, the tubers should be repotted in light, rich soil, and the pots plunged in a hotbed. When the plants begin to grow they should be removed to a warm greenhouse, till their flower-buds are formed; after which, all the kinds, except *A. coccinea* and *A. pedunculata*, may be placed in a common greenhouse, or in a living-room, to flower. *A. longiflora* is by far the handsomest and the hardiest; and its

thickened roots are more like scaly bulbs than tubers. *A. pedunculata* and *A. hirsuta* have the peculiarity of forming little bulbs in the axils of their leaves, particularly if kept in a moist heat. The varieties which have been obtained from the originally introduced species are exceedingly numerous, and many of them very splendid. When growing, they all require a moist but well-drained soil, with a humid atmosphere of the temperature of between 60° and 75°; and they must be carefully shaded from hot sun.—For the culture of *A. coccinea*, see *TREVIRANA*.

**ACONITUM.**—*Ranunculaceæ*.—Monkshood and Wolfsbane.—Herbaceous perennials, chiefly natives of Europe, but partly of North America and Japan. They are all hardy in British gardens, and they are generally tall-growing handsome plants, producing an abundance of dark-blue, purple, or yellow flowers. They will all grow freely in any common garden soil, and are readily increased by division of the roots, which are generally tuberous, or by seeds. All the species are more or less poisonous, the poison being strongest in the root. Like all plants which grow with tall erect stems, and produce their flowers in terminal spikes, they are only suitable for growing in borders in large gardens, or for clumps on a lawn. The species may be divided into two kinds: those with the helmet like a monk's cowl, which are called Monkshood; and those which have an elongated conical helmet, and are called Wolfsbane. Of this first division the handsomest species are *A. Napellus*, the common Monkshood, with purple flowers; and *A. Anthora*, the Yellow Monkshood. Of the Wolfsbane the handsomest species are *A. barbatum*, with pale-yellow flowers, and *A. australe*, a beautiful

plant with dark purple flowers tipped with green, a native of the Carpathian Mountains; *A. japonicum* has flowers of an intense azure blue, and flowering from September till November, is valuable on this account.

**ACONITE, WINTER.**—See *ERA'NTHIS*.

**ACROCLINUM ROSEUM.**—*Compositæ*.—A native of South-West Australia, forming in this country a half-hardy annual, with bright rose-colour, everlasting flowers, and pale-green stems and leaves.

**A'CYNOS.**—*Labiata*.—A perennial plant somewhat resembling Thyme. *A. vulgâris*, the only ornamental species, is a native of Europe, not above six inches high, and of easy culture in any common soil.

**ADAM'S NEEDLE.**—See *YU'CCA*.

**ADENOCA'RPUS.**—*Leguminosæ*.—A genus of hardy shrubs, with yellow pea-flowers, resembling those of the Broom. These plants were formerly included in *CYTISUS*.

**ADENO'PHORA.**—*Campanulacæ*.—Perennial plants with blue bell-shaped flowers, resembling the Campanulas. They require to be planted in rich but light soil, and are easily killed by much moisture. They are natives of Siberia, and are propagated by division of the root.

**ADE'SMIA Dec.**—*Leguminosæ*.—Herbaceous plants and shrubs with yellow pea-like flowers, growing freely in the open air in any common soil.

**ADHATO'DA.**—*Acnathacæ*.—A Brazilian plant, with striking, showy flowers, some of the petals of which are of a rich dark purple, and others of a pure white. Introduced in 1855.

**ADIA'NTUM.**—*Cryptogamia*.—Maidenhair, beautiful ferns, remarkable for their slender, polished, wiry



stalks, as black as ebony, bearing light and graceful foliage, very useful for introducing into nosegays. *A. pedatum* may be grown in the open ground, in peat soil and in the shade; the *A. Capillus-veneris*, Venus's hair, also hardy, is a native of Britain; *A. tenerum*, and *A. trapeziforme*, are species preferred for cultivating in the stove, but require the shaded side.

ADLUMIA. — *Fumariaceæ*. — A climbing biennial, with pinkish flowers like those of the Fumitory. It is a native of North America, and will grow in any common soil. The seeds should be sown in autumn, and the young plants kept in pots in a greenhouse or frame, for planting out in spring. Thus treated, and trained to a trellis or wire frame, they will begin to flower in June, and will continue producing abundance of flowers during the whole summer.

ADONIS. — *Ranunculaceæ*. — Herbaceous plants with showy flowers, natives of Europe, of easy culture in any common soil. The most ornamental species are *A. vernalis*, the spring flowering Adonis, a perennial with bright-yellow flowers, which is quite hardy, and is easily increased by division of the root; and *A. autumnalis*, the common annual *Fls Adonis*, or Pheasant's Eye, with dark crimson flowers. All the species will grow in any common garden-soil; and the annual kinds should be sown in autumn, as they will stand the winter in the open air—or in February or March, as they are a long time before they come up. The seeds will keep good several years.

ÆCIDIUM. — A kind of Fungus which is sometimes found on the leaves of pear-trees and other plants belonging to the genus *Pyrus*.

ÆONIUM Webb. — *Crassulaceæ*.

— This is a new genus formed out of *Sempervivum*, of which *S. ardreum* is taken for the type. Some of the species are very ornamental. They are all greenhouse plants, which require a warm dry situation in summer, and a cool place with very little water in winter; and they grow best in wide, shallow pots, well drained with potsherds, and filled with a mixture of loam and old mortar, covered with fine sand.

ÆRIDES. — *Orchidaceæ*. — Stove epiphytes, natives of the East Indies, with whitish flowers that have the odour of the Tuberose. They should be grown on moss, and suspended from the rafters of a very damp hothouse.

ÆSOHYNA'NTHUS Jack. : INCARVILLEA Roxb. — *Cyrtandrææ*.

— Stove parasitical shrubs, growing four or five feet high, natives of India, where they are found in moist, shady woods, hanging from tree to tree, and producing large bunches of their showy orange, yellow, purple, scarlet, or vermilion flowers. Most of the species are very ornamental, and more especially so are *A. grandiflorus*, *pulcher*, *javanicus*, *tricolor*, *Boschianus*, *speciosus*, *Lobbianus*, *longiflorus*, and *ramosissimus*. They are very suitable for being grown in suspended baskets, from which they form charming pendent garlands. They should be grown in peat, or in vegetable mould and sand, and should be allowed abundance of heat and moisture.

ÆSCULUS. — *Æsculaceæ*. — Most of the Horse-chestnuts are too large trees to be admitted into a work like the present; but the red-flowered Horse-chestnut (*Æ. rubicunda*) and its varieties are seldom above twelve or fifteen feet high, and they are, therefore, very suitable for a shrubbery. The most beautiful variety

is *Whitley's Scarlet*. These trees should be grown in a sheltered situation, or they will not flower well. For the yellow-flowered Horse-chestnut, see PA'VIA.

AFRICAN LILY.—See AGAPA'NTHUS.

AFRICAN MARIGOLD.—See TAGETES.

AGAPA'NTHUS. — *Hemerocallidaceæ*.—The blue African Lily, *A. umbellatus*, is a noble plant, with a bulbous root, somewhat resembling that of a leek; and it retains its leaves all the winter. There is a variety with striped leaves. *A. albidus* has white flowers, but it does not differ from the common kind in any other respect. *A. maximus* has a very tall stem and narrow leaves, and the flowers, which are of an extremely dark blue, with a white stripe, form rather a small head in proportion to the great length of the stem. Both these last-named plants are, however, probably only varieties of *A. umbellatus*. The following directions are given in the *Botanical Register* for February, 1843, for the cultivation of this genus:—"About the end of February, the plants should be fresh potted, in a mixture of rich loam and well-decomposed leaf mould, or well-rotted dung, and placed in a warm part of the greenhouse, where they will soon begin to grow freely. They will then require to be abundantly supplied with water, and about the end of May should be removed to the open air, if it is intended that they should flower out of doors. The pots should be placed in a sheltered situation, in large pans filled with water, so that one-third of the pots are immersed; or the pots may be placed by the side of a pond, and treated as sub-aquatic, in which situation they will

flower freely during the summer. If they are retained in the greenhouse during the flowering season, they must have plenty of air and water, or they will become weak, and lose that beautiful deep-blue colour which usually distinguishes them. When they have done flowering in autumn, they should be gradually dried, by withholding water; and finally, when the soil in the pots has become tolerably dry, and there is danger of frost, the pots should be removed for the winter, either into a cold pit, or under the stage of the greenhouse; or they may be placed in a cellar: but then they must be kept very dry, and should be removed from such a situation as soon as they show signs of vegetation. These plants will also force freely, if well supplied with moisture and bottom-heat; but in that case the flowers become very pale. They are easily increased by dividing the old plant when in a dormant state. They seldom require shifting when once established, if supplied once or twice during the growing season with a little liquid manure." When properly treated, and kept in a greenhouse or living-room, or under a verandah, this plant will frequently send up a flower-stalk above three feet high, crowned with twenty or thirty heads of flowers, which will come into blossom in succession; and when grown in the open air, it forms a noble ornament to an architectural terrace, or a fine object on a lawn. When the roots have become so large as to require a pot of inconvenient size (for the roots must have plenty of pot-room), it is said that the bulb may be divided, and the strongest of the fibrous roots cut off, without injuring the plant, or preventing it from flowering.

AGATHÆA AMELLOIDES, or A.

**CÆLESTIS.** — *Compósitæ*. — Green-house, or open ground in summer; flowers nearly all the year, centre yellow, ray a beautiful azure blue.

**AGA'VE.** — *Amaryl'idææ*. — Succulent plants from South America, of which one species, the American Aloe, *A. americana*, and a variegated-leaved variety of it, are old inhabitants of British gardens; having been formerly kept in tubs, in the orangery or in some other house during winter, and set out during summer. The large leaves of the Agave render it by no means adapted for a small greenhouse; but as it only requires protection from frost, it may be kept during the winter in a shed where there is very little light, till summer, when it may be set out on a lawn or terrace, giving it very little water while in a state of repose. This mode of treatment may be applied to all succulent plants that are dormant during our winters. The American Aloe requires a rich loamy soil, and is increased by suckers. It was formerly supposed that it produced its candelabra-like blossoms only once in a hundred years; but this is a vulgar error, as it sometimes produces its flowers, in hot countries, in ten years — the period varying to twenty, fifty, or even seventy years, according to the climate and the care bestowed on the plant by the gardener. The flower-stem is frequently forty feet high, and the plant dies as soon as it has done flowering. The Aloe is a native of Mexico, and the other tropical parts of America; but it has been almost naturalised in the south of Europe. In its native country a strong spirit is distilled from its sap; the fibres of its leaves are used for thread, and the feculent matter contained in its stem, for soap; an excellent starch is also made from it. *A.*

*Celsiana* is a very fine species, which has recently flowered at Kew, and also with *M. Cels* at Paris. Its leaves are thick and fleshy, ten inches broad, and upwards of three feet long; its flower-stem, straight, cylindrical, rises to the height of from eight to twenty-three feet; flowers blue, appearing in succession.

**AGRATUM.** — *Compósitæ*. — Mexican annuals, with curious heads of small pale-blue flowers. The seeds should be sown in a warm border, in a light soil, in April, or on a hotbed in February.

**AGROSTEMMA.** — *Caryophyllææ* — The Rose Campion. — This genus, and that of *Lychnis*, have been so strangely mixed up together, that it is difficult to know what plants belong to each. The showy greenhouse plant generally called *Lychnis Bungeana*, and the pretty little annual *L. Læta*, are now removed to *Agrostemma*; while, on the contrary, *A. Cæli-Rosa* and *A. Flbs Jovis* have been taken from *Agrostemma* and given to *Lychnis*. The Corn-cockle, *A. Githago*, is also now *Githago segetum*; but the Rose Campion is still called *Agrostemma coronaria*. All the species of the genus, both annuals and perennials, are quite hardy, and will grow in any common garden-soil.

**AILANTUS.** — *Xanthoxylææ*. — The *A. glandulosus*, native of Japan, although it grows to be a lofty tree, with a massive trunk, is nevertheless worthy of notice here, firstly, because its long pinnated foliage is very elegant, and the tree is ornamental, even for small gardens, whilst young and till it become too large for the space; and secondly, because its leaves supply food for the new species of Silkworm introduced and lately exhibited by Lady Doro-

thy Nevill, and said to be much hardier than the common one, producing a stronger fibre, though not quite so fine. The tree is perfectly hardy, and will grow in any ordinary soil not too wet and heavy; easily propagated by seeds, or by cuttings of the roots.

**AIR PLANTS.**—See **ORCHIDEOUS EPIPHYTES**.

**AKE'BIA.**—A slender evergreen shrub, a native of China, brought to England by Mr. Fortune. It is remarkable for having two distinct kinds of flowers on the same plant, differing in size, shape, and colour.

**ALATERNUS.**—See **RHAMNUS**.

**ALBU'CA.**—*Asphodèleæ*.—Pretty Cape bulbs, with white flowers, resembling the Star of Bethlehem. For culture, see **ORNITHOGALUM**.

**ALCHEMILLA.**—*Rosacææ*.—Lady's Mantle.—Hardy herbaceous plants, chiefly natives of the middle of Europe: of the easiest culture. The most ornamental species is *A. alpina*, which seldom exceeds half a foot in height, with leaves of a deep green above, of a silky whiteness underneath, and with greenish-yellow flowers. It is admirably adapted for rockwork, or growing in pots.

**ALEXANDRIAN LAUREL.**—See **RUSCUS**.

**ALISMA.**—*Plantaginææ*.—A genus of aquatic plants, with ornamental flowers, several of which are natives of Great Britain.

**ALKANET.**—The root of Dyers' Bugloss (*Anchusa tinctoria* Lin.), which has the property of giving a fine red colour to oil, wax, and other similar substances.

**ALKEKE'NGI.**—See **NICA'NDRA**.

**ALLAMA'NDA.**—*Apocynacææ*.—Stove shrubs, with splendid yellow convolvulus-shaped flowers. *A. cathartica*, a native of Guiana, a climbing plant, is the most com-

mon species. It requires a light rich soil, kept frequently watered; and it is increased by cuttings. Where a conservatory adjoins an orchideous house or stove, this Allamanda and other splendid stove-climbers may be planted in the hothouse and trained through a hole in the back wall into the conservatory, in the cool air of which the flowers will be more brilliant, and more generally seen, than in the damp hot air necessary for the roots. *A. Schottii*, a native of Brazil, introduced in 1847, and *A. nerifolia*, differ from most of the other species of the genus in being erect evergreen shrubs, flowering when about two feet high.

**ALLIUM.**—*Asphodèleæ*.—The Garlic and Onion tribe, of which there are above a hundred and fifty species in cultivation, natives of Europe and America, some few of which are considered ornamental, and one, *A. odorum*, is sweet-scented. Among the ornamental species are *A. Möly*, with yellow flowers; *A. descendens*, with dark purple flowers; *A. incarnatum* with red flowers; and *A. Cowani*, *A. Chamæmöly*, and *A. neapolitanum*, with white flowers. All the species thrive in any common soil, and are increased abundantly by offsets from the bulbs. In a garden devoted exclusively to bulbs, the Alliums form a large and important group, from the great variety and different colours of the flowers; but they differ from almost all other ornamental plants, as they do not admit of being gathered and put into nosegays, on account of their unpleasant smell.

**ALLOSURUS.**—*Filices*.—A genus of ferns, with short broad leaves, natives of Mexico and New Granada. *A. flexuosus* is a climbing plant; *A. cordatus* is nearly hardy.

ALLSPICE-TREE.—See CALYCA'N-THUS.

ALMOND.—See AMY'GDALUS.

ALOCASIA.—*Araceæ*.—This belongs to the order in which the Arums are included; the *Alocasia metallica* is one of the most splendid of the *foliated* plants (or those cultivated for their foliage), on account of its fine shining bronze appearance, whilst its under side, likewise shining, is of a deep purple; a native of Borneo; requires stove heat and peat soil. *A. Lowii* is of a deep green, with conspicuous white veins.

A'LOE. — *Hemerocallidaceæ*. — The name of Aloe is so frequently applied in conversation to the American Aloe, or Agave, that many persons are not aware that the true Aloe is not only quite a different genus, but belongs to a different natural order: the American Aloe being one of the *Amaryllis* tribe, and the true Aloe one of the *Day-lily* tribe. The qualities of the two plants are also essentially different: the American Aloe abounds in starchy nourishing matter, while every part of the true Aloe is a drastic purgative, which is poisonous if taken in excess. The true Aloe also flowers every year, and the flowers are tube-shaped, and produced on a spike; while each plant of the American Aloe flowers but once, sending up an enormous flower-stem, with candelabra-like branches and cup-shaped flowers. The true Aloes are succulent plants, natives of the Cape of Good Hope; and they grow best in this country in greenhouses, or rooms, the pots being well drained, and the soil composed of a sandy loam, mixed with a little lime-rubbish or gravel. To this, when the plants are wanted to attain a large size, may be added

a little leaf-mould. The plants should be duly supplied with water when they are in a growing state, but in winter they should be kept in a dry place, and watering should be discontinued.

ALO'NA. — *Nolandeæ*. — Very beautiful half-hardy shrubs, natives of Chili and Peru. *A. cælestis* resembles, in its leaves and general appearance, a soft-leaved Heath, but its flowers are like those of *Nolana atriplicifolia*, that is, closely resembling those of a minor *Convolvulus*, but with less white in them.

ALONSO'A. — *Scrophularinæ*. — The Mask-flower.—The species are low under-shrubs, or herbaceous plants, natives of Peru; to the two formerly most esteemed, *A. incisifolia* (R. et P.) and *A. linearis* (H. K.), is now preferred *A. Warzewiczii*, which has larger flowers than the preceding, and is very elegant either for the greenhouse, or for the open border in summer; colour rosy scarlet; it should be sown on a hotbed in March, and planted out in the end of May. When the plants are about six inches high, the extremity of the principal stem should be pinched off, in order to render them more compact, and their flowering more abundant.

ALOY'SIA. — *Verbenææ*. — The only species of this genus known in Britain is *A. citriodora*, a native of South America, formerly called *Verbena triphylla*, or the Lemon-scented Verbena. It is a half-hardy shrub, with panicles of small pinkish-white flowers, and very fragrant leaves, which fall off in the winter. It requires a rich but light soil, well drained; and, when grown in pots, it should never have water kept in the saucer. In winter, after its leaves have dropped, it should be kept nearly dry till the buds begin

to swell, when it should be watered frequently and abundantly ; but the water should never be suffered to remain in a stagnant state about the roots. It is easily propagated by cuttings, and only requires to be protected from severe frosts.

**ALPINE PLANTS.**—Dwarf Plants, natives of high mountains, and usually with bright-coloured flowers; generally employed for ornamental rockwork, and which, as they are covered with snow during winter in their native countries, require protection from severe frosts.

**ALPYNIA.**—*Scitaminceæ*.—A genus of reed-like plants, natives of the East Indies and South America, with large and showy white or pink flowers, of which one or two species merit a place in select collections of stove-plants. *A. nutans* is one of the most common, and when grown in rich sandy soil, in a moist heat, with plenty of room, it will flower freely. Like most of the Scitaminceous genera, there is a considerable degree of sameness in all the species, both in flowers and fruit, and therefore one kind is enough for a small collection.

**ALSTROEMERIA.**—*Amaryllidaceæ*.—This is a genus of tuberous-rooted plants, with beautiful flowers, natives of South America, and capable of being grown to a high degree of perfection in British gardens, in the stove, greenhouse, or open air, according to the species. The soil which suits all the Alstroemerias is a mixture of sandy loam and leaf-mould, or well-rotted dung. Of all the stove species, *A. Ligtu*, with white and scarlet flowers, is the most difficult to flower ; but by giving it abundance of water during summer, and a strong heat in December, it will flower in February ; and one plant will scent a whole house with fragrance like that of Mignonette.

After flowering, the plants ought to be allowed to rest for three months, during which time very little water ought to be given to them. After this they should be repotted, and encouraged to grow by giving them plenty of water, &c. *A. edulis* Juss., is another stove species, which climbs to the height of ten or twelve feet, and, like all other climbers, thrives best when turned out into the free soil. It may, however, be grown in a pot, commencing with one of small size, and shifting it several times, till it is at last put into a pot of eight or nine inches in diameter, when a frame of wire, three or four feet high, may be fixed to the pot, and the stems trained over it. These species will live and flower in a conservatory, but not so freely as in a stove. The treatment of the greenhouse species of Alstroemeria (which are very numerous) consists in setting the plants to rest by withholding water after they have done flowering, which is generally about the end of July ; fresh potting them about October or November, and giving them plenty of heat and water during April and May, the time when their growth is most rapid, and when, from the brittleness of their shoots and the tenderness of their leaves, they require to be sheltered or shaded from the sun and wind. The climbing species, *A. acutifolia* (L. et. O.), *A. hirsella* (Kunth), and *A. Salicilla* (L.), succeed best, both in flowering and ripening seeds, when planted in the free soil of a conservatory, or in the front of a stove or greenhouse, close under the wall, with protection during severe weather. Several of the species from Mexico, Chili, and Peru, will live in the open air, in similar situations ; and the greater part of these will grow

luxuriantly, and in fine seasons will flower freely, producing flowers of a much darker colour than those which have been grown under glass; and they will even ripen seeds. Those species which have been found to succeed best in the open air are, *A. pulchella* (Sims), *A. Pelegrina* (L.), and *A. versicolor* (R. et P.). All the species are readily increased by parting the roots, or by seeds.

**ALTHEA. — *Malvaceæ*.**—The Hollyhock.—Strong herbaceous plants, natives of the middle and south of Europe, and also of India and China, of which one species, *A. rosea*, the common Hollyhock, is one of our most splendid ornamental biennials. It grows to the height of from five to eight feet; and there are varieties of almost every colour, including white, and purple so deep as to be almost black. The flowers being large, and the stems erect, the plants have the best effect when grown in rows at the back of a border; or when each plant rises by itself from a circular patch in a lawn. An avenue of Hollyhocks, without any other flowering plants, is also very grand and ornamental, especially if the background on each side of the avenue be a hedge of Laurel or some other evergreen shrub. The fine effect of the Hollyhock with such a background is nowhere better seen than at Dropmore. The seeds of the Hollyhock, which is a biennial, should be sown in March; and in April, when the plants come up, they should be thinned out, and then suffered to remain till September, when they should be transplanted to the place where they are to flower. As the Hollyhock requires a rich and strong soil, it will be advisable, if the general soil of the garden be not of that nature, to dig a pit two feet in diameter and two feet deep, which should be filled with equal parts of

good strong loam and thoroughly rotten dung, chopped up and well mixed together with the spade. When the pit is filled, the earth should be allowed a few days to settle, and then filled up to the general level of the garden; after which the young Hollyhocks should be planted in it, singly if the plants be very strong, and three together if they should be weak. When the flower-stem appears, it should be tied to a stake, if not strong enough to support itself.

**ALTHEA FRUTEX.**—See HIBISCUS.

**ALYSSUM. — *Cruciferae*.**—Madwort.—Herbaceous plants, both perennial and annual, of low growth, and with showy flowers, chiefly natives of Europe. *A. saxatile*, which grows about a foot high, and which produces yellow flowers in April, is one of the most ornamental of the perennial species, and is well adapted either for rockwork or pots; as is *A. deltoideum* L. (*Aubrieta deltoidea* Dec.), which has purple flowers. The Sweet Alyssum, *A. halimifolium*, or *A. calycinum*, now called *Koniga maritima*, which has white flowers, is well adapted for edgings to beds. *A. saxatile*, and all the other perennial and shrubby species, are placed by some botanists in a new genus called *Adysetum*; but this genus is not generally adopted. All the species are of the easiest culture in common soil, if not kept too moist; but they thrive best in sand or gravel. The perennial species are readily increased by cuttings planted under a hand-glass, and the annual ones by seeds. Though the perennial species are very hardy, yet as they are, in truth, not true perennials, but plants with half-shrubby or suffrutescent stems; they are apt to be injured by either severe winters or very hot summers

(for though injured by much wet, the roots will soon wither if they are kept too dry), and consequently they require to be renewed every three or four years.

**AMARANTH.**—The Amaranth of the poets is generally supposed to be the Globe Amaranth.—See GOMPHRENA.

**AMARA'NTUS.** — *Amaranthaceæ.*

—An extensive genus of annuals, chiefly natives of warm climates, most of which will flower in the open air in this country, if sown in February on a hotbed, and planted out in May. The most common species are *A. hypochondriacus* (the Prince's Feather), and *A. caudatus* (Love-lies-bleeding), both old inhabitants of British gardens, and of the easiest culture. *A. tricolor* is a greenhouse annual, chiefly remarkable for the red and white blotches in the centre of its leaves. *A. melancholicus* has ruby-red leaves, which render it admirably adapted for coloured beds; sow in heat, prick out again in gentle heat, and plant out in a warm situation in June. The leaves of all the species may be used as Spinach; and those of one species, *Amarántus oleráceus* (Chusan-Han-Tsi), are so employed in China.

**AMARY'LLIS.** — *Amaryllidææ.*

Bulbous plants, chiefly natives of the Cape of Good Hope and South America; but which have been increased in number tenfold by hybrids and varieties raised in England. All the kinds are eminently ornamental, and they are all of easy culture; the great secret being to give them alternately a season of excitement and a season of repose. To do this effectually, the plants should be abundantly supplied with water and heat, and placed near the glass when they are coming into flower, and water

should be withheld from them by degrees when they have done flowering, till they have entirely ceased growing; when they should be kept quite dry and in a state of rest. When in this state, they may be placed in any obscure part of a stove or greenhouse where it is dry, and of a temperature not under forty or fifty degrees. If kept in such a situation during winter, some kinds may be turned out into a warm border in spring, where they will flower; and if the season be fine, they will renew their bulbs in time to be taken up before the approach of frost. The chief value of these plants, however, is to produce flowers in the winter season, which they readily do if they are kept dry and dormant during the latter part of the summer and autumn. Indeed, by having a large stock of these bulbs, a regular succession of flowers might be procured during every month in the year. When the dormant bulbs are intended to be thrown into flower, they should be fresh-potted in sandy loam and leaf-mould, and put into a stove or hotbed, the heat beginning at fifty degrees, and ascending to sixty or seventy degrees; and when the leaves appear, they should be supplied abundantly with water. Where seeds are wanted, the watering must be continued, though somewhat less abundantly, after the flowers have faded, till the seeds are ripe; and when these are gathered, they ought to be sown immediately in light sandy loam, and placed in a frame, or near the glass in a moist part of the hothouse. If the young plants are potted off as soon as they are an inch or two in height, and shifted frequently in the course of the growing season, they will attain a flowering size in from fifteen to twenty months. The pots in which these and all other bulbs are grown



ought to be thoroughly drained by a handful or more of potsherds (broken pots) laid in the bottom of each pot, and covered with turfy peat; and the mould used should also be turfy, in order the more freely to admit the passage of water. The Belladonna Lily (*A. Belladonna*) flowers most splendidly in the open air in Devonshire, where the bulbs are planted in rows, close together, so as to allow the fibrous roots to form a mass, which is never disturbed.

**AMBERBOA Dec.**—*Compositæ*.—Sweet or Yellow Sultan. Well-known half-hardy annuals, natives of Persia, formerly included in the genus *Centaurea*; the seeds of which may besown in a hotbed in February, and the young plants transplanted to the open border in April or May.

**AMELANCHIER.**—*Rosaceæ*.—Deciduous shrubs or low trees, with showy white flowers, which appear in April. *A. vulgaris* and *A. Botrydium*, the Snowy Mespilus (formerly called *Mespilus canadensis*), are very desirable species for shrubberies. They are commonly propagated by grafting on the Hawthorn, and they will grow in any soil, and require very little pruning. Like other rosaceous shrubs, however, they are very liable to have their foliage injured by caterpillars.

**AMELLUS Dec.**—*Compositæ*.—There are only two species, one a greenhouse perennial, and the other an aster-like annual, *Amellus annuus*, which was formerly called *Kaulfussia amelloides*, and which is a very pretty little plant, being remarkable from the curious rolling up of its petals. Both species are natives of the Cape, and will not grow in loam without the addition of sand.

**AMERICAN ALOE.**—See AGAVE.

**AMERICAN CONVULVULUS.**—See CALYSTEGIA.

**AMERICAN COWSLIP.**—See DODECA'THEON.

**AMETHYSTEA.**—*Labiataæ*.—An annual plant with blue flowers, a native of Siberia, of easy culture in any soil or situation, except that it will not bear transplanting, unless when very young.

**AMMOBIUM.**—*Compositæ*.—A kind of Everlasting flower, with a yellow disc and white ray like a Daisy. A native of New South Wales, where it was found growing in pure sand. It is generally grown from seeds as an annual; but by striking cuttings, it may be kept two or three years.

**AMORPHA.**—*Leguminosæ*.—Deciduous shrubs, with pinnate leaves, from North America, varying from two to six feet in height, with showy dark-blue and orange flowers in terminal spikes. *A. Lewisii* has flowers of gold and purple of great beauty when examined closely. All the species are of comparatively short duration: their wood being soft, with a large proportion of pith, and their branches very liable to be broken off by high winds; in other respects they are of easy culture in sandy soil, and they are readily propagated by cuttings or layers. Indigo is made from the pulpy part of the leaves of *A. indigofera*, an East Indian species.

**AMPELOPSIS Mx.**—*Vitaceæ*.—*A. hederacea* is well known by its English names of Virginian Creeper and Five-leaved Ivy. Its flowers have no beauty, but it is worth cultivating as an ornamental plant, from the brilliant scarlet which its leaves assume in autumn; and which look particularly well at that season, when intermingled with those of the common Ivy, from the fine contrast they afford. The plant is of very rapid growth in any common soil, and

it is propagated by layers or cuttings.

**AMPHICOME** *Royle.* — *Bignoniaceæ.* — A very beautiful Nepal greenhouse perennial, with tubeshaped pink flowers. It may be propagated by either seeds or cuttings, though the first are sometimes two years before they vegetate, and the cuttings are very difficult to strike. The soil it is grown in should be loam, mixed with peat and sand; and to make it flower well, very little water should be given to it from the time of the leaves dying down, till the young shoots appear in spring.

**AMYGDALUS.** — *Rosaceæ.* — There are two species of Almonds which are highly ornamental, on account of their flowers: *A. nana*, which does not grow above two feet high, and produces its pink flowers in March; and *A. communis*, which forms a small deciduous tree, profusely covered with flowers in March and April, before it expands its leaves. There are several varieties of both species, but the only one which is worth notice is the large-flowered Almond, *A. c. macrocarpa*, which has much larger flowers than the common kind, though they are much paler. The dwarf Almond is propagated by suckers, and the other species and varieties by grafting on the common Plum. What is generally known in gardens as the double dwarf Almond, is now called by botanists *Cerasus*, or *Prunus japonica*. Whenever the tree Almond is planted for its flowers, care should be taken to let it have a background of evergreens; as otherwise, from the flowers being produced before the leaves, half their beauty will be lost from the cold and naked appearance of the tree.

**ANAGALLIS.** — *Primulaceæ.* — The Pimpernel. — Trailing herba-

ceous plants, natives of the middle and south of Europe. The common wild Pimpernel, or Poor Man's Weather Glass, from its flowers opening fully in fine dry weather, but closing on the approach of rain, or when the air is becoming moist, *A. arvensis*, is red; but the exotic species vary to several shades of purple, lilac, and blue. The finest species is *A. monelli*, which requires the protection of the greenhouse during winter, but which forms a beautiful close covering for a flower-bed in the open garden in summer, producing its fine mazarine-blue flowers from May to September. It is easily propagated by cuttings, which root immediately, in sand, under a hand-glass, and it will thrive in any light soil.

**ANCHUSA.** — *Boraginææ.* — Coarse-growing plants, annuals and perennials, natives of the south of Europe, and in part of Asia and Africa, remarkable for their intensely blue flowers, in some cases varied with red and white. The finest species is *A. paniculata* or *italica*, the Italian Bugloss, which is common in gardens. The flowers are in erect leafy spikes, and are of a brilliant blue, with their backs and buds of a reddish purple, and the plant continues flowering from June to September. The most ornamental of the annual species are now included in the genus *NOËA*.

**ANDRACHNE.** — See *A'RBUTUS*.

**ANDROMEDA.** — *Ericaceæ.* — Low deciduous and evergreen heath-like shrubs, chiefly natives of North America, and some of which are very ornamental. All the species are generally grown in heath mould or peat, but they will also thrive in very sandy loam. In whatever soil they may be grown, the roots should never be suffered to become quite dry; as, like those of all the hair-

rooted plants, when once withered they cannot be restored; and the plant has seldom vigour enough to send out a sufficient quantity of new ones. All the kinds are propagated by layers.

ANDROSACE. — *Primulacææ*. — Little insignificant plants, not worth growing except for rockwork; and only suited for that purpose from their feeble habit of growth, which prevents them from spreading fast.

ANDROSÆMUM. — *Hypericinacææ*. — A handsome evergreen British plant, with showy yellow flowers; very useful in covering the ground in shrubberies. It prefers a moist, shady situation, and is uninjured by the drip of trees. The English name of this plant is Tutsan.

ANEMONE. — *Ranunculacææ*. — All the plants belonging to this genus are beautiful and well deserving of cultivation, from the little white wood Anemone (*A. nemoralis*), to the large Dutch varieties of *A. coronaria*, which have been sometimes known to be six inches in diameter. The common hardy kinds, including the beautiful blue *A. apennina*, and the Pasque-flower, *A. Pulsatilla*, or as it is sometimes called, *Pulsatilla vulgaris*, are of very easy culture. They should be planted in a warm dry border, in face of a south wall, in a light soil, and they may be left in the ground for several years without taking up. Of the other kinds, *A. palmata*, with bright yellow flowers, *A. vitifolia*, a Nepal species, both with large white flowers, and *A. narcissiflora*, are well deserving of cultivation. The Japan Anemone, *A. japonica*, is, however, perhaps, the finest species of the genus. It is a native of China, where it grows in moist woods, and whence it was introduced in 1846. It is quite hardy in the open air in the neighbourhood of London, and continues producing its

beautiful rose-coloured flowers till the end of September or beginning of October. It grows best in a moist and somewhat shady situation. There is a hybrid raised between this species and *A. vitifolia*, which has pale pink flowers, and is of most luxuriant growth. It is much more hardy than the common kind, but its foliage is so abundant, that it requires considerable space. The Hepatica was once called *Anemone Hepatica*, though this name has been long changed to *Hepatica triloba*. (See *HEPATICA*.) The garden Anemones, on the contrary, which are what are called Florists' Flowers, require the utmost care in their cultivation. All the numerous and splendid kinds of these plants which are met with in gardens, spring from three species: viz., *A. coronaria*, the garland or Poppy Anemone, the sepals of which are white, with a red ring round the centre inside the flower, and the sepals rounded at the tip; *A. stellata*, or *pavonina*, the sepals of which are purplish, and of one colour throughout; and *A. hortensis*, the sepals of which are pointed and purplish, with a white centre. The tubers of these fine kinds of Anemones, and their hybrids and varieties, are sold in the seed shops by the hundred. They resemble little bunches of small black potatoes, which may be divided, each portion producing a new plant, though it will probably be too weak to flower the first year. As *A. coronaria*, which is the parent of the finest florists' Anemones, comes from Syria and Asia Minor, where the ground is parched and dry in the hot season, the tubers should be taken up in our moist climate every summer, as soon as the flowers are over, and the leaves have turned yellow. They should be laid on shelves formed of laths, and then be kept in a warm, dry, airy

situation till October, when they should be planted in beds prepared for their reception; and, where expense is not an object, these beds should be dug out to the depth of about a foot. In the bottom of the pit thus formed, should be spread a layer, six or eight inches thick, of rotten cow-dung—if two years old so much the better; and on this, fresh loamy soil, so as to raise the bed three or four inches above the level of the walks. The surface of the bed is then raked smooth, and drills or furrows made in it about five inches apart and two inches deep. A little sand should be strewn along these drills, and the Anemone roots placed in them three or four inches apart. Care must be taken, in planting, to let the tubers have the side which contains the bud, uppermost; and it sometimes requires rather a close examination to discover which side this is, particularly if the dry fibrous roots have been rubbed off, as the bud is not very conspicuous. All the pieces accidentally broken off should be preserved, as they will all grow and form fresh tubers. The bed should be covered with bast mats stretched over hoops, or bundles of straw tied together, when danger is apprehended from frost; but this covering should be so contrived as to be easily removed when necessary, as the tubers are very liable to be injured, and even to become mouldy, by damp. When the plants begin to grow, they should be frequently watered with rain-water, so as never to allow the fibrous roots to wither from drought; and when the plants have done flowering, the mats on hoops should be again stretched over the bed, and the plants kept quite dry, till their leaves become brown and wither, which will generally be in about a month after they have done flower-

ing. The tubers should then be taken up, and kept dry till the return of the proper season for planting. Another mode of cultivating the garden Anemone, which is said to produce flowers of extraordinary size and beauty, is to form a bed about eighteen inches deep, and to place a layer of stones, brickbats, and other drainage at the bottom, about six inches deep. The bed is then filled with fresh loam, and the tubers are planted in drills with sand, and covered as before directed; and then, over the whole is placed a layer of cow-dung, three or four inches thick. The beds which are planted in February, are watered with pond or rain-water regularly once a day, if the weather be dry and not frosty, during the month of March, and twice a-day afterwards till they are in flower; but those that are planted in the autumn are seldom watered till the leaves appear above ground; and afterwards till they flower. The watering carries the manure in small quantities into the ground, and the young plants thus treated are said both to grow and to flower with extraordinary vigour. It must be observed, however, that there should be at least two inches of loamy soil between the cow-dung and the tubers; as, if this were not the case, the tubers would be rotted. When seedling Anemones are to be raised, the seed should be divested of its pappus, by rubbing it between the hands or through a sieve, and sown in pots or boxes in August; the young tubers should be taken up when the leaves wither the following summer, and replanted in autumn, when they will flower the following spring.

ANGELICA-TREE.—See ARA'LIA.

ANGELO'NIA.—*Scrophularinae*.—An evergreen perennial, with very

beautiful blue flowers, a native of South America. It should be kept in a cool airy part of the stove, or in a warm greenhouse; and it should be allowed a season of rest, during which it should be kept cool, and have scarcely any water. The soil should be a very sandy loam, mixed with peat earth, and it may be propagated, though with difficulty, by cuttings struck in pure sand.

**ANNUALS.**—Plants which live only one summer; and which, with reference to their culture in British gardens, are either tender, half-hardy, or hardy. Tender annuals are kept during the whole period of their growth under glass; half-hardy annuals are raised under glass, and afterwards transplanted into the open garden; and hardy annuals are sown in the open garden.

*Tender Annuals* are sown in February or March, in pots of light rich earth, plunged in a hotbed; and as soon as the plants are come up, they are transplanted into pots of the very smallest size, one in each pot; which is called pricking them out. These small pots are again set in the hotbed, as near the glass as possible, and slightly shaded during sunshine. In a week or two, when the roots have made their appearance on the outside of the ball of earth, which is known by turning the plant out of the pot, to examine the ball, and replacing it, the plants are shifted into pots one size larger; and this shifting is continued from time to time, always into pots only a little larger than those the plants were taken out of; till at last the plants are in pots six, eight, or nine inches in diameter, according to their nature, and the size to which it is wished to grow them. In all these shiftings, light rich mould must be used to fill up the pots, and suffi-

cient drainage must be secured, by placing pots herds in the bottom of each pot. In general, the more frequently the plant is shifted, the larger and more bushy it will become before it flowers; but when once flower-buds have made their appearance, no farther advantage can be gained from shifting, the growth of the plant being then mature. Some persons water tender annuals with liquid manure, which is found to answer in the case of Balsams, Cock's-combs, and other strong-growing plants, but to injure more tender-growing kinds. The extraordinary size that Balsams and Cock's-combs may be brought to by repeatedly shifting them into larger pots, is not only gratifying in itself, but interesting and instructive, as showing the effect of art on plants. The common Balsam in a wild state, in the East Indies, is seldom seen above a foot in height, with a stem half an inch in diameter; but in British hot-houses it has been grown to the height of five feet, with a stem as thick as a man's wrist. We have omitted to observe that during the whole process of shifting, the temperature in which the plants are kept should be from sixty to seventy, or even eighty degrees, during sunshine; and that they should be so abundantly supplied with water, that the air should be constantly charged with moisture: but when the plants begin to flower, they ought to be removed to a dry airy situation, and the temperature gradually lowered. The dry air, and the lowering of the temperature, will not only increase the intensity of the colours of the flowers and leaves, but will prolong the duration of the plant.

*Half-hardy Annuals* may be sown either in plunged pots, or in a bed of earth on a slight hotbed, in

February or March; and after they have come up they may be pricked out into plunged pots, or into the earth covering another slight hotbed, where they may remain till the beginning of May, when they should be transplanted into the beds or borders in the open garden where they are finally to remain. In most cases, however, it is not worth while to prick out the plants in a second hotbed; and sometimes they may be sown in pots, and thinned out to two or three plants in a pot; and when they have grown two or three inches high, the ball of earth, and the plants in it may be turned out into the open border. This mode is well adapted for strong clayey soils, because when plants from a hotbed are transplanted into such soils, they commonly receive a severe check; whereas when they are turned out with balls, provided the soil round them is settled by a good watering, they receive no check whatever. The soil in which half-hardy annuals are raised, should be light and rich, because it is only in such a soil that the tender seedlings will grow vigorously and produce numerous fibrous roots, without which they would produce but little effect when turned out into the open garden. The more showy kinds of half-hardy annuals are the French and African Marigolds, Chinese and German Asters, Zinnias; the purple Jacobæa, and a number of others. Brompton, Tenweek, and German Stocks, though quite hardy, make better plants, and consequently flower more vigorously, when so raised. There are few plants more truly ornamental than the different kinds of stock; and when these are raised under glass, pricked out into pots of the smallest size, and gradually shifted from pots of two inches to those of ten inches in dia-

meter, they will make winter ornaments for greenhouses and dining-rooms, which for fine masses of colour are unequalled by any production of tropical climates. Brompton Stocks, treated in this manner have been known to attain the height of six feet, and to live and flower for three years.

*Hardy Annuals* are generally sown in the open garden, where they are finally to remain; or they may be sown in pots or seed-beds to transplant into their final situation, when they are two or three inches high. The latter mode is preferable with all the Californian annuals, which grow stronger and flower better when sown in autumn, and suffered to stand the winter in the open air, than when they are sown with the other annuals in spring. About an inch in thickness of very light soil should be laid on a hard surface of rock or gravel, in any obscure part of the ground, and in this the seeds should be sown the first week in September. In March or April, according to the season, when the flower-beds and borders have been dug over and prepared, the young seedlings should be taken up by spadefuls and laid over the bed, filling up all the interstices between the patches with earth, so as to make the surface even. Thus treated, the *Nemophilas*, the *Leptosiphons*, the *Collinsias*, the *Lasthenias*, and, in short, all the Californian annuals, will be splendidly in flower in May and June.

When the seeds of annuals are sown, the ground should first be made firm by pressing it with the saucer of a flower-pot, or the back of the spade; the seeds should then be sprinkled thinly over the ground, and just covered with fine earth, which should be slightly pressed down over them. When they come

up, if they appear too thick they should be thinned out, so as to leave each plant standing apart; the distance at which they are left from each other varying, of course, according to the strength and habit of growth of the plant. The plants of some kinds of annuals will bear transplanting after they have been taken up in thinning, but generally they are not worth the trouble of replanting. The seeds when sown are often destroyed by birds; but this may be prevented by turning a flower-pot over each batch till the seeds have germinated, taking care, however, to remove it as soon as the plants begin to grow, lest they should be drawn up by the shelter thus afforded, and become weak. Snails and slugs are dangerous enemies to young and tender annuals, and care should be taken to search for them early in the morning and late in the evening; or to destroy them by watering the ground with lime-water, so weak, as not to disfigure the plants.

ANONA *L.*—*Anonaceæ*. — The Custard Apple.—Stove-shrubs and low trees, natives of the East and West Indies. The hardy species are now formed into a separate genus, under the name *Asimina*; and one species, *A. triloba*, which has very curious flowers, is frequently found in gardens and shrubberies.

ANTHEMIS.—*Compositæ*. — The Chamomile.—*A. Pyrethrum*, the Pellitory of Spain, is a pretty little perennial, with large white flowers, stained with lilac on the back. It is a suitable plant for rockwork, or boxes in a balcony, as it requires a warm dry situation. Miller raised this plant in rather a curious way in 1732, finding its seeds among some Malaga raisins, to which they had adhered. The root was formerly considered a cure for the toothache.

The Arabian Chamomile, a pretty low-growing hardy annual, with yellow flowers, is now called *Cladanthus arābicus*.

ANTHOCE'RCIS.—*Scrophulariæ*. — *A. viscosa* is a very handsome greenhouse shrub, with smooth dark-green leaves and large white flowers, which appear in May and June. The flowers have a short tube, within which is a kind of star of green rays, and a widely-spreading limb, deeply cut into five distinct segments. The culture of this plant requires care, as the wood is of a very soft nature, and the plant is easily injured by over-watering; and when this is the case, the leaves turn yellow, and finally drop off.

ANTHYLLIS. — *Leguminosæ*. — Kidney Vetch.—Dwarf plants with pretty flowers; generally used for rockwork; which are quite hardy, and will grow in any common soil.

ANTIRRHINUM.—*Scrophulariæ*. — The Snapdragon.—Annual and perennial plants, natives of the middle and south of Europe, and of which one species, *A. majus*, the common Snapdragon, is in almost every garden. There are many varieties of this species, the finest of which, *A. m. caryophylloides*, has the flowers striped like those of a flaked Carnation. All the species of Snapdragon grow in any soil that is tolerably dry, and they are readily increased by cuttings; for though they produce abundance of seeds, yet the varieties can only be perpetuated with certainty by the former mode of propagation. The beautiful carnation-like variety will, indeed, very seldom produce striped flowers two years in succession from the same root; and thus a person who has purchased a plant with beautifully striped flowers, will generally have the mortification, the second year, to find it produce

nothing but flowers of the common Snapdragon, unless cuttings have been made from the young shoots of the plant, and the old root thrown away. As this plant in its wild state is very commonly found growing on the tops of old walls, or among fragments of limestone, it may be considered as one of the most ornamental plants for placing in similar situations. Many of the plants formerly called *Antirrhinum*, are now removed to the genus *Linaria*.

ANTS are very troublesome in hot-houses and greenhouses, and it is very difficult to get rid of them. As however, it has been found that the liquor discharged by ants is very acid and acrid, the idea presented itself that alkalies would be disagreeable to them; and experience proves this so far to be the case, that a circle of chalk or lime laid round any plant will effectually prevent the ants from touching it.

A'PHIS.—The green-fly, or plant-louse, is one of the most troublesome insects to the gardener, particularly on Rose-trees. These insects lay their first set of eggs (which are small and black) in autumn, near the axils of the buds. The eggs are hatched in February or March; but as only a few insects appear, they generally escape unnoticed, and, after twice casting their skins, arrive at their full growth in April. From this period to the end of summer, brood after brood is produced with almost inconceivable rapidity; and as these latter broods of aphides are all born alive, they begin to devour the plants on which they appear immediately. The tenth generation usually appears about September, and these insects lay eggs for the first brood the following spring. The best way of preventing the attacks of these

insects is washing the branches of the Rose-trees with soft soap and water in January or February; or, in short, any time before the buds begin to swell. When they have appeared, the best way to destroy them is to lay the infested branches on the hand, and gently to brush off the insects with a soft brush and plain water. Or if this be not found sufficient, to make a decoction of quassia, in the proportion of an ounce of quassia chips to every quart of water, and to dip the infested branches in it. Quassia is not injurious to plants, though it is instantaneously destructive to animal life. Some gardeners employ tobacco-water, but when this is used, the shoots should only remain a few seconds in the tobacco-water, and then be washed immediately in clean cold water, or they will become so blackened and withered, that the remedy will be worse than the insects. Snuff will kill the aphides if merely sprinkled on the moistened foliage and allowed to remain to imbibe the dews of one or two nights; if the insects be not all destroyed by the first dressing, a second dose will effectually clear the plant, which may then be washed clean. Lime-water is not so effectual, whilst at the same time it greatly disfigures the plants.

AQUARIUM.—A pond, basin, or cistern of water, for the growth of water-plants. In a pond in the open garden, the plants may either be grown in pots, plunged to the depth of one or two feet in the water, or they may be planted in the bottom of the pond. The former is generally the best mode, because the plants are by that means kept distinct, and the stronger cannot overpower the weaker. At the same time very strong ground plants, such as the white and yellow Water-



lilies, do not flower freely unless in the free soil, or in very large tubs. There are few greenhouse aquatics, but a number of stove plants which require to be grown in water; such as the Indian Lotus, or *Nelumbium*, &c., and these are necessarily grown in pots of moderate size. The most suitable soil is a rich loam. The Victoria Regia, being a river plant, requires the water to be gently agitated, to keep it in a healthy state; and this effect is produced either by a wheel continually turning, as at Chatsworth, or by a bucket moved by machinery so as to empty itself when it rises to a certain height, and then descend to be refilled. The plant is grown on little hillocks of loamy soil under the surface of the water, so that the root and stem is in shallower water than the leaves. If this plant be kept in stagnant water, the leaves will rot when about half grown. The Papyrus, though properly speaking it is a marsh plant, is also grown on mounds of earth in an aquarium.—See MARSH PLANTS.

AQUILEGIA.—*Ranunculaceæ*.—The Columbine.—Perennial herbaceous plants, growing from one to two feet high, of which several species are very ornamental; more especially the common Columbine, *A. vulgaris*, and its varieties, *A. alpina*, *A. canadensis*, *A. glandulosa*, and *A. glandulosa grandiflora*. They grow in any common soil that is dry; and the species are increased by seeds, which will keep a long time, and the varieties by division of the root.

A'RABIS.—*Cruciferae*.—Wall-cress.—Herbaceous plants, chiefly annuals and biennials, natives of Europe, many of which are remarkable for their early flowering. *A. alpina* has white and yellow flowers, which appear in March, and *A.*

*albina* flowers the greater part of the year, commencing in mild winters in January, and producing its large tufts of white blossoms till October. Some of the species and varieties, such as *A. verna*, *A. alpina nana*, and *A. bellidifolia*, do not grow above three inches high, and are admirable plants for rockwork, or gardens of pots.

ARA'LIA.—*Araliaceæ*.—Hardy suffruticose plants, and stove shrubs, with umbels of small white flowers. The commonest species is *A. spinosa*, useful in a shrubbery for its hardiness, and for its thriving in any poor gravelly soil. There is a new species, *A. japonica*, which is much handsomer than the common kind.

ARAUCA'RIA.—*Coniferae*.—Some of the species are very ornamental. *A. imbricata*, or the Chilian Pine, is quite hardy, and though it attains a large size in its native country, it grows so slowly in Britain, that it may be safely planted on a lawn. *A. brasiliæna*, which resembles *A. imbricata*, but has longer and looser leaves, is much more tender. *A. excelsa*, the Norfolk Island Pine, and *A. Cunninghami*, the Moreton Bay Pine, are both greenhouse plants in Great Britain, and are seldom seen in perfection, on account of the great space they require. *A. Cooki* is a very singular plant of this genus, which was first discovered by Captain Cook on a small island near New Caledonia. He describes its appearance as that of a tower, or basaltic column, and hence it was first called *A. columnaris*.

ARBORETUM.—A collection of trees and shrubs, containing only one or two plants of a kind, arranged together according to some system or method. The most common arrangement is that of the Natural System; but the plants in an arbo-retum may be placed together ac-

cording to the countries of which they are natives ; according to the soil in which they grow ; or according to their sizes and habits, or time of leafing, or flowering. In all small villa residences an arboretum is the most effectual means of procuring a maximum of enjoyment in a minimum of space, as far as trees and shrubs are concerned. To render an arboretum useful and interesting, each tree and shrub should be named.

A'RBORVITÆ.—See THU'JA.

ARBOURS. — Seats or resting-places, forming terminations to walks, or fixed in retired parts of shrubberies or pleasure-grounds. In general every straight walk ought to lead to some object of use, as well as of beauty ; and an arbour is one of those in most common use. The structure being formed, climbing plants, ligneous or herbaceous, are planted all round it at the base of the trellis-work, or frame, against which, as they climb up, they ought to be tied and trained, so as to spread over the whole arbour. Some of the best plants for this purpose are the different species of Honey-suckle, Roses, and Clematis ; and the Laburnum, the *Periplocagracea*, the Maurandias, the Wistarias, *Eccremocarpus scaber*, *Lophospermum*, *Rhodochiton*, the Virginian Creeper, *Cobæa scandens*, *Menispermum canadense*, and Ivy.

ARBU'TUS. — *Ericæcæ*. — The Strawberry-tree.—Well-known evergreen shrubs, of which *A. Unedo rubra* deserves to be mentioned for the beauty of its flowers ; *A. canariensis*, a greenhouse species, has also very showy flowers ; and *A. Andrachne*, which is the tenderest of the open air kinds, is remarkable for the looseness and redness of its bark. All the species are very ornamental, and of free growth ; and they all thrive best in heath mould,

or very sandy loam. They are propagated by layers or cuttings.

ARCTOSTA'PHYLOS.—*Ericæcæ*. — The Bearberry.—A Mexican evergreen shrub, with arbutus-like flowers. It is very difficult to cultivate, as it will sometimes die off suddenly in hot weather after a few hours' rain, if planted in the open border. Mr. Gordon, in the *Botanical Register*, recommends these seeds to be sown in pots, in a mixture of peat and loam, with a little decomposed cow-dung ; and when the plants come up, that they should be transplanted into other pots, and kept closely shut up and well shaded till they have made three or four leaves. The plants should then be shifted at once into larger pots, and returned to the frame, "which should now have the back turned to the sun, and be kept close for several weeks, air not being given at any time until the plants are fairly started and growing again." Mr. Gordon continues : "afterwards remove the lights entirely during the night, and keep them quite close in the day during the summer and autumn." In winter, keep the plants in a cold pit, where there is plenty of light and air, but no damp.

ARCTOTIS. — *Compositæ*. — Under shrubs and herbaceous plants, natives of the Cape of Good Hope, and of which one species, *A. aspera*, has large yellow flowers, and is truly ornamental. It grows freely in loamy soil, and is increased by cuttings planted in sand under a handglass.

ARDISIA.—*Myrsinæ*. — A genus of stove shrubs, of which *A. lentiginosa* is very ornamental for its scarlet fruit. All the species grow in loam and peat, and cuttings root freely in sand in a moist heat under a hand-glass. They may also be increased by cuttings of the root placed in heat.

**ARENARIA.**—*Caryophyllaceæ*.—Pretty little plants, with flowers shaped like those of the Pink. Most of the species are natives of Europe, and they are all quite hardy. The flowers are red, white, or purple. These plants are of easy culture in any dry sandy soil, and they are particularly suitable for rockwork.

**ARGEMONE.**—*Papaveraceæ*.—Prickly-poppy.—Highly ornamental hardy annuals and perennials from Mexico, with large flowers like those of the Poppy, and of the easiest culture. The plants, spreading widely, require a good deal of room to look handsome.

**ARGYREIA.**—*Convolvulaceæ*.—A very showy tropical climber, bearing considerable resemblance to an Ipomœa, but with large bright lilac flowers.

**ARISTOLOCHIA.**—*Asarina*.—Birth-wort.—The Aristolochias are mostly climbing plants, requiring the heat of a stove; but *A. Siphon*, *A. tomentosa*, and *A. Arkansa*, natives of North America, are hardy enough to endure the open air in Britain, without the slightest protection. They are all remarkable for the very singular shape of their flowers, and their large handsome leaves. They should be grown in sandy loam and peat; and they are propagated by cuttings.

**ARME'RIA.**—*Plumbaginææ*.—Thrift.—Hardy perennials, most of which are ornamental; and one species, *A. vulgaris*, the common Thrift, is a good flowering plant for edgings to beds and borders. It thrives in any soil not saturated with moisture, and is rapidly increased by division. *A. alpina*, which produces its pink flowers from May to August, is a most desirable plant for pots or rockwork.

**ARTEMISIA.**—*Compositæ*.—This genus contains, among other plants,

two well-known shrubs; the Southernwood, or Old Man (*Artemisia Abrotanum*), and the Wormwood (*A. Absinthium*). There is another very handsome species, a native of Siberia. All the kinds are very hardy, and will grow in any common soil; and the Southernwood is valuable for bearing want of air, and smoke, without injury. The leaves of this plant, slender as they are, will be found, if held up to the light, to be full of transparent dots, like those of all other plants having highly-scented leaves. These dots are the cells or vesicles containing the fragrant oil that gives out the scent; and breaking them, by rubbing the leaves between the fingers, makes the scent stronger.

**A' RUM.**—*Aroideæ*.—A genus of perennials, chiefly natives of warm climates, and of which a few species are hardy in British gardens. Of these, *A. Dracunculus*, the Dragon Arum, deserves a place in the flower-garden, for its very remarkable flowers. The large and splendid plant, with arrow-shaped leaves and white flowers, commonly called the Arum, belongs to a different genus, and was first called by botanists *Calla*, and afterwards *Richardia æthiopica*. It is a native of the Cape of Good Hope and St. Helena, where it grows in rich soil by the side of rivers. In England, it will not bear the winter in the open air, unless well protected; and on this account it is generally grown in pots. It is increased by offsets, which form on its thick fleshy roots in August or September. These should be potted in small pots, in soil composed of three parts of sandy loam, and one of leaf-mould, or thoroughly rotten manure. The pots should be well drained, and the plants frequently watered, while they are in a growing state. About May or June, the leaves

will begin to wither at their points; and when this is perceived, the supply of water should be lessened, till at last only enough is given just to keep the plant alive. During the time the leaves are dying off, the plants should have abundance of light; but when they are all withered, the plant should be removed to any shed or other place where it may enjoy complete repose for about a month. In October or November it should be repotted, and supplied with abundance of water, particularly if kept in a sitting-room where there is a daily fire. It should indeed always stand in a saucer full of water (changing the water every day), as the plant will not flower if once suffered to become too dry while in a growing state; and as it has the extraordinary power of discharging the superabundant water from the points of its leaves in drops, there is no danger of the water injuring it. The power of throwing off its superabundant moisture renders it also suitable for culture as an aquatic plant; and when thus treated, it will live in the open air all the winter, as when the leaves die down, the water, being only frozen a few inches below the surface, will be at a sufficiently high temperature to keep the root from frost. The roots must be planted in the mud at the bottom of the pond, and a part should be chosen where the water is not more than three feet deep. This must be attended to; because as the plant will not expand its flowers till its leaves rise above the surface, the stem would become weakened by being more elongated. The plant generally flowers in March or April; but by prolonging its season of repose, it may be made to flower in May or June.

ARUNDO.—*Gramineæ*.—*A. Dò-*

*nax* is a splendid bamboo-looking reed, rather tender in severe winters; but which, if the season be favourable, will grow in rich soil, kept moist, to the height of ten or twelve feet in one year; producing a fine oriental appearance when standing singly on a lawn, or near water. There is a variety with striped leaves, which is common in gardens; and which is called Rib-bon-grass in England, and in Scotland, Gardener's-garters. This variety is quite hardy. The species is a native of Italy, and it is often used instead of bamboo for chairs, canes, &c.; the imperfect canes are in general use in Rome for lighting fires.

ASCLEPIAS. — *Asclepiadææ*. — Swallow-wort. — North American herbaceous plants, for the greater part hardy in British gardens. The most ornamental species is *A. tuberosa*, which has fine scarlet-orange flowers, but is somewhat difficult to cultivate. It thrives, however, in sandy peat, kept rather dry than otherwise, and seldom disturbed by removal; and it is increased by division. *A. incarnata* is supposed to be a variety of *A. tuberosa*, but it has rose-coloured flowers. *A. amœna* has purple flowers, and thrives in a mixture of peat and loam.

ASH BERBERRY. — See MAHO'NIA.

ASPERULA. — *Rubiadææ*. — Wood-roof. — Hardy herbaceous plants, of which one species, *A. odorata*, the common Woodrooff, or Woodruff, deserves culture for its sweet-scented white flowers, which, together with the leaves, even in the dried state retain their fragrance. It is well adapted for growing in pots, but as it increases rapidly by its creeping roots, it is by no means desirable for rockwork.

ASPHODELUS. — *Asphodellææ*. — King's-spear, or King's-rod. — Ornamental herbaceous plants, mostly

quite hardy, of which *A. albus* and *A. luteus* are the most ornamental species. They are coarse-growing plants, and increase rapidly by suckers in any common soil.

**A'STER.**—*Compositæ*.—The Michaelmas Daisy.—Hardy herbaceous plants, mostly perennials. There are also a few Cape and New Holland shrubs. The herbaceous species are of great value, from their flowering late in autumn, and from their requiring very little care or labour in their culture. They will grow in any soil or situation, and spread rapidly by throwing up suckers and sending out root-stems. Among the handsomest perennial species are *A. alpinus*, and *A. ericoides*, the common Michaelmas Daisy. The China Aster has been separated by botanists from the genus *A'ster*; it was first placed in the genus *Callistemma*, but it and its varieties, the German Asters, &c., now form the new genus *Callistephus*, under which the culture of the plant is given. *A'ster tenellus* is thus the only annual species left in the old genus, and it is a pretty little hardy plant, which may be sown in the open ground in March or April. Among the greenhouse species of Aster, *A. argophyllus*, sometimes called the Musk-plant, is remarkable for its white leaves and strong scent; and *A. fruticosus* has pretty blue flowers. These two last species are grown in sandy peat, or a mixture of loam and peat, and are readily propagated.

**ASTILBE.**—*Saxifragææ*.—A very pretty hardy plant, with clusters of pink flowers, and very much the habit of *A. Spirea*. It is a native of lofty mountains in Eastern Bengal, and thrives best in peat soil.

**ASTRA'GALUS.**—*Legumindææ*.—The Milk Vetch.—Vigorous-growing pea-flowered plants, of which

several deserve culture, on account of their flowers. They grow in any common soil with a dry bottom, and are readily increased by seed or by a division of the root.

**ATAMA'SCO LILY.**—See *ZEPHYR-ANTHES*.

**ATRA'GENE.**—*Ranunculidææ*.—This genus is nearly allied to *Clématis*. The species are half-shrubby climbers, very suitable for training against walls or trellis-work, or for covering bowers. They all grow freely in any common garden soil, and they are readily increased by layers, or by cuttings of the growing wood planted in sand under a hand-glass. They also frequently ripen seeds, which ought to be sown immediately; in which case they will come up the following spring; otherwise, if kept some months before sowing, they will probably lie in the ground a year. All the species are beautiful, but *A. austriaca*, with blue flowers, and *A. sibirica*, with white flowers, are the most ornamental.

**A'TROPA.**—*Solanidææ*.—*A. Belladonna* is the Deadly Nightshade.

**AUBRIET'IA.**—*Cruciferææ*.—A genus of pretty little plants, generally with purple flowers, not above three inches high, which flower in March, and are admirably adapted for pots, or miniature rock-work. They grow in any common soil, and are readily propagated by division. *A. deltoidea*, and *A. purpurea*, are the most desirable species.

**AU'CUBA.**—*Cornidææ*.—A hardy evergreen shrub, which, though a native of Japan, endures the severest winters in the climate of London. It is common in every garden, and it is often called the Japan, or spotted Laurel. The leaves are leathery and variegated; and the bark of the shoots is of a pale green. It will grow in

any soil, either in an open situation, or under the drip of trees; and it bears the smoke of towns.

The Aucuba is a diœcious plant, some individuals producing only male, and others only female flowers. The blotched-leaved variety, with which we have been so long acquainted, being a female plant, of course bore no fruit. But recently both male and female plants of the normal green-leaved Aucuba have been introduced by Mr. Fortune; and a plant from this introduction was exhibited in March, 1864, before the Royal Horticultural Society: A glorious shrub laden with bunches of large oblong berries of the brightest coral red. This is certainly a great acquisition to our hardy evergreen shrubs; and what renders it still more valuable is that it will grow in a smoky atmosphere, and will form a pleasing object even in the very small gardens attached to houses in cities and towns where other evergreens cannot exist. It is more vigorous than the blotched-leaved variety. Propagated by cuttings, layers, or seeds.

AURI'GULA.—See PRÍ'MULA.

AUSTRALIAN SHRUBS have generally a strong tap-root, which sends out very fine fibres; they require a sandy loam, or peat, mixed with decayed leaves; and they should be frequently watered, but the water never suffered to remain in a stagnant state round their roots. They are all easily killed by an excess of either stagnant moisture, or drought; as in the former case the slender fibres of the roots rot, and in the latter they wither, and are seldom, if ever, renewed. The seeds of nearly all of them are also very long before they vegetate, unless steeped for at least twenty-four hours in warm water, of the tem-

perature of 120°. Some of the Acacia seeds may even be boiled two or three minutes without injuring them. All the Australian shrubs and trees are very tenacious of life; and when apparently killed, they will generally, if cut down, spring again from the root.

AVENS.—See GE'UM.

AZA'LEA L.—*Ericacæ*.—Beautiful flowering plants, natives of North America, Turkey, and China. They are divided by the French into two sections: First, *Hardy Azaleas*; *leaves deciduous*; *flowers with five stamens*. This section includes *A. viscidæa*, *nudiflora*, *calendulæcea*, and *pontica*; the last is a native of Turkey and the Caucasus, the others of North America. Section second consists of *Greenhouse Azaleas*; *leaves evergreen*; *stamens generally ten*. To this belong the original species, *A. ledifolia*, from China, and *A. indica*, a native of India. The varieties obtained from the above hardy and greenhouse species are exceedingly numerous, and have a splendid appearance from the profusion of flowers with which, when well grown, the whole plant is almost entirely covered; in colours varying from pure white to deep red and bright scarlet. The hardy sorts will succeed in a peat border. The greenhouse ones should be grown in sandy peat, in pots well drained with crocks, over which should be placed a layer of only the fibres of peat turf, obtained by beating the latter: this is found to answer well, by keeping the drainage clear and encouraging the rootlets. The pot being thus prepared for the reception of the plant, let it be introduced and the pot filled up with good sandy peat. Water with soft water, either rain or river: hard spring water should never be employed for

this tribe of plants. Great care is necessary so as not to give water in excess; nor, on the other hand, should the plants at any time be allowed to get too dry. They will of course require to be shaded after shifting; but plants well established, with good roots, and duly attended to as regards moisture, will bear full exposure to the sun's rays; but in that case they must have abundant ventilation, and indeed plenty of air at all times is essential in order to firm the wood. For handsome specimens, the plants must be kept under training by pinching off the extremities of such shoots as are growing too strong for the others; and those that are taking a bad form of growth should be checked at once. Pinching, judiciously, may be done at any time; but after flowering is the preferable time for the more general performance of this operation. Propagation is effected by grafting, in arching, layering, and cuttings, for increasing existing varieties; and new sorts, in many splendid varieties, have been and are still being raised from seeds. The Ghent Azaleas are hybrids, and varieties raised from the yellow *A. pontica* and the American species.

AZAROLE-TREE.—See CRATE'GUS.

AZEDARA'CH.—See ME'LIA.

**B**ABIA'NA.—*Iridaceæ*.—A genus of Cape plants, with solid bulbs of corn, which are eaten by the Hottentots; and which, when roasted, are said to resemble Chestnuts. The species have all showy flowers. For their culture see BULBS.

BABINGTO'NIA.—*Myrtaceæ* § *Lep-tospermeæ*.—A very curious little greenhouse shrub from the Swan River, which produces its long spike of white flowers tinged with pink in

autumn and winter. The leaves resemble those of a Heath. The genus was formerly included in BÆ'CKIA.

**BALCONY GARDENS.**—The most suitable plants for balconies are those of low growth; and as, from their exposed situation, they are liable to great and sudden changes, with regard to temperature, winds, and moisture, they ought to be naturally tolerably hardy. To prevent the soil in the pots from becoming over-dried, from the pot being constantly exposed to the wind, one pot ought to be placed within another, with a little sand or moss between, and this sand or moss ought to be kept constantly moist. The pots may be set in saucers, provided a little gravel be placed in the bottom of each saucer, so as to allow the free escape of water from the hole in the bottom of the pot. When there is no gravel in the saucers, the plants should be well and frequently watered; but the water that runs through the earth in the pot into the saucer, should be poured out immediately and thrown away. A very good mode of growing plants in balconies is, to set the pots in wooden or slate boxes or troughs, painted stone-colour, with a little gravel at the bottom for the pots to stand on, and with the interstices filled in with moss, which may also cover the rims and surface of the pots, so as to make the plants appear to be growing out of moss. Mignonette and trailing plants are best grown entirely in wooden or slate boxes, without the intervention of pots.

BALM.—See DRACOC'PHALUM.

BALSAM.—See BALSAMI'NA.

BALSAMI'NA.—*Balsaminaceæ*.—Tender and half-hardy annuals, with splendid flowers, mostly natives of the East Indies. The common Bal-

sam (*B. hortensis*) is a well-known greenhouse plant of great beauty. To grow it in perfection, seeds at least a year old should be sown on a hotbed, and when the plants come up they should be transplanted into very small pots, which should be plunged into the hotbed, and well supplied with water. In about a week, the plants should be transferred to larger pots; and this operation should be repeated ten or twelve times, always removing the plants to pots only a little larger than those they were taken from. As soon as the flower-buds begin to form, the plants should not be shifted any more, and the pots which contain them must no longer be placed in the hotbed, but the plants must be gradually accustomed to the open air. Many gardeners never plunge the pots after the plants are three or four inches high, and remove them from the hotbed to the greenhouse as soon as possible. Repeated shiftings are, however, essential to produce fine large flowers and handsome plants. The great secret in growing Balsams is to allow them plenty of air and light, and never to suffer them to become drawn up; as, when that is the case, they will never afterwards make handsome plants. As Balsams, from their succulent nature, require a great deal of moisture, the saucers in which the pots stand may be kept constantly full of water; but this water should be changed every day. Balsams generally ripen seeds, even from the double flowers, and thus numerous varieties are raised. Where there is any difficulty in raising the plants, new seeds should be used; but though the plants raised from seeds ripened the same year will be very robust, the flowers will be generally single, and their colours neither bright nor distinct.

Careful growers of Balsams, who wish to raise prize flowers, never use seeds less than three years old; and they are particular in saving them from the handsomest and most double flowers; the best being those which have their colours distinctly marked, like a Carnation. The more choice varieties may be preserved by cuttings, which root readily in sand kept moist below, but dry at top, and covered with a bell-glass. The seed-pods of *Balsamina*, and those of *Impatiens*, or Touch-me-not, open with a jerk when touched, so as to throw the seeds to a distance.

BAMBOO. — See BAMBU'SA.

BAMBU'SA. — *Gramineæ*. — A rapid-growing stove-plant, which has a noble appearance where there is abundance of room. There are some species so hardy as to stand the open air in the island of Jersey; and one of these, *B. nigra*, will thrive in a greenhouse, or against a conservatory wall, in the climate of London, whilst *B. gracilis* from the Himalayas, will grow in the open ground, and some cultivate it for the purpose of being employed as flower sticks. The Bamboos should be grown in loamy soil, and they are increased by offsets.

BANA'NA. — See MU'SA.

BA'NKSIA. — *Proteaceæ*. — Ever-green New Holland Shrubs, with flowers resembling a kind of brush, and curiously notched and cut leaves. All the species grow well in a mixture of sandy peat and loam, with the pots well drained; and cuttings of the young wood root with some difficulty in sand under a bell-glass, with a slight bottom-heat.

BAPTISIA. — *Leguminosæ*. — Herbaceous pea-flowered plants, from North America, of vigorous growth and rather elegant appearance; of which one species, *B. australis*, well



deserves a place in collections. They may be grown in the open air in common soil, and may be propagated by division of the root, or by seeds.

BA'RBÄ JOVIS. — A species of *Anthyllis*.

BARBADOES CHERRY. — See MALPI'GHIA.

BARBADOES GOOSEBERRY. — See PERESKIA.

BARBARE'A. — *Cruciferae*. — Perennial plants, of which *B. vulgaris flore pleno*, the double Yellow Rocket, is worthy of culture. It is propagated either by cuttings or division of the root, in common soil.

BARBERRY. — See BE'BBERIS.

BARK. — The refuse bark which has been used for tanning leather, and which produces considerable heat by its fermentation. When obtained from the tannery, it is generally soaked in water, and then spread out in an open shed, and turned over several times; after this, it is laid in a ridge or heap, and when it has begun to heat, it is again turned over once or twice, when it is fit to be put into the bark-bed. In this bed or pit it continues to ferment, and gives out heat for several months: and when the heat begins to decline, fresh bark is added from the reserve stock in the shed. The bark-bed may be of any dimensions in regard of length and width, but it should seldom be more than two feet in depth, to prevent an excess of heat. The plants in pots are generally plunged in it, at first to half the depth of the pot, and afterwards to the rim. Substitutes for bark are stable-dung, leaves of trees, chaff, and any other vegetable or animal substances which ferment in decaying. The best substitute for the peculiar heat of the bark is, however, a mass of stones heated by steam, or a mass of soil, or sand,

heated by pipes of hot water. The spent bark, after it will no longer afford heat for a hotbed, should not be used as a substitute for peat for the growth of plants, nor for mulching, for it produces fungi, which seize on the roots, and many plants, have been killed in consequence, among others valuable conifers.

BARK, OR MOIST STOVE. — A plant structure, with a glass roof, and a bed or pit in its centre, containing a mass of fermenting matter, or of earth or sand, heated by artificial means, in which plants in pots are to be plunged. The plants grown in such houses being natives of the warmest parts of tropical countries, the temperature in a bark-stove should never be lower than 60°, and during summer it may rise as high as 80° or 85°. To supply the air in the house with sufficient moisture, the floors of the passages should be frequently watered; and to facilitate the same object, and to subdue insects, the plants should be syringed or watered overhead most days in the year, in the summer season, about 5 o'clock in the afternoon, and about 3 o'clock when required in winter. After this watering the house should be shut up for the night, excepting when the weather is very warm, when some air may be given by opening the sashes at 8 or 9 p.m., and leaving them open till the following morning at 6 or 7. Independently of the bark-bed, the air of the moist stove requires to be heated by pipes of hot water or steam, or by smoke flues; the first mode being found by experience to be the best.

BARKE'RIA. — *Orchidaceae*. — Small but free flowering Orchids which require to be grown on blocks, and in a cooler temperature than the generality of this order. *B. Lind-*

*legana*, purple and white; *B. Skinnerii*, deep rose-coloured blossoms on spikes two feet long, a magnificent species; *B. spectabilis* and *B. elegans* are also fine.

**BARNADESIA.**—*Compositæ* § *Labiatifloræ*.—A very curious plant, with scarlet flowers, and a prickly stem. It requires a warm greenhouse, in which the heat should be at an average of 47°, and it should be grown in a compost of peat, loam, and sand, in equal proportions; abundance of water should be given in summer, but very little in winter, as it is easily killed if kept too damp.

**BARTONIA.**—*Loasaceæ*.—*B. aurea* is a splendid annual, from California, with golden-yellow flowers, which have quite a varnished metallic lustre when the sun shines upon them. The seed-pod is curiously twisted. It should be sown in the open border, in the end of April, in soil that is not wet, and in a sheltered situation, otherwise its stems, which are brittle, are apt to be broken by the wind.

**BAST, OR BASS.**—The inner bark of the lime-tree, separated by steeping the bark in water till it can be readily pulled asunder into ribbands or strands; these are hung up for some months in the shade to dry, and they are then woven into mats. The manufacture of these mats is confined to Russia, and some parts of Sweden, where the name for bark is bast.

**BASTARD ACACIA.**—See **ROBINIA**.

**BASTARD SAFFRON.**—See **CARTHAMUS**.

**BATAVIA.**—The Sweet Potatoe; a kind of *Convolvulus*, the root of which is eaten.

**BAUHINIA.**—*Leguminosæ*.—Mountain Ebony. Stove shrubs, mostly with white flowers, and re-

markable for their leaves always being produced in twins; on which account the genus was named in compliment to J. and C. Bauhin, both eminent botanists.

**BAY TREE.**—See **LAURUS**.

**BEAD TREE.**—See **MELIA**.

**BEAUFOURIA.**—*Myrtaceæ*.—Splendid New Holland Shrubs, with scarlet and red flowers; free growers and abundant flowerers, and well adapted either for planting out in a conservatory, or growing in pots. The best soil is sandy loam and peat, well drained; and cuttings, taken off with a small portion of half-ripened wood, root freely in sand, under a bell-glass. *B. decussata*, which produces its scarlet flowers from May to July, is one of the handsomest species.

**BEAUMONTIA Wal.**—*Apocynææ*.—Climbing shrubs from the East Indies, of elegant foliage with large white flowers; of easy culture in the stove, and propagated by cuttings either of the stem or roots. The best soil is sandy loam, mixed with rotten dung or leaf-mould. By careful management they may be made to flower in the open air.—See **ALLAMANDA**.

**BEDEGUAR.**—A disease which affects the Rose-tree.—See **CYNIPS**.

**BEDS FOR FLOWERS.**—Divisions of a flower-garden, which are formed in different figures, and which are generally covered with a mass of flowers of one kind, or at least of one colour, though sometimes they contain single plants, or small tufts of plants and flowers, at regular distances, with naked spaces showing the soil between. The plants most suitable for completely covering flower-beds are trailers and creepers; and those for standing singly at regular distances, are erect plants, which have their flowers in terminal spikes, corymbs, or umbels; or

compact-growing plants, which make neat little bushes, entirely covered with flowers. The stems of the plants often require to be pegged down with hooked sticks, so as to cover every part of the bed equally; and in wet seasons, when the plants are apt to run too much to leaves, the tips of the shoots should be taken off. The beds intended for trailing plants will only require a thin stratum of soil; but those intended for tall, vigorous plants, ought to have a deep soil.

**BEE LARKSPUR.**—See DELPHINIUM.

**BEE ORCHIS.**—*Ophrys apifera*.—The plants belonging to the genus *Ophrys* have all a remarkable resemblance in their appearance to an insect nestling in the flower, and hence they take their generic name.

**BEGONIA.**—*Ericaceæ*.—A very beautiful plant with large bell-shaped rose-coloured flowers. It is a native of South America, and in its native country it forms a shrub from six feet to eight feet high. There are several species, most of which have rose-coloured flowers; but one species, *B. Mathewsii*, has the flowers a pale yellow or a pure white.

**BEGONIA.**—*Begoniaceæ*.—Tropical under-shrubs or herbaceous plants, some of which require the stove, and others the greenhouse. The flowers are showy, pink or white, and the leaves are succulent, oblique at the base, and red underneath. Many of the herbaceous kinds have tuberous roots, and all should be grown in a rich light soil; they require plenty of water when in a growing state, but little or none when at rest. One of the finest species is *B. octopétala*, but it is rather rare. *B. discolor*, which has the leaves beautifully veined with crimson underneath, is the

commonest kind, and it thrives in the greenhouse, or in a room, throwing out numerous suckers, each with a small tuberous root, which only require separating from the parent and potting, to become fresh plants; when planted out in the summer season, it continues to produce flowers for several months.

*B. fuchsiorides* is a very remarkable species, which was introduced, in 1846, from the mountains of New Granada. At first sight it resembles a *Fuchsia* (hence its specific name); in its native country the flowers, which are of a most agreeable acid, are frequently eaten by the mule-drivers to allay their thirst, which is excessive in the dry season, as there are very few rivers. The leaves are small, and less coarse than those of most of the other species of the genus, which are very numerous, and by crossing have given rise to a vast number of varieties, many of them only esteemed whilst new. *B. coccinea*, *B. nitida*, *B. amabilis*, *B. imperialis*, and *B. rex*, may however be mentioned as species deserving cultivation, and likely to continue in estimation. *B. discolor*, R. Br. *Evansiana*, Andr., from China, is comparatively hardy, flowers all the summer, bright rose, very suitable for growing in rooms; cocoa-nut refuse, as manure, suits *Begonias* particularly well; and it is cleaner than most other fertilising substances.

**BELLADO'NNA.**—One of the names for *Atropa Belladonna*, the Deadly Nightshade.

**BELLADO'NNA LILY.**—See AMARYLLIS.

**BELL FLOWER.**—See CAMPANULA.

**BELL-GLASS.**—A glass cylinder, with a globular top, used for covering tender cuttings or seedlings. It

differs from a hand-glass in being all in one piece; whereas a hand-glass consists of several pieces fixed in a frame of lead, wood, or iron.

**BELLIS.** — *Compositæ*. — The Daisy. — Well-known perennials, of which *B. perennis*, the common Daisy, has been in cultivation in British and continental gardens from time immemorial. The most beautiful varieties are the large double, the large quilled, and the hen-and-chickens, but there are many others. In Germany, numerous curious varieties have been raised by saving the seed of the handsomest kinds. Each sort is much improved by being taken up, divided, and replanted at least annually. They are all admirable plants for making edgings to borders, and they are well suited for growing in pots, though at present they are almost neglected. They thrive best in a loamy soil, richly manured, which should be dug over and well broken before planting; and they will bear transplanting even when in flower, provided they are taken up with a portion of soil attached. No plants are better adapted for covering a bed with one mass of colour. Masses of any of the kinds of Daisies may be brought from the reserve ground and laid down on a bed in the flower-garden, when just coming into flower, and taken back again to make room for other plants, when they have gone out of flower. Wireworms, which, as it is known, are extremely destructive to Pinks and Carnations, are said to be so fond of Daisies, as never to touch any other flower when they are near.

**BELLOWS FOR FUMIGATION.** — A machine composed of the common bellows, or patent blower, used for blowing fires, with the addition of

a tube or vessel for containing tobacco, pierced with holes. The tobacco is placed in this vessel, and, being lighted, the air is blown through it, till a sufficient quantity of smoke is forced out to fill the pit, frame, or house which is to be fumigated for the destruction of insects. The tobacco should not be so dry as to produce flame, or to burn rapidly, for then the oil which should be carried in vapour with the smoke, is immediately consumed without affecting the insects.

**BELVIDERE**, or Summer Cypress. — See KO'CHIA.

**BENTHAMIA.** — *Cornæacæ*. — A very handsome evergreen shrub, with large white showy flowers, which are succeeded by scarlet fruit, having the appearance of a large strawberry. It is somewhat tender, and, north of London, it requires a wall. It thrives best in loam, and may be propagated by layers, cuttings, or seeds, which it produces in abundance.

**BERBERIS.** — *Berberidææ*. — The Berberry. — Deciduous shrubs, natives of Europe, North America, and Nepal, several of the species of which are very ornamental. *B. vulgaris*, the common Berberry, is a most elegant plant when trained to a single stem, and then allowed to expand its head freely on every side; so treated, the branches become drooping, and have a fine effect in spring, when they are covered with their rich yellow blossoms; and in autumn, from their long red fruit. But the most interesting species is the *B. Darwinii*, a native of Chili; it forms a beautiful evergreen shrub, 3 to 4½ feet high, with leaves of a fine shining green, and numerous orange yellow flowers which appear in May.

**BERBERRY.** — See BERBERIS.

**BERGAMOT.**—The true Bergamot is an exotic plant, called *Monarda didyma*; but there is also a Bergamot Mint (*Méntha citrâta*), which smells nearly the same.

**BIENNIALS.**—Plants that do not produce their flowers till the second year, and then die after they have ripened their seeds. The Brompton Stocks, Hollyhocks, Wall-flowers, Snapdragons, and Canterbury-bells, are also generally considered biennials, though some of them live three or four years. Biennials should be sown in March or April, thinned out in May, and transplanted in September to the place where they are to flower the ensuing year. A little earth should be taken up with the roots, when they are transplanted, and they should be well watered, and shaded for a day or two, till they are thoroughly established.

**BIGNONIA.**—*Bignoniaceæ*.—The Bignonias or Trumpet-flowers once formed a very large and splendid genus, chiefly of climbers, and remarkable for their large, brilliant-coloured flowers. Many of the species have, however, been now removed to the genera *Técoma* and *Spathòdea*. *B. capreolâta* is hardy enough to withstand our winters on a south wall. *B. speciosa*, *Chamberlainii* and *B. venusta* are splendid conservatory climbers. They are all of easy culture, requiring chiefly abundance of room, and cuttings of them all root readily in sand.—See *TÉCOMA*.

**BILBERRY.**—See *VACCINIUM*.

**BILLARDIERA.**—*Pittosporeæ*.—Appleberry.—Climbing, half-hardy shrubs, natives of Australia, with bell-shaped flowers, and long berry-like fruit which tastes like roasted apples. The beautiful plant now called *Sollya* was at first supposed to belong to this genus. For

the culture, see *AUSTRALIAN SHRUBS*.

**BINDWEED.**—The common Bindweed (*Convolvulus sepium* L.; *Calyptègia sepium* R. Br.), with large white flowers, and not unfrequent in hedges, is one of the most ornamental of British twiners; but in gardens it has this disadvantage, that its roots or rather underground shoots, spread rapidly, and are very difficult to eradicate.

**BIRDS** are generally considered enemies of gardens, and some kinds, as the common sparrow (when seeds, which are their usual food, are scarce), are apt to live upon buds, especially blossom-buds, as being the largest; and others live upon fruits. As, however, all the soft-billed kinds, which constitute the great majority of singing-birds found in our gardens, live upon insects, especially on the aphides, and the caterpillars or grubs of moths, flies, and beetles, they are rather to be considered as advantageous to gardens than otherwise.

**BIRD CHERRY.**—*Cerasus Pádus*.—See *CÉRASUS*.

**BIRD'S-EYE PRIMROSE.**—*Primula farinosa*.—A very neat little plant, when cultivated in peat soil and kept moist.

**BIRD'S-FOOT TREFOIL.**—See *LO'TUS*.

**BIRTHWORT.**—See *ARISTOLO'CHIA*.

**BISCUTELLA.**—*Cruciferae*.—Buckler Mustard.—Hardy annuals with yellow flowers, natives of Europe, which only require sowing in the open border in March or April.

**BITTER-SWEET.**—*Solanum Dulcamàra*.—An indigenous climbing shrub, with pretty flowers and red berries, but poisonous, common in hedges.

**BITTER-VETCH.**—See *O'ROBUS*.

**BLACKBERRY.**—The common name of the bramble.—See *RUBUS*.

BLACK BRYONY.—See BRYONY.

BLADDER KETMIA. — *Hibiscus Tridnum* and *Africanus*.—Hardy annuals, natives of Italy and Barbary. The seeds should be sown in March or April.—See ANNUALS.

BLADDER NUT.—See STAPHYLE'A.

BLADDER SENNA.—See COLUTEA.

BLANDFORDIA. — *Hemerocallidææ*.—Showy plants with scarlet, yellow, and green tube-like flowers, natives of New South Wales, of which *B. nobilis*, *B. flammæa*, and *B. grandiflora* well deserve culture. These species ought to be grown in sandy loam and peat; and they are increased by seeds and suckers.

BLESSED THISTLE.—See CENTAUREA.

BLETTIA. — *Orchidæææ*.—Showy plants, natives of the tropics, and requiring stove-heat in Britain. They should be grown in sandy loam and peat; and they are propagated by division of the roots.

BLIGHT.—A popular term for the sudden injuries which plants receive, apparently from the weather, but in reality from the attacks of insects, or the growth of parasitic fungi. In general, whenever the progress of plants is suddenly arrested by some cause not understood, it is attributed to blight. Blight differs from mildew, which is always a fungus, in the latter exhibiting a white, bluish, or mouldy appearance.

BLITUM. — *Chenopodiæææ*.—Annuals of the easiest culture, of no beauty with respect to the flowers, but remarkable for the showy appearance of their spikes of succulent scarlet fruit. The English names of the species are Strawberry and Spinach Blite.

BLOOD FLOWER.—See HÆMANTHUS.

BLUEBOTTLE.—See CENTAUREA.

BLUMENBACHIA. — *Loasæææ*.—

Dwarf annuals, with pretty white flowers, and very curiously twisted seed-pods, which only require sowing in the open border in April. There is, however, one drawback to their general cultivation, which is, that they sting as badly as a nettle.

BOG EARTH.—See PEAT and HEATH MOULD.

BONAPARTEA.—See LYTTÆA.

BORAGE.—See BORA'GO.

BORA'GO. — *Boraginæææ*.—Annual and perennial plants, with blue, white, or pink flowers, nearly allied to the Forget-me-not. Natives of the South of Europe and Persia; of easy culture in any common soil.

BORDER.—A border differs from a bed in having a walk only on one side; and an ornamental border, in which flowers or shrubs, or both, are grown, ought to have the plants so arranged in regard to height and distance, as to have them seen to the greatest advantage from the walk. For this purpose the lowest-growing plants should be placed in front, and the highest kinds behind them, and the distance between the different plants should be proportioned to their breadth, not to their height; because a very tall growing plant, such as the common Lily, is sometimes a very narrow one, and a low bushy plant, such as the Pæony, is sometimes three times as broad as it is high. Hence, in a border which is to be composed of a great variety of flowers, the plants cannot be placed in rows, or at regular distances; but a space must be apportioned to each plant according to its width; keeping in view the necessity of always leaving a clear space of a few inches round every plant, whether large or small. With regard to the mode of arranging herbaceous plants in borders, with reference to the colour of their

flowers and time of flowering, the object ought to be to have an equal number of plants in flower in each of the floral months; and among the plants of each month to have as nearly as possible an equal number of each of the principal colours. This is the *beau idéal* that the cultivator should keep in view; but it is not easy to carry it out into practice without the assistance of a reserve garden, and a number of plants in pots, that can be substituted for any plant which perhaps has not come into flower sufficiently soon, or which has not produced a sufficient quantity of flowers. The best mode is to make a plan of the border, and then to mark it with circles in the desired colours. When this has been done, the names of two or three flowers, of the proper size and colour for the situation, should be written in each circle; and then there will be no trouble in planting the bed, as it will be only necessary to refer to the plan to know what flowers are wanted. When this is not done, and the flowers are planted at random, they will require taking up with a ball of earth attached to each when in flower, and shifting about till a proper effect is produced. When the plants named in the circles continue only a short time in flower, the names of others should be given to fill their place when they are out of bloom; and in this case the circles may be numbered, and the numbers referred to a book, in which the names of all the suitable plants and all necessary particulars respecting them may be inscribed. As a concise summary of the distinctions between a bed and a border in a flower garden, it may be observed that in a bed the flowering plants should be trained so as completely to cover the

ground, while in a border, a distinct space should be left round each; and that a bed has a walk all round it, while in a border there is a walk only on one side.

**BORDER FLOWERS.**—Herbaceous plants of hardy constitution, showy in appearance, and of easy culture, and therefore well adapted for ornamenting the borders of flower gardens. Border flowers are classed as perennials with fibrous roots, perennials with bulbous or tuberous roots, biennials, and hardy annuals. Among the fibrous-rooted perennials are some, such as certain species of Saxifrage, Pinks, Carnations, &c., which are evergreen; and these are most desirable plants for the borders of winter gardens. There are also some evergreen biennials, such as Wallflowers, Stock Gillyflowers, &c.

**BORO'NTA.**—*Ruticææ*.—Evergreen New Holland Shrubs, which flower during the greater part of the summer, and which are all very ornamental. *B. serrulata* is a most desirable species, forming a neat compact plant for a room, or greenhouse, and requiring plenty of light and air, but very little heat. It, and all the other species, will grow freely in sandy peat, well drained, and they may be propagated by layers or cuttings of the young wood in sand, under a bell-glass, taking care to wipe the glass frequently, so as to keep the cuttings free from damp.

**BOTANIC GARDEN.**—A garden in which the plants are arranged according to some system of botanical science, only one of a kind being planted, and a name appended to each. The most convenient mode for study is to place the plants in straight rows of narrow beds, one row in a bed, with paths between the beds; but the best mode for effect is to place them in groups of

one order, tribe, or genus, in a group. These groups have the best effect when of a circular form, and placed on a lawn. The position of the groups relatively to each other should be such as to correspond with the botanical system followed.

BOTTOM-HEAT is the warmth imparted to the roots of plants, by plunging the pots in which they grow into a hotbed or bark-pit. The effect this produces in stimulating the plants is very great; and it is particularly advantageous in striking those cuttings which, under ordinary circumstances, do not readily throw out roots. Bottom-heat is often very useful in enabling hothouse plants to stand in the open air during summer. A bed may be formed of bark, decayed leaves, or stable manure, in which the pots may be plunged, and the surface covered with a thin coating of turf; and in this manner all the hothouse climbers might be trained over the trellis-work of a verandah, and Palms, Bananas, and other tropical plants might be made to decorate the open ground of an English garden.

BOUYA'RDIA. — *Rubiaceæ*. — *B. triphylla* and its varieties are very ornamental, with scarlet flowers and smooth shining leaves. It grows freely in loam and peat in a warm situation in the open air, or in a greenhouse; and it is increased by cuttings of the roots. *B. versicolor* has fine red flowers and is very ornamental, though it is more tender than *B. triphylla*.

BOWERS. — Slight arbours, formed by training climbing shrubs over trellis-work so as to form a covered seat. They only differ from arbours in being less closely covered. — See ARBOURS.

BOX-EDGINGS. — The kind of Box used for this purpose is *Buxus sem-*

*pervirens nana*. For its culture, see BUXUS.

BOX-TREE. — See BUXUS.

BRACHYCOME. — *Compositæ*. — The great Swan River Daisy. — A very beautiful annual plant from the banks of the Swan River in South Australia. It was introduced in 1840, and grows freely in the open ground, though it flowers best in the greenhouse, being easily injured by wet. When raised from seed, the flowers are of several different shades, varying from the darkest purple to a pink or white.

BRACHYSE'MA. — *Leguminosæ*. — *B. latifolium* is a very ornamental New Holland climber, with fine large glaucous leaves and crimson flowers; and it grows freely in loam and peat, flowering abundantly, and ripening seeds; by which, or by layers or cuttings, it may be readily propagated.

BRAMBLE. — See RUBUS.

BRILLANTA'ISIA. — *Acanthaceæ*. — *B. Ovariensis* is a very showy stove plant with purple sage-like flowers, which appear in March. It is a native of Sierra Leone.

BRIZA. — *Graminææ*. — Quaking-grass. — *B. media*, the common kind, is a perennial; and *B. maxima*, a gigantic species, is an annual, requiring only to be sown in March or April, in the open borders.

BROMPTON STOCKS. — *Matthiola incana*. — These splendid flowers are biennials, and their seed should be sown early in May, in a border of light sandy soil with an eastern exposure, and never in front of a hothouse or south wall, as they cannot bear too much heat. The seeds should be sown very thinly in narrow drills, made about six inches apart. As soon as the plants begin to grow, and have expanded their second pair of leaves, they should be watered every evening with a watering-pot or garden-engine having a very fine



rose. When the plants are about three inches high, they should be thinned out so as to be at least six inches apart, and the plants removed should be carefully replanted in another bed. In about a month's time they should be thinned again, and the alternate rows taken up, so as to leave the remaining plants about a foot apart every way; the plants removed being taken up with balls of earth, and carefully transplanted, watered, and shaded till they have re-established themselves. Great care is necessary in transplanting, as the Stocks have long tap-roots, with very few fibrils attached. When the plants are wanted to be very fine, they may be protected during winter by hoops and mats, or hand-glasses; but in general this is not thought necessary. In March or April a compost should be formed of very sandy loam, or sand enriched with the remains of an old hotbed, or vegetable mould, formed of decayed leaves; and pits about two feet deep and two feet in diameter dug in the flower-borders and filled with it, into which the Stocks should be transplanted, with as large balls of earth attached as can be taken up. They should be carefully shaded and watered till they have taken root; and afterwards they should be watered every night till they come into flower. Thus treated, the spikes of flowers will sometimes be from eighteen inches to two feet long, and proportionably thick.

**BROOM.**—See **SPARTIUM** and **GENISTA**.

**BROWALLIA.**—*Scrophulariaceæ*, or *Solanaceæ*.—South American tender annuals, generally with blue flowers, requiring to be raised on a hotbed, and generally grown in pots.—See **ANNUALS**.

**BROWNIA.**—*Leguminosæ*.—

This is a genus of rather singular plants, named in honour of Dr. Patrick Browne, author of the *History of Jamaica*. *B. coccinea* is a very singular plant, with large crimson flowers, which only last about twenty-four hours before they drop off. It is a native of Jamaica, whence it was introduced in 1793, though it did not flower till February 1842, nearly fifty years after its introduction.

**BRUGMANSIA.**—*Solanaceæ*.—Peruvian shrubs, or low succulent-stemmed trees, of which *B. suaveolens* (better known by the name of *Datura arborea*), and *B. sanguinea*, are magnificent species. Being large plants, growing to the height of ten or twelve feet, they look best when planted in the ground, in a conservatory; but they will grow well in large pots: or they may be planted in the open garden in the summer season, and taken up and preserved in a back shed, from which the frost is excluded, during winter, to be replaced in the open border the following spring. The flowers are trumpet-shaped, a foot or more in length, and very fragrant. The plants grow freely in light rich soil: and they are readily propagated by cuttings either of the shoots or roots.

**BRUNSFELZIA.**—*Scrophulariaceæ*.—Handsome stove-plants, natives of South America and the West Indies. *B. nitida* has large yellow flowers, which it produces copiously the whole of the summer months in a cool stove or warm greenhouse. It is an erect shrub, growing four or five feet high, and is readily increased by cuttings.

**BRYONIA.**—*Cucurbitaceæ*.—See **BRYONY**.

**BRYONY.**—There are two kinds of Bryony common in English woods, very different in the eyes of a bota-

nist, but bearing considerable resemblance to each other in the eyes of an amateur. They are both found wild in hedges and thickets, through which they contrive to insinuate their long slender stems and branches, hanging from tree to tree; they have both greenish-white inconspicuous flowers; the fruit of both consists of bunches of showy red berries; and they have tuberous roots, of a very acrid nature. They are also diœcious; but this is the only botanical resemblance between them. The White Bryony (*Bryonia dioica*) belongs to the natural order Cucurbitaceæ, and it is the only British plant belonging to that order. Its leaves are rough and palmate; its flowers have a calyx and a corolla, both of which are five-cleft, and its stem is climbing and furnished with numerous tendrils. The Black Bryony (*Tamus communis*) has, on the contrary, smooth, shining, heart-shaped leaves of a very deep and glossy green; the flowers consist of only one covering, which is six-cleft, and the stem is twining without tendrils. The names of black and white Bryony allude to the colour of the skin covering the thick fleshy roots, which in one species is black and in the other white. The root of the White Bryony may easily be made to grow in any shape that may be wished, by placing it when young in an earthenware mould. This curious property was formerly frequently taken advantage of by designing people, who, having thus obtained roots of frightful forms, exhibited them for money as natural curiosities.

**BUCK-EYE.**—The American name for the smooth-fruited Horse-chestnut.—See PA'VIA.

**BUCKLER MUSTARD.**—See BISCU'TELLA.

**BUCKTHORN.**—See RHA'MNUS.

**BUDDING** is an operation for propagating ligneous plants, as a substitute, in particular cases, for grafting, or other modes of propagation. In floriculture, it is more particularly used for propagating select species of Roses. The time of performing the operation is from July to September; and the mode is as follows:—The first thing to be done is to select a young shoot of the current year, from which the bud is to be taken, and a stock of one or of several years' growth, into which the bud is to be inserted. The bud is cut out with a portion of the bark and the wood attached above and below the foot-stalk of a leaf, in the axil of which leaf the bud is situated. To do this, a sharp penknife or budding-knife is inserted in the shoot, about three-fourths of an inch below the bud, and passed up beneath the bud to about half an inch above it; the bud, with the bark and wood to which it is attached, is then held in the left hand, and with a knife in the right hand the thin film of wood is quickly picked out, leaving the bud attached to a piece of bark, technically called the shield. A slit is then made in the bark of the stock, about one-third of an inch in length, and a transverse cut is made within one-fourth of an inch of the upper part of the longitudinal slit. The bark is opened on both sides of the longitudinal slit by mean of a thin flat piece of bone or ivory; or, in Nursery practice, with the end of the handle of the knife, which is made thin on purpose. The bud is now inserted in its natural position, with the bud pointing upwards, and a portion of the upper part of the bark to which the bud is attached is cut across, so as to fit to the transverse cut which was formed in

the stock. The bud is made fast in its situation by tying it with a strand or ribbon of bast matting. This being done in summer or autumn, the matting remains on for a month or six weeks, according to circumstances, till the bark of the bud shows, by its healthy appearance, that a vital union has taken place. The matting may now be loosened, and in a week or two altogether removed. By another mode, differing a little from the above, the



FIG. 1.—COMMON OR SHIELD-BUDDING.

cut across is made below the slit, as shown in *fig. 1*, in which *d* shows the cuts made in the stock, *e* the bud inserted, and *f* the bast mat applied.

Niche-budding is when the wood is retained in the bud, as shown in



FIG. 2.—NICHE-BUDDING.

*fig. 2*, in which *g* is the prepared stock; *c* the bud turned to show the wood, and *a b* the bud applied, which should afterwards be bound with bast mat, as before. In placing the bud on the stock in niche-budding, the principal thing to be at-

tended to is, to bring the horizontal edges of the base of the niche in the stock, and those of the bud which is to fit into it, into the most perfect contact possible; because the union is produced, not as in common summer budding, by the junction of the soft wood of the stock with the rudiment of the soft wood on the inside of the bark of the bud, but by the junction of soft wood with soft wood, as in common grafting. This mode of budding will always succeed best when the niche in the stock is made where there is already a bud (as shown at *g*), making the horizontal cut through the base of the bud.

Another mode is called annular flute-budding, in which a branch or shoot is chosen on the tree which is to be propagated, as thick as, or thicker than, the stock in which the bud is to be inserted. A ring of bark including a bud is then cut off from the branch of the shrub which is to be propagated, and detached by splitting it longitudinally on one side. A similar ring of bark is then detached from the stock, and the former inserted in its place, and tied on with matting. This mode of budding is found particularly suitable for all trees or shrubs having thick bark. There are many other kinds of budding, but these are in the most general use.

It sometimes happens in the case of Roses, that the bud will produce a shoot the same season in which it has been inserted; but it more frequently remains dormant till the following spring. At this period the stock should be cut over a few inches above the bud; and the shoot, as it grows, should be slightly tied to the portion of the stock left on above the bud, in order to prevent it from being injured by high winds. The second year this por-

tion of the stock may be cut off close to the bud.

Buds may be inserted in stocks at a few inches from the ground : in which case, the plants produced are called dwarfs ; or in straight stems at four, five, or six feet from the ground : in which case the plants produced are called standards. The latter is the most common mode of budding Roses and Orange-trees ; but other shrubs and trees of rare or ornamental kinds are commonly budded within a foot, or a few inches from the ground. Sometimes buds of several kinds are inserted in the same stock ; and sometimes buds are inserted in branches in different parts of the tree, for the sake either of supplying vacant places in the branches, or of producing several kinds on the same tree. Thus, on climbing British Roses, several varieties of Chinese Roses may be budded ; and on the single red Camellia, several varieties of double red or white Camellias.

In all cases of budding, it is essential that the stock shall not be very different from the bud to be inserted in it. In some cases it is even necessary that the bud and the stock should be of the same species ; while, on the other hand, it sometimes happens that a bud may be inserted successfully in any stock which is of the same natural order. Thus, it is said, the Lilac, the Orange, and the Fringe-tree may be budded on the common Ash ; all the four species being of the same natural order, *Oleaceæ*. Roses and thorns are the plants to which budding is most commonly applied by amateurs ; and the finer kinds of the former genus are generally budded on wild briars of the Dog Rose, and of the latter (*Crataegus*), on the common Hawthorn.

BU'DDLEA. — *Scrophularinæ*. —

Deciduous or evergreen shrubs, natives of India or South America, of which one species, *B. globosa*, is worth culture in the shrubbery. It has fine golden-yellow, ball-like flowers, grows in any common soil, and is tolerably hardy, though it is sometimes killed by a very severe frost. It is readily increased by cuttings under a hand-glass. *B. Lindleyana* is the handsomest species of the genus. The flowers are produced in a long spike ; and are of a beautiful lavender purple.

BUGAINVILLEA *spectabilis*. — *Nyctaginaceæ*, a climbing stove shrub, from Brazil, remarkable for its splendid rose and carmine petal-like bracts ; it is easily propagated by cuttings.

BULBS are plants which belong to a particular division of vegetables, having certain peculiarities which require a particular mode of culture. They are all, with scarcely a single exception, very ornamental, from the large size of their flowers in proportion to the entire plants, and from the brilliancy of their colours. Their principal peculiarity is, that they produce but a limited number of leaves every season ; and hence, if these leaves are cut off or injured, no new leaves are produced that season. In all other herbaceous plants, when the leaves are destroyed, fresh leaves are produced to a comparatively unlimited extent ; and hence, if the season be long enough, the plant may produce a sufficiency of foliage in the current year to enable it to mature flowers in the next. But in bulbs the case is different ; the leaves produced are very few, and if they are shortened before they are fully grown, or cut off before they begin to decay, the bulb is deprived of nourishment to such an extent, as either not to flower at all the following season, or to flower very weakly.

Thus the great art in the culture of bulbs is to preserve all their leaves uninjured, to expose them fully to the sun and air, and by no means to cut them off till they have begun to decay at the extremities. By far the greater number of bulbs flower in spring, and produce their flower-stems immediately after they begin to grow; and shortly after they have flowered they cease growing and remain dormant and without leaves during the remainder of the year. Hence almost all bulbs require to be planted in autumn; and hence, also, they require a free, dry, and somewhat rich soil, into which their roots may penetrate easily, and procure nourishment without difficulty, for their rapidly-growing leaves. The bulb is in all cases strengthened by preventing the flowers from producing seeds; and in most cases it ought to be taken up as soon as the leaves have decayed, and preserved in dry sand or earth, and in some cases on shelves, or in papers in a dry room, till the planting season in autumn. Bulbs which are indigenous to Britain, such as those of the common wild Hyacinth, and some of the Narcissi, receive little injury from remaining in the ground all the year; but improved varieties of indigenous bulbs, and all bulbs from warm climates, such as those of the Hyacinth, the *Ixia*, &c., are greatly injured by the moisture of our summers; and when left in the ground, require the interposition of art to keep the soil tolerably dry, till the bulbs have increased by means of their offsets, so as to form a dense mass. From the circumstance of bulbs growing with great rapidity when in a state of vegetation, they require abundance of water; and this is the reason why the soil in which they are planted should always be deep, so as to retain moisture. A

bulb is essentially a bud, and contains within itself the germs of the leaves and flowers which are to be produced the following season. In plants belonging to the other division of vegetables, those with netted leaves, or what are called *Dicotyledones*, a plant which is weak in the beginning of the year may, by increased care and nourishment, be made to flower in the course of the season; but this is by no means the case with bulbs, not one additional leaf or flower being in their case capable of being produced during the season that is not previously in an embryo state in the bulb. Thus, in one sense bulbs are of more easy culture than any other class of plants; because the germ being previously formed, and the nourishment being provided in the body of the bulb, it is only necessary to supply heat and moisture to cause these to develop. Hence, the practice of growing bulbs of Hyacinths, Tulips, Narcissi, Crocuses, Irises, Snowdrops, Fritillarias, &c., placed over water in glasses, or vessels of earthenware, or in moist moss. Bulbs never last more than one year, a new one forming every season after the plant has done flowering, as the old bulb wastes away. Hence new bulbs are formed every year in the Tulip and the Hyacinth, at the side of the old bulb; in the Crocus and the *Gladolus*, and many of the Cape Iridaceæ, over the old bulb; and in the bulbous Irises, &c., under the old bulb. Hence in the cultivation of bulbs in the open garden, there is a constant tendency in some species to sink deeply into the ground, and in others to rise to the surface, which must be carefully counteracted by the cultivator, by taking up and replanting; thus, the bulbous *Iris*, when left three or four years in the ground, produces

weak leaves, and ceases to flower freely, from the sinking of the bulbs; the Crocus, on the other hand, produces weak flowers and leaves from the bulbs rising above the surface; and the Tulip, if left in the ground for a few years, in consequence of the bulb being always produced at one side, is never found to come up twice exactly in the same spot. Experience proves, that certain bulbs which are in a state far removed from wild nature require the greatest care to preserve them from disease, such as the cultivated Hyacinth. These, therefore, must be taken up every year, and carefully preserved; while others, comparatively incapable of much cultivation, such as the Snowdrop, may be left in the ground a number of years without injury. Bulbs are generally propagated by little bulbs, produced by the side of the old ones, which are called offsets; but, like all other plants, they may be propagated by seeds, and from these, in the case of the Crocus and Hyacinth, the Crown Imperial, Iris Xiphium, and Iris Xiphioides, an endless number of beautiful varieties may be produced. This furnishes a fine source of interesting amusement to the amateur. The seeds should be sown in beds of light earth, where the plants may remain till they come into flower, which will generally be in from three to five years. The soil for almost all bulbs should be a free sandy loam, and the situation open, and fully exposed to the sun.

**BULBOCODIUM.** — *Melanthaceæ*. — Bulbous plants, natives of Spain and the Crimea; flowering in March and August, and of easy culture in loamy soil. *B. vernalis*, which does not grow above four inches in height, is a desirable plant for growing in a pot.

**BUFLEURUM.** — *Umbelliferae*. —

Hare's-ear. — Herbaceous plants, with greenish-yellow flowers, and very glaucous or bluish leaves. They are natives of Europe, and will grow in any common garden-soil. Several shrubs are included by some botanists in this genus; but they were separated by Sprengel, and formed into the genus *Tendria*. These are rather tender, being natives of the shores of the Mediterranean and the Cape of Good Hope; but near London they will bear ordinary winters in the open air. They should be grown in sandy loam.

**BURTONIA.** — *Leguminosæ*. — New Holland Shrubs, of which *B. conferta* was the first species introduced. It grows to the height of two feet, and produces its violet-coloured flowers from July to September. *B. pulchella* is, however, far more beautiful. It has heath-like leaves, and clusters of very large bright scarlet flowers at the end of the branches. It is a native of the Swan River settlement, and was introduced in 1848. *B. villosa*, from the same place, has purple flowers marked with a large yellow spot. For its culture, see AUSTRALIAN SHRUBS.

**BUTCHER'S BROOM.** — See RUSSOUS.

**BUTOMUS.** — *Butidææ*. — The flowering Rush. — One of the handsomest of British aquatic plants, well deserving of cultivation. It grows to the height of two feet, and produces its elegant head of pink flowers in June and July.

**BUTTER AND EGGS.** — A kind of Narcissus.

**BUTTERFLIES.** — These beautiful insects are never injurious to gardens except in their caterpillar state. As butterflies, they only sip a little honey from the flowers; their sole business being to propa-

gate their species, and then they die. Thus, the butterflies that are almost always on the wing, and which are the males, may be suffered to flutter out their brief existence unmolested; but when a butterfly is found sitting on a branch with its wings folded, in bright sunshine, it should be destroyed, as the butterflies found in this position are generally females, just about to lay their eggs. Sometimes butterflies, thus placed, are found, when they are examined, to be dead; and when this is the case, the adjacent branches and leaves should be searched for eggs.

BUTTERFLY PLANTS.—See *ONOCIDIUM* and *PHALANOPSIS*.

*BU'XUS L.* — *Euphorbiaceæ*. — The most common cultivated species are *B. sempervirens*, and *B. balearica*, the Minorca Box, both hardy shrubs or low trees. The former is one of the most valuable plants in European gardens, both as an undergrowth in woods, and as an ornamental hedge for sheltering gardens. Box is also much used for forming edges to walks; but the kind employed for this purpose, though it is considered to be only a dwarf variety of *B. sempervirens*, is so different from the Tree-box in its habit, that it might almost be considered as a distinct species. The Box-tree has been grown in European gardens almost from time immemorial. It was one of the principal ornaments in the gardens of Pliny; and in more modern times the Dwarf-box was almost the only plant used for forming the embroidery or scroll-work, or whatever that terrestrial arabesque may be called, which came into fashion in the time of Louis XIV., and it is employed for that purpose at the present time. The Dwarf-box is still a favourite for edgings to beds, and

it will be perhaps always preferred to all other plants, from its hardiness, easy culture, and compact habit of growth. It is also evergreen, and of great duration; it is easily propagated, and bears clipping or cutting remarkably well. It is readily propagated by taking up the plants, and after dividing them, replanting them farther apart, and a little deeper than they were before. It will grow in any soil not saturated with moisture, and it may be cut or clipped at any season of the year. The best time for clipping Box, however, is about the end of June; after which, especially if well-watered, the Box makes a second shoot of half an inch, or an inch in length, which obliterates the marks of the shears. To form edgings of Box properly, is an operation of gardening that requires considerable care. First, the ground should be rendered firm and even; secondly, a narrow trench should be accurately cut out with the spade in the direction in which the edging is to be planted; thirdly, the Box should be thinly and equally laid in along the trench, the tops being all about an inch above the surface of the soil; and, fourthly, the soil should be applied to the plants, and firmly trodden in against them, so as to keep the edging exactly in the position required. The trench should always be made on the side next the walk; and after the soil is pressed down, and the walk gravelled, the gravel is brought up over the soil, close to the stems of the Box, so as to cover the soil at least an inch in thickness, and to prevent any soil being seen on the gravel-walk side of the Box. This also prevents the Box from growing too luxuriantly; as it would be apt to do if the trench were on the border side, when the

plants would lean against the gravel, and the roots, being entirely covered with soil, would grow with so much luxuriance, that the plants would be with difficulty kept within bounds by clipping. A Box-edging once properly made, and clipped every year, so as to form a miniature hedge, about three inches wide at bottom, three inches high, and two inches wide at top, will last ten or twelve years before it requires to be taken up and replanted; but, if the edging be allowed to attain a larger size—say six inches wide at bottom, six inches high, and three inches wide at top—it will last fifteen or twenty years, or probably a much longer period.

Box-hedges for shelter are treated like other hedges, and being clipped at the same period as Box-edgings, will last for an unknown period, probably for centuries, provided the surface of the edge, or, in other words, the points of the shoots, are cut back occasionally, so as to admit the air to the centre of the hedge. The Box, when used to execute arabesques, or scroll-work on the ground, is not allowed to grow higher than two or three inches, and is cut quite flat at top; the entire figure of the arabesque being formed of Box, without the introduction of flowers or other plants, though occasionally with the addition of small cones or globes of Box rising up from the terminal points of the arabesque figure. These cones, pyramids, globes, or other figures, are kept in correct shape by being clipped every year. When verdant sculpture was in fashion, no tree excepting the Yew was so well adapted for it as the Box; and the tree was cut into the proper shape, by putting a wire frame of the desired form

over the tree, and clipping the branches to it.

**CACALIA L.**—*Compositæ*. — *C. coccinea* L., *Emilia coccinea* Cass., is a half-hardy annual, with a bright scarlet flower, in form somewhat resembling that of the common Groundsel. It is sometimes cultivated for the brilliant colour of its flowers, though it is scarcely worth the trouble it requires; as it must not only be raised on a hotbed, but its long slender stalks must be staked and tied up, to make it look at all neat. There are several perennial species of *Cacalia*, but they are very seldom seen in British gardens.

**CACTUS.**—*L. Cactaceæ*. — The very remarkable succulent plants, arranged by Linnæus under the name of *Cactus*, have been distributed by modern botanists over numerous genera, which they are still continually changing and rearranging. At first a few plants were left in the genus *Cactus*, but now that genus is annihilated, and seven or eight new genera substituted for it; still, as all the plants that once composed it, and the new ones of the same nature that collectors are continually sending home, are known by the general name of *Cacti*, it has been thought advisable to give here a slight sketch of the whole family.

In the time of Linnæus, very few *Cacti* were known; and even in the year 1807, Persoon enumerated only thirty-two; but now above five hundred living species are to be found in a single collection; and numbers of new species are being sent home by collectors every year. These new species are chiefly found in the tropical regions of America, but they extend over 75 degrees of lati-



tude, some being found near the boundary of the United States, and some near the town of Concepcion in Chili. By far the greater number, however, grow in the dry, burning plains of Mexico and Brazil, where they are subjected to the alternate seasons of extreme moisture and extreme drought. In these arid plains, where all nature seems parched up for six months in every year, the Cacti have been mercifully provided to serve as reservoirs of moisture; and not only the natives, by wounding the fleshy stems with their long forest-knives, supply themselves with a cool and refreshing juice, but even the cattle contrive to break through the skin with their hoofs, and then to suck the liquid they contain—instinct teaching them to avoid wounding themselves with the spines.

The Cacti are arranged by nature in several distinct groups; the first of which consists of the tree Cacti, or those kinds of *Cereus* which have long slender stems, and which usually grow on the summits of the mountains of Brazil, forming a singular kind of crest. These are generally thirty or forty feet high, and sometimes are branched like candelabra, and sometimes consist of only one naked stem, not thicker than a man's arm, though of such enormous height. The *Mammillarias*, and *Echinocacti*, or Porcupine Cacti, which form another group, grow in the valleys of the temperate regions, generally in loamy soils, and low grass; and the *Opuntias* and *Pereskias*, which form two others, are also principally found in the temperate latitudes. The *Melocacti*, or Melon-Cacti, and the *Rhipsalis*, which has narrow-jointed stems, are two other groups which are only found in the hottest parts of the tropics. Among the

many peculiarities of this family of plants, it may be mentioned, that if collectors cut off the top of any of the Cacti which they may find in flower, and send it with the flower on it to England, the seeds will perfect themselves, and ripen on the passage home, from the supply of moisture contained in the divided part.

With regard to the culture of the Cacti in this country, it is found that, generally speaking, they ought to have a season of complete rest, followed by one of violent excitement; that is, they ought to be kept almost without water from October to March, and then watered profusely while they are coming into flower. They ought all to be grown in pots well drained with cinders, instead of potsherds, as the latter retain too much moisture for the delicate and succulent roots; and they all enjoy bottom-heat, which makes them throw out abundance of fibrils. When received late in the year, that is to say in October or later, they should not be potted till the following spring; and when raised from seed (which is frequently sent over even in dead specimens), the seed should be sown in silver sand, and the young plants when transplanted should not be watered for several days.

*CÆSALPINIA Pluk.*—*Leguminosæ*.—The splendidly-flowering plant, known in the West Indies by the name of the Barbadoes Flower-fence, which was formerly included in this genus, is now called *Poinciana*. It should be grown in a mixture of loam and peat, with abundance of room for its roots; and though generally considered a stove-plant, it is found to live in the open air in London and Paris, if slightly protected during winter. It is propagated by cuttings struck

in sand, in a moist heat under glass. The other plants belonging to the genus are seldom found in British gardens.

*CALAMPELIS* D. Don.—See *ECREMOGARPUS*.

*CALANDRINIA*.—*Portulacææ*.—Peruvian and Californian plants, with fleshy leaves and showy flowers, generally treated as annuals in the open ground, but most of which will live two or three years in a greenhouse. There is some confusion about the specific names; the plants figured in the *Botanical Magazine* as *C. speciosa*, and *C. grandiflora*, being quite different from those figured under these names in the *Botanical Register*, and known by them in the London nurseries. Newer sorts than the preceding are *C. Burridgei*, flowers copper-red, proper for borders and baskets; *C. umbellata* (*Talmum umbellatum*) is very dwarf, from 4 to 6 inches high; flowers, numerous, deep reddish violet, disposed in a corymb. *C. grandiflora* Lindl. has flowers which, notwithstanding its name, are much smaller than those of the *C. discolor* Lindl., the latter being one of the most splendid flowers that will grow in the open air in England. The seeds of the latter two species (both of which grow rather tall) are generally raised on a slight hot-bed, but they may be sown in a warm border in the open air in April, when they will flower in June.

**CALCAREOUS SOILS.**—Soils containing a considerable portion of lime or chalk, mixed with sand or loam, and decaying vegetable and animal matter. Calcareous soils are generally very productive; and when manured, they retain and give out slowly the nourishing parts of the manure longer than any other kind of soil.

**CALCEOLARIA.**—*Scrophularinææ*.

—Perhaps no plants hybridise more freely than the different species of this genus; and what is remarkable is, that the shrubby kinds appear to unite freely with those that are herbaceous. In 1820, only half a dozen species were known, only one of which *C. corymbosa* Cav., with large yellow flowers, had any pretensions to beauty. In the next ten years, five or six more species were introduced from Chili, two of which, *C. arachnoidæa* and *C. purpurea* Grah., had purple flowers. The latter closely resembled *C. corymbosa* in its habit of growth; and about April, 1830, the happy idea struck the late Mr. Penny, of the Milford Nursery, to attempt to hybridise them. The result was the hybrid, *C. Gellaniæana*, the flowers of which were orange and dark-brown. Mr. Penny then tried *C. arachnoidæa* as one of the parents, instead of *C. purpurea*, and he produced the magnificent *Calceolaria* which he called *C. Youngii*, and which is still common in collections. In 1831, the spotted-flowered *Calceolaria*, *C. crenatiflora* Cav. (*C. pendula* D. Don), was introduced, and from this several splendid hybrids were raised. Some cultivator was then induced to try to hybridise one of the shrubby kinds, *C. bicolor*, the flowers of which were pale-yellow and white, with the herbaceous kinds, having dark-yellow and purple flowers, and some beautiful plants were the result. From that time to the present, innumerable hybrids have been raised every year, varying through every possible shade of crimson, brown, orange, purple, pink, and yellow, sometimes spotted, and sometimes delicately melting into white. One or two have been raised which were pure white, and others white with

clearly marked and distinct spots. They are all half-hardy, only requiring protection from frost; and they should be grown in a compost of equal parts of turfy loam and peat, with a little sand. They all require a good deal of water, as even the little hardy shrubby kind, *C. rugosa*, with small, dark-yellow flowers, will flag if water should be neglected even for a single day. The herbaceous kinds are still more susceptible in this respect, and when grown in pots, should stand in saucers of water, the water being changed every day, and never given to them till it has been warmed by standing for a little time in the same temperature as the plants. *C. violacea* is a shrubby kind, with pale lilac flowers, which requires a greenhouse.

Calceolarias are propagated by cuttings, which strike readily in the same soil as that in which the plants are grown; and which do not even require the aid of a bell-glass, though they will certainly strike sooner under one than without one. The seeds ripen in great abundance, and they should be sown as soon as they are ripe. The young plants should be pricked out as soon as they come up, and then transplanted into larger and larger pots, increasing gradually in size, and each being only a little larger than the preceding one, till they begin to show flower-buds: and when thus treated, they will flower in the following summer. When the seeds are not sown till spring, they will not flower till the second summer. There is only one annual Calceolaria, *C. pinnata*, and it is not worth growing.

**CALENDULA.**—*Compositæ*.—The Marigold.—There are several handsome species, some of which are shrubby, and some annuals; the

common Marigold, *C. officinalis*, and its varieties, and *C. stellata*, are the handsomest of the annual species. The Cape Marigolds, *C. pluviâlis*, and *C. hybrida*, have been removed by Professor de Candolle to a new genus, which he calls *Dimorphotheca*. Both these species are hardy annual plants, with very elegant flowers, which close at the withdrawal of the sun; and, as they do not open at all when dark heavy clouds foretell the approach of rain, Linnaeus called the commonest species *Calendula pluviâlis*, or the Rainy Marigold. The florets of the ray of the flowers of this plant are of a pure white inside, and of a dark purple on the outside; while those of *C. hybrida* are of a dingy orange outside.

**CALIFORNIAN ANNUALS.**—Beautiful annual plants, mostly sent home by Douglas, and natives of California, on the north-west coast of North America. They all bear cold much better than they do heat; and they will live through the British winters in the open air without any protection, though they are easily killed by the heat of summer, particularly if their roots become by any chance exposed to the full rays of the sun. The roots are indeed very feeble, particularly at the collar, where most plants are strong; and they will die in a few hours if the sun strikes this vital part. Nature has provided against this danger, by giving most of these plants a trailing habit, and thus covering the roots with abundance of leaves and stems: but cultivators, not being aware of the use of this, often, by training their plants over a frame, &c., expose the collar, and thus kill their plants. For the mode of sowing, &c., see **ANNUALS**.

**CAL'LA.**—See **A'BUM**.

**CALLICHROA.**—*Compositæ*.—*C.*

*platyglōssa*, the only species known, is a showy Californian annual, with golden-yellow flowers, requiring the usual treatment of Californian annuals.

**CALLIOPSIS.** — *Compositæ*. — Everyone knows the beautiful plants which compose this genus, under their old name of *Coreopsis*; from which genus they have been separated on account of a slight difference in the internal structure of the flower. The new and old names have some resemblance in point of sound, but they are very different in origin, for *Coreopsis* is derived from the Greek word *koris*, a bug, from the resemblance of the seeds to that insect; while *Calliopsis* is from *kallistos*, signifying most beautiful. The species are hardy annuals and perennials; the former of which may be sown in autumn, as they will stand the winter without any protection, and will thus come into flower early in summer. All the species will grow in any common soil; and the perennial kinds are propagated by division of the root. *Calliopsis bicolor* is the same as *Coreopsis tinctoria*.

**CALLIRRHŌE.** — *Malvaceæ*. — *C. pedata*; hardy annual from Arkansas; about eighteen inches high. Flowers purple, spotted with white at the base; proper for beds and borders.

**CALLISTEMMA.** — One of the botanical names for the China Aster.

**CALLISTEMON.** — *Myrtaceæ*. — Australian shrubs, with evergreen leaves and tassel-like flowers, better known by their old name of *Metrosideros*. They should be grown in sandy loam; and cuttings of the old wood strike freely in sand under a bell-glass.

**CALLISTEPHUS Dec.** — *Compositæ*. — The name given to the China Aster in De Candolle's *Prodromus*.

**CALLUNA D. Don.** — The common Heather or Ling. — See *Erica*.

**CALOCHORTUS.** — *Tulipaceæ*. — Californian bulbs with splendid flowers, but rather difficult of culture. They require a very sandy soil, which should be covered with litter in frosty weather, if the bulbs are not taken up as soon as they have done flowering in autumn. They produce their large lilac and white flowers in August and September, and occasionally ripen a few seeds, by which, or by offsets, they may be increased slowly.

**CALTHA.** — *Ranunculaceæ*. — The Marsh Marigold.

**CALYCANTHUS.** — *Calycanthaceæ*. — Deciduous shrubs from North America, with dark-brownish purple flowers, remarkable for their fragrance, as well as their rich colour. The plants thrive best in loam and peat, but they will grow in any soil that is not very stiff and moist; and they are commonly propagated by layers. Most of what are called different species, are only varieties of *C. floridus*, the American Allspice-tree. The scent of the flowers is commonly thought to resemble that of ripe fruit. The handsomest species is *C. occidentalis*, from California, with very large dark crimson flowers. *Calycanthus præcox*, the Japan Allspice, is now called by De Candolle *Chimonanthus fragrans*, or the Winter-flower, as it produces its flowers about Christmas. — See *CHIMONANTHUS*.

**CALYSTEGIA.** — *Convolvulaceæ*. — The new name for the common hedge Convolvulus, and some other species from America resembling it. The red variety of *C. sepium*, commonly called the American Convolvulus, makes a very pretty covering for a bower. *Calystegia pubescens* is a Chinese species, with pale-blush double flowers, introduced in 1844,

and is a very ornamental hardy twiner, very suitable for low trellises or the bases of columns. *C. dahurica* is also suitable for the same purpose; it has deep rose-coloured flowers. All the kinds grow best in sandy or gravelly soil.

**CAMELLIA.**—*Ternstroemiaceae*.—Evergreen shrubs with splendid flowers, from China, of which *C. japonica*, and its numerous garden varieties, are in general cultivation in all the greenhouses of Europe and America. Some of the varieties, as for example *C. j. variegata*, the variegated red, are so hardy as to stand the open air, either as standards, or planted against a wall; particularly if their roots are protected during frosty weather. It is a curious fact, that many tender and half-hardy plants will grow freely, and produce abundance of flowers, if their roots and collars are protected, in a temperature that would kill them immediately if these tender parts were exposed to the influence of the cold. Thus, when Camellias are planted out, if the roots are protected during winter by mulching (that is, covering with straw or litter), and the main trunk is wrapped round for about six or eight inches from the ground, with a hayband, or any other covering, the rest of the plant may be left entirely exposed without its sustaining the slightest injury. Camellias are commonly cultivated in sandy loam and peat, and this soil is perhaps the best for them when they are grown in pots; but when they are planted out in a conservatory, or the open ground, they will thrive exceedingly well in sandy loam, mixed with rotten dung, or leaf-mould. In France they use sandy peat; in Belgium, chiefly leaf-mould; in Italy, marly clay. The pots should be well drained

with crocks and peat fibre. When the plants are in a growing state, they require abundance of water,—which should be soft,—both at the roots and over the leaves; taking care, however, never to wet the leaves when the sun is shining upon them; as, wherever this occurs, the leaves become stained, or blotched, and look as though they were scalded. When Camellias are kept in a greenhouse or conservatory, imperfections in the glass will produce the same effect. About July the supply of water should be gradually diminished, in order to ripen the wood and induce the formation of flower-buds. The temperature of the Camellia house should be between 60° and 75° or 80° by sun heat, during the growing season; but when the flower-buds are formed, it may be lower, till the beginning of winter, when the buds begin to swell. At this season the temperature ought not to be suffered to fall below 45° or 50°, otherwise the buds will be liable to drop off; and they will also drop if watering be neglected. In severe weather it is better to use warm covering than to keep up the requisite temperature by much fire heat, for with this it is difficult to maintain a sufficiently humid atmosphere. On the Continent they cover the glass with leaves, which they keep on day and night during very cold weather. All the species and varieties may be propagated by cuttings, taken off at the base of a leaf, or at a joint, as soon as the wood has ripened, and planted in sand under a glass; but the finer varieties are generally propagated by layering, and inarching, or grafting. The French nurserymen have a very rapid mode of procuring plants by grafting, which they effect under bell-glasses, in a strong moist

heat, with scions of the young wood on stocks formed of cuttings struck the same season. From the *Camellia* being an evergreen, and its leaves being large, dark-green, and shining, it makes a very fine appearance against a conservative wall: and no plant whatever is more magnificent in a conservatory. It must be observed that all the varieties of *C. japonica* cannot bear a high temperature, and they prefer the shade to broad sunshine; also that when they are planted against a wall, it is better with a south-east aspect than full south. *C. Sasánqua*, and its beautiful variety, *C. S. maliflora*, are the most tender. *C. reticulata* is quite a different species from *C. japonica*, and it is certainly a noble plant, from the large size and brilliant colour of the flowers. It was first thought tender, but it is now found to be quite as hardy as *C. japonica*, only requiring a slight protection during winter.

**CAMPANULA.** — *Campanulaceæ.* — Beautiful herbaceous plants, natives of Europe and Asia; the greater part of which are perennials, and are hardy in British gardens. There are also some handsome hardy biennials and annuals, and one or two greenhouse species. Many of the hardy perennials are dwarf plants, which produce a profusion of flowers, more conspicuous than the leaves; which renders them particularly adapted for rock-work, or growing in pots. Some of the species are so tall, as to require to be planted at the back of borders, or in a single row, along with other tall plants; such, for example, as *C. pyramidalis*, the pyramidal Bell-flower; *C. Trachelium*, the Throat-wort, &c. *C. pyramidalis* is one of those plants that by repeated repotting can be brought to an extraordinary size, either as a narrow cone covered with

deep-blue flowers from the base to the summit, or trained against a frame in the fan manner. By either mode it makes a very splendid object; and all the art required to produce it, consists in employing rich soil, and in shifting the plant for two years into pots always a little larger and larger, so as to prevent it from coming into flower till it has acquired extraordinary vigour. Some of the prettiest little species for pots or rockwork, are *C. cenisia* and *C. uniflora*, which do not exceed three inches in height, and are covered during June or July with blue flowers; *C. carpatica*, *C. rotundifolia*, *C. garganica*, and upwards of fifty others, which do not exceed six inches in height. All these are very valuable for forming beds in a geometric or regularly-shaped flower-garden, from their dwarf and compact habit of growth, and from the great profusion of their leaves and brilliant-looking flowers. *C. Medium*, the Canterbury Bell, is one of the most ornamental of biennials; and *C. Spéculum*, Venus's Looking-glass, is a well-known and pretty annual. This last species has been, however, twice removed from the genus *Campanula*; having been called *Prismatocarpus Spéculum* by L'Héritier, and *Specularia Spécula* by De Candolle. The new Venus's Looking-glass of the nurseries, *Campanula Lœrei*, has, however, been always considered to belong to *Campanula*; it is an annual, height one to two feet, flowers large, of a fine blue or white; *C. pentagonia*, also an annual, about 9 inches high, is very suitable for small beds and borders. All the species grow freely in any common soil, and are increased by dividing the roots, or by seeds. The roots of all the species are eatable.

**CAMPION.**—This name is given

to several flowers, with different prefixes, such as the Rose Campion (see LY'CHNIS or AGROSTE'MMA), and the Berry-bearing Campion.—See SILE'NE.

CANARY BIRD FLOWER.—*Tropeolum peregrinum*, or *aduncum*; sometimes also called *T. canariense*, though wrongly, as it is a native of Peru. This plant is generally considered a half-hardy annual, but it is found to grow without any hot-bed, if the seeds are sown as soon as ripe, in pots, and kept in a room during winter. The young plants should be regularly watered, and trained to a stick or frame till spring, when they should be planted out. They will then grow and flower luxuriantly, producing a succession of blossoms till the plants are destroyed by frost.

CANDLEBERRY MYRTLE.—See MYRT'EA.

CANDYTUFT.—See IBIS'IS.

CA'NNA Linn.—*Marantiaceæ*.—Splendid reed-like plants, from the East and West Indies, and South America, of which two species, *C. patens* and *C. speciosa*, are sufficiently hardy to stand the winter at the base of a south wall, where they will flower freely during the summer. The common Indian Shot, *C. indica*, and almost all of the other kinds, require a stove. They are all grown in rich light soil, and are readily increased by dividing the roots, or by seeds. The seeds of the hardy kinds generally require to be steeped in water before they are sown. They should then be raised on a hotbed, and shifted two or three times before they are planted out.

CANTERBURY BELL.—See CAM-PA'NULA.

CA'NTUA W.—*Polemoniaceæ*.—A great confusion has arisen regarding the plants called by this name, some of those called *Cantua* by

Willdenow having been afterwards called *Ipomopsis* and *Gilia* by other botanists. Two species have, however, been lately introduced, which appear decidedly to belong to the genus *Cantua*, viz., *C. bicolor* and *C. pyrifolia*. *C. bicolor*, which has very ornamental scarlet flowers, tinged with yellow in the centre and in the tube of the flower, is the Magic Tree of the Peruvian Indians. In this country it forms a greenhouse shrub of easy cultivation. *C. pyrifolia* has white flowers with bright yellow tubes. It was introduced in 1848.

CAPE BULBS are remarkable for the beauty of their flowers; and as they occupy but little space, a considerable collection of them may be grown in a very small garden, in a great measure without the aid of glass. The situation should be exposed to the south, and protected from the north; and the soil should consist of sand and peat, or sand and leaf-mould, to the depth of two feet, thoroughly drained. In such a bed, all the Cape Iridaceæ may be planted, placing the bulbs not less than six inches below the surface of the ground, and protecting the plants when they come up with a mat; and after they die down, covering the bed with rotten leaves, or litter. No other plants ought to be planted in the bed during the summer, nor any water given to it during winter, lest the bulbs should be rotted. If there is a sufficient length of wall, with no trees planted against it—as, for example, the front wall of a pit or greenhouse—the best mode is to make the bed not more than two or three feet in width; by which means it may be easily and effectually protected by shutters, made to rest on the ground on one edge, and to lean against the wall on the other. When

there is no such wall, a very good mode of affording protection during winter, is to surround the bed with a wooden frame, or a brick or stone wall; and either to cover it with glazed sashes; or with boards, or mats; taking care always to uncover the bed in fine weather.

CAPE JASMINE.—See *GARDENIA*.

CAPE PHILLYREA.—*Cassine capensis* L.—A low, half-hardy shrub, allied to the Holly.

CAPE SHRUBS in their native country grow chiefly in very sandy soil, mixed with vegetable mould, formed by the decay of the same shrubs which it nourishes. The best imitation of such a soil in British gardens is sandy loam, which ought to be well drained, by putting crocks or potsherds in the bottom of the pots, to the depth of an inch or two, and afterwards covering them with turfy peat, to prevent the soil from being washed through the crocks. In the management of Cape Shrubs, the great art is, to keep them always in the same state with regard to moisture; that is, never very wet, and yet never so dry as to cause the plants to droop their leaves. If ever they are allowed to droop their leaves for three or four hours, death is almost the certain consequence; and this is the reason why so many Cape Heaths are killed by those who will not take the trouble to water them regularly. To lessen the risk of destruction by drought, some cultivators have an outer and an inner pot; the object of the former being to lessen the evaporation from the latter. Others mix lumps of freestone with the soil in the pots; and these being powerful absorbers of moisture, retain, as it were, a reserve of water for the plant to have recourse to when it is neglected by the gardener. It may be useful to observe, that when

peat, or a mixture of sand and peat, in a pot where the soil has become matted with roots, is once thoroughly dried, it is extremely difficult to moisten it again properly; and hence, many persons who pour water on the surface of pots containing plants in sandy peat, imagine that it penetrates the ball of earth, and reaches all the roots, while, in fact, it very frequently escapes between the ball and the pot, moistening only the outer surface of the ball, and leaving the great mass of roots in its centre quite dry. Perhaps as many Cape Heaths and Shrubs, and Australian Shrubs, are killed in this way, as Geraniums and bulbs are killed by over-watering. When it is found that the water escapes without penetrating to the centre of the ball of earth, it is advisable to immerse the pot in water till the whole of the ball is thoroughly soaked. See *ERR'CA*.

CA'PPARIS. — *Capparidææ*. — A genus of rambling shrubs, natives of both the East and West Indies, and of South America. One species, *C. spinosa*, the common Caper, grows wild in the south of Europe, and forms in England a greenhouse trailer as well as a most suitable plant for a conservative wall, remarkable in both situations for the beauty of its flowers. It grows in common soil, and is readily propagated by cuttings of the roots. A plant grew for many years in the garden of Camden House, Kensington.

CAPRIFOLIUM. — *Caprifoliææ*. — The Honeysuckle. — Well-known climbing plants, remarkable for the delightful fragrance of their flowers. *C. italicum*, the Italian Honeysuckle; *C. Periclymenum*, the common Woodbine, and its varieties; and *C. sempervirens*, the



Trumpet Honeysuckle, are those most common in collections. The beautiful and very fragrant plant generally called *Lonicera flexuosa*, is sometimes found under the name of *Caprifolium chinense*, or *japonicum*: but the gold and silver Honeysuckle is generally called *C. japonicum*. Both these plants are natives of Japan and China, and they are rather tender in British gardens. They should be grown in a soil composed of sand, peat, and loam, and are propagated by cuttings. The Trumpet and Yellow Honeysuckles, *C. flavum*, should also be grown in sandy peat, and they require a slight protection in severe weather; but all the other kinds may be grown in common soil, without any further care than training them against a wall, or over paling.

CAPSICUM. — *Solanaceæ*. — The pods of the plants belonging to this genus produce the Cayenne Pepper; and some of the species are very ornamental from their bright scarlet colour, and their remaining on all the winter. They are generally tender annuals, requiring the heat of a stove to ripen their fruit; but there is one species, *C. cerasifforme*, sometimes called Cherry Pepper, or Bell Pepper, which does not require any greater heat than that of a greenhouse.

CARAGANA. — *Leguminosæ*. — The principal species contained in the genus Caragana are low trees and large shrubs, with abruptly pinnate leaves, and pea-flowers, which are generally yellow. They are mostly natives of Siberia, and flower early in spring; their light elegant foliage often appearing as early as March. All the species are very ornamental; but the tree kinds are more so than the others. *C. jubata*, which differs from the

rest in having white flowers tinged with red, is a low shrub, not above eighteen inches high, presenting a curious shaggy appearance from the footstalks of the leaves remaining on, and becoming hard and thorny, after the leaflets have dropped off. *C. Chamlagu*, the Chinese Caragana, which is naturally a low shrub, forms a very graceful pendulous tree, when grafted on a stock of *C. arborescens*, ten or twelve feet high. All the Caraganas were formerly considered to belong to the genus Robinia. They are all quite hardy, and will grow in any common garden-soil; most of the species prefer a poor gravel; but *C. arborescens* thrives best in the neighbourhood of water. The species are propagated by layers or cuttings, or by seeds, which they ripen in abundance.

CARDA'MINE. — *Cruciferae*. — Low herbaceous plants, natives of Europe, and of which *C. pratensis*, the common Cuckoo-flower, or Lady's Smock, especially the double flowering variety, and one or two other species, deserve a place in the flower-garden. *C. trifolia* is valuable for its early flowering, and, with several other species, is well adapted for pots or rockwork. The soil should be kept moist.

CARDINAL-FLOWER. — The Scarlet Lobelia. — See LOBELIA.

CARDUUS. — *Compositæ*. — The Thistle. — Some of the species are very ornamental; though they are many of them tall robust-growing plants, which require a great deal of room, and are too large for a small garden.

CAREX. — *Cyperaceæ*. — The Sedges are well-known British and American plants, of which only one species, *C. Fraseriana* Ait., a native of America, deserves a place in the flower-garden. It grows about half

a foot in height, has broader leaves than the common Sedges, and produces its large white flowers, which look like little Lilies, from April to June. It requires a moist loamy soil, or to be grown in a pot, and kept in a pan of water.

CARNATION.—See DIA'NTHUS.

CAROB TREE.—See CERATO'NIA.

CAR'ETHAMUS. — *Compositæ*. — Hardy annuals. *C. tinctorius*, the Bastard Saffron, is an old inhabitant of British gardens, and it only requires sowing in the open air in March or April. From the dried flowers of this plant is made what is called vegetable rouge. *C. lanatus* L., the Distaff Thistle, is called *Kentrophylum lanatum* by De Candolle.

CASSIA. — *Leguminosæ*. — The Senna Tree.—Only a few of the species are from temperate climates; and among these, *C. corymbosa* Lam., is a very showy greenhouse shrub, with yellow flowers; and *C. marilandica*, from Maryland, is a perennial herbaceous plant of easy culture in the open garden. All the ligneous species are readily propagated by cuttings, and the others by seeds or division of the roots.

CASTILLE'JA. — *Scrophulariæcæ*. —The American Painted Cup, *C. coccinea* Sprengel, *Bartsia* L., *Euchroma* Nut., is a hardy annual, with yellow flowers and scarlet bracts, which only require sowing in March or April in the open ground.

CATAL'PA. — *Bignoniæcæ*. —Deciduous trees, one of which, *C. syriacaefolia* Bot. Mag., is quite hardy in British shrubberies, in which it richly deserves a place on account of its fine leaves and splendid flowers. It will grow in any common soil that is tolerably dry; but if it has too much moisture, the shoots which

are naturally soft, with a large pith, will never be thoroughly ripened, and the tree will very probably be killed by the first frost. For the same reason, the situation ought to be airy. It is propagated by seeds, or by cuttings of the roots.

CATANAN'CHE. — *Compositæ*. — Herbaceous plants, natives of the South of Europe. *C. cærulea* is a perennial; *C. bicolor* is a biennial; and *C. lutea*, an annual. All the species have pretty flowers, but are rather awkward-looking plants, from their long and very slender flower-stalks. They are of easy culture, but grow best in poor gravelly soil.

CATCHFLY.—See SILE'NE.

CATERPILLARS. — The larvæ of moths and butterflies, are very destructive to vegetation. Many gardeners keep their gardens clear by destroying the female butterflies and moths before they have laid their eggs (see BUTTERFLIES and MOTH); and others, by carefully searching for the eggs early in spring, when the trees are without leaves. When these preventive measures have been neglected, the only effectual way to prevent the ravages of caterpillars is to pick them off the trees separately. The visits of caterpillars are very uncertain, and some seasons they are much more abundant than in others. Sometimes the caterpillars of the Magpie Moth will entirely strip the gooseberry bushes of their leaves, and the fruit will in consequence become tough and insipid; and in other seasons, the caterpillars of the Lackey Moth, the Hawthorn Butterfly, and the Ermine Moth, will strip the Hawthorn and other shrubs. In all these cases hand-picking should be resorted to as soon as the insects are perceived. Many persons recommend fumigating with tobacco-smoke, or by burn-

ing wet straw under the tree; and others, washing with tobacco or lime water; but most of the remedies are worse than the disease.

CATMINT.—See NE'PETA.

CATTLE'YA.—*Orchidaceæ*.—Orchideous plants, with large and splendid flowers, natives of South America. They may be grown either in pots, in peat mixed with crocks and sphagnum, or on pieces of wood or cocoa husks hung up in a hot-house, the roots being wrapped in wet moss. All the species of Cattle'ya are easily propagated by dividing their roots; and they are particularly valuable, as they will thrive in a common hothouse if well supplied with water, without requiring the excessive heat and moisture generally necessary for the tropical Orchideæ.

CEANO'THUS.—*Rhamnaceæ*.—Red Root.—American hardy and half-hardy shrubs, with large spikes of very small flowers. The most ornamental species of the genus is *C. azureus*, which is only half-hardy in the climate of London, requiring protection from severe frosts. *Ceanothus pallidus* is much hardier than *C. azureus*, and strongly resembles that species; but its leaves are not hoary beneath, and its flowers, Dr. Lindley tells us in the *Bot. Reg.*, "are smaller, as well as much paler." He adds, that it is often confused with *C. ovatus*, which "is a mere variety of *C. americanus*," and *C. thyrsiflorus*, which "is a Californian tree, with deep-blue flowers, and very strong angular branches." *C. americanus* is the least ornamental of all the kinds; and *C. colinus* is a dwarf plant, not above two feet high, with a profusion of white flowers. The last two are quite hardy, but the other kinds should be trained against a south wall, and protected from severe frosts

by a thatched coping. *C. dentatus* is a very ornamental half-hardy shrub. Three new species were introduced in 1854, one of which, *C. floribundus* from California, is very splendid. They should all be grown in a compost consisting of three-fourths of heath-mould, or a mixture of sand and peat, with one of loam, and the soil should be well drained.

CEDAR OF GOA.—*Cupressus lusitanica* Tou.; *C. glauca* Lam.—A very ornamental half-hardy tree, which in a sheltered situation has a beautiful effect on a lawn, from its drooping branches and glaucous foliage. It requires a light soil, and to be occasionally watered, as its roots are very apt to wither if suffered to become too dry.

CELANDINE.—There are two plants bearing this name: the common (see CHELIDONIUM), and the lesser (see FIGARIA).

CELA'STRUS L.—*Celastraceæ*.—The Staff-tree.—Half-hardy shrubs, mostly natives of the Cape, with white flowers. For culture, see CEANO'THUS.

CELOSIA.—*Amaranthaceæ*.—Tender annuals, with showy flowers. The common Cock's-comb, *C. cristata*, may be grown to a very large size by raising the plants on a hot-bed and frequently shifting them into larger and larger pots, as directed for the Balsam (see BALSAMINA). Another mode is to put the plants when quite small into pots about four inches across and three inches deep, into a compost of fresh horse-dung, turf in lumps of at least an inch in diameter, and decayed leaves. As soon as the roots reach the sides of the pot, the plants are to be removed to pots a foot in diameter and nine inches deep, filled with the same compost. Plants treated according to this

method, which was that of the late Mr. Knight, are a long time before they show any disposition to flower; but when they do, if they are placed near the glass, and kept in the same heat as Pine-apples, they grow to an enormous size.

CELSIA. — *Solanaceæ* or *Verbas-cineæ*. Half-hardy annuals and biennials, with showy yellow flowers, and nearly allied to the genus *Verbascum*. They are generally raised on a hotbed, and the biennials are kept in the greenhouse during winter, as they are killed by a slight frost. *C. lineàris* and *C. urticafolia*, which have scarlet flowers, are now included in the genus *Alonsoa*. — See ALONSOA.

CENTAUREA. — *Compositæ*. — The common perennial species are known by the English name of Knapweed; and the only quite hardy annual one, *C. Cyanus*, by the name of Corn Bluebottle: the most beautiful species, *C. Crocodygium* L., is a half-hardy annual, which should be raised on a hotbed and planted out in May. *C. benedicta* L., *Onicus benedictus* Dec., the Blessed Thistle, is a hardy annual, which may be sown in March or April, and will flower all the summer; and *C. suaveolens* and *C. moschata* L., the yellow and purple Sweet Sultans, have been formed into the genus *Amberboa* by Professor de Candolle.

CENTAURY. — A British plant with clusters of small pink flowers, growing in chalky soils, the botanical name of which is *Erythræa Centaurium*.

CEPHEALIS. — *Rubiaceæ*. — See IPOCAOUA'NHA. — This plant is interesting from its producing the medicine called Ipecacuanha; though it has been long known in medicine, and large quantities of it have been imported every year from Brazil, it has only lately been introduced into

England, having flowered for the first time in this country in the stove at Kew, in January, 1843. The word *Ipecacuanha* is derived from "*Ipe* (bark), *caa* (plant), *cua* (scented), and *nha* (striped); thus forming the words '*bark of a scented and striped plant*.'"

CÉRASUS. — *Rosaceæ*. — The Cherry. — Hardy trees and shrubs, for the most part deciduous, and all more or less ornamental on account of their flowers. The common double Cherry, and the French double Cherry, deserve a place in every garden; and equally so do the Chinese Cherry, *C. pseudo-cérasus*; the All-Saint's Cherry, *C. semperflorens*; the Bird Cherry, *C. Pádus*; the Virginian Bird Cherry, *C. virginiana*; the Mahaleb Plum or Cherry, *C. Mahaleb*; and the Japan Cherry, *C. japonica*, known in the nurseries as the double Dwarf Almond. Many of the plants here enumerated are known at some of the nurseries by the name of Prúnus: as *P. Mahaleb*, *P. Pádus*, &c.; but in others they are called *Cerasus*. It is necessary to know this to avoid buying the same plant under different names. All the species grow in common soil, and are propagated by grafting or seeds. The common Laurel, *Cerasus Lauro-cérasus*, and the Portugal Laurel, *Cerasus lusitânica*, which also belong to this genus, have showy spikes of flowers, and deserve culture on that account, independently of their shining evergreen leaves.

CERATONIA. — *Leguminosæ*. — An evergreen greenhouse shrub, a native of the South of Europe and Asia. The pod is fleshy, like that of the Tamarind, and it is said to have been the food St. John fed on in the Wilderness, the seeds being called "locusts," and the pulp

"wild honey." Hence the popular name of St. John's Bread. It is also called the Carob-tree. The tree is of very slow growth, and the flowers have no beauty; but the plant is worth cultivation for its dark-green leathery leaves. In Spain and Italy it is cultivated for feeding horses. It should be grown in a mixture of equal parts of loam and peat, well-drained and frequently watered; and it is propagated by cuttings of the old wood struck in sand. The wood is very hard, and is said to be almost incorruptible.

**CERATOSTEMA.**—*Vacciniaceæ*.—A showy plant with large, tubular, scarlet flowers; a native of the Andes of Peru, at a height of twelve thousand feet above the level of the sea, and consequently very nearly hardy. It was introduced in 1854.

**CERCIS.**—*Leguminosæ*.—The Judas-tree.—Few trees are more ornamental in a shrubbery than the two species of this genus: but *Cercis siliquastrum*, the common kind, is decidedly the handsomest. The leaves are curiously shaped, and the flowers, which are of a beautiful pink, grow out of the bark of the stem and branches, and not like those of other plants, among the leaves; these flowers have an agreeably acid taste, and when fried in batter make excellent fritter. The common Judas-tree is a native of the Levant, and it is frequently grown against a wall, producing its flowers in April; but the American kind, *C. canadensis*, is quite hardy. They both produce abundance of seeds, and grow best in a deep sandy loam, rather rich than poor.

**CEREUS.**—*Cactaceæ*.—The Torch Thistle.—One of the genera into which the Linnæan genus *Cactus* is now divided. This genus was first

formed by Mr. Haworth, who made it consist only of all the *Cacti* that had long angular or round stems; but modern botanists include in it those of the short round stemmed porcupine *Cacti*, that have long tube-shaped flowers. Of the true kinds of *Cereus*, which are still generally the only ones known by that name in most private collections and nurseries, the best known are *C. speciosissimus*, the crimson-flowered Torch Thistle, and its hybrids and varieties, the stems of which are erect and angular, and the flowers dark crimson; *C. flagelliformis*, the Creeping *Cereus*, the long round stems of which hang down like cords, and the flowers of which are pink; and *C. grandiflorus*, the Night-blowing *Cereus*, the flowers of which are white and yellow. A new kind of Night-blowing *Cereus* has been lately introduced, called Mrs. Macdonald's, with flowers 14 inches in diameter. One of the handsomest species of the genus is, however, *C. crenatus* Lindl., which flowered for the first time in England in 1843. The plant resembles *C. speciosissimus*, but the flowers are like those of the Night-blowing *Cereus*; they have the advantage, however, of opening in the daytime, and remaining expanded a week or more. The Old Man's Head, or Monkey Cactus, *Cereus senilis*, which is covered with long white hairs, is more curious than ornamental; but it well deserves a place in every collection from its singular appearance, which is, however, most striking when the plants are small. All the kinds of *Cereus* only require greenhouse heat; they should all be grown in loam mixed with pounded brick and lime-rubbish, in pots well drained with cinders; and they all require abundance of air and light. It is best to give them a season of

method, which was that of the late Mr. Knight, are a long time before they show any disposition to flower; but when they do, if they are placed near the glass, and kept in the same heat as Pine-apples, they grow to an enormous size.

**CELSIA.**—*Solanaceæ* or *Verbas-cineæ*. Half-hardy annuals and biennials, with showy yellow flowers, and nearly allied to the genus *Verbascum*. They are generally raised on a hotbed, and the biennials are kept in the greenhouse during winter, as they are killed by a slight frost. *C. linedris* and *C. urticafolia*, which have scarlet flowers, are now included in the genus *Alonsoa*.—See ALONSOA.

**CENTAUREA.**—*Compositæ*.—The common perennial species are known by the English name of Knapweed; and the only quite hardy annual one, *C. Cyanus*, by the name of Corn Bluebottle: the most beautiful species, *C. Crocodylium* L., is a half-hardy annual, which should be raised on a hotbed and planted out in May. *C. benedicta* L., *Oniscus benedictus* Dec., the Blessed Thistle, is a hardy annual, which may be sown in March or April, and will flower all the summer; and *C. suaveolens* and *C. moschata* L., the yellow and purple Sweet Sultans, have been formed into the genus *Amberboda* by Professor de Candolle.

**CENTAURY.**—A British plant with clusters of small pink flowers, growing in chalky soils, the botanical name of which is *Erythræa Centaúrium*.

**CERFÆE'LIS.**—*Rubiaceæ*.—See **IPECACUA'NHA**.—This plant is interesting from its producing the medicine called *Ipecacuanha*; though it has been long known in medicine, and large quantities of it have been imported every year from Brazil, it has only lately been introduced into

England, having flowered for the first time in this country in the stove at Kew, in January, 1843. The word *Ipecacuanha* is derived from "*Ipe* (bark), *caa* (plant), *cua* (scented), and *nha* (striped); thus forming the words 'bark of a scented and striped plant.'"

**CÉRASUS.**—*Rosaceæ*.—The Cherry.—Hardy trees and shrubs, for the most part deciduous, and all more or less ornamental on account of their flowers. The common double Cherry, and the French double Cherry, deserve a place in every garden; and equally so do the Chinese Cherry, *C. pseudo-cerasus*; the All-Saint's Cherry, *C. semperflorens*; the Bird Cherry, *C. Padus*; the Virginian Bird Cherry, *C. virginiana*; the Mahaleb Plum or Cherry, *C. Mahaleb*; and the Japan Cherry, *C. japonica*, known in the nurseries as the double Dwarf Almond. Many of the plants here enumerated are known at some of the nurseries by the name of *Prunus*: as *P. Mahaleb*, *P. Padus*, &c.; but in others they are called *Cerasus*. It is necessary to know this to avoid buying the same plant under different names. All the species grow in common soil, and are propagated by grafting or seeds. The common Laurel, *Cerasus Lauro-cerasus*, and the Portugal Laurel, *Cerasus lusitánica*, which also belong to this genus, have showy spikes of flowers, and deserve culture on that account, independently of their shining evergreen leaves.

**CERATO'NIA.**—*Leguminosæ*.—An evergreen greenhouse shrub, a native of the South of Europe and Asia. The pod is fleshy, like that of the Tamarind, and it is said to have been the food St. John fed on in the Wilderness, the seeds being called "locusts," and the pulp

"wild honey." Hence the popular name of St. John's Bread. It is also called the Carob-tree. The tree is of very slow growth, and the flowers have no beauty; but the plant is worth cultivation for its dark-green leathery leaves. In Spain and Italy it is cultivated for feeding horses. It should be grown in a mixture of equal parts of loam and peat, well-drained and frequently watered; and it is propagated by cuttings of the old wood struck in sand. The wood is very hard, and is said to be almost incorruptible.

**CERATOSTEMA.**—*Vacciniaceae*.—A showy plant with large, tubular, scarlet flowers; a native of the Andes of Peru, at a height of twelve thousand feet above the level of the sea, and consequently very nearly hardy. It was introduced in 1854.

**CEREUS.**—*Leguminosae*.—The Judas-tree.—Few trees are more ornamental in a shrubbery than the two species of this genus: but *Cercis siliquastrum*, the common kind, is decidedly the handsomest. The leaves are curiously shaped, and the flowers, which are of a beautiful pink, grow out of the bark of the stem and branches, and not like those of other plants, among the leaves; these flowers have an agreeably acid taste, and when fried in batter make excellent fritter. The common Judas-tree is a native of the Levant, and it is frequently grown against a wall, producing its flowers in April; but the American kind, *C. canadensis*, is quite hardy. They both produce abundance of seeds, and grow best in a deep sandy loam, rather rich than poor.

**CEREUS.**—*Cactaceae*.—The Torch Thistle.—One of the genera into which the Linnean genus *Cactus* is now divided. This genus was first

formed by Mr. Haworth, who made it consist only of all the *Cacti* that had long angular or round stems; but modern botanists include in it those of the short round stemmed porcupine *Cacti*, that have long tube-shaped flowers. Of the true kinds of *Cereus*, which are still generally the only ones known by that name in most private collections and nurseries, the best known are *C. speciosissimus*, the crimson-flowered Torch Thistle, and its hybrids and varieties, the stems of which are erect and angular, and the flowers dark crimson; *C. flagelliformis*, the Creeping *Cereus*, the long round stems of which hang down like cords, and the flowers of which are pink; and *C. grandiflorus*, the Night-blowing *Cereus*, the flowers of which are white and yellow. A new kind of Night-blowing *Cereus* has been lately introduced, called Mrs. Macdonald's, with flowers 14 inches in diameter. One of the handsomest species of the genus is, however, *C. crenatus* Lindl., which flowered for the first time in England in 1843. The plant resembles *C. speciosissimus*, but the flowers are like those of the Night-blowing *Cereus*; they have the advantage, however, of opening in the daytime, and remaining expanded a week or more. The Old Man's Head, or Monkey Cactus, *Cereus senilis*, which is covered with long white hairs, is more curious than ornamental; but it well deserves a place in every collection from its singular appearance, which is, however, most striking when the plants are small. All the kinds of *Cereus* only require greenhouse heat; they should all be grown in loam mixed with pounded brick and lime-rubbish, in pots well drained with cinders; and they all require abundance of air and light. It is best to give them a season of

method, which was that of the late Mr. Knight, are a long time before they show any disposition to flower; but when they do, if they are placed near the glass, and kept in the same heat as Pine-apples, they grow to an enormous size.

**CELSIA.**—*Solanaceæ* or *Verbas-cineæ*. Half-hardy annuals and biennials, with showy yellow flowers, and nearly allied to the genus *Verbascum*. They are generally raised on a hotbed, and the biennials are kept in the greenhouse during winter, as they are killed by a slight frost. *C. linearis* and *C. verticillata*, which have scarlet flowers, are now included in the genus *Alonsoa*.—See ALONSOA.

**CENTAUREA.**—*Compositæ*.—The common perennial species are known by the English name of Knapweed; and the only quite hardy annual one, *C. Cyanus*, by the name of Corn Bluebottle: the most beautiful species, *C. Crocodilum* L., is a half-hardy annual, which should be raised on a hotbed and planted out in May. *C. benedicta* L., *Cnicus benedictus* Dec., the Blessed Thistle, is a hardy annual, which may be sown in March or April, and will flower all the summer; and *C. suaveolens* and *C. moschata* L., the yellow and purple Sweet Sultans, have been formed into the genus *Amberboa* by Professor de Candolle.

**CENTAURY.**—A British plant with clusters of small pink flowers, growing in chalky soils, the botanical name of which is *Erythræa Centaureum*.

**CERPHALIS.**—*Rubiaceæ*.—See **IPECACUANHA**.—This plant is interesting from its producing the medicine called *Ipecacuanha*; though it has been long known in medicine, and large quantities of it have been imported every year from Brazil, it has only lately been introduced into

England, having flowered for the first time in this country in the stove at Kew, in January, 1843. The word *Ipecacuanha* is derived from "*Ipe* (bark), *caa* (plant), *cua* (scented), and *nha* (striped); thus forming the words '*bark of a scented and striped plant*.'"

**CERASUS.**—*Rosaceæ*.—The Cherry.—Hardy trees and shrubs, for the most part deciduous, and all more or less ornamental on account of their flowers. The common double Cherry, and the French double Cherry, deserve a place in every garden; and equally so do the Chinese Cherry, *C. pseudo-cerasus*; the All-Saint's Cherry, *C. semperflorens*; the Bird Cherry, *C. Padus*; the Virginian Bird Cherry, *C. virginiana*; the Mahaleb Plum or Cherry, *C. Mahaleb*; and the Japan Cherry, *C. japonica*, known in the nurseries as the double Dwarf Almond. Many of the plants here enumerated are known at some of the nurseries by the name of *Prunus*: as *P. Mahaleb*, *P. Padus*, &c.; but in others they are called *Cerasus*. It is necessary to know this to avoid buying the same plant under different names. All the species grow in common soil, and are propagated by grafting or seeds. The common Laurel, *Cerasus Lauro-cerasus*, and the Portugal Laurel, *Cerasus lusitânica*, which also belong to this genus, have showy spikes of flowers, and deserve culture on that account, independently of their shining evergreen leaves.

**CERATONIA.**—*Leguminosæ*.—An evergreen greenhouse shrub, a native of the South of Europe and Asia. The pod is fleshy, like that of the Tamarind, and it is said to have been the food St. John fed on in the Wilderness, the seeds being called "*locusts*," and the pulp



"wild honey." Hence the popular name of St. John's Bread. It is also called the Carob-tree. The tree is of very slow growth, and the flowers have no beauty; but the plant is worth cultivation for its dark-green leathery leaves. In Spain and Italy it is cultivated for feeding horses. It should be grown in a mixture of equal parts of loam and peat, well-drained and frequently watered; and it is propagated by cuttings of the old wood struck in sand. The wood is very hard, and is said to be almost incorruptible.

**CERATOSTEMA.**—*Vacciniaceæ*.—A showy plant with large, tubular, scarlet flowers; a native of the Andes of Peru, at a height of twelve thousand feet above the level of the sea, and consequently very nearly hardy. It was introduced in 1854.

**CERBIS.**—*Leguminosæ*.—The Judas-tree.—Few trees are more ornamental in a shrubbery than the two species of this genus: but *Cercis siliquastrum*, the common kind, is decidedly the handsomest. The leaves are curiously shaped, and the flowers, which are of a beautiful pink, grow out of the bark of the stem and branches, and not like those of other plants, among the leaves; these flowers have an agreeably acid taste, and when fried in batter make excellent fritter. The common Judas-tree is a native of the Levant, and it is frequently grown against a wall, producing its flowers in April; but the American kind, *C. canadensis*, is quite hardy. They both produce abundance of seeds, and grow best in a deep sandy loam, rather rich than poor.

**CEREUS.**—*Cactaceæ*.—The Torch Thistle.—One of the genera into which the Linnæan genus *Cactus* is now divided. This genus was first

formed by Mr. Haworth, who made it consist only of all the *Cacti* that had long angular or round stems; but modern botanists include in it those of the short round stemmed porcupine *Cacti*, that have long tube-shaped flowers. Of the true kinds of *Cereus*, which are still generally the only ones known by that name in most private collections and nurseries, the best known are *C. speciosissimus*, the crimson-flowered Torch Thistle, and its hybrids and varieties, the stems of which are erect and angular, and the flowers dark crimson; *C. flagelliformis*, the Creeping *Cereus*, the long round stems of which hang down like cords, and the flowers of which are pink; and *C. grandiflorus*, the Night-blowing *Cereus*, the flowers of which are white and yellow. A new kind of Night-blowing *Cereus* has been lately introduced, called Mrs. Macdonald's, with flowers 14 inches in diameter. One of the handsomest species of the genus is, however, *C. crenatus* Lindl., which flowered for the first time in England in 1843. The plant resembles *C. speciosissimus*, but the flowers are like those of the Night-blowing *Cereus*; they have the advantage, however, of opening in the daytime, and remaining expanded a week or more. The Old Man's Head, or Monkey Cactus, *Cereus senilis*, which is covered with long white hairs, is more curious than ornamental; but it well deserves a place in every collection from its singular appearance, which is, however, most striking when the plants are small. All the kinds of *Cereus* only require greenhouse heat; they should all be grown in loam mixed with pounded brick and lime-rubbish, in pots well drained with cinders; and they all require abundance of air and light. It is best to give them a season of

rest when they have done flowering; and this is done by removing them to a colder house and withholding water. If, however, they are continued in the same house in which they were flowered, the supply of water should be lessened, but not stopped entirely. In other respects their culture resembles that of the other Cacti.—See CA'CTUS.

CE'STRUM.—*Solanaceæ*.—A genus of stove and greenhouse plants, most of which have ornamental flowers and poisonous berries. Some of the species are fragrant, but others have a very disagreeable smell. The most ornamental kind is *C. aurantiacum*, a native of Guatemala, which was introduced in 1846. It is a greenhouse plant, with bright orange flowers, which in winter are succeeded by white pear-shaped berries, which continue to hang on after the leaves have fallen.

CHALK.—Carbonate of Lime.—See KARTHS.

CHAMBU'XUS.—A kind of Polygala.

CHAMÉDO'REA.—*Palmaceæ*.—A very curious genus of Dwarf Palms, none of them exceeding the height of a man. They are natives of tropical America, and look more like reeds than palms. It is said, that there are forty-two species in the genus; and four or five of them are in the Royal Gardens at Kew.

CHAMÉMOLLY.—A species of Alilium.

CHARCOAL.—Powdered charcoal, sifted so as to have the particles not larger than those of sand, has been used in Germany for striking cuttings in; and was thought to be superior to sand from its supplying them with nourishment after they are rooted, by attracting oxygen from the atmosphere, and thus forming carbonic acid gas round the roots, but notwithstanding this, sand

continues to be almost exclusively employed for striking cuttings. Charcoal in larger pieces is also occasionally mixed with the soil in pots and tubs, and is found in many cases to produce rapid and vigorous growth.

CHARD'NIA.—The new name for *Xeranthemum orientale*.

CHEIRA'NTHUS.—*Cruciferae*.—The Wall-flower.—Well-known herbaceous plants, which are much prized for the delightful odour of their flowers, which are produced from April to July. *C. Cheiri*, the common Wall-flower, and its varieties, both double and single, are in general cultivation, growing in any common soil; and the varieties are readily increased by cuttings. The best varieties are the double-blood, the double-striped, the double-yellow or Polish, and the double-purple, all of which may be obtained from the nurserymen. There is also a kind with very dark flowers and striped leaves; and a single pale purple, called the French Wall-flower. *C. alpinus* is a pretty hardy little plant, with yellow flowers, well suited for growing in pots, or on rock-work. *C. mutabilis* is a curious species from Madeira, requiring the greenhouse, and flowering from December to May.

CHELIDONIUM.—*Papaveraceæ*.—The common Celandine, or Swallow-wort (*C. majus*), is a hardy perennial, with yellow flowers, common on the sea-coast, and in churchyards, in many parts of England. It grows in any common soil, and is readily increased by division of the roots, or by seeds, which it produces in abundance.

CHELO'NE.—*Scrophularinæ*.—Handsome herbaceous plants, natives of North America, most of which are, however, now included in the genus *Pentstemon*. The four

still called Chelone, are *C. glabra*, *C. obliqua*, *C. Lyôni* (*C. major*, Bot. Mag.), and *C. nemorosa*. All the species grow freely in light, rich soil, and are readily increased by cuttings, suckers, or seeds, which, in favourable seasons, are produced in abundance.

**CHERMES.**—*Kermes*.—A scale-like insect that raises a kind of gall-apple on a species of Oak (*Quercus coccifera*), and which produces a brilliant scarlet dye. The true Chermes is a kind of Coccus; but the name was applied by Linnaeus to a genus of leaping insects known by the popular name of false Aphides, because the larvæ resemble those insects; though, in their perfect state, they have red bodies, and long snow-white wings. The insects, which are now called Psylla, are generally found on plants of the genus *Pyrus*; and they may be known to have attacked a tree by the curling up of its leaves, and withering of its branches. They frequently attack the *Pyrus* or *Cydonia japonica*, and the snowy Mespilus, which they destroy by sucking the sap out of the young shoots. The best way of getting rid of them is to wash and brush the branches with soft soap and water in winter and spring.—See A'PHIS.

**CHERRY.**—See CERASUS.

**CHERRY-BAY and CHERRY-LAUREL.**—Old English names for the common Laurel.

**CHIMONANTHUS.**—*Calycanthaceæ*.—*C. fragrans*, the Winter-flower (*Calycanthus præcox*), and its varieties, are well deserving a place against a conservative wall, or in the conservatory; for though hardy enough to stand our winters in the open air, yet from their very fragrant flowers being produced in December, January, and February, they are liable to be injured by

the frost. *C. grandiflorus*, trained against a south wall, produces its yellow flowers in great abundance, and forms a beautiful object when but few flowers can be seen out of doors. Its flowers have also a delightful fragrance. They thrive in almost any soil, but prefer a mixture of loam and peat. They are readily increased by layers.

**CHINA ASTER.**—The China Aster, which some botanists now call by this name, is one of the most ornamental annuals in British gardens. There are many varieties, and those known as the German Asters are considered the most beautiful. They should be raised on a hotbed in February or March, pricked out when the plants have two or three leaves, and transplanted into the open garden in May, where they will make a very fine appearance in September and October. They should be grown in light rich soil, or in loam, or in thoroughly rotten dung.

**CHINA ROSE.**—See RO'SA.

**CHINA TREE.**—The Oriental Plane.

**CHINQUAPIN.**—Dwarf Chestnut.

**CHIONANTHUS.**—*Oleaceæ*.—*C. virginica*, the Fringe-tree, is a large shrub, well deserving a place in all peat borders, both for the beauty of its white fringe-like flowers, and for its leaves, which are often as large as those of *Magnolia grandiflora*, and die off of a fine rich yellow. It is readily increased by layers or seeds, and it may also be grafted or budded standard high on the common Ash, when it will form a fine object for a lawn, or for the centre of a flower-bed.

**CHIRITA.**—*Cyrtandræacæ*.—Very handsome plants, bearing considerable resemblance to the Gloxinias, and flowering nearly all the summer. They may be propa-

gated by cuttings of the leaves, as any portion of a leaf will emit leaves and roots if planted in moist sand, and kept in a warm, humid atmosphere. The plants flower best in a stove; but *C. sinensis*, which is, perhaps, the most beautiful species, will thrive in a warm green-house.

**CHIRO'NIA.** — *Gentianaceæ*. — Greenhouse plants of short duration, and consequently requiring to be frequently raised from cuttings, which strike freely in peat under a hand-glass. *C. frutescens*, with rose-coloured flowers, and its variety, with white flowers, are the most desirable kinds, and may be easily procured from the nurseries. They are also frequently raised from Cape seeds, the plants being all indigenous at the Cape of Good Hope.

**CHORO'ZEMA.** — *Legumindæ*. — Beautiful New Holland shrubs, thriving well in an equal mixture of loam, sand, and peat. They are readily increased by cuttings in sand under a bell-glass, or by seeds, which are frequently ripened in abundance. All the species are worth cultivating; and they are interesting not only for their beauty, but on account of the story told as to the origin of their name. It is said that Labillardière had been wandering in New South Wales for several days in great distress for water, all the springs he found being too brackish to drink; when, at last, he and his companions found a fresh-water spring, near which grew some of these plants, which Labillardière named Choroze-ma, from two Greek words, signifying to dance with joy from drinking.

**CHRISTMAS ROSE.**—See **HELLE'BORUS**.

**CHRIST'S THORN.**—See **PALIU'RUS**.

**CHRYSA'NTHEMUM.** — *Compositæ*.

—The Chinese chrysanthemum and its varieties are well known, and have, for many years, attracted the attention of the cultivator, on account of the great variety of their showy flowers, which are produced from October to December. They grow freely in any light rich soil, and are readily increased by suckers, division of the roots, layers, and cuttings, which flower the same year they are struck. Division of the roots is best made in March; layers by pegging down the shoots in August and covering with light soil, but leaving 6 inches of the top of the shoot above ground; when sufficiently rooted, they should be separated from the parent plant and put in 6-inch pots, where they will form compact plants for the greenhouse. Cuttings may be taken off at any time: at an early period for the plants intended for early flowering, and as late as July or August for a late succession of bloom. The cuttings may be struck in a mixture of sandy loam and leaf mould, on a moderate hotbed, generally in March or early in April, and in order to obtain shoots for the purpose the old plants should be put in gentle heat, and their shoots should be taken off for cuttings when they have made four or five leaves, and put in small pots; when these are filled with roots, the young plants should be shifted into larger pots, to remain till the weather permits of their being planted out in the open ground. In a fortnight or three weeks after planting out, the extremity of the shoot ought to be pinched off, in order to make it ramify; and when the branches have pushed three or four inches they should likewise be pinched; and this operation may be repeated, but not later than the end of July, otherwise the flowering might be

prevented. Plants intended to be retained and flowered in pots should be shifted on as is found necessary, and finally into their blooming pots about the middle of July, and these pots should be well drained. The plants should be well attended to as regards watering at the root during their season of growing, and they should also be frequently syringed. Manure-water should also be given occasionally. Left to their natural growth the plants would exhibit an unsightly, naked stem to nearly their tops; but by frequent pinching and careful training this is avoided, and the plant, made to assume any desirable form, flat, conical, or hemispherical, will be everywhere covered with flowers. The varieties are exceedingly numerous. The large-flowered have been obtained from the *C. sinense*, a native of China, and the Chusan daisy sent home by Mr. Fortune has given rise to the dwarf small-flowering varieties called Pompones. The best annual Chrysanthemums are *C. coronarium*, *C. carinatum* and its varieties, *venustum*, or *tricolor*, and *Burridgeanum*. These are all very showy, and easily raised from seeds, which should be sown in the open ground in April. The varieties are continually changing; new ones being raised every year; but nearly all the kinds may be classed in one or other of the following seven divisions:—the Ranunculus-flowered, the Incurved, the China Aster-flowered, the Marigold-flowered, the Clustered, the Tasseled, and the Quilled.

**CHRYSE'IS.**—Another name for *ESCHSCHÖLTZIA*.

**CHRYSO'OMA.**—*Compositæ*.—Golden-locks. — Low soft-wooded shrubs from the Cape, with yellow flowers. They thrive well in a mixture of loam and peat, and are

readily increased by cuttings. The herbaceous plants which were formerly included in this genus are now removed to the genera *Linosyris*, *Euthamia*, and *Bigelovia*. These are all natives of North America, and all hardy perennials, which will grow in any common soil, and are speedily propagated by division of the roots.

**CHRYSO'PLENIUM.**—*Saxifragaceæ*.—Golden Saxifrage.—Herbaceous plants, with yellow flowers, natives of Britain, North America, and Nepal, not growing more than 4 or 5 inches high. They are rather difficult to cultivate, but succeed best in a moist shady situation, near a rivulet, or at the foot of rockwork, or in a grotto. They should be grown in a mixture of loam and peat, and are propagated by division of the roots.

**CHYMOCA'RPUS.**—*Tropæolaceæ*.—*C. pentaphyllus* is Prof. Don's name for *Tropæolum pentaphyllum*. The general appearance of the plant resembles that of *Tropæolum tricolorum*; but, when examined closely, the flowers will be found to differ in their construction, and in the number of the little inner petals, which are five in *Tropæolum*, and only two in *Chymocarpus*. The root of the first also somewhat resembles a potato, and that of the last a carrot. *Chymocarpus pentaphyllus* is a beautiful climbing plant from Buenos Ayres, growing freely in sandy peat and loam, in the open air, if planted against a south wall; but generally kept in a greenhouse. It grows very rapidly, and produces a profusion of red and green flowers during the whole summer, which, should the autumn be favourable, are succeeded by a number of black juicy berries, which, in flavour and appearance, are not unlike the Zante grape. It grows freely from seeds,

if sown in a gentle heat immediately they are ripe, and may be increased by cuttings, or division of the roots. When it is grown in a pot, care must be taken not to over-water it, when the stems have died down in the autumn. When trained over a wire frame, it makes a splendid show when in flower or fruit.

CINCHO'NA.—Peruvian Bark.

CINERARIA.—*Compōsitæ*.—The Cape Aster. Many species have been transferred from this genus to Senecio. Some of the Cinerarias are stove or greenhouse shrubs, but all are included amongst those called soft-wooded plants; others are herbaceous, or annual. From *C. cruenta* have been derived the Cinerarias of the florists, consisting of endless varieties, arising every year from seeds, of various shades of colour—purple, rose, carmine, violet, azure-blue, lilac, and white—and uniformly of one colour or bicoloured. They afford a brilliant display in the greenhouse, or in apartments, during winter and spring. They are easily propagated by seeds or offsets. The seeds are best sown as soon as ripe, in pans or wide pots, in light soil, or in a mixture of sifted peat, leaf-mould, and sand, with a little loam; the seeds should be scarcely covered. For cuttings, the plants should be cut down after flowering, and when they have pushed sufficiently take off the cuttings and insert them in soil like that recommended for the seeds, but with a layer of silver sand at top. When the plants from cuttings or from offsets have made shoots about 3 inches high, they should be stopped to make them branch. After this, they should be shifted when the roots have filled the pot, and before they get matted. Turfy-loam, leaf-mould, and sandy-peat, will form a good mixture for re-potting, and weak liquid manure

may occasionally be given. They are very subject to the attacks of green fly; therefore fumigations with tobacco, and dusting with snuff will be frequently necessary. *C. maritima* is a native of the south of Europe, consequently it requires a warm soil and situation, and protection from the frost. It is covered with whitish silvery down, especially on the stems and under sides of the leaves; its flowers are yellow, but it is the effect produced by its foliage which renders it so desirable for bedding purposes, and for contrast. Propagated by offsets, and by cuttings, in a hotbed.

CIRCÆA.—*Onagrææ*.—Enchanter's Nightshade. A pretty little British plant, growing in any soil and situation.

CISSUS.—*Vitææ*.—*C. Stans* is a very ornamental creeper, owing to its elegant, finely-cut leaves. *C. discolor*, a rapid-growing stove twiner, is one of the most ornamental foliaged plants known. The leaves are oval, acuminate, dull green and white, the underside beautiful purple.

CISTUS.—*Cistææ*.—The Rock Rose.—Beautiful hardy and half hardy shrubs, which grow freely in a mixture of loam and peat, and are readily increased by cuttings planted under a hand-glass, layers, or seeds, which are ripened in abundance. Most of the species are of low growth, and are generally used for rockwork; but some are tall handsome shrubs, such as the Gum Cistus (*C. cypricus* and *C. ladaniferus*), and the Purple-flowered Cistus (*C. purpureus*). The dwarf kinds, being generally rather tender, will require a slight protection during severe winters, when they are planted out on rockwork.

CITRUS L.—*Aurantiææ*.—The genus *Citrus* includes Oranges,

Lemons, Limes, Citrons, Shaddocks, &c., all well deserving cultivation, both for their flowers and their fruit, but of which only a few kinds of Oranges and Lemons are generally grown. They all thrive well in a mixture of rich loam with a little rotten dung; but great care is necessary not to overpot them, or to give them too much water when not in a growing state. On the Continent, they are indeed frequently kept during winter in a cellar, almost without either light or water, and brought into the open air during summer. The different species and varieties are generally propagated by budding, grafting, and inarching on the common Lemon, which grows readily from seed. The best time to do this is in February or March, when the grafts, &c., will take well, and in a very short time; and if grafted on good strong stocks, they will make handsome plants by the autumn. As soon as the grafting or budding has been performed, the plants should be set in a close frame on a moderate hot-bed, but not plunged into it, as from the tenderness of their roots, that might injure them. Oranges are also frequently raised from seeds; but unless they are budded or grafted when about two years old, it will be many years before they flower. Orange-trees may also be propagated by cuttings, which are best of the old wood, struck in sand in a gentle bottom-heat, and shaded. Plants raised in this manner flower and fruit much sooner than any others, but they scarcely ever attain a large size.

CLARKIA.—*Onagraceæ*.—Beautiful hardy annuals, with rose-coloured, white, and purple flowers, natives of California, requiring the same treatment as the California annuals. They may, however, be

sown in spring; and as, when this is the case, they are apt to become drawn up, the general appearance of the bed is much improved by sowing Mignonette with the Clarkia seeds in March or April. There is a variety, *C. pulchella alba*, the flowers of which are entirely white.

CLARY.—A kind of *SA'LZIA*.

CLAY.—See EARTHS.

CLAYTONIA.—*Portulacææ*.—Hardy herbaceous plants, some annual and some perennial, with pretty pink and white flowers, but having rather a weedy appearance. They grow best in a peat border, and are increased by seeds which sometimes ripen in abundance.

CLERMATIS.—*Ranunculacææ*.—Half-hardy and hardy climbers; shrubby and herbaceous; with white and purple flowers. They are all most desirable plants, of the easiest culture in any light rich soil, and readily propagated by cuttings of the young wood, or seeds, which are frequently ripened plentifully. *C. montana* is very ornamental and quite hardy. It is also of very rapid growth. *C. florida*, with white flowers; *C. Sieboldii* or *bicolor*, with white and purple flowers, and *C. azurea* or *cærulea*, with beautiful violet-blue flowers, are among the handsomest of conservatory climbers; and under glass they frequently come into blossom early in March. In the open air, they do not flower till May or June. *C. Sieboldii* and *C. azurea* will flower and grow well in the open air, but they are sometimes killed to the ground by frost. *C. viticella*, and its varieties, *C. flammula*, *C. Hendersonii*, and *C. cylindrica*, are all quite hardy; *C. Fortunii* has large, white double flowers, nearly six inches across. It flowered for the first time in this country in 1863; is hardy, fragrant, and continues long

in flower. *C. Standishii*, another new introduction from Japan, has purple flowers, and is also hardy. They form most beautiful objects when trained over lattice work, or baskets in the flower-garden; and no garden, however small, ought to be without one or more of these species.

CLEOME. — *Capparidææ*. — Splendid stove shrubs, annuals and biennials, with one or two half-hardy annuals, with white, rose, and purple flowers, of easy culture in any light rich soil.

CLERODENDRON. — *Verbenacææ*. — Very ornamental stove shrubs, chiefly natives of the tropics. They all grow freely in a light rich soil, composed of two parts of loam, one of rotten dung, and one of peat. They require frequent shifting from small pots to larger ones, to make them flower freely. They strike readily from cuttings of the young wood planted under a hand-glass; or cuttings of the roots planted in a pot, with their tops just above the surface of the mould, and plunged in a hot bed, will root readily. The most desirable species are *C. fragrans*, with pink flowers; *C. paniculatum* and *C. squamatum*, with scarlet flowers; and *C. macrophyllum*, with white flowers; but the most splendid of all is the *C. fallax*, with large cordiform leaves, and very long petioles; these and the calyx are coloured, flowers intense cinnabar red; from Java.

CLETHRA. — *Ericacææ*. — Hardy and half-hardy shrubs, with white flowers; of which *C. arborea* forms a very handsome small tree, when planted out in free soil in a conservatory, or in a sheltered situation in the open air, producing a great profusion of spikes of white flowers from August to October. *C. alni-folia* and some other species are

quite hardy. All the species thrive well in a mixture of loam and peat, and they are all readily increased by layers, cuttings, or seeds.

CLIANTHUS. — *Leguminosææ*. — *C. puniceus*, the crimson Glory Pea, is a magnificent half-hardy shrub, with bright crimson flowers, a native of New Zealand. It grows very freely in rich loam, if its roots are allowed sufficient room; and it generally thrives most when planted against the back wall of a conservatory or against a south wall in the open air, requiring only the protection of a mat in winter. Cuttings planted in pots in the autumn, and kept in a shady part of the greenhouse, will be rooted by the spring, when they may be planted in the open border. It is a plant that rarely flowers well in a pot; as it requires abundance of room for its roots, and grows rapidly with rather succulent shoots, requiring abundance of water during the growing season, and very little at any other time. When grown in the open ground, the juicy nature of its roots renders it a favourite food for snails; and when kept in the conservatory or greenhouse, it is very apt to be attacked by the red spider. If these enemies be kept away, and the plant be grown in rich soil, composed of equal parts of loam and thoroughly rotten manure, and well supplied with air, light, and water, with abundance of room for its roots, the rapidity of its growth, and the splendour of its flowers, will almost surpass belief; but unless these points are attended to, the plant is scarcely worth growing. *C. Dampieri* is considered one of the most gorgeous greenhouse plants known; it produces from the axis of every leaf a spike of orange scarlet blossoms, with a glossy black spot in the centre; it should be



grown in a mixture of turfy loam, peat, and silver sand.

CLIMATE is the grand regulator of vegetable culture; and the garden or landscape scenery of every country depends far more on the climate of that country than on its soil. In modern times the climates of all other countries are imitated by hot-houses; a practice scarcely, if at all, known to the ancients. In imitating a climate, it is not only necessary to attend to temperature, but equally so to light, and, to a certain extent, to the moisture of the atmosphere, and to the motion of the air and its change. Heat is communicated to plant-structures by the decomposition of fermenting substances, and by the combustion of fuel, operating by means of smoke or heated air in flues, or by water circulated in pipes, either in a fluid state or in an aëriform state, as steam; or by the heat of the sun passing through glass, and heating air which is not allowed to escape. The last mode is never wanting, whichever of the former modes may be adopted. The moisture of the atmosphere in plant-structures is maintained by watering the plants; and by keeping the surface of the ground and floor more or less moistened with water, according to the height of the temperature. The motion of the air is effected by ventilation, and opening the doors and windows of the plant-houses, so as to create a current through them, whenever the weather will permit.

CLIMBING PLANTS are those plants that raise themselves from the ground by attaching themselves to whatever objects may be near them. One class of climbers attach themselves by tendrils, such as the Vine and the Passion-flower; others by the foot-stalks of leaves, as in

the Nasturtium, and some species of Clematis; another class twine their stems round objects, such as the Convolvulus; while some attach themselves by small root-like bodies, such as the common Ivy, and the Ampelopsis, or Virginian Creeper; and others raise themselves by ascending through other plants, such as the common Nightshade in hedges, and the plant called the Duke of Argyle's Tea-tree, *Lycium barbarum*. The twiners may be supported by single rods; but all the others, excepting those which support themselves in the manner of the Ivy, require branched stakes, such as the sticks put into rows of peas; while plants of the nature of Ivy require a wall, a rock, or the rugged trunk of a tree. In general, all climbing plants, when they are not furnished with the means of raising themselves up, extend their shoots along the surface of the ground, when they become what are called trailers; or they root into it like the Ivy, and become what are called creepers. Climbing plants are of great use in gardening, for covering walls, ornamenting trellis-work, arcades, verandahs, ornamental props, in the form of cones, pyramids, parasols, &c.

CLINTONIA.—*Lobeliaceæ*.—Beautiful little annuals, flowering profusely the whole summer. They are natives of California, but will bear heat better than the generality of annuals from that country. They are generally raised on a hotbed (the seeds being sown in February), and planted out in May; but they may be sown in the open border in April. They require a very rich soil, consisting of one part of sandy loam, two of vegetable mould, and one of rotten manure; or, where vegetable mould cannot readily be procured, of equal parts of sandy loam and

method, which was that of the late Mr. Knight, are a long time before they show any disposition to flower; but when they do, if they are placed near the glass, and kept in the same heat as Pine-apples, they grow to an enormous size.

**CELSIA.**—*Solanaceæ* or *Verbascineæ*. Half-hardy annuals and biennials, with showy yellow flowers, and nearly allied to the genus *Verbascum*. They are generally raised on a hotbed, and the biennials are kept in the greenhouse during winter, as they are killed by a slight frost. *C. linearis* and *C. curticaefolia*, which have scarlet flowers, are now included in the genus *Alonsoa*.—See ALONSOA.

**CENTAUREA.**—*Compositæ*.—The common perennial species are known by the English name of Knapweed; and the only quite hardy annual one, *C. Cyanus*, by the name of Corn Bluebottle: the most beautiful species, *C. Crocodylium* L., is a half-hardy annual, which should be raised on a hotbed and planted out in May. *C. benedicta* L., *Onicus benedictus* Dec., the Blessed Thistle, is a hardy annual, which may be sown in March or April, and will flower all the summer; and *C. suaveolens* and *C. moschata* L., the yellow and purple Sweet Sultans, have been formed into the genus *Amberboda* by Professor de Candolle.

**CENTAURY.**—A British plant with clusters of small pink flowers, growing in chalky soils, the botanical name of which is *Erythræa Centaúrium*.

**CEPHÆALIS.**—*Rubiaceæ*.—See **IPECACUANHA.**—This plant is interesting from its producing the medicine called *Ipecacuanha*; though it has been long known in medicine, and large quantities of it have been imported every year from Brazil, it has only lately been introduced into

England, having flowered for the first time in this country in the stove at Kew, in January, 1843. The word *Ipecacuanha* is derived from "*Ipe* (bark), *caa* (plant), *cua* (scented), and *nha* (striped); thus forming the words '*bark of a scented and striped plant*.'"

**CÉRASUS.**—*Rosaceæ*.—The Cherry.—Hardy trees and shrubs, for the most part deciduous, and all more or less ornamental on account of their flowers. The common double Cherry, and the French double Cherry, deserve a place in every garden; and equally so do the Chinese Cherry, *C. pseudo-cerasus*; the All-Saint's Cherry, *C. semperflorens*; the Bird Cherry, *C. Pádus*; the Virginian Bird Cherry, *C. virginiana*; the Mahaleb Plum or Cherry, *C. Mahaleb*; and the Japan Cherry, *C. japonica*, known in the nurseries as the double Dwarf Almond. Many of the plants here enumerated are known at some of the nurseries by the name of *Prúnus*: as *P. Mahaleb*, *P. Pádus*, &c.; but in others they are called *Cerasus*. It is necessary to know this to avoid buying the same plant under different names. All the species grow in common soil, and are propagated by grafting or seeds. The common Laurel, *Cerasus Lauro-cerasus*, and the Portugal Laurel, *Cerasus lusitánica*, which also belong to this genus, have showy spikes of flowers, and deserve culture on that account, independently of their shining evergreen leaves.

**CERATONIA.**—*Legumindæ*.—An evergreen greenhouse shrub, a native of the South of Europe and Asia. The pod is fleshy, like that of the Tamarind, and it is said to have been the food St. John fed on in the Wilderness, the seeds being called "*locusts*," and the pulp

"wild honey." Hence the popular name of St. John's Bread. It is also called the Carob-tree. The tree is of very slow growth, and the flowers have no beauty; but the plant is worth cultivation for its dark-green leathery leaves. In Spain and Italy it is cultivated for feeding horses. It should be grown in a mixture of equal parts of loam and peat, well-drained and frequently watered; and it is propagated by cuttings of the old wood struck in sand. The wood is very hard, and is said to be almost incorruptible.

CERATOSTEMA.—*Vacciniaceæ*.—A showy plant with large, tubular, scarlet flowers; a native of the Andes of Peru, at a height of twelve thousand feet above the level of the sea, and consequently very nearly hardy. It was introduced in 1854.

CERCIS. — *Leguminosæ*. — The Judas-tree.—Few trees are more ornamental in a shrubbery than the two species of this genus: but *Cercis siliquastrum*, the common kind, is decidedly the handsomest. The leaves are curiously shaped, and the flowers, which are of a beautiful pink, grow out of the bark of the stem and branches, and not like those of other plants, among the leaves; these flowers have an agreeably acid taste, and when fried in batter make excellent fritter. The common Judas-tree is a native of the Levant, and it is frequently grown against a wall, producing its flowers in April; but the American kind, *C. canadensis*, is quite hardy. They both produce abundance of seeds, and grow best in a deep sandy loam, rather rich than poor.

CEREUS.—*Cactacææ*.—The Torch Thistle.—One of the genera into which the Linnæan genus Cactus is now divided. This genus was first

formed by Mr. Haworth, who made it consist only of all the Cacti that had long angular or round stems; but modern botanists include in it those of the short round stemmed porcupine Cacti, that have long tube-shaped flowers. Of the true kinds of Cereus, which are still generally the only ones known by that name in most private collections and nurseries, the best known are *C. speciosissimus*, the crimson-flowered Torch Thistle, and its hybrids and varieties, the stems of which are erect and angular, and the flowers dark crimson; *C. flagelliformis*, the Creeping Cereus, the long round stems of which hang down like cords, and the flowers of which are pink; and *C. grandiflorus*, the Night-blowing Cereus, the flowers of which are white and yellow. A new kind of Night-blowing Cereus has been lately introduced, called Mrs. Macdonald's, with flowers 14 inches in diameter. One of the handsomest species of the genus is, however, *C. crenatus* Lindl., which flowered for the first time in England in 1843. The plant resembles *C. speciosissimus*, but the flowers are like those of the Night-blowing Cereus; they have the advantage, however, of opening in the daytime, and remaining expanded a week or more. The Old Man's Head, or Monkey Cactus, *Cereus senilis*, which is covered with long white hairs, is more curious than ornamental; but it well deserves a place in every collection from its singular appearance, which is, however, most striking when the plants are small. All the kinds of Cereus only require greenhouse heat; they should all be grown in loam mixed with pounded brick and lime-rubbish, in pots well drained with cinders; and they all require abundance of air and light. It is best to give them a season of

bright yellow, are always found on the leaves of the shoots, the points of which are covered with the green-fly. The larvæ are flattish, fleshy grubs, tapering to the tail; they have six legs, and are very active. Some years lady-birds are much more numerous than in others; but their numbers are always found to bear a proportion to those of the aphides on which they feed. In France and Germany, no peasant will kill them, because they are considered to be sacred to the Holy Virgin; whence, no doubt, they have received the name of lady-bird. Seeing that these insects prove so useful in destroying aphides, it is the interest of all amateurs of gardening, and particularly all lovers of roses, to protect them.

COCCUS. — The scale-insect. — These insects are troublesome on many plants; but more so in the kitchen-garden, on the Vine and the Pine-apple, than on flowering plants. One species of Coccus infests the Opuntia, and is what we call cochineal; and another, on a kind of Fig-tree in India, produces the substance we call shell-lac, which is used in making sealing-wax. The only cure for these insects is brushing them off, and washing the branches affected with soft soap and water.

COCHINEAL FIG. — See OPUNTIA.

COCHLEARIA. — *Cruciferae*. — The Scurvy-grass. Two very pretty little plants, suitable for rock-work, have been lately introduced, which were classed, by D. Candolle, under this genus, viz., *C. saxifragæfolia* and *C. acutis*, but both have been removed to new genera; and for the first see GRANELLSIA, and for the second see IONOPSIDIUM.

COCK'S-COMB. — See CELOSIA.

COCKSPUR-THORN. — See CRÆGUS.

COFFEA. — *Cinchonaceæ*, or *Rubiaceæ*. — The Coffee-tree in England becomes a stove-shrub, which should be grown in loam and peat, in pots well drained, and sufficiently large to allow of plenty of room for its roots. The flowers, which appear in August or September, are white and sweet-scented, and the fruit is round and of a brilliant scarlet, inclosing two closely-packed seeds, which are the coffee. If the plant is kept well watered, it will flower every year, and the seeds will often ripen in England; but the coffee made from them is very inferior to even the worst of that ripened in the tropics. The Coffee-tree, being a native of Arabia, requires a dry heat when it is in a growing state, and only a moderate degree of warmth in winter. When kept in a moist stove, without a free circulation of air, the leaves become mildewed and infested with insects.

COLCHICUM. — *Melanthaceæ*. — Meadow Saffron. — A hardy bulbous-rooted plant, which will grow in any common soil. — The flowers come up through the ground without the leaves in autumn, and closely resemble those of the Crocus. The leaves do not appear till the following spring, and great care should be taken of them; as if they should be injured, so as to prevent them from exercising their proper functions in maturing the sap, the bulb will not flower the next autumn. An extract of Colchicum is given in medicine for the rheumatism and the gout; and it is said to form the basis of the celebrated *eau médicinale*. It is, however, poisonous if taken in even but a very small over-dose.

COLD HOUSES FOR PLANTS are not generally in use, though it is a

common practice with gardeners to remove plants from hothouses into the back sheds, in order to retard their blossoming or the ripening of their fruit. It is also the practice in some countries to place pots of fruit-bearing or flowering shrubs in ice-houses, so as to keep them dormant through the summer; and in autumn to remove them to forcing-houses, where in consequence of having been so long in a state of rest, they grow with great rapidity, and come into flower much sooner than if they had not been so long retarded. Bulbs are also retarded in a similar manner; and even nosegays are placed in ice-houses in Italy and other warm countries, when it is wished to retard their decay for particular occasions.

**CO'LEUS** *Verchaffelti*.—*Labiatae*.—A very strikingly ornamental foliaged plant, with richly coloured velvety deep crimson leaves; it is easily propagated by cuttings, and may be grown in the stove, greenhouse, and even in a warm situation in the open ground during the hottest period of the summer.

**COLLI'NSIA**.—*Scrophulariaceæ*.—California annuals, of great beauty, and well deserving cultivation. The handsomest species are *C. bicolor* and *C. heterophylla*, which are very nearly allied; and which, if sown in autumn, and grown in rich loamy soil, will grow two feet high, and will produce splendid spikes of flowers. *C. grandiflora* and *C. verna* are also very nearly allied, if not the same; and they are smaller plants, with rather small, but bright coloured flowers. They grow best in stiff loam.

**COLLO'MIA**.—*Polemoniaceæ*.—Hardy annuals, natives of California, but scarcely worth growing from their coarse and weedy appearance. *C. coccinea* is, perhaps, the best.

**COLT'S-FOOT**.—See *TUSSILA'GO*.

**COLUMBINE**.—See *AQUILE'GIA*.

**COLU'TEA**.—*Leguminosæ*.—The Bladder Senna. — Large deciduous hardy shrubs, growing and flowering freely in any common soil. *C. cruenta* is the smallest and the handsomest species. They are all propagated by layers or cuttings.

**COMBRE'TUM**.—*Combretaceæ*.—Splendid climbing stove-shrubs, natives of Sierra Leone, where they support themselves by means of a very curious kind of hook, formed by the persistent foot-stalks of the withered leaves. The principal kinds are *C. purpureum*, *C. comdum*, and *C. grandiflorum*. They are all very beautiful, and require to be grown in a mixture of loam and peat. They are propagated by cuttings or layers. Though generally grown in a stove, they may be made to flower in a greenhouse, or in the open air. — See *ALLAMA'NDA*.

**COMMELI'NA**.—*Commelinææ*.—Perennial and annual plants, hardy and tender, with beautiful bright blue flowers. *C. cælestis*, L. has tuberous roots, but it may be raised from seed, by sowing it in a hotbed early in the season, and turning it out into the open border in common garden-soil, tolerably rich, during the summer; and in autumn its tuberous roots may be taken up, and preserved during the winter, to be replanted in the open ground in spring; or they may be protected by covering the ground with ashes or sand.

**COMPO'SITÆ**.—The composite flowers, such as the Daisy, are in fact heads of flowers, composed of hundreds of little flowers or florets, as they are called by botanists, each of which has its corolla, stamens, pistil, and fruit; the whole being surrounded by an involucre which looks like a calyx. The central part,

which in the Daisy is yellow, is called the disk, and the florets composing it are tubular; while the outer part, which in the Daisy is white, is called the ray, and its florets are ligulate, or flat, and open at the extremity, and tubular at the base. Other genera have all the florets tubular, as the common Bluebottle, and the Sweet Sultan; and others are all ligulate, as in the Dandelion, and Sowthistle. This last genus affords a good example of the pappus, a sort of feathery crown apparently attached to the seed, but which is in fact the upper part of the calyx cut into very fine hair-like divisions; the calyx remaining attached to the seed when ripe. The pappus is also seen conspicuously in Thistle-down and the Dandelion; but some genera of the Compositæ are without it, as for example, the Daisy and the Chrysanthemum.

**COMPOST-GROUND.**—A space in some secluded part of a garden, near the hothouses and pits, and the tool-house, and reserve-ground, in which different kinds of soils, manures, and composts are prepared and kept. Though secluded, it should not be shaded altogether from the sun; and the ground should be drained, in order that the manure, &c., may not be soaked with moisture.

**COMPOST.**—This word is applied to any soil that is composed of several different ingredients; such as sand, loam and peat, or vegetable mould, &c. These mixed soils are found to be much better for plants than any soil consisting of only one material; and thus, whenever choice plants are to be grown, directions are generally given for making a compost for them. In all large gardens, heaps of several different kinds of earths are kept

in the reserve-ground ready for mixing as they may be required; but in small suburban gardens, peat, loam, and sand will suffice. These soils may be bought in small quantities from the London nurserymen, say sixpenny worth or a shilling's worth of each; and they may be kept in large pots in a back shed, for mixing as required.

**CONSERVATIVE WALL.**—Many greenhouse and some hothouse plants, particularly such as are deciduous, and are naturally of rapid and vigorous growth, are found to succeed remarkably well when planted out during the summer season in the open garden, either as standards or against a wall. Those which are planted as standards or bushes in the open beds or borders, grow vigorously during the months of June, July, and August, but require to be taken up in September and preserved during the winter in pots or boxes for planting out next season. This is practised with Fuchsias, Brugmansias, Pelargoniums, and similar plants. Other shrubs are planted against a wall with a southern exposure; and these not only grow and sometimes flower during the summer, but if protected during the winter with matting, or a projecting roof, or both, they will live for several years, growing vigorously, and flowering every season. The common myrtle, some of the Acacias, the Eucalypti, and a number of the rapid-growing New Holland shrubs, are so treated with great success; and the fine appearance which they make in the summer season, amply repays the expense and trouble which must be taken with them. There is scarcely any limit to the number and kinds of shrubs which may be treated in this way; for while the taller and

more rapid-growing kinds are made to cover the upper part of the wall, the dwarfier species may be trained against the lower part, and herbaceous plants, including bulbs, may be planted all along the base. The border in which the plants are grown should be a light sandy soil, of no great depth; and it would be an advantage to thatch it during the winter season, to carry off the rain to a distance from the roots of the plants. The drier all half-hardy plants are kept in the open ground, the better, excepting during the growing and flowering season, in order that the plants may make no more wood than what they can thoroughly ripen. Walls used for purposes of this kind are called conservative walls; and next to conservatories, they form the most interesting scenes to the lovers of plants in an ornamental garden.

**CONSERVATORY.**—This term originally implied a house in which orange-trees and other large shrubs, or small trees, were preserved from frost during the winter; but, at present, it is applied to houses with glass roofs, in which the plants are grown in the free soil, and allowed to assume their natural shapes and habits of growth. A conservatory is generally situated so as to be entered from one of the rooms of the house to which it belongs; and from which it is often separated only by a glass door, or by a small lobby with glass doors. It should, if possible, have one side facing the south; but if it is glazed on every side, it may have any aspect, not even excepting the north; though, in the latter case, it will only be suitable for very strong leathery-leaved evergreens, such as Camellias, Myrtles, &c. The bed for the plants should be of sandy loam (that being the soil that will

suit most plants), two or three feet deep, and thoroughly drained. The plants should be of kinds that will grow in a few years nearly as high as the glass; and they should, as much as possible, be all of the same degree of vigour, otherwise the stronger kinds will fill the soil with their roots, and overpower the weaker. This, to a certain extent, takes place in all conservatories, and is unavoidable. The only remedy for the evil is occasionally to cut in the large roots of the stronger plants, and prune in their tops, and every six or seven years to take up all the plants, excepting, perhaps, some of the climbers, and to renew the soil, and replant either with the same or with other plants, or with part of both. The pillars which support the roof, and, to a certain extent, the under side of the rafters, may be clothed with creepers; but great care must be taken that these do not exclude too much light from the plants beneath them, which may always be known by the etiolated sickly appearance of the latter. The most suitable plants for conservatories are those that flower in the winter season, or very early in spring; such as the Acacias, Camellias, Melaleucas, Metrosideroses, Banksias, Oleanders, &c.; and for climbers, the Kennedias, Zichyas, Hardenbergias, Bignonias, Tecomas, Ipomceas, Cobseas, Passifloras, Tacsonias, Clematisses, &c.

**CONVALLARIA.**—*Smilacææ*.—The Lily of the Valley.—A well-known and very fragrant little flower, said to be found wild in some parts of England. It requires rather a dry soil, which should be tolerably light. The plant is increased by dividing the roots, which are very numerous; and though it is generally supposed to like the shade, it will not flower well unless it has plenty of light.

Solomon's Seal is also a kind of convallaria.

CONVOLVULUS.—*Convolvulaceæ*.

—Well-known splendid climbing plants, hardy and half-hardy, annual and perennial. They all require a rich but light soil, and will grow well in a compost of equal parts of heath-mould and loam, enriched with about the proportion of a fourth part to the whole of decayed leaves, or thoroughly rotten manure; and they should be trained against stakes or trellis work, as their stems are too feeble to support themselves. Most of the tender kinds of Convolvulus were separated from it by Linnæus, and formed into the genus *Ipomœa*. All the store kinds may be made to flower in the open air, during summer, by contriving to keep the roots in heat; and the hardy species only require sowing in the open ground. The hardy kinds of Convolvulus, or Bindweed, have been separated from the others and formed into a genus under the name of *Calystègia*; and in 1844, a double-flowered kind was introduced from China by Mr. Fortune, called *Calystègia pubescens*, being the first double Convolvulus ever known. It is a half-hardy climber, requiring a rich loamy soil, and being increased by the roots. It flowers in July and August, and its blossoms, which are of a very pale delicate blush colour, or French white, remain open several days.

CORAL TREE.—See ERYTHRI'NA.

CO'RBORUS.—*Tiliacæ*.—Hot-house plants, not sufficiently ornamental to be worthy of general cultivation. For the well-known Japan half-hardy shrub, generally called *Côrchorus japonicus*, see K'ER'RIA.

CORDYLI'NE.—*Liliacæ*.—*C. australis* var. *indivisa*, is a very ornamental foliaged plant.

CORCO'PSIS.—*Compôsita*.—Most of the showy annuals formerly known by this name, are now called Calliopis, while most of the perennial species are still left in the former genus. For the difference between the derivation of the two names, and the culture of the annual species, see CALLIO'PSIS. The perennial kinds are quite hardy; but as they are tall-growing spreading plants, they require a great deal of room, and should be planted at the back of the borders. They will grow in any common soil; and they are propagated by division of the roots.

CORMS.—Bulbous plants, such as the Crocus, the different kinds of Morœa, the Babianas, and most of the Iridacæ. Bulbs are of different kinds: those which have a number of coats, or skins, one within the other, like the Hyacinth, which are called tunicated bulbs, and those which consist of a number of scales, only attached to the base, like the Lily; but what are called corms, are only a solid mass of feculent matter, which modern botanists do not allow to be bulbs, but call underground stems. Corms do not require taking up so often as bulbs; and when they are intended to remain for several years in the ground, they should be planted from four to six inches deep at first; as every year a new corm will form above the old one; and thus, if planted too near the surface, the corm, in a few years, will be pushed out of the ground.

CORN COCKLE.—See GITHA'GO.

CORNELIAN CHERRY.—See CO'R-NUS.

CORN FLAG.—See GLADI'OLUS.

CO'RNUS.—*Cornacæ*.—The Dogwood.—Well-known shrubs, with whitish or yellowish flowers, and dark purple berries. The species are generally ornamental, from the shining red bark of their branches



in winter, and the intensely dark purplish red of their leaves in autumn. One species, *Cornus mas*, the Cornelian Cherry-tree, a native of Europe, is remarkable for the large size and brilliant colour of its fruit; and another, a native of North America, *Cornus florida*, for the large size of its involucre, or floral leaves, which surround its flowers, and which are of a brilliant white inside, and tinged with violet on the outside. All the species are remarkable for the great length of time which their seeds will remain in the ground before they come up. On this account, when any kind of Cornus is to be raised from seed, the seeds should be steeped in water before sowing; but, generally speaking, all the kinds are propagated by layers or cuttings of the old wood, both of which strike root freely. *C. florida* is generally grown in peat, in a sheltered situation, and thrives best when its roots are kept in the shade; but unless its foliage is fully exposed to the influence of the sun, it will not flower. Travellers in North America describe what are called there the Dogwoods, as vast forests of this tree, about twelve feet high, with their branches so interlaced as to prevent a gleam of sunshine from reaching their roots.

CORONILLA. — *Leguminosæ*. — Ornamental shrubs, hardy and half-hardy, with bright yellow flowers, and pinnate leaves. *C. Emericus*, the Scorpion Senna, a native of the South of Europe, and the commonest and hardiest species, has the flower-buds red, and the expanded flowers of a bright yellow. It will grow in any soil or situation, and, as it will bear clipping, without much injury, it may be used as a hedge-plant. It will thrive in any garden-soil, and it is propagated by cuttings of the ripe wood or by layers. *C. glauca*, which

is a native of France, has bluish-green leaves and yellow flowers, which are fragrant during the day, but lose their scent at night. It flowers early and freely, and though generally kept in the greenhouse, it is very nearly hardy. The soil should be a sandy loam, mixed with a fourth part of vegetable mould, or rotten manure; and the pots should be well drained. It is propagated by seeds, which it ripens in abundance, or by cuttings in sand, under a bell-glass.

CORRÆA. — *Rutaceæ*. — Dwarf greenhouse shrubs, with leathery leaves, which are generally either brown or white on the under surface. The flowers are tubular, but those of *C. alba*, and *C. rufa*, which are white, are much less so than the others. Several new species, or hybrids, have been introduced since 1835, all of which appear most nearly allied to *C. speciosa*. *C. cardinalis* is the most elegant and splendid species of this beautiful genus. All the species and varieties flower abundantly, producing in a greenhouse a constant succession of flowers from November to June. They require an airy, but a somewhat shaded situation. The pots should be well drained, and the soil should be leath-mould, mixed with a little loam.

CORYANTHES. — *Orchidaceæ*. — Helmet-flower. — *C. macrantha* Lindl. (*Gongora macrantha*, Hook.), has a most singular red and yellow flower, part of which resembles a skeleton's head, with the vertebrae of the neck, and part two folded bat's wings. The plant is grown in a pot in sandy peat, mixed with lime rubbish; and the soil is raised above the level of the pot, as the flower-stalk hangs down from the root. It is a native of the West Indies; and, like most of the other tropical *Orchidaceæ*, it requires abundance of heat

and moisture to throw it into flower. A new species of this genus, with still more singular flowers than those of *C. macrantha*, was introduced in 1842. It is called *C. Feildingii*, and is the largest orchideous flower that has ever yet been found.

**CORYDALIS.**—*Fumariaceæ*.—The plants composing this genus were formerly considered to belong to *Fumaria*, the Fumitory, but they have been separated on account of the different conformation of the capsule. *C. glauca*, which is the most common species, is an annual from North America, which may be sown at almost any season, and in any soil and situation. *C. claviculata* is a British climber, also an annual, and pretty from the abundance of its small white flowers. It is of very rapid growth, and it is useful in covering a trellis, &c., from the number and dense habit of growth of its leaves. It grows best in a poor sandy or gravelly soil. Other plants formerly included in this genus are now called *Diselytra*.

**CORYLUS.**—*Amentaceæ* or *Cupulifereæ*.—The botanic name of the Hazel, Filbert, &c. The species are generally shrubs; but *C. Colurna*, the Constantinople nut, is a large ornamental tree.—See HAZEL.

**CORYSANTHES.**—*Orchidaceæ*.—Terrestrial orchidaceous plants, from New Holland, which will grow in the open air in England, if protected from frost during winter. They have dark brown flowers, and are so seldom cultivated, that they would not have been mentioned in the present work, had it not been to prevent them from being confounded with *Coryanthes*, a genus of Stove *Orchidaceæ* from the West Indies.

**COSMEA, or COSMOS.**—*Compositæ*.—Mexican plants, generally grown as annuals, but which have tuberous roots like the Dahlia, and may be

treated like that plant. The flowers are very showy, and of a reddish purple; and the seeds, when the plants are grown as annuals, should be sown in March and April, in the open ground; or in autumn, if the young plants can be protected during winter. The plants will grow four or five feet high in any common garden-soil.

**COTONEASTER.**—*Rosaceæ*.—Small trees and shrubs, natives of Europe and India, formerly considered to belong to the same genus as the Medlar. They are all well deserving of cultivation in shrubberies, for their bright scarlet or black fruit, and their pretty white or pink flowers. The Nepal species, *C. frigida*, *C. affinis*, *C. acuminata*, and *C. nummularia*, are the most ornamental. *C. rotundifolia*, and *C. microphylla*, also natives of Nepal, are remarkable for their thick leathery evergreen leaves, their snow-white flowers, and their profusion of bright scarlet fruit. Both the latter species form dwarf spreading shrubs, and are very ornamental for a lawn. All the species are hardy, and will grow in any common soil; and they may all be propagated by seeds, layers, cuttings, or grafting on the common quince or hawthorn.

**COTTON GRASS.**—See *ERIOPHORUM*.

**COTYLEDON.**—*Crassulacæ*.—Navelwort.—Succulent plants, with fleshy leaves, and yellow or red flowers, nearly allied to the Houseleek. They should be grown in light earth, mixed with lime rubbish, or in a compost of peat and loam; and the pots should be well drained. The most ornamental species are natives of the Cape of Good Hope; and they are propagated by cuttings, which should be laid on a shelf for a few days to dry before they are planted.

The European species are scarcely worth cultivating. The plant called Venus's Navelwort does not belong to this genus, but to *Omphalodes*. *C. sempervivum* Bieb. (*Umbilicus sempervivum*, Dec.) is one of the commonest species.

**COTULA.**—*Compositæ*.—Hardy and tender annuals, of which *C. aurea*, L., the flowers of which are like little golden balls, is the only one worth cultivating. It will grow in any common garden soil, and requires to be sown in March, with the usual treatment of hardy annuals.

**COW-ITCH.**—See *MUOU'NA*.

**COWSLIP.**—*Primulææ*.—*Primula vèris*, the common Cowslip, is a well known British plant, which, when cultivated in gardens, should be grown in a loamy soil and sheltered situation.

**CRANE'S BILL.**—See *GERANIUM*.

**CRASSULA.**—*Crassulææ*.—Succulent greenhouse plants, natives of the Cape of Good Hope, with heads of red or white flowers. They should be grown in sandy loam, and lime or brick rubbish, and the pots should be well drained. Like all the Cape plants, all the kinds of *Crassula* should have alternate seasons of stimulus and repose. When they are growing, and about to flower, they should be well watered, at least once every day, though the water should never be suffered to stand in the saucer; and when the flowers begin to fade, the supply of water should be gradually lessened, till, at last, very little is given, and that not oftener than once a week. The plants are propagated by cuttings, which should be laid on a shelf two or three days to dry before planting, or they will rot. When plants of *Crassula* are not well drained, or if stagnant water is retained round the roots, by letting water stand in the saucer, the stems are very apt to damp off.

*C. coccinea* and some other species were separated from the others by Mr. Haworth, and formed into the genus *Kalosanthes*; but this name does not appear to have been adopted by many persons, and the plants are still generally called *Crassula*, both in nurseries and private collections.

**CRATÆGUS.**—*Rosææ*.—The common Hawthorn, *C. Oxyacantha*, is so well known for its fragrant and beautiful flowers, that most persons will be anxious to know the other species of the same genus; and, in fact, several of the North American thorns are the most ornamental low trees we have in our gardens and shrubberies. The species are all hardy, and they all flower and fruit freely, and are equally ornamental in both states. Almost all the flowers are white; but the fruit varies in colour, some being scarlet, some yellow, some purple, and some green. The fruit varies also in size from that of *C. spathulata*, which is not larger than a grain of mustard-seed, to that of *C. mexicana*, which is nearly as large as a Golden Pippin. The fruit of *C. Azardus*, *C. Aronia*, and *C. tanacetifolia*, all large and yellow, and that of *C. odoratissima*, of a bright coral colour, are all very good to eat; and many persons do not dislike the haws of the common Hawthorn. There are nearly a hundred different kinds of *Cratægus*, including the hybrids and varieties; and of these thirty-one are varieties of the common Hawthorn. The handsomest species for their flowers are the red-blossomed and double-flowered Hawthorns; the handsomest for their leaves are the different kinds of Cockspur-thorn (*C. Cras-galli*), *C. punctata*, *C. pyrifolia*, *C. prunifolia* (the leaves of which die off of a deep red), and *C. Obleii*: and the most curious for their fruit are

*C. Douglasii*, *C. mexicana*, and *C. orientalis*. The earliest flowering in spring are *C. purpurea* and *C. nigra*, the latter of which is said to attract nightingales; and the Glastonbury-thorn, a variety of the common Hawthorn, often flowers at Christmas. *C. Oxyacantha pendula*, and *C. O. reginae*, Queen Mary's thorn, have both pendulous branches; and *C. O. stricta*, and *C. tanacetifolia*, grow stiff and upright, like a Lombardy poplar. *C. tanacetifolia* and *C. odoratissima* have bluish green leaves, which look as though they had been slightly powdered; and *C. Crus-galli splendens*, and several other kinds, have their leaves of a shining dark blackish green. *C. Pyracantha* is an evergreen, and has a very good effect, when trained against a wall, from its shining leaves, its bunches of pure white flowers, and its brilliant scarlet fruit, which are so abundant in winter as to induce the French to call the plant *Buisson ardent*, or the Burning Bush.

All the species of *Cratægus* will grow well in any soil that is naturally dry; but if planted in marshy ground, they will be stunted in their growth, and their leaves and fruit will become spotted and unhealthy. The common Hawthorn is propagated by seeds, which often lie two years in the ground before they germinate, if not prepared before sowing by being suffered to lie for several months in what is called a rot-heap; and which is often turned over during that time, to prevent the seeds from having their vital powers destroyed by the heat generated by fermentation. The finer kinds of thorns are generally grafted or budded on seedlings of the common Hawthorn.

**CREEPING CER'EUS.**—*Cereus flagelliformis*.—A succulent plant with

long, round, pendent stems, beautiful pink flowers, and dark, purple, eatable fruit. For the culture, &c., see CER'EUS.

**CREPIS.**—*Compositæ*.—Annual, biennial, and perennial plants, natives of Europe, of easy culture in any common soil. The two kinds most common in gardens are, however, now removed to other genera: *C. barbata*, the yellow Hawkweed, being now made *Tolpis barbata*, and *Crepis rubra*, the red Hawkweed, being now called *Berkausia rubra*. The first kind only requires sowing in the open ground with the other annuals in March or April, and may be transplanted if necessary; the second is also quite hardy, but it should be sown where it is to remain, as it does not well bear transplanting.

**CRESS-ROCKET.**—See V'ELLA.

**CRINUM.**—*Amaryllidaceæ*.—Stove bulbous, showy, lily-like plants, with very long leaves and large white flowers, which in some species are fragrant. The plants should be grown in rich loam, mixed with a little peat and sand, and allowed plenty of pot-room. They are increased by suckers, which are produced very sparingly. Several of the plants which are called by some botanists *Crinum*, are called by others *Pancratium* or *Amaryllis*.

**CROCUS.**—*Iridaceæ*.—There are nearly a hundred named kinds of Crocus, including hybrids and varieties; but there are only about thirty distinct species. All the kinds have bulb-tubers or corms, and they should not be taken out of the ground oftener than once in three years, being replanted as soon as possible. The commonest kinds are *C. vernus*, of which there are many varieties, all, however, having in them some shade of lilac mixed with white;

*C. versicolor*, to which division belong the beautifully - feathered kinds of purple; *C. biflorus*, the Scotch Crocus, striped white and purple, and generally the first to flower in spring; *C. susianus*, the Cloth of Gold, striped orange and very dark purple; *C. sulphureus*, very pale yellow, or cream-coloured; and *C. luteus*, the common yellow. Besides these, there is *C. sativus*, the autumn-flowering Crocus, or saffron, which is cultivated, on a large scale, in some parts of England, particularly near Saffron Walden, in Essex for the stigmas of its flowers, which, when dried, become saffron, and are used in dyeing. There are also large plantations of saffron in France; but in that country the bulb is frequently attacked by a fungus which the French call *mort de safran*, which makes it wither up and perish. All the kinds of spring Crocuses should be grown in light sandy loam well drained, and they may be planted either in rows or beds; or they may be made to form a kind of arabesque pattern in the borders.

In whatever way the Crocus may be planted, the leaves should never be cut off till they begin to wither, as without their assistance the plant cannot accumulate matter to form its new corm for the ensuing season. The new corm always forms above the old one; so that in four or five years they will have almost pushed themselves out of the ground; and from this habit of growth, Crocuses are generally planted three or four inches deep. Crocuses, when in flower, are frequently destroyed by sparrows, which peck at them, and the corms are often eaten by mice. They ripen abundance of seed, but the seedlings do not flower till the third or fourth year.

CROCKS or POT-SHERDS.—Broken pieces of flower-pots, bricks, or tiles,

used for draining flower pots containing plants.

CROSSBREDS differ from hybrids in being produced by plants more nearly allied to each other; as two varieties of one species, or two nearly allied species, &c. For the mode of obtaining these crosses, see GERMANIUM and HYBRID.

CROTALARIA.—*Leguminosæ*.—Herbaceous plants, natives of the East and West Indies, and a few shrubs, natives of the Cape, with showy pea-flowers, generally either purple or yellow. There are a few annual species, the hardy ones of which are natives of North America, but the species most commonly cultivated are greenhouse shrubs. They should be grown in sandy loam and peat, well drained; and they are propagated by cuttings of the young wood and by seeds.

CROTON.—*Euphorbiacæ*.—Mostly stove-shrubs, natives of the East Indies and South America. *C. picta* (*Codiaeum pictum* Juss.) is a very remarkable and ornamental plant, from the brilliant colour of its leaves, which are variegated with blotches of scarlet, yellow, and dark purple. This species should be grown in lime-rubbish and peat, or in sand only, and the pots must be well drained, or the leaves will soon become green, and lose their beauty. *C. variegata*, with foliage green and golden yellow, is also very ornamental. The Croton oil is made from an annual species, *C. Tiglium*, a native of the East Indies. The shrubby kinds are propagated by cuttings, which should not have their leaves shortened, and which strike readily in a moist heat.

CROWFOOT.—See RANUNCULUS.

CROWEA.—*Rutacæ*.—A very pretty New Holland shrub, which will flower nearly all the year. It

should be grown in a compost of vegetable mould, sand, and peat, and the pots must be well drained; as, though it requires frequent watering, no plant suffers more from the effects of water being allowed to remain in a stagnant state about its roots. Whenever the leaves turn yellow, and the flowers drop off without expanding, the cultivator may feel assured that there is some fault in the drainage, and the plant should be repotted. It is increased by cuttings.

**CROWN IMPERIAL.**—A very showy bulbous rooted plant, formerly included in the genus *Fritillaria*; but it has lately been placed in another genus. It is quite hardy, and when the bulb is once planted in any common garden soil, the plant needs no other culture.

**CRYPTOGAMOUS PLANTS.**—Ferns, Mosses, Lichens, and other plants, which do not produce any visible flowers.

**CRYPTOMERIA.**—*Cupressinae*.—The Japan Cedar (*Cryptomeria japonica*) is one of the handsomest of its tribe that has ever been introduced into British gardens. Seeds were sent home from China by Mr. Fortune in 1844, and so many young plants were raised from them, that the tree is rapidly becoming common. In its native country it is said to form a tree 60 or 100 feet high. It is quite hardy near London; but in cold, exposed situations it frequently becomes stunted. If grown in too dry a soil, it is apt to have its lower branches become bare.

**CUPHEA.**—*Lythraceae*.—South American plants, with very curious flowers, some of which are half-hardy annuals, some green-house plants, and some stove-shrubs.—They require a moist rich soil, and a shaded situation. *C. strigillata*, *C. manicata*, and *C. platycentra*,

particularly the latter, are ornamental green-house plants introduced about 1846. They are all half-hardy, and will flower profusely in the open ground if planted out in spring.

**CUSCUTA.**—*Convolvulaceae*.—The Dodder. Parasitical plants which are sometimes grown in greenhouses as objects of curiosity. When this is the case, the seeds should be sown in a pot, in which is growing a common horse-shoe geranium (*Pelargonium zonale*). As soon as the seed of the Cuscuta begins to germinate, it sends out a delicate thread-like stem, which is leafless, and which soon coils itself round the stem and branches of the poor geranium, adhering to them by a number of wart-like protuberances, or suckers, which appear at intervals along its surface. The root of the parasite now withers, but the plant itself continues to thrive, as it feeds, vampire-like, on the sap of the doomed geranium, and to grow vigorously, producing abundance of leaves and flowers; while the geranium appears to sicken, its leaves turn yellow and drop off, and it finally wastes away. The geranium should be tall and much branched; and when this is the case, the Cuscuta forms a very ornamental object, hanging down in graceful festoons, and producing abundance of its glossy pale bluish-coloured flowers, which are very fragrant. Sometimes this parasite is propagated by shoots, which should be wrapped in wet moss, and tied on the plant to which they are to adhere. Two species of Cuscuta are natives of Britain, and are very troublesome in oat-fields; but the other kinds are natives of the south of Europe and the tropics. The handsomest species, *C. veruculosa*, is from Nepal.

CUSTARD APPLE.—See ANO'NA.

CUTTINGS.—It may be received as a general principle that all plants which produce shoots may be propagated by cuttings; though some plants are much more difficult to propagate in this manner than others. Generally speaking, all the soft-wooded succulent plants, which have abundance of sap, such as Pelargoniums (Geraniums), Fuchsias, Petunias and Verbenas, strike root readily; while dry, hard-wooded plants, such as Heaths, and the different kinds of Epacris, are very difficult to strike. The usual directions for striking cuttings are, to put them in pure sand, and to cover them with a bell-glass, and this may be done as a precautionary method with all cuttings, though it is only essential with those that are difficult to strike. Some cuttings are directed to be made of the old wood, and some of the young tender shoots of the current year: in general, however, the safest plan is to take off the shoot just below where the young wood is united to that of the previous season, so that a small portion of the old wood may remain attached to the cutting. The shoot should be cut off with what gardeners call a clean cut (as, if it be bruised, or left jagged, or uneven, it most probably will not grow); and it should be planted in sandy soil, to ensure drainage, as the cutting will rot, or, as gardeners term it, damp off, if water in a stagnant state be suffered to remain round it. When the cutting is put into the ground, the earth should be made quite firm to its lower end; as, if any space be left below it, the roots will wither as soon as they shoot forth. Cuttings are considered most likely to succeed when taken from the horizontal branches of the plant nearest the ground;

and as least likely to strike root, when taken from the upright shoots at the summit of the plant; though this rule has many exceptions. A shoot of the soft-wooded kinds, which strike easily, may be divided into several cuttings, all of which will grow; but with all the hard-wooded kinds, only one cutting must be taken from the tip of each shoot. Shoots which are of the average strength are preferable to those that are either very strong or very weak; and those are best that have only leaf-buds, and no flower-buds on them.

Some cuttings which are difficult to strike are directed to have bottom heat. This means, that the pots in which they are planted are to be plunged into a hotbed, that the stimulus afforded by the heat may induce the cuttings to throw out roots. Care must, however, be taken that the hotbed is not too hot, as in that case it sometimes burns the tender roots of the cuttings.

The following are the principal kinds of plants propagated by cuttings, divided into classes, each of which requires a different treatment. — Soft-wooded greenhouse plants, such as Geraniums, Fuchsias, Brugmansias, Petunias, Verbenas, Tropæolums, Maurandias, &c. These may have cuttings taken off in spring, or at almost any period during summer, and planted in sandy soil, with or without a glass over them, and with or without bottom heat. They may be considered as the easiest of all cuttings to strike, the principal art consisting in cutting the shoot across, through, or immediately under the joint, with a clean cut, preserving a few of the leaves on, and making the lower end of the cutting quite firm in the sandy soil in which it is planted. In the summer time, such

cuttings may be planted in the free soil : and at other seasons, in order to admit of protection, in pots. In whichever mode they are planted,



FIG. 3.—CUTTING OF *ACACIA ALATA*.

they must be kept in the shade, and in an uniform state in regard to moisture, till they have begun to grow. Their growing is an indication of their having taken root, when they should be taken up, and each planted in a separate pot.

Hard-wooded greenhouse plants, such as Camellias, Myrtles, ever-green Acacias, and most Cape and Australian shrubs with comparatively broad leaves, are a degree or two more difficult to strike than Geraniums and Fuchsias. The points of the shoots, after the spring growth has been completed, and before the young wood is thoroughly ripened, should be used ; and the soil should contain a large proportion of sand, and be thoroughly drained. If cuttings of this kind are put in during autumn, they require to be kept through the winter under glass, and they will not produce roots till

spring ; but if the plants have made their growth, as most Australian shrubs do, in February or March, and the cuttings are taken off and



FIG. 4.—CUTTING OF A *CAMELLIA*.

planted in these months, they will root that same season, and be fit to transplant into small pots in the course of the summer. To accomplish this object, it is common with cultivators to force forward the plants from which cuttings are to be taken, by removing them from the greenhouse to the hothouse in January ; and after they have made their shoots, to harden these before making the cuttings, by removing the plants back again to the greenhouse. Most cuttings of this kind require to be covered with a hand-glass, and some with a bell-glass.

Heath-like plants, such as *Erica*,



FIG. 5.—CUTTING OF A *HEATH*.

*E'pacia*, *Diósma*, are among the most difficult to propagate by cuttings. The points of the shoots only are to be taken ; and these, in some



cases, should be not more than one inch in length. These should be taken off early in spring, when the plants have nearly ceased growing; and they should be cut clean across at a joint, and the leaves clipped, or cut off, for about half-an-inch of their length. The cuttings, thus prepared, are planted in pure white sand, well drained, with a little peat-soil, as a substratum; and they are covered with a bell-glass, and placed in a frame near the glass, and shaded. The best time for putting in Heath cuttings is in December; when plants, that have



FIG. 6.—CUTTING OF AN EPACRIS.

about half finished their growth, should be selected. The cuttings ought not to be more than an inch long; and even shorter cuttings sometimes strike better. The leaves must then be clipped off with a small and very sharp-pointed pair of scissors, to about half the length of the cutting, or less; as the shorter the shank of the cutting, the quicker it strikes, and there is less chance of its rotting. Great care is necessary in clipping off these leaves, and cutting the cutting across, so as not in the slightest degree to lacerate the bark, for the smallest wound or laceration will prove fatal to the cutting, by allowing the moisture to enter it, and thus damp it off. This, after all, is perhaps one of the principal reasons why so few, even of gardeners, strike Heath-cuttings

well; for the cuttings being very small and succulent, the operators are seldom sufficiently careful in clipping off the leaves with scissors, but cut them off with a knife, resting the cutting on the thumb-nail; though it is evident, that by this process they cannot make a very clean cut; and moreover, that they must bruise the bark, or tear down the petiole of every leaf they cut off. Having prepared the cutting properly, it must be gently taken in the left hand, with a pricker (a knitting-needle answers exceedingly well) in the right, with which a hole is made in the sand to about the depth of the shank of the cutting; the cutting is then placed in the hole, and the pricker is again put into the sand, to close the sand round it; as great care must be taken that no vacuity is left between the sand and the cutting anywhere. As soon as the pots are filled with cuttings, a bell-glass should be put over them, and the pots should be placed on a green-house shelf, where the temperature is not lower than sixty degrees. They will require little attention afterwards: excepting now and then when the sun is out, or when snow has fallen, to shade them from excessive light, and to remove such cuttings as begin to rot; for one rotten cutting, if not taken away immediately, will infect the whole pot, and they will all damp off in a very little time. If a potful of each sort should be more than is required, care must be taken to sort the cuttings out in such a way that the smooth kinds may be placed together, and the hairy ones, the viscid ones, &c., by themselves. This separation is the more necessary, as the hairy kinds generally collect more moisture than the smooth sorts; besides the great difference of time required to strike

them, some of the smooth or glabrous sorts striking in a month, while some of the viscid ones require three or four months. When the cuttings are made in December, the greater part of them will be struck by February or March, when they should be carefully potted into thumb-pots, about half-full of very fine potsherds, and the other half filled up with soil composed of equal parts of finely-sifted peat and silver sand. The plants will now only require to be kept under the hand-glass for a few days, to let them root again; and then they must remain for about a fortnight or three weeks on the greenhouse shelf, after which they may be with safety removed to the cold frame.

Cuttings of stove-plants generally require to be planted in the same kind of soil as the parent plant, and plunged in a gentle bottom heat, from a hotbed of tan or stable manure, under a bell-glass; though some of the more slender-growing kinds require silver sand, without bottom heat. As cuttings of many stove-plants are very large, care must be taken never to allow them to flag or droop, and also to preserve as many of their leaves as possible; indeed, this rule may be applied to almost all cuttings.

Succulent plants, such as Cactuses, Euphorbias, Mesembryanthemums, Crassulas, and the like, require to be kept out of the ground for a few days to dry, after they have been cut off; and then to be planted in a mixture of peat, sand, and brick rubbish, well drained. The pots may afterwards be set on the dry shelf of a warm greenhouse, and only occasionally and slightly watered; many of them, indeed, will require no water till they have struck.

The French have several ways of making cuttings which are not yet

common in British gardens; but some of which have been introduced in a few places with very great success. The principal of these are called the heeled cutting (*bouture à talon*), and the ringed cutting (*bouture par étranglement*). The first of these merely consists of taking out a small portion of the branch on which the sprig used in making the cutting grew, as shown in *fig. 7*.



FIG. 7.



FIG. 8.

This forms a kind of heel, and the cuttings thus made are said to take root much more readily than those made in the ordinary manner. The *bouture par étranglement* is formed by tying a ligature round the branch from which the cutting is to be made, just below one of the buds. This will cause a swelling (*a*, in *fig. 8*) to form just below the ligature, and from this swelling roots are soon protruded.

Many plants, the shoots of which will not root readily, are easily increased by cuttings of the roots; such as some of the *Acacias*, *Roses*, &c. Roots not less than a quarter of an inch in diameter should be chosen, and planted in the same kind of soil in which they have pre-

viously been growing, with their tops just above the surface of the soil, and plunged in a gentle bottom heat, when they will, in a few weeks, form a bud and send up a shoot, and thus become well-established plants in a shorter time than by almost any other method. Many hardy plants are raised from cuttings of the roots, and these only require to be put into light rich soil near a wall, or in any other sheltered situation, and to be kept rather moist, and shaded occasionally.

Cuttings of leaves have been frequently made by the French nur-




FIG. 9.—LOWER HALF OF THE LEAF.

serymen; and a very curious experiment was tried in 1839 by M. Neumann of the Jardin des Plantes. Finding that *Theophrasta longifolia* (*Clavija ornata* Don) would grow readily from a cutting formed of a leaf, he conceived the idea of cutting a leaf in two, and trying to strike both parts. He did so, plunging the plants in the pit of a hothouse, and succeeded in striking both; but he found that though the lower half of

the leaf made roots in three months (see fig. 9), the upper half (fig. 10) was nearly double that time before it was quite established. The dotted lines in fig. 10 show where portions



FIG. 10.—UPPER HALF OF THE LEAF.

of the leaf were cut off. In June, 1840, the two half leaves had become beautiful and healthy plants, which it was impossible to distinguish from those struck in the usual manner. Half leaves of various plants have also been rooted in charcoal, in Germany.

CY'ANUS.—The Corn Bluebottle. See CENTAURE'A.

CY'CAS.—*Cycadeæ*.—A kind of herbaceous Palm, requiring the heat of a stove, and remarkable for its curious root-like stem, and enormous fern-like leaves. It very rarely produces seed in England, and when it does, the seeds are placed on the margin of the leaves. The male flowers are in cones. It should be grown in a strong rich loam.

CY'CLAMEN. — *Primulacæ*. — Handsome and curious tuberous-rooted herbaceous plants. *C. europæum* is a native of Switzerland, and is very fragrant; *C. edum* and *C. vèrnum* are natives of the South

of Europe; and all these kinds are hardy in British gardens, and require no other care than to be grown in light rich soil. *C. persicum* is a greenhouse species, the tubers of which should be planted in well-drained pots, early in September, and kept in the open air till they have thrown out leaves, when they should be removed to the greenhouse. They require plenty of air, and but very little heat; and during the months of November and December, they should have very little water; though, when the flowers begin to form, they should be abundantly supplied. When they have ceased flowering, the supply of water should be diminished; and about June the tubers should be taken out of the ground and kept dry till the season for planting the following autumn. The best soil for them is equal parts of loam and rotten manure, or leaf-mould, with a little peat and sand, or heath-mould. All the kinds are propagated by seed, which they ripen in abundance; and they all require an open airy situation.

**CYCNOCHES.**—*Orchidaceæ*.—An orchideous plant, commonly called Swanwort, from the graceful curve of the column of the flower, which resembles the neck of a swan. It requires a very damp atmosphere, and the greatest heat ever applied to a damp stove. For the culture, see ORCHIDEOUS EPIPHYTES.

**CYDONIA.**—*Rosæcæ*.—The botanic name of the Quince tree; and now also applied to that beautiful and well-known shrub with bright scarlet flowers formerly called *Pyrus japonica*. *Cydonia japonica*, though a native of Japan, is quite hardy, and will grow in any soil and situation if not too much exposed. It bears pruning without injury, and makes a good hedge.

It retains its leaves nearly all the winter; and in mild seasons, and sheltered situations, it is almost always in flower. There are three or four varieties; some with half double flowers, and some the flowers of which are of a pale bluish colour.

**CYNIPS.**—The Gall Fly.—A kind of gnat, which occasions the galls on oaks, &c. The Bedeguar, a disease which affects rose-trees, is occasioned by *Cynips rosæ*, a little insect, not more than the twelfth of an inch long, having the legs and body red, tipped with black. This little creature wounds the twig of the rose-tree, and deposits its eggs under the bark. The wound swells, and forms an excrescence, often two inches in diameter, and covered with green or pink hairs, which are curiously branched at their extremities like little masses of coral. The excrescence is so ornamental that it seems almost a pity to destroy it, and yet, when opened, it will be found to contain a great number of the grubs or pupæ of the fly.

**CYNOGLOSSUM.**—*Boraginææ*.—Hound's-tongue.—Pretty little biennial and annual plants; natives of Europe, and requiring only the common culture of plants of a similar nature. Venus's Navel-wort was formerly considered to belong to this genus, but it is now removed to **OMPHALODES**.

**CYPRIPEDIUM.**—*Orchidaceæ*.—The Ladies' Slipper.—Terrestrial orchideous plants, mostly natives of North America. They should be grown in peat-soil in a shady border, and covered with a hand-glass, or in some other manner, so as to keep them dry during winter. They are very difficult to propagate in this country, and the plants bought in the seed shops and nurseries have generally been imported from America.

**CYRTOCHILUM.** — *Orchidaceæ*. — Splendid Mexican Epiphytes ; which are generally grown on part of the branch of a tree, or in the husk of a cocoa-nut, hung up from the rafters of a hothouse, or damp stove. When planted, the roots should be wrapped up in wet moss, and tied on the branch, or placed in the husk ; and the plants should be kept in a damp atmosphere, and frequently watered. Sometimes these Epiphytes are grown in pots, in which case the soil should be peat mixed with lime-rubbish.

**CYTISUS.** — *Leguminosæ*. — There are above fifty kinds of *Cytisus* ; but the kinds best known are the Laburnums, the common Broom (*C. scoparius*), and the Portugal Broom, (*C. albus*). The common Laburnum (*C. Laburnum*) is a well-known tree, which, if it were less common, would be thought extremely beautiful. There are only three or four distinct varieties, but the plant varies very much in the size of its flowers, in their colour, and the length of the racemes in which they are disposed, and in their fragrance. The Scotch Laburnum (*C. alpinus*) is much more beautiful than the common kind ; both the flowers and leaves are larger, and the flowers are more frequently fragrant. They are also produced much later in the season, not coming into flower till the others are quite over. This is the plant which the Italians call May, as we do the Hawthorn. The French call both species False Ebony, from the blackness of the wood ; which, however, is much darker in *C. Laburnum* than in *C. alpinus*. Both kinds will grow in any soil and situation, but they do best in a deep sandy loam, and a sheltered situation. Rabbits and hares are very fond of the young bark of the Laburnum, so much so, that whilst they can get it they will

not bark other plants, and accordingly in some instances Laburnums have been planted in order to save certain trees from being attacked by these animals.

**DABECIA.** — *Ericaceæ*. — The late Professor Don's name for *Andrœmeda Dabœcia* L., Irish worts, or St. Dabec's-heath. It is quite hardy, but requires a moist, peaty soil. The species has purple flowers ; but there is a beautiful variety, the flowers of which are white.

**DAFFODIL.** — See **NARCISSUS**.

**DAHLIA.** — *Compositæ*. — The importance that has within the last few years attached to this genus would render it easy to fill a volume with descriptions of its various species and varieties, and the details of their culture. Its history is also somewhat curious ; as, strange to say, though it has become so great a favourite, and is so universally cultivated, the history of its introduction is very obscure. It is generally said to have been introduced by Lady Holland in 1804 ; but the fact is it had been introduced many years before that period, and was only brought from Madrid, in 1804, by Lady Holland, who apparently did not know that it was already in the country. The first kind of Dahlia known to Europeans (*D. superflua* Cav., *D. variabilis* Dec., *Georgina pinnata* W.) was discovered in Mexico by Baron Humboldt in 1789, and sent by him to Professor Cavanilles, of the Botanical Garden, Madrid, who gave the genus the name of Dahlia, in honour of the Swedish Professor Dahl. Cavanilles sent a plant of it the same year to the Marchioness of Bute, who was very fond of flowers, and who kept it in the greenhouse. From this species nearly all the

varieties known in the gardens have been raised ; as it seeds freely, and varies very much when raised from seed. In 1802, *D. frustranea* Ait. (*D. coccinea*) was introduced from France, in which country it had been raised from Mexican seeds. A few varieties have been raised from this kind, but they are much smaller than the others. It is rather remarkable, that the two species do not hybridise together ; and that *D. superflua* or *variabilis*, should produce flowers of colour so different as crimson, purple, white, yellow, orange, and scarlet, without hybridisation. Among all the colours, however, displayed by these varieties, no flowers have yet appeared of blue, and comparatively few of a pure white. These two species, and their varieties, were the only Dahlias known in English gardens for many years ; as, though a few kinds were introduced from time to time from France and Spain, yet as they did not hybridise with the others, and were rather more tender, they were not generally cultivated, and appear to have been soon lost. Most of these have, however, been re-introduced from Mexico, with several new species, within the last few years ; and there are now ten or twelve distinct species, besides innumerable varieties of *D. variabilis* to be procured in England. The most remarkable of the new species is the tree Dahlia, *D. excelsa*, which is said to grow in Mexico thirty feet high, with a trunk thick in proportion. The name of Georgina was applied to the Dahlia by Willdenow ; because the word Dahlia was thought to bear too close a resemblance to the word Dalea, which had been previously given by Thunberg to a small leguminous genus. As, however, the words are both spelt and pronounced differently, Professor de Candolle has

recommended that the name Dahlia shall be retained, and most botanists of the present day have followed his recommendation. The name Georgina was given in honour of Georgi, a German botanist, who resided for several years at St. Petersburg.

The Dahlia is a tuberous-rooted plant, which is propagated either by seeds, or division of the root. The seeds are chiefly used for raising new sorts ; and they should be treated like tender annuals, being sown on a slight hot-bed in February or March, and planted out in May. The plants rarely flower the first year, but the tubers will form in the course of the summer, and may be taken up in autumn with those of the old plants. When the plants are propagated by division of the root, care must be taken that each piece has a bud attached to it. These buds, or eyes, as the gardeners call them, are not scattered all over the tubers, like those of the potato, but collected in a ring round the collar of the root. These eyes, when the tubers are in a dry state, are sometimes scarcely perceptible ; and to discover them, nurserymen often plant their Dahlia-tubers in a hot-bed, "to start the eyes," as they call it ; that is, to force the latent buds sufficiently forward to show where they are situated, before they divide the tubers for the purpose of forming new plants. Sometimes the eyes do not form a ring round the collar or crown of the root, but a considerable portion of it is without any buds. These parts, when divided from the rest, are called blind tubers ; and, though, if put into the ground, they will live for several years, sending out abundance of fibrous roots every year, no gardener has yet been able to induce a blind tuber to form an eye, or to send up

a shoot. This peculiarity should be kept in mind by all novices in floriculture, as dishonest persons frequently sell large and healthy-looking tubers, which are, however, worthless, from their being without eyes. To remedy this evil, an expedient has been devised of grafting the tubers of Dahlias in the same manner as is practised with the tubers of the Pæony in France (see GRAFTING); but it requires great skill in the gardener to do this successfully, as the tuber is very apt to rot at the point of junction between it and the graft. One mode of performing the operation is to take a growing shoot of a choice Dahlia, and to cut it so as to form the lower extremity into a wedge shape (as shown at *a* in



FIG. 11.—CLEFT-GRAFTING THE DAHLIA.

fig. 11). A barren tuber must then be prepared (as shown at *b*), and the shoot inserted. Another method is to make one or two holes in the neck of a barren tuber, and inserting a bud (see fig. 12), taking care to make the two surfaces fit exactly, and covering the edges with grafting-wax. The tuber is then planted,

and the pot is plunged into a hot-bed till the leaves begin to shoot.

Dahlias are also propagated by cuttings, which indeed is the usual mode. To obtain cuttings the roots should be planted in light sandy



FIG. 12.—PEG-GRAFTING THE DAHLIA.

soil, but so as to leave the crowns exposed, and placed in a bottom heat of about 60°, and in a rather moist atmosphere. The shoots, when about three inches in length, should be taken off close to the root, if they are plentiful; but if scarce they should be allowed to grow a little longer, and then cut off so as to leave one or two buds at the base to push again. The cuttings should be put in singly in small pots in light sandy soil, with a little silver sand at top; the pots should be placed in a frame in a gentle hot-bed, where the cuttings will soon strike root.

The best soil for Dahlias is a compost of equal parts of sand and loam, with a little peat; which may be enriched with part of an old hot-bed, or decayed leaves. Manure of any kind should, however, be used very sparingly, as too much will cause the plant to produce strong coarse-growing leaves and stems, instead of fine flowers. Striped flowers are never either bright or distinct in their colours in very rich soil. Dahlias will not grow well in

the richest clayey soil without sand ; and though they will grow freely in sand without loam, the flowers will be poor and only semi-double. Though they flower so late in the year, Dahlias are killed by the slightest frost ; and thus their beauty, great as it is, is generally rather short-lived. As soon as the leaves turn brown from frost, which is generally in October, the stems should be cut down ; and in November the tubers should be taken up. A dry day should be chosen if possible ; and the tubers should be carefully taken up, and laid on boards in an open shed, or some similar place, to dry. While drying, they should be turned every day, and the earth that falls from them should be swept away. They should be dried in an open shed, if possible, where they will be only sheltered from the rain ; for if dried suddenly by fire-heat or exposure to the sun, the tubers are apt to wither up ; and if dried too slowly, without the admission of plenty of air, they will rot. They generally do best kept during the winter in a dry cellar in sand or sawdust ; but any dry place will do which is not too hot. In spring the tubers are replanted, either in pots plunged in a slight hotbed, about the middle of February or the beginning of March, or in the open ground in May or June ; but the dwarf early-flowering kinds may be planted in the open air in April. When the tall kinds are wanted to flower early, they may be forced rapidly forward by being plunged into stronger heat, and kept in the hotbed till just ready to flower. If, however, the summer should prove hot and dry, the plants thus forced are frequently attacked by a disease called the curl, which is caused by an insect called the green bug, that perforates the young

leaves, and occasions them to wither and shrivel up. All Dahlias are also frequently infested with earwigs, which pierce the flower-buds, and prevent them from expanding.

The beauty of the Dahlia is estimated principally by the shape of




FIG. 13.—DAHLIA-RINGS.

the flower, which should be perfectly circular, without any of the petals projecting beyond the others ; and if the disk in the centre be seen in a full-blown flower, it is considered as a great defect. As this imperfection disqualifies even a fine Dahlia from competing for a prize, dishonest florists frequently try to remove it artificially, after the flower has expanded. The size and colour of the flowers are considered as of inferior consequence to the form by professed



florists; though, of course, large flowers are generally preferred to small ones; and the colours, whatever they may be, should be always clear and distinct, without any blotches, clouding, or muddiness. There are several distinct classes, if they may be so called, of the flowers; as, for example, the Globe Dahlias, the dwarfs, the quilled, &c. As the plants are very luxuriant in their stems and leaves, they require some kind of confinement; and they are generally either tied to cast-iron stakes painted green, or drawn through what are called Dahliarings, which are generally made of cast-iron; but as these are rather dear, they may be imitated by fixing three slender stakes of wood, in a triangular form, and forming rings of split willows, which may be purchased of the basket-makers, and tying them to the stakes at regular distances; or the stakes may be pierced with holes, and leaden wire or slender laths passed through them. The dwarf Dahlias may be pegged down so as to cover a bed in a systematic flower-garden; and thus treated, they have a most beautiful effect. But what are now called *Bedding Dahlias* are very different from what they once were. By the perseverance of florists in selecting and breeding from the sorts which most nearly resembled what they desired, they have obtained a race of varieties displaying masses of colour by plants of dwarf and symmetrical form; and whilst this applies to the larger flowered kinds the small neat flowered sorts called *Pompones* will doubtless also be subjected to the dwarfing process by selection, which has been so successfully acted upon as regards the others of formerly rambling and irregular habits of growth.

DAISY.—See *BELLIS*.

**DAMP STOVE.**—A name frequently applied by gardeners to the bark stove; but more properly belonging to the Orchideous house, the atmosphere of which is kept constantly surcharged with moisture.

**DA'PHNE.** — *Thymelæacæ*. — A genus of beautiful low shrubs, nearly equally remarkable for their elegant and often fragrant flowers and their bright red poisonous berries. The best known species of the genus is the common Mezereon (*D. Mezerium*), which is so general a favourite that it has pet names in almost every language. The French call it genteel wood, and pretty wood; the Italians, the fair plant; the Germans, silky bark; and even the grave Spaniards term it the lady-laurel. In our own language, Cowper, one of our sweetest poets in all that relates to sylvan scenery, thus beautifully describes it, alluding to the circumstance of its flowers appearing before its leaves:—

“Though leafless, well attired and  
thick beset  
With blushing wreaths investing  
every spray.”

There are several varieties, one with white flowers and yellow berries, and the others with red flowers of various shades. All the kinds are quite hardy, and will grow in any common garden-soil, but they prefer a rich loam, and a shady situation. In the nurseries they are generally propagated by seeds, which are often two years before they come up, unless sown as soon as they are ripe. When young plants are purchased, they should always be transplanted in October, as the sap begins to be in motion about Christmas; and the plants are almost sure to die (or at least to become sickly) if taken up after the sap has begun to move. The poison

of the berries and the inner bark is acrid, and the best remedy, if a child should unfortunately eat the berries, is swallowing oil, melted butter, or milk. The Mezereon is a native of the North of Europe, and it is sometimes found wild in England. The common and twin-flowered Spurge Laurels (*D. Laureola* and *D. pónica*) are evergreen bushy shrubs, with dark green glossy leaves, and greenish flowers, which they produce about Christmas. The first is a native of Britain, the latter of Asia Minor. They both require the same culture as the Mezereon, and the common Spurge Laurel thrives under the drip of trees, where few other plants will live. The dwarf Daphnes are generally somewhat tender, with pink fragrant flowers; and *D. odora*, the Chinese Daphne, is a very fragrant and beautiful greenhouse shrub. *D. Fortini*, a new species, introduced in 1844, forms a dwarf shrub, nearly allied to the Mezereon, and probably about as hardy as that well-known plant. In its native country it grows in the same situations as the Macartney Rose and *Wistaria sinensis*. The plant is a native of China, where its bark, which is extremely acrid and poisonous, "is used by the natives to produce blisters on the skin, particularly in cases of rheumatism."

**DATU'RA.**—*Solanaceæ*.—Strong-growing, large-leaved plants, generally with showy flowers. Most of the kinds are annuals; the best known of which are the common Thorn Apple, *D. Stramonium*, now naturalised in England; *D. Metel*, a dwarf species, common in gardens; *D. ceratocaulon*, a magnificent plant; and *D. Tatula*, the purple-flowered Thorn Apple. They should be all raised on a hotbed, and planted out in May. The

splendid half-shrubby plant, with large, white, tube-shaped fragrant flowers, formerly called *Datura arborea*, is now called *Brugmansia suaveolens*. This splendid plant may be grown in a large tub in the greenhouse, in heath-mould, during the winter; and in May, a pit may be prepared for it in the open air, about a foot wider in diameter than its tub. This pit should be partially filled with very rotten manure and decayed leaves; and the *Datura*, being turned out of its tub, and its decayed roots pared off, may be put into the rich compost prepared for it, when it will grow most vigorously. A plant treated in this manner, in 1835, expanded 1050 flowers from the middle of May to the middle of September. About the last week in that month the plant was taken up out of the ground in which it had been growing, its roots and its branches were cut in, and it was again placed in a tub, to be kept in the greenhouse till the following spring. It must be observed, that the pit prepared for the *Datura* must be in soil which is either naturally dry, from being of a gravelly or sandy nature, or which has been well drained; or that the bottom of the pit be filled with broken bricks, in order that the plant may be well and frequently watered while it is growing without danger of the roots rotting from too much moisture. Probably, if its roots and collar were well protected, it might be left in the open air without injury during winter.

**DAVIE'SIA.**—*Leguminosæ*.—Australian shrubs, with orange-yellow coloured pea-flowers; which should be grown in a greenhouse in well-drained pots, and in a soil composed of equal parts of sandy loam and peat. The pots will require to be often watered, but should have no

saucers, as the roots are easily withered by drought, or rotted by excess of moisture. The species are propagated by cuttings, struck in sand under a bell-glass, but without bottom-heat.

**DAY LILY.**—See *HEMEROCA'LLIS*.

**DEAD LEAVES.**—Few persons are aware of the great value of dead leaves to a florist; but the fact is that, when decayed, leaves form the best of all manures for flowering plants. In this state they are called leaf-mould or vegetable-mould; and under one of these names they will be found continually referred to in all books treating of the culture of flowers. To prepare this vegetable-mould, the dead leaves should be swept up in November, and laid in a heap in the reserve ground; the heap should be occasionally turned over, say perhaps once a month, and in about a year, or at any rate by the end of the second spring, the mould will be fit for use.

**DEADLY NIGHTSHADE.**—*A'tropa Belladonna*, a plant of little beauty, and a deadly poison.

**DECAYING LEAVES.**—Many trees and shrubs are very ornamental from the beautiful colours which their leaves assume in autumn; and among these may be mentioned the Ampelopsis, or Virginian Creeper, the different kinds of Rhús or Sumach, the Liquidámbar, the American Oaks and Maples, the Rhododendrons, Azaléas, &c. Many large trees, such as the Birch, the Beech, the Oak, and the deciduous Cypress, are also very ornamental, from the colours of their decaying leaves.

**DECIDUOUS CYPRESS.**—Though these trees, in favourable situations, become too large to be included in a work like the present, yet as they are often introduced in shrubberies when of a small size, it may be here ob-

served that they never grow large unless near water. In their native country (North America) they grow in swamps and morasses, and are there from seventy to one hundred feet high. When grown in dry soil, they became stunted, and rarely exceed ten or fifteen feet high; but their foliage assumes a beautiful red in dying off, instead of its natural yellow. Botanists have had some trouble to know where to place this tree, as it was first called *Cupressus disticha*, and the generic name was then changed, first to *Schubertia*, and afterwards to *Taxodium*.

**DELPHINIUM.**—*Ranunculácea*. The Larkspur.—Well-known annual, biennial, and perennial plants, with curiously-cut leaves and splendid flowers, which are either purple, pink, blue, or white, and never yellow. The Siberian Larkspurs are remarkable for the metallic lustre of their flowers, the hue of which resembles that of silver which has been tarnished by fire; and the Bee Larkspurs are both remarkable and interesting for the curious manner in which their petals are folded up in the centre of the flower, so as to resemble a bee, or a large blue-bottle fly. Several very showy species of Delphinium were introduced in 1855 and 1856, and particularly one from California, with bright scarlet flowers, *D. cardinale*. It is a hardy annual, and a most valuable addition to our flower-gardens. The Larkspurs will grow in any soil or situation; but a rich friable loam, and a situation open to the sun, suit them best. They are improved by the addition of a good deal of thoroughly rotten manure to the soil in which they grow, instead of being injured by it, as is the case with most other flowering plants. The seeds keep good a long time; and those of the annual kinds do

best sown in autumn, as, when sown in spring, they are a long time before they flower. The perennials are propagated by division of the root.

**DENDROBIUM.**—*Orchidaceæ*.—Splendid orchideous Epiphytes, of which some are best grown in pots, others on blocks of wood, and the drooping kinds in baskets suspended from the roof. Those grown in pots with peat and sphagnum should be well drained, and during their period of growth the peat or sphagnum should never be allowed to get dry. They are generally propagated by taking off a joint of the pseudo-bulb or stem, and planting it in turfy loam, well drained, or in peat and sphagnum. No water should be given till the plant begins to shoot from below; but in a short time, the green tips of its roots will be seen protruding through the loose soil in the pot, and hanging down over the rim. It is now in a growing state, and if well supplied with water, and kept in a damp atmosphere, it will increase rapidly; but care should be taken that its long roots are not injured, as those that are will wither away, and never recover. The most ornamental species are natives of Nepal and other parts of the East Indies, and some of them are hardier than many other kinds of Orchids. *D. nobile* is a most beautiful free-flowering evergreen species, of upright growth, and its flowers will keep in good condition for several weeks; it may be grown in a pot or basket with moss or peat. It has been exhibited by Mr. Williams with 300 flowers on a single plant.

**DEPTFORD PINK.**—*Dianthus Armeria*.—An annual species of Dianthus, with clusters of small pink scentless flowers, something like those of Löbel's Catchfly. A native

of Britain, generally found in gravelly soil, and growing freely in any garden where the soil is not too rich.

**DESFONTAINIA.**—*Solanaceæ*.—A very curious South American plant, with leaves like a holly, and long tube-like scarlet and yellow flowers.

**DEUTZIA.**—*Philadelphicææ*.—Slender-branched, graceful shrubs, with compound panicles of beautiful white flowers. They will thrive in any light soil in the open ground; but as they require a slight protection during winter, they are generally grown in pots, and kept in the greenhouse. *D. scabra*, the most common species, takes its specific name from the roughness of its leaves; which, in its native country, Japan, are said by Thunberg to be used by the cabinet-makers in polishing the finer kinds of wood. *D. gracilis* has pure white flowers in great abundance in the open air in May and June; and it will bear forcing so as to flower in winter in the greenhouse and conservatory, and is very useful on that account.

**DEVIL IN A BUSH.**—See NIGELLA.

**DIA'NTHUS.**—*Caryophyllacææ*, or *Silenacææ*.—A genus of perennial and herbaceous plants, containing several beautiful and well-known flowers. The most popular perhaps of these is the Carnation (*Dianthus Caryophyllus*), which is occasionally found in a wild state in Britain on old walls, particularly on the ruins of Rochester Castle, &c. In a cultivated state, the Clove Carnation may be called the breeder, or normal form, as it bears about the same relation to the variegated Carnations as the self-coloured Tulips and Auriculas do to the named varieties of those plants. The varieties of Carnations are divided into three kinds: the Flakes, which are striped with broad bands of two colours; the

Bizarres, which are striped or streaked with three colours; and the Picotees, which are much the hardiest, and are only bordered with a narrow margin of some dark colour, or dotted with very small and almost imperceptible spots. Carnations should be grown in a rich loam, mixed with sand or peat to keep it open, and a little rotten cow-dung, or vegetable-mould to enrich it. They do best in pots, and the earth should be pressed into the pots rather firmly. The plants raised from layers should be separated from the parent in August, and they may be potted three in a five-inch pot. The pots should be well drained, and the plants frequently watered till about the middle of October, when the watering should be gradually decreased. The layers, when first potted, may be kept in the open air; shading them for a few days after potting from the sun, and putting a hand-glass over them if there should be apprehended any danger of severe frost at night, though a little frost will not hurt them. About the middle of November, the plants should be removed to a cold frame, greenhouse or shed, where they should be kept merely protected from the frost, as they will bear a considerable degree of cold much better than too much heat. Here they may remain till March or April, according to the season, when they should be repotted, and after a few days turned into the open air. In May they may be either planted out in beds or removed to larger pots for flowering, which they will do in June and July. When the buds have formed, the plants should be well watered morning and evening, and in the evening they should be syringed over the leaves, always waiting till the sun is low. The

principal points of beauty in a Carnation are, that the stem should be strong and erect, the calyx well and regularly opened, the flower round, with the petals regularly disposed, the largest on the outside, and gradually decreasing in size to the centre, and the colours clear and distinct, those with a white ground being preferred. The stripes should also be broadest at the margin of each petal. As the calyx of the Carnation is very apt to burst on one side before it opens on the other, and as this spoils the shape of the flower, many cultivators gently divide the sepals with a pin as soon as the buds are fully swelled; and others slip a round piece of card-board, with a hole in the centre, over the bud while it is yet quite small, and push it up over the calyx, so as to force it to open first at the top. This piece of pasteboard is kept on after the expansion of the flower, and serves to keep the petals in their proper places. Others tie a strip of bass-mat round the lower part of the buds, to prevent them from opening improperly. The flower is also furnished with a stake to tie it to, and a paper or tin cap to shade it from the sun. July is the month for making layers. For this purpose, the outer, strongest, and lowest shoots of the plants should be preferred; and each shoot should be cut about half through, in a slanting direction, at a joint. A furrow should be made in the ground an inch or two deep, in which the cut stem should be buried, and fastened down with a bit of hooked twig, so as to have the wounded part completely covered, and the end of the layer upright, an inch or two out of the earth. The layer should be moderately watered as soon as it is made, and the plant

should be shaded after the operation. It may be observed with relation to Carnations grown in pots, that as their stems are generally very brittle when they are moist and succulent, it may be as well to set the pot in the hot sun for about an hour before the layer is made, to render the stalks flaccid. Carnations are also propagated by cuttings (see PIPINGS), and some sorts are raised from seed.

The Pink (*Dianthus plumarius*) is by some supposed to be a variety of the Carnation; but others make it a distinct species, though it does not appear to be known in a wild state. There are many kinds, but only what are called the laced Pinks rank as florists' flowers. The laced Pinks, to be esteemed by florists, should have their flowers about two inches and a half in diameter; and the petals should be white, with rose edges, and a broad ring of rich dark purple or crimson, as nearly black as possible, in the centre; the colours being all strongly marked, and quite clear and distinct. The culture of the laced Pink is exactly the same as that of the Carnation; but the common Pinks may be planted in the open garden, and treated exactly the same as the other hardy perennial border-flowers. The Tree Pink (*D. arboreus*) is merely a woody kind of Carnation; and the Mule Pink is a hybrid between the Carnation and the Sweet-William. They both require only the common treatment of border-flowers. The leaves of all the kinds of Pinks and Carnations are called by gardeners the grass.

The greenhouse species of *Dianthus* grow freely in light rich mould, with a moderate allowance of air and water; and they do not require any particular care in their culture. They are all very ornamental, and

they are propagated by cuttings, which strike readily, and do not require bottom-heat.

For the culture of *Dianthus barbatus*, see SWEET-WILLIAM. *D. chinensis*, the Chinese Pink, is generally treated as a hardy annual; but it may be preserved in dry soil for two or three years.

DICHOIRISA'NDRA.—*Commelineæ*.

—A curious stove-plant, which produces its showy flowers (which are dark blue, with a pure white centre and bright yellow stamens) from the root. It is a native of Brazil.

DICOTYLEDONOUS plants have seeds which separate into two or more cotyledons or seed-leaves, when they vegetate: and this class comprehends three-fourths of all the known plants in the world. They have all reticulated leaves, that is, leaves the veins in which appear like net-work when held up to the light; and the ligneous species have the thickness of their stems increased every year by successive layers of new wood, deposited on the outside of the old wood immediately under the bark. In all these points, and many others less conspicuous, they differ from the monocotyledonous plants, or those the seeds of which have only one seed leaf or cotyledon.

DICTAMNUS.—*Ruticææ*.—*Fraxinella*.—There are two species, the purple and the white, both hardy perennials, and both natives of Germany. The leaves have a pleasant smell, like lemon-peel, when rubbed, and the plant emits a phosphoric vapour, which may be easily ignited by a candle, and burns like gas. The flowers are very ornamental; and the plants will grow in any common garden-soil, and in any situation not immediately under the drip of trees. They are increased by division of the root.

**DIDISCUS.**—*Umbelliferae*.—The beautiful Australian plants, sometimes called by this name, and sometimes by that of *Trachymene*, are half-hardy annuals, that require to be raised on a hot-bed, and not planted out till May or June. In very cold exposed situations, they are generally grown in pots, and kept in the greenhouse; but they never flower so well as in the open ground. The best way to grow them is to sow the seed in autumn, as soon as it can be procured from the seed-shops, on a slight hotbed, to pot the plants as soon as they have formed their second pair of leaves, and to keep the pots in a frame or greenhouse, shifting the plants occasionally, till the following spring, when they may be planted in the open ground in a light rich soil, and they will flower beautifully.

**DIELYTRA.**—*Fumariaceae*.—The new name given to several kinds of *Fumaria*; as, for example, *F. cœmia*, *F. formosa*, &c. A very handsome species of this genus (*D. spectabilis*) was introduced by Mr. Fortune, from China, in 1846. It grows to the height of eighteen inches or two feet; the flowers hang down gracefully on one side. It requires a light rich soil, and is easily propagated by division of the roots, and by cuttings, and forms one of our most showy spring-flowering plants, suitable both for the open border and for the greenhouse.

**DIERVILLA.**—*Caprifoliaceae*.—A little North American shrub, with yellow flowers, something like those of the Honeysuckle in shape. It was formerly considered to belong to *Lonicera*. It is very hardy, and will grow in almost any soil or situation, sending up abundance of suckers, by which it is easily increased.

**DIGGING.**—The art of pulverising the ground so as to reduce it to a

fit state to be penetrated by the roots of plants; and also to render it pervious to the rain and air, without the aid of which neither seeds could vegetate nor trees grow. Digging (or ploughing, which is the same thing on a larger scale) is the first operation performed by man on a barren waste when he takes it into cultivation.

**DIGITALIS.**—*Scrophulariæ*.—The Foxglove.—If this plant were not a common British weed, it would be thought very ornamental; and, in fact, the Teneriffe species, *D. canariensis*, L. (*Isoplexis canariensis*, G. Don), with yellow flowers, and *D. scēptrum*, L. (*I. scēptrum*, G. Don), with orange flowers, are favourite greenhouse shrubs. They should be grown in a mixture of lime and peat, and may be propagated by cuttings or seeds, which they ripen in abundance. The hardy herbaceous species, which modern botanists have left in the genus *Digitalis*, are mostly natives of the south of Europe, and are all ornamental. They require a light rich soil, and are propagated by seeds.

**DILLWYNIA.**—*Leguminosæ*.—Australian shrubs, with heath-like leaves, and pea-flowers, which are generally scarlet and orange. They should be grown in pots well drained, and in a mixture of peat, loam, and sand; and they should be well and regularly watered. They are propagated by cuttings, which should be struck in sand under a bell-glass.

**DIMORPHOTHECA.**—*Compositæ*.—Professor De Candolle's new name for the Cape Marigolds, formerly called *Caléndula pluvialis* and *C. hybrida*.—See *CALÉNDULA*.

**DIONÆA.**—*Droseraceæ*.—Venus's Fly-trap.—A curious little American plant, nearly allied to the common Sundew, so often found in boggy meadows in different parts

of England. — (See *DRO'SERA*.) *Dionaea muscipula* has a scaly root, almost like a liliaceous bulb, and it sends out few fibres; it is, therefore, very difficult to keep, but it does best in a greenhouse, grown in moss, with a little mould at the bottom of the pot, and the pot kept standing in water, and covered with a bell-glass during the heat of the day. The glass is generally taken off towards the evening, and the plant allowed plenty of fresh air; but some gardeners do not think this necessary. The margins of the leaves are ciliated with long hairs, and when these are touched by an insect they collapse, and the insect is entrapped and imprisoned till it is dead, or at all events till it is motionless, and then the trap gradually opens, and the fringed margins of the leaves become unclasped. It is supposed that the flies this plant catches, are useful in nourishing it, though not essential to its support; and the experiment has been tried of feeding it with very small pieces of raw meat, which in a few days appeared surrounded by a kind of mucus, and soon disappeared. In the like manner, the remains of the bodies of flies are often found in the leaves of this plant and those of the common Sundew, though both plants will thrive, if kept sufficiently moist, without such nourishment. Propagated by seeds, which should be sown as soon as they are ripe, and by cuttings struck in moist peat soil, the surface of which should be covered with sphagnum.

*DIO'SMA*. — *Rutàceæ*. — Cape shrubs with hair-like roots, which require to be grown in pots in a greenhouse or room, in sandy peat, well drained, and frequently watered. Like all the Cape shrubs, they are easily killed by too much or too little water; and should never be suffered

to stand with water in a saucer, or to get too dry. They have a very peculiar smell, which some persons like, and which is said to be very wholesome; but which is generally thought to be very disagreeable, and which remains in gloves, or any other article of dress that may have touched the plant, for a long time. The Hottentot belles are said to use it as a perfume. The plants have heath-like leaves, and small but pretty flowers; they are propagated by cuttings, which root freely in sand under a glass.

*DY'FLAUS*. — *Scrophularinæ*. — The Monkey-plant. — The shrubby kinds of *Mimulus*, with yellow or scarlet flowers; which should be grown in a mixture of sandy loam and peat. They are natives of California, and like all the plants from that country, they are easily killed by the sun striking on the collar of the root; they likewise suffer severely from drought, or too much moisture. They are propagated by cuttings struck in sand, without bottom-heat.

*DIPLADE'NIA*. — *Apocynàceæ*. — *D. flava* is a very showy bright golden yellow flower, very like the *Allamànda*. It is a native of New Granada, whence it was first sent to England in 1845; but it has only lately flowered in this country. *D. crassinòda*, a stove climber, has splendid rose-coloured flowers, and *D. urophy'lla*, rose and yellow. They require light rich soil, or fresh loam, peat, and silver sand. The genus *Dipladènia* was formerly called *Echites*; and the species are generally climbing plants, shrubby towards the base. See *ROSE'TES*.

*DI'SA*. — *Orchidàceæ*. — Terrestrial Orchids, natives of the Cape of Good Hope. *D. grandiflora* has scarlet flowers, very ornamental;



and it continues long in flower. Greenhouse; in pots in sandy peat.

**DISEMMA.**—*Passifloraceæ*.—This is a genus of very handsome plants, natives of Australia, and nearly allied to the Passion Flower. The flowers of *D. aurántia* are remarkable for their change of colour, being nearly white in the bud, and when they first expand; afterwards assuming a yellow or buff tint; and finally becoming a brick red.

**DITTANY OF CRETE.**—*Origanum Dictamnus*.—A kind of Marjoram, with pink flowers; a native of Candia, and quite hardy, but should be grown in rich mould. On the Continent, a branch of it hung up in a room is said to keep away fleas and other vermin.

**DIVISION.**—Plants are said to be propagated by division when they are taken up and separated into portions; each portion having part of the root and one or more buds attached, if in herbaceous plants; or a root and part of a stem, if in shrubs or other ligneous plants. Hence, almost all herbaceous plants may be propagated by division, as they generally send up many stems from their roots; and also all those shrubs or low trees that send up suckers. In one sense, almost all ligneous plants may be said to be propagated by division; as cuttings are divisions of the stem or branches. Indeed, as every bud has the power, like a seed, of sending a shoot upwards, and roots downwards from its base, every plant may be divided into as many new plants as it has buds; but the common application of the term division, is to the dividing of those roots which send many stems or suckers.

**DODDER.** See *CUSCUTA*.

**DODECATEON.**—*Primulacæ*.—The American Cowslip. — A very pretty plant, to which Linnæus gave

a very strange name; Dodecateon signifying the twelve Roman divinities. The plant is a native of Virginia, and it is generally considered quite hardy; but it is very difficult to keep. It should be grown in the open ground, in a sandy loam, in rather a shady situation, and kept moist. One reason of its being lost is, that if the roots are once suffered to become too dry, they wither, and when moisture is given they rot instead of reviving; and another reason is, that as the stem and leaves die away in winter, the root is often dug up and thrown away as dead by jobbing gardeners, who are unacquainted with the plants of the garden they are working in. To prevent this, a mark of some kind should always be fixed to the plant in small gardens; or when a new gardener is employed, its situation should be pointed out to him. There are several garden varieties.

**DOG'S-TOOTH VIOLET.**—*Erythronium Dens canis* is a pretty bulbous-rooted plant, with spotted leaves and purple flowers. There is a variety with white flowers; and *E. americanum* has large dark yellow flowers. The European kinds will grow in any common garden soil, but require to be taken up every two or three years. The American species, which is much the handsomest, is apt to waste its strength in producing roots instead of flowers. For this reason it does best grown in well-drained pots, in rather poor soil, or, what is better, in sandy peat.

**DOGWOOD.**—See *CORNUS*.

**DO'LICHOS.**—*Leguminosæ*. — Climbing annual and perennial plants, from the East and West Indies, generally with purple or yellow pea-flowers. The pods and seeds are eatable, and in some cases

also the roots. Soy is made from the seeds of one of the East Indian species. They are generally grown in a stove; but most of the kinds will thrive in greenhouse heat, particularly if planted in the free ground in a conservatory, and trained up a pillar, or over trellis-work. The soil for all the species should be sandy loam. *D. Láblab* L. (*Lablavia vulgaris* D. Don), the Egyptian Bean, has splendid dark-purple flowers, and will grow well in the open air if treated as a half-hardy annual.

**DORO'NICUM.** — *Compositæ.* — Leopard's-bane. — Showy perennial plants, with large dark-yellow flowers, which look very well in a border, and which will grow with scarcely any care in any common garden-soil. One species, a native of Siberia, has white flowers; and another, *D. Bourgei*, has lilac or pinkish flowers.

**DORTMA'NNEA.** — *Lobeliaceæ.* — Professor De Candelles's new name for the common British species of Lobelia. It is an aquatic plant, and is generally found in ponds, or small lakes. There is an American species of the same habits, and both have blue flowers.

**DORYA'NTHEA.** — *Amaryllidaceæ.* — *D. excelsa*, the only species known, is a splendid Australian plant, sending up a flower-stalk twenty or thirty feet high, crowned with a head of bright scarlet flowers. The plant is herbaceous, and it requires a peat soil and greenhouse heat. It dies as soon as it has produced its flowers.

**DORY'CNUM.** — *Leguminosæ.* — A genus of little hardy plants, separated by Tournefort from the Lotus, or Bird's-foot Trefoil, and growing freely in any common soil. They are most suitable for rock-work.

**DOUBLE DWARF ALMOND.** — See **CH'RASUS.**

**DOUBLE FLOWERS** are particularly desirable to cultivate in gardens, not only from their beauty, but from the comparative certainty that exists of their producing their flowers every year, the plant not being weakened by ripening seed; as the stamens and pistil are generally all turned into petals. This is peculiarly the case with the double-flowered trees and shrubs; the double-flowered Peach, the double-flowered Cherry, and the double-flowered Hawthorn never failing to produce abundance of blossoms every year so long as the tree continues in health; while the single-flowered kinds generally fail in producing an abundant crop of blossoms every second or third year. The observation, however, does not apply so forcibly to semi-double flowers, as from only a part of their styles and stamens being turned into petals, they generally ripen abundance of seeds.

**DOVE FLOWER.** — Beautiful orchidaceous plants, the flowers of which resemble a dove sitting in her nest.

— See **PERIST'ERIA.**

**DRA'BA.** — *Cruciferae.* — Whitlow-grass. — Very low plants, admirably adapted for rock-work, as they are generally found in a wild state in the fissures and crevices of rocks and mountains. They have white or yellow flowers, and should be grown in sandy soil, on a bank, or in any open situation exposed to the sun.

**DRAC'ENA.** — *Asphodelaceæ.* — The Dragon Tree. — Eastern trees and shrubs with the habit of palms. They require a stove in England, and to be grown in peat and loam. The tooth-brushes called Dragon's-root, are made from the root of the tree species cut into pieces, about

four inches long; each of which is beaten at one end with a wooden mallet, to split it into fibres.

**DRACOCEPHALUM.**—*Labiata*.—Dragon's-head.—Several species of this genus are well known as garden flowers; particularly *D. moldavicum*, the Moldavian Balm, a hardy annual, and *D. canariense*, the Balm of Gilead, a greenhouse shrub, which should be grown in rich mould, and is propagated by cuttings. Some of the perennial species, such as *D. canescens*, *D. grandiflorum* (a native of Siberia), and *D. austriacum*, have large and splendid blue flowers; all these are quite hardy in any common garden-soil, and they are all propagated by seeds or by division of the roots.

**DRAINING.**—Draining in the open garden is effected either by surface-gutters, into which the water may run, which does not sink into the soil; or by underground channels formed by earthenware tubes called draining-tiles, or by tunnels built of brick or stone, or by open drains partially filled with small pebbles, broken stones or bricks, or even by faggots, branches of trees, or other similar materials, which will preserve a porous channel through which the water may percolate. The draining-tiles or other materials should not rise nearer to the surface than the common depth of dug ground, say about a foot or eighteen inches; and they need not be placed deeper than the usual depth of trenched ground, say between two and three feet. Plant-pots and boxes are drained by placing crocks or potsherds, shells, small stones, or cinders, over the hole in the bottom of the pot; and in large pots these materials may be covered with any fibrous matter, such as old matted roots, loose moss, pieces of turf, &c., which will prevent the earth from

mixing with the potsherds, stones, or other substances employed for draining. The great object of draining is to prevent the stagnation of water about the roots which rots the spongioles or elastic extremities of the fibres, and soddens or consolidates the earth in such a manner that the roots cannot penetrate into it, or if they do, that they decay for want of air. For most plants the best materials are old pots, broken into pieces little more than an inch in diameter, which gardeners call crocks or potsherds, as from their porous nature they form reservoirs of moisture, which will prevent the plants from ever becoming too dry. Cinders, on the contrary, are to be preferred for delicate or succulent-rooted plants, as the crocks retain so much moisture as to be injurious to the roots of these plants. The Australian or Cape shrubs should have their pots drained with two or three layers of crocks, as these will retain sufficient moisture to prevent the roots from withering, which even an hour or two of perfect dryness would occasion them to do.

**DRILLING.**—Sowing seeds singly in furrows made in straight lines; a mode of sowing very useful in culinary crops, especially those which require to be earthed up; and it is now frequently practised with flowers.

**DRO'SERA.**—*Droseraceæ*.—The Sundew.—British, American, and Australian plants, with hairy leaves and curious flowers, which require to be grown in moss, or peat, or heath-mould, kept moist, and during the heat of the day covered with a bell-glass. The hairs on the leaves support drops of water in the hottest weather, and being very irritable, close on any insect that may chance to touch them, like those of *Dionæa*

*muscipula*, Venus's Fly-trap, the leaf bending over the insect, and holding it in prison. The Italian liqueur called *Rossgolia* is said to take its name from one of the species being used in its composition. The Australian species from the Swan River, seeds of which have been introduced by Captain Mangles, promises to be very beautiful. All the kinds of *Drósera* appear to be very short-lived; and probably will not live longer than three or four years, whatever care may be taken of them.

**DRY STOVE.**—A hothouse, or plant structure, for tropical plants which do not require a moist heat, such as some of the kinds of *Cácti*, or other succulent plants. The temperature of the dry stove should not be less, even in winter, than between 55° and 65°, but in summer it may be from 10° to 20° higher. The plants are placed on shelves or benches; and they are grown in pots of sandy peat, or very porous soil, thoroughly drained, which in general should be kept much drier than the soil of plants either in the greenhouse, or in the moist or bark stove. The plants generally grown in a dry stove are the different species of *Melocácti*, *Epiphyllum*, *Cereus*, *Euphórbia*, *Stapélia*, *Agave*, *Mesembryanthemum*, *Crassula*, *Sedum*, *Sempervivum*, *Laròchea*, and several sorts of bulbs, such as *Lachenália*, *Oxalis*, &c.

**DUMB CANE.**—*Caladium sequium*.—A kind of *Arum*, requiring a bark stove, and more curious than beautiful.

**DUVA'DA.**—*Anacardiaceæ*, or *Terebinthaceæ*.—Chilian shrubs, which prove nearly hardy in the climate of London. They were called *A. myris* by Cavanilles, and *Schinus* by Ortega, both professors of botany at Madrid; and they are

occasionally found under these names in gardens and nurseries. The commonest kind, *D. dependens* Dec. (*A. myris polygámia*, Cav.), withstood the winter of 1837-8, in the Horticultural Society's Garden, with very little protection. The leaves of plants of this genus, if thrown upon water, will start and jump about in a very extraordinary manner; and they smell strongly of turpentine. The plants should be grown in a light dry soil, and trained against a south wall, where they can be protected by a thatched coping during winter. The flowers, which are white, are produced in small spikes, and they are succeeded by dark-purple berries.

**DWARF-PALM.**—*Chamaerops humilis*.—This plant is the hardiest of the Palm tribe, and it will succeed if planted out on a lawn, and slightly protected during severe frosts. It should be grown in rich mould, well drained and occasionally watered. When planted out on a lawn, a pit should be dug for it about two feet deep; at the bottom of which should be two or three layers of pebbles, to insure drainage, and then the pit filled up with rich sandy loam. Thus treated, and protected during severe winters by a moveable frame of canvas, stretched on hoops, or of basket-work, it will grow vigorously, and live many years.—See **PROTECTING**.

**DWARFING.**—In some cases, where there is very little room, it may be desirable to know how to obtain dwarf trees; though generally speaking, they are, like all unnatural objects, in bad taste, and rather disagreeable than pleasing. Wherever Chinese buildings are introduced, however, a few dwarf-stunted elms in China vases should be placed near them; as in China it is said that no garden is con-

sidered complete without several of these little monsters. The mode of making them is to take a ring of bark off one of the branches of a full grown Elm tree, and to surround it with earth wrapped in moss, which should be kept constantly moist, by water being thrown on it several times a day, or by a vessel being suspended over it, so contrived that the water may ooze out a drop at a time, and thus be continually and regularly falling on the moss.

In the course of a few weeks, the branch will have thrown out roots : and when this is supposed to be the case, it should be detached from the parent tree, and planted with the moss still round it in a small pot in very poor soil ; as soon as it begins to grow, it should be shifted into another pot a little larger ; and this shifting should be repeated several times, into larger and larger pots, always using poor stony, or gravelly soil, and giving the plant very little water. Thus treated, the plant will soon become a little stunted tree, bearing all the marks of old age ; and looking like a poor, decrepit, old man, bent double with age. It is obvious that other forest-trees might be dwarfed in the same manner ; so that a miniature forest might easily be formed, the Oaks assuming a gnarled and rugged character, and bearing acorns, and the Pines and Firs with rough furrowed bark, and covered with cones, and yet the whole not above two feet high.

Another mode of dwarfing ligneous plants is employed to throw them into flower or fruit. It is found that many stove-plants only bear fruit at the extremity of their branches, and that our hothouses are not large enough to permit them to attain the requisite size. Cuttings are there-

fore made from the points of the shoots ; and when these grow, other cuttings are made from their shoots. In this way small compact plants are obtained, the wood of which may be more easily ripened than that of large plants, and which seldom fail to produce flowers and fruit. The late Professor Van Mons practised this mode of dwarfing to obtain fruit from his seedling pears sooner than he could otherwise have done.

Another mode of dwarfing trees and shrubs is by grafting them on other low-growing species of the same, or some nearly allied genus : thus, for example, the common Horse-chestnut, *Aesculus hippocastanum*, may be grafted on *Pavia humilis*, which does not grow above three or four feet high : the Azarole, or any of the large American thorns, might be grafted on *Crataegus parviflora*, or *C. viridis*, which are about two feet high ; and the common British, or any of the large-growing American Oaks, on the Bear-oak, *Quercus Banisteri*, or *ilicifolia*, which grows to the height of about three feet.

Herbaceous plants, whether annual or perennial, may be dwarfed, by growing them first in very small pots, and shifting them into other pots, gradually increasing in size every time ; taking care that each pot shall be well drained, and that the soil used to fill up the pots shall be a rich sandy loam. Thus treated, and supplied with abundance, of water, which is not suffered to remain round the roots, and kept in an open situation, where they can have plenty of light and air, and not be exposed to cold winds, all herbaceous plants will become bushy and compact, and will produce flowers at the extremity of every shoot ; while, on the contrary, if

suffered to remain in small pots, they will become drawn up, with weak naked stems, and produce comparatively few flowers.

**EARTHS.**—Most amateur gardeners confound the words earth and soil; but they are quite distinct. There are only three primitive earths, viz., lime, sand, and clay; and these, by the admixture of other substances, and particularly of decayed animal or vegetable matter, become soils. Thus lime, by absorbing carbon, changes to chalk, and becomes the basis of all calcareous soils; and clay, mixed with a little sand and decayed animals and vegetables, becomes loam. When sand predominates in this composition, or when pure sand is added to it, the soil is called sandy loam, and this is the very best of all soils for vegetation; and when chalk or lime is added, instead of an extra proportion of sand, the soil is called calcareous loam, and is admirably suited for culinary vegetables, &c., and some kinds of flowers. Gravel is a kind of coarse sand; and sandstone, sand in a solid state. Peat is not properly an earth, but decayed vegetable matter, which has been saturated with water while the process of decomposition was going on.

**EARTH PEA.**—*Lathyrus amphicarpos*.—An annual Pea, which forms part of its flowers and pods under ground; and which, though not very beautiful, is often cultivated for its singularity. It is a hardy annual, and should be sown in March or April.

**EARWIG.**—*Forficula auricularia*.—A well-known insect, that, by a singular chance, has obtained a bad character for the mischief that it does not do; while that which it

really does passes comparatively without notice. Many persons destroy earwigs whenever they see them, from a fear of their creeping into the ear, and, by eating through the drum, occasioning deafness,—though this is what they cannot do; while but few persons, except florists, are aware of the great mischief that they do in flower-gardens, and that they should be destroyed on that account, with as much care as slugs, snails, or woodlice. They are particularly fond of attacking flowers in the bud; and they destroy, in this manner, great numbers of Dahlias and Carnations. They also attack bulbous-rooted plants, and all flowers that have succulent petals. Many expedients have been devised to catch these troublesome insects, and among others, troughs of water have been placed round particular plants. These are, however, of no avail, as the earwigs are furnished with wings, though they are so delicate in their texture, and fold into such little space, as to be rarely seen. Earwig-traps are also formed of hollow pieces of cane, or rhubarb-stalks, and sometimes of wood, or even of tin. The earwigs feed during the night, and creep into these hollow tubes in the morning, to avoid the heat of the sun; and consequently may be shaken out and killed, at any time during the day. The earwig differs in its habits from other insects, in regard to its young; as it sits on its eggs, and broods over the young ones, like a hen over her chickens: most other insects, on the contrary, die as soon as they have laid their eggs, which they leave to be hatched by the sun, and the young to take care of themselves.

**ECCREMOCARPUS.**—*Bignoniaceæ*.—*E. scabra*, Ruiz et Pavon (*Calampelis scabra*, D. Don).—A half-hardy

climber, of exceedingly vigorous growth, producing a great profusion of orange-scarlet flowers, and ripening abundance of seed. It will grow in any common garden-soil; and if cut down to the root in autumn, and covered with dead leaves, straw, or anything to preserve it from the frost during winter, it will shoot up again the following spring. It may be propagated by cuttings struck under a bell-glass; but it ripens seeds so freely, that it is most easily raised from them. They should be sown in autumn as soon as they are ripe, on a slight hotbed; and the plants, which should be kept in a frame or greenhouse, should be shifted two or three times till they are ready for planting out in April or May. They should be watered and shaded for a day or two, till they seem established; but after that they will require no further care, except a little training, if they are wanted to cover any particular part of the wall, &c.

**ECHEVERIA.** — *Crassulaceæ*. — Mexican or Californian plants, of the habit of growth of the House-leek, but generally with very ornamental bright scarlet or rose-coloured flowers, which are remarkable for retaining their beauty for two weeks after they have been gathered. *E. retusa*, introduced by Mr. Hartweg from Mexico in 1846, is a very pretty, half-shrubby, dwarf species, which produces its beautiful panicles of crimson and orange-coloured flowers in the greenhouse from November to April. It is easily increased by cuttings of the leaves. It should be grown in a mixture of light loam, with leaf-mould and plenty of sand.

**ECHINOCACTUS.** — *Cactaceæ*. — Round-shaped Cacti, which take their name from their resemblance in form and spines to a curled-up

hedgehog. There is, however, a great degree of confusion about them, and some species that are called *Echinocacti* by some botanists, are called *Melocacti* by others; and those with very long tube-shaped flowers have lately been called *Cæreus*, because the flowers in their construction resemble those of the other plants belonging to the genus *Cæreus*. Whatever botanic name may be given to them, all the round-shaped, ribbed, spiny, or porcupine Cacti, require the same treatment; that is, to be grown in vegetable-mould, mixed with pounded bricks, or lime-rubbish, and allowed bottom-heat where practicable. The pots should be drained with cinders; and the plants should be frequently watered, but the water should never be given overhead; as it will rot the centre, where there is an indentation, if suffered to lie there, and this can hardly be avoided, if water is poured all over the plants. They are propagated by seeds, which should be sown in silver sand, and placed in a warm shaded situation; or by cutting off the top of the plant, and after letting it lie a day or two to dry, planting it in silver sand, and not watering it; when it will soon throw out shoots, while the other part of the plant will form a new top. The young plants, when raised from seed, should not be watered when transplanted, for several days after transplantation. The flowers of all the porcupine Cacti are very ornamental; and those which are considered to belong to *Cæreus*, sometimes have the tubes of the flowers a foot long.

**ECHINOPS.** — *Compositæ*. — The Globe Thistle. — Hardy annual, biennial, and perennial plants, generally with blue flowers; that require only the common culture of their respec-

tive kinds, and which will grow in almost any soil and situation.

**ECHITES.**—*Apocynaceæ*.—Beautiful stove and greenhouse climbers, which grow freely in a mixture of sandy loam and peat; and which should be trained up the pillars, and under the rafters. They are propagated by cuttings, which strike readily. Several new species have been lately introduced by Messrs. Veitch, of Exeter, one of the handsomest of which is *E. atropurpurea*, a greenhouse climber from South Brazil, with very dark purple flowers. See **DIPLADYNIA**.

**E'CHIU'.**—*Boraginaceæ*.—Viper's Bugloss.—Perennial, biennial, and annual plants, generally with rich dark blue flowers; though some of the kinds that are natives of the Cape of Good Hope and the Canaries, have red, white, or violet flowers. They all require a light soil, and will grow well in either sandy or peaty loam; and they are easily propagated by seeds or division of the root.

**EDGINGS** are lines of plants, generally evergreens, to separate walks from beds or borders. The plant in most universal use for this purpose in British Gardens is the dwarf Box; a low evergreen shrub, which retains its leaves for two or three, and even four years, and bears clipping, so as to be kept not more than three or four inches high, two inches or three inches broad at the base, and one inch at top. For the mode of forming box-edgings, see **BU'XUS**.

Edgings to beds and borders are also formed of other materials, such as lines of bricks, tiles, or slates, or of narrow strips of stone, or even of wood; they may also be formed in various patterns of artificial stone, or of terra cotta, with good effect; but in general edgings of this kind

have a meagre appearance, especially in small gardens, though they have this advantage, that they do not harbour snails, slugs, or other vermin. In architectural flower-gardens, near a house, where the garden must necessarily partake of the character of the architecture of the building, stone or brick edgings are essential, and they should be formed of strips of curb-stone, bedded on stone or brickwork, so as never to sink. These stone-edgings should never be more than two or three inches wide, and they should not rise above the surface of the walk more than two inches; otherwise, when they rise higher, unless the walk be of more than the usual breadth, they give it a sunken appearance, which is very unpleasant to the eye. In forming edgings of brick, the bricks should generally be placed in the ground endwise; and the best effect is produced by using bricks that have been moulded with round ends on purpose. Edgings of tiles, to be kept securely in their places, should be set in concealed brickwork; otherwise they are apt to get out of place, and to have a ragged and temporary appearance. The same may be said of edgings of slate; and, in general, brick and slate edgings are much improved by a line of dwarf evergreens, planted close to them on the bed, or border side. Edgings of boards should be of oak, for the sake of durability; still they are objectionable as being expensive, and liable to warp; besides, wood in contact with soil gives the idea of decay. Edgings of terra cotta, or of *terro metallic*, which is the most lasting, or of artificial stone, are preferable to those above mentioned, as they not only appear more substantial, but are so in reality; and they can be moulded in any



pattern to suit the architecture of the place. Whatever substance is employed it should be placed on a solid foundation, and with this view a narrow trench may be cut out and filled with concrete, so as to allow the edging when placed to be at the proper height. If bedded in cement above the concrete so much the better.

Much of the beauty of all gardens, whether useful or ornamental, depends on the neatness and high keeping of the edgings; for whatever may be the state of the boundary fence, of the gravel, or pavement of the walks, and of the soil or plants of the borders, if the edgings have an uneven, ragged appearance, or if the plants be either too large or too small, the garden will be at once felt to be in bad keeping.

Hitherto nothing has been said of edgings of turf, because these are chiefly applicable to pleasure-grounds. To form them, the ground is first dug, and then levelled, so as to be about the intended height of the gravel, or half an inch below it. It is then firmly beaten, so that it may not sink afterwards; and the turf, which should be procured from a smooth, even pasture, is laid down, and rolled or beaten with a broad flat mallet, fixed in a long handle, called a turf-beater, so as to be rendered perfectly firm and even. The breadth of turf-edgings should seldom be less than one foot, because less than this width cannot be conveniently mown. After the turf has been laid down, a garden-line should be stretched along its margin, and the edges should be cut smooth with a spade or an edging iron. The walk may now be filled in with gravel to within an inch of the upper surface of the turf, and the soil of the border may also be raised to the same height. In the management

of the turf afterwards, the greatest care must be taken not to cut the edgings of the turf so as to show a line of earth, which always produces a raw and harsh appearance. It will be occasionally necessary to pare the edgings so as to maintain the original breadth of the walks, but generally speaking only the grass should be clipped close on the side next the walk, and so as to show a distinct line between the grass and gravel.

EDWARDSIA. — *Leguminosæ*. — Half-hardy low trees and shrubs, with pinnate leaves, and very curiously-shaped flowers (which are of a dark golden yellow) and seed-pods. The plants will grow well in the open air, against a wall, if protected during winter by a thatched coping. The soil should be sandy loam, and kept moderately dry, as too much moisture at the roots is apt to make the leaflets turn yellow and drop off. The species are all natives of New Zealand; and, on their first introduction, they were supposed to belong to the genus *Sophora*. They are propagated by cuttings, in sand, under a bell-glass. The handsomest species is *Edwardsia Macnabiana*.

EGG PLANT. — *Solanum Melongena*, L. — A tender annual, nearly allied to the Tomato, the fruit of which, when white, greatly resembles an egg. There are some varieties with violet-coloured, and some with dark purple fruit. All the kinds are eatable, if dressed like the Tomato. The seed should be sown in light rich earth, on a hot-bed, in February or March, and the young plants pricked out into pots, and shifted several times, till they are ready to flower. They may then be removed to the hot-house or greenhouse; but they will not ripen their fruit without a good deal of heat.

**ELMAGNUS.** — *Elæagnaceæ*. — The Oleaster, or Wild Olive. Curious-looking low trees, or shrubs, with bluish-green leaves, covered with a white silky down, that gives them a silvery look in the sunbeams. The flowers are small and tubeshaped; they are of a pale yellow, and rather fragrant. The fruit resembles the Olive in shape, and is of a dark reddish brown. There are only two hardy species, one of which is a native of the Levant, and the other of America; they both require a light rich soil, and a somewhat sheltered situation; and they are both propagated by seeds or cuttings. The Nepal species require a greenhouse.

**ELDER.** — See *SAMBUCUS*.

**ELEPHANT'S FOOT.** — See *TESTUDINARIA*.

**ELICHRYSUM.** — See *HELICHRYSUM*.

**ELSHOLTZIA.** — *Labiata*. — A plant of no beauty, the flowers of which somewhat resemble those of the common Mint, but are smaller and less conspicuous. The plant is only noticed here from the resemblance of its name to that of the *Eschscholtzia*, which induced Dr. Lindley to propose to change the name of the latter genus to *Chrysæis*; in the same way as it was proposed to change the name of the *Dahlia* on account of its similarity to *Dalea*. As, however, the German names are found to be quite as distinct as *Dahl* and *Dale*, the *Eschscholtzia* retains its appellation.

**EMBOTHRUM.** — *Protacææ*. — A very handsome evergreen shrub with racemes of bright scarlet tubular flowers. A native of the Straits of Magellan, whence it was introduced in 1853.

**EMPETRUM.** — *Empetreeæ*. — The Crowberry; spreading or trailing heath-like plants, adapted for rock-

work. They should be grown in peat-soil. *E. nigrum* is exceedingly prolific; berries black and shining. Although called the crowberry, it is said that neither crows nor ravens eat them; but rooks are certainly very fond of them.

**ENCHANTER'S NIGHTSHADE.** — See *CIROEA*.

**ENDOGENS.** — Monocotyledonous plants. The trees belonging to this division, such as the Palms, Tree Ferns, &c., increase very little in thickness as they advance in age; but their wood becomes gradually more solid, by the woody fibres formed every year in the interior of their stems. Trees of this kind have no medullary rays, and their trunks, when cut down, show none of those marks of the successive layers of wood which are so conspicuous in exogenous trees.

**ENKIANTHUS.** — *Ericacææ*. — Greenhouse shrubs, with very handsome arbutus-like pink and white flowers, which are produced from September to February. The plants are very difficult to manage. They should be grown in very sandy loam, mixed with a little peat; and they should be allowed plenty of air and light, with only enough of heat to exclude the frost. The pots should be well drained with crocks, and care should be taken neither to over-water the plants, nor to let them become very dry. They are propagated by cuttings of the ripe wood, which are struck in sand, under a bell-glass, but without bottom-heat; and which, when transplanted, should have balls of earth attached. For this reason, only two or three cuttings should be put into each pot, and these should be as far asunder as possible.

**EPACRIS.** — *Epacrideæ*. — The *E'pacrís* is a New Holland shrub, which the first settlers mistook for

a kind of Heath, and which is still called the Heath in Australia, where the true Heath (*Erica*) is unknown, The *Epacris* should be grown in a soil composed of turf-bog, chopped small, but not crumbled, and mixed with sand; and the plants do best in double pots, with moss, kept moist, stuffed between; as, if the hot sun comes on the outside of the pot, the tender roots, which soon become matted round the ball of earth in the pot, will be withered, and the plants will receive a severe check, if they are not killed. The pots should be well drained, by filling them about a third full of broken pots, or pieces of brickbat, the largest of which should not exceed two inches in diameter, and small lumps of freestone; and this will provide a reservoir of moisture for the nourishment of the roots. The plants should be potted high, like Heaths, as the collar is inevitably rotted, if buried, by the moisture which is essential for the roots. They require plenty of air and light, but not much heat; sufficient to exclude the frost in winter is quite enough for them. Cuttings of the young wood may be struck in pure sand, under a bell-glass, and with the aid of bottom-heat. They may also be propagated by layers, and often more readily than by cuttings. See *ERICA*, and *CUTTINGS*.

*EPHEDRA*. — *Genetaceæ*. — The shrubby Horse-tail, or Sea Grape. Very curious small evergreen shrubs, with jointed branches, and apparently without leaves. They grow best in sea-sand; and, when pegged down and kept clipped closely, they may be made to present the extraordinary appearance of green turf stretching to the very brink of the sea, and even covered by it at full tide. They are used for this purpose, Du Hamel tells us, in Africa,

to cover those dry burning sands, and to give the appearance of an English lawn where not a single blade of grass will grow. The berries are wholesome, and, when ripe, taste like mulberries.

*EPIDENDRUM*. — *Orchidaceæ*. — Parasitic plants, which should be grown in a damp stove or orchideous house, on pieces of wood hung up from the rafters for that purpose. The roots must be wrapped in damp moss, and tied on the wood, to which they will soon penetrate. These plants may also be grown in baskets, or cocoa-nuts filled with crocks and chopped sphagnum, and hung up in the same manner. They require a season of rest, which should be given when they are naturally inclined not to make growth, generally from November till February; and during that period the temperature may be 55° at night, and 60° by day. — Some of the finest species are *E. macrochilum* var. *roseum*, *E. verrucosum*, and *E. Stamfordianum*, the latter is especially desirable on account of the fragrance of its blossoms.

*EPIGÆA*. — *Ericaceæ*. — The Ground Laurel. — A little creeping plant, with white flowers, suitable for rock-work. It should be grown in sandy peat, and never suffered to become too dry. There is a pink-flowered variety, which was raised by the late Mr. Milne, of Stoke Newington.

*EPILOBIUM*. — *Onagraceæ*. — The French Willow-Herb. — A tall showy perennial, with stoloniferous roots, only suited to a shrubbery. It requires no care in its culture; the only difficulty being to prevent its overpowering everything else, when it is once planted in any situation not exceedingly dry. There are several wild species of *Epilobium* common in Britain, one of which, *E. hirsutum*,

is called by the odd name of Codlings-and-Cream. *E. alpinum* is a pretty little plant for rock-work. *E. angustifolium rubrum* and *E. spicatum* are pretty, and may be employed for cottage gardens, and indeed in others of a higher class with good effect.

EPIPHYLLUM.—*Cactaceæ*.—One of the genera formed out of the Linnæan genus *Cactus*, by Mr. Haworth, and comprising those *Cacti* that produce their flowers on their leaves. The genus *Epiphyllum* is, however, now given up, and the plants in it are called *Cereus* by botanists. *E. truncatum*, and *E. speciosum*, two of the best known species of this division of *Cacti*, are, however, still generally called by their original names of *Cactus truncata*, and *Cactus speciosa*. Both species are abundant flowerers, and require only greenhouse heat. *Cactus truncata* will grow grafted on almost any other species, and it will bear other species grafted on it. For culture, see *CEREUS*.

ERANTHEMUM.—*Acanthaceæ*.—Stove shrubs with very ornamental flowers, which in some of the species are of a bright blue, in others purple, as in *E. montanum*, and in others white, as in *E. albiflorum*.

ERANTHIS.—*Ranunculaceæ*.—The modern botanic name of the Winter Aconite. The Linnæan name of this plant was *Helleborus hibernicus*. This plant has a creeping underground fleshy stem, which sends up shoots from every bud; and when it is wished to propagate it by division, the young plants or suckers must be taken up with a portion of this tuberous underground stem attached, or they will not grow; and when they are planted, it should be in rather a dry, open situation, and they should not be too much watered, or the wounded

tuberous part will decay. The plant may also be propagated by seeds, which it ripens abundantly, but which do not flower till the second year. When the plant is to be divided, it should be done in June, or as soon as the leaves have withered, as otherwise the plant will wither from the decay of the tuberous part. When once established, the Winter Aconite spreads rapidly, and generally appears to change its position every year, as the flowers come up singly, and often far apart from each other, springing from buds in the underground stem, which in some situations grows to a great length, and produces few buds, when of course the flowers come up far apart; while in warm, open, and dry places, the tuberous stem being short and full of buds, the flowers appear in a cluster.

EREMURUS.—*Aspholdææ*.—A very handsome perennial plant, which produces its long racemes of sulphur-coloured flowers, with large bright orange anthers, in the open air in June. It is a native of Siberia.

ERICA.—*Ericaceæ*.—The different species of Heaths are among the most beautiful of our greenhouse plants, and are much more easily grown than is generally supposed. The principal cause of so many failures is, first, that Heaths are generally potted much too low, and thus the collar of the plant is frequently rotted; secondly, that sufficient attention is not paid to watering, as sometimes they are allowed to be sodden with moisture, from the pots being improperly drained, and at others kept much too dry, by irregular or imperfect watering; and, thirdly, that they are often grown on a stone shelf in a greenhouse, or in a balcony during

the summer, when a powerful sun striking on the pot is sure to scorch their delicate fibrous roots, or, in the winter, shut up among other plants, and scarcely allowed any air at all; in either of which cases they are sure to perish. These being the principal reasons why Heath's do not generally succeed, it is now necessary to describe what is considered the best method of cultivating them. The soil most suitable to Heath's is a mixture of three parts of well-sifted peat to one of white or silver-sand, thoroughly mixed; and if the plants are very large a small portion of loam may sometimes be added, though this is not often required. In potting Heath's, great attention must be paid to the drainage; and, in order to render it as perfect as possible, two or three moderate-sized pots should be put over the hole in the bottom of the pot; after which it should be filled about a quarter full with very small pieces of broken tiles; and over this there should be a thin layer of unsifted peat. Above the unsifted peat should be a layer of prepared peat and sand, and on this the roots of the Heath should be placed, and more of the mixture of peat and sand shaken in among them; the plants being so placed, that the collar may be above the level of the mould in the pot, when sufficiently full. The compost should be pressed tightly into the pot; but a little space should be left between it and the brim, to hold water; and as soon as the potting is finished, the plant should be set aside in the shade, or in a cold frame.

Heath's, to be well-grown, should always be kept in a frame, or a house, by themselves; as they are of too delicate a nature to bear the respiration from other plants, and they also require a very different

treatment. During summer, when in a frame, they should be allowed all the air that can possibly be given to them, and they should be frequently watered overhead, as the gardeners call it, when the sun is not upon them; as the winter comes on, less air should be given, and they should then never be watered over their tops; but still in fine weather a little air may be allowed to them, even during a slight frost. It may indeed be taken as a proverb, that Heath's like to feel the wind between every leaf. When grown in greenhouses, Heath's need not be watered overhead; but great care must be taken that the roots never get dried up, for if they do they seldom recover; indeed, these plants ought never to be put in greenhouses or rooms, except during the season of flowering. When they are kept in rooms or on balconies, their pots should each be plunged in another pot somewhat larger, and the space between the two filled with moss lightly put in, which should be kept moist, but not too wet. In very frosty weather, the only protection necessary for Heath's kept in pits, is a double mat thrown over the glass of the frame, and suffered to remain there till the frost is gone away; for should the frost affect the plants, and they should be afterwards exposed to the sun and air, they become what is called scorched, and they will either die, or lose the greater part of their leaves.

Heath's are raised from seeds, cuttings, or layers, but most frequently from cuttings, full details for making which have been already given.—(See CUTTINGS.) Heath seed should be sown, if foreign, as soon as it arrives; and if native, as soon as it is ripe. For sowing the seed, shallow pots or pans should be pre-

pared in the same manner as was described for potting, but with rather more sand; and the seed should be mixed with a little sand, and scattered over the surface of the mould; after which it may be watered, and set on a greenhouse shelf, where it may remain till the young plants are about an inch high, when they should be carefully taken up, and set round the edges of pots, about three in a thumb-pot, and then replaced on the shelf till they have grown sufficiently large to be potted off singly into small pots, when they should be allowed to remain a few days in the house till they are well rooted; after which they may be placed in the frame with the large plants. Heaths in pots should never have saucers to stand in, and they should be watered twice a day in summer, and once in winter.

ERINUS.—*Scrophulariæ*.—Only two species are known, one of which is a beautiful little plant with purple flowers, which grows naturally on old walls, and is admirably adapted for rock-work, as it continues flowering profusely all the summer. It is increased by seeds, or by dividing the roots; and it requires scarcely any soil to grow in, but the most suitable is peat, mixed with pounded bricks or lime-rubbish.

ERIOBOTRYA.—*Rosæ*.—*E. japonica*, formerly called *Mespilus japonica*, the Loquat-tree of the East Indies, is a very handsome tree for planting in a conservatory for its noble leaves. It bears clusters of white flowers and yellow fruit. In warm situations it will stand in the open air, but it requires protection from severe frosts. It should be grown in a rich loamy soil, and is generally propagated by grafting on the common Hawthorn.

ERIOPHORUM.—*Cyperæ*.—Cotton Grass.—The very curious

plants contained in this genus are natives of Great Britain. The commonest species, *E. angustifolium*, is by far the handsomest, and the tufts of long snow-white silky hairs, which envelope the seed, are so extremely ornamental, that the plant might be introduced advantageously in any marshy situation, or on the edge of a pond, &c., as all the species will only grow in moist places.

ERIOSTEMON.—*Rutæ*.—*E. buxifolium* is a very handsome New Holland shrub, which requires a greenhouse in this country, and produces its large showy flowers early in spring. The leaves resemble those of the Box tree, and the flowers are white, tinged with pink. *E. nerii-folium* is a very handsome species of this genus. A plant of it, exhibited at one of the meetings of the Horticultural Society of London, “formed a dense pyramid nearly five feet high, profusely clothed with white starry blossoms to the very pot.”

ERODIUM.—*Geraniæ*.—The Wild Geranium.—The genus *Erodium* differs from *Geranium* and *Pelargonium* in the shape of its seed-vessel. In all the three the seed-pod resembles the head and beak of a bird; in *Geranium* it resembles a crane's bill, in *Pelargonium* it is a stork's bill, and in *Erodium* a heron's bill. Besides these, the late Mr. Sweet divided the *Geraniæ* into a great many genera, the names of which it is useless to state here, as they are now seldom used. The *Erodiums* are dwarf annuals, and perennials, with pretty flowers, only suitable for rock-work. The tender kinds are grown in a mixture of sandy loam and peat, and the hardy ones in any common garden-soil; and they are increased by seeds, division of the roots, and cuttings.—See GERANIUM.

**ERY'SIMUM.**—*Cruciferae*.—Hedge Mustard.—Most of the kinds are weedy plants, generally biennials, seldom grown in British gardens. One species, *E. Perovskianum*, an annual, with deep orange flowers, introduced in 1838, has become popular from its beauty. *E. ibericum*, Dec. (*Cheiranthus armeniæcus*, Botanical Magazine), a perennial introduced in 1803, somewhat resembles *E. Perovskianum* in appearance, except that its flowers are yellow instead of orange. *E. Marshallianum* is a biennial or sometimes a perennial, eight to twelve inches high, with bright orange-yellow flowers; it rarely seeds, but may be readily propagated by cuttings in August or September. These plants grow best in sandy peat mixed with a little loam; but they will grow almost anywhere, and they are quite hardy.

**ERYTHRÆA.**—*Gentianaceæ*.—The Lesser Centaury.—Little pink-flowered plants, mostly annuals, suitable for rock-work. The seeds should be sown in autumn in the open border, and the plants removed in patches, with earth attached, to the rock-work in spring.

**ERYTHRI'NA.**—*Leguminosæ*.—The Coral Tree.—Stove and greenhouse shrubs, with splendid coral-coloured flowers. *E. laurifolia* and *E. Crista galli* will grow in the open air, and they will flower magnificently in a warm sunny border, if sheltered by a south wall, and so will likewise the new varieties *E. conspicua* and *E. profusa*; the former of these is of dwarf habit, with magnificent flower-spikes from 1 to 1½ feet in length, with rich crimson blossoms upwards of 2 inches in length. *E. profusa* has spikes 2 to 3 feet long, each set with upwards of 120 dark crimson blossoms. All these, together with

*E. Caffra*, may be cultivated to form gorgeous plants in pots for the conservatory, greenhouse, and mansion entrances. Gum lac, according to Dr. Royle, is the produce of *E. monosperma*. The soil should be a sandy loam, or loam and peat; and they are propagated by cuttings of the young wood struck in sand under a glass, but without bottom-heat.

**ERYTHRO'NIUM.**—*Tulipacææ*.—See DOG'S-TOOTH VIOLET.

**ESCALLO'NIA.**—*Escalloniaceæ*.—Beautiful shrubs, natives of South America, which are nearly hardy in the climate of London. They grow best in peaty soil, or in very sandy loam. *E. rubra* is generally trained against a wall, but *E. montevidensis*, which produces large clusters of white flowers, is grown as a bush, as is also *E. macrantha*, which produces very fine umbels of rose-carmine flowers. *E. pterocladon* and *organensis* are to be recommended as being more hardy than the preceding. Both kinds require protection from severe frosts.

**ESCHSCH'OLTZIA.**—*Papaveracææ*.—*E. californica*, and its variety, *crœcea*, or Chryseis crœcea, *E. tenuifolia*, annual, or sometimes biennial plants, with showy flowers, natives of California, on which account, and from the flowers resembling in shape those of the Poppy, the first species introduced was called the Californian Poppy. The seeds should be sown in the open border as soon as they are ripe, as, if the sowing be delayed till spring, the plants frequently do not flower till the second year. Sometimes they will live and flower two, or even three, years in succession, though this is very rarely the case.

**ETIOLATED.**—This term is applied to plants which have been blanched, and drawn up with weak and slender stems, by being kept too far from the

light, and not allowed a sufficient quantity of fresh air.

**EUCALYPTUS.** — *Myrtaceæ*. — Australian trees of enormous size, some species of which are grown in England as greenhouse shrubs. They should be grown in loam and peat, and are propagated by cuttings, which are very difficult to strike.

**EUCHARI'DIUM.** — *Onagrææ*. — *E. concinnum*, flowers deep red, and *E. grandiflorum*, flowers purplish-rose, are hardy free-flowering annuals, natives of California, nearly allied to the Clarkias. They should be grown in loam and peat.

**EUGENIA.** — *Myrtaceæ*. — The Rose Apple. — Handsome shrubs, grown as fruit trees in the East Indies, which produce their splendid flowers freely in British stoves. They should be grown in a mixture of two-thirds sandy-loam and one-third peat, and are propagated by cuttings of the ripe wood, which strike freely. *E. Ugni* is the hardiest of the genus, and which will grow against a south wall; it forms a handsome pot plant, ornamental when in fruit, which is of an agreeable sweet aromatic flavour.

**EUCO'NYMUS.** — *Celastrinææ*. — The Spindle Tree. — The common British species is well known for its curious and very ornamental fruit; but the American kind, *E. latifolius*, is much handsomer, both in fruit and foliage. It is a very valuable shrub for a small garden; as it will continue to thrive, and to produce abundance of flowers and fruit every year, for many years in succession, without increasing much in size, or requiring to be cut in. It is also ornamental in early spring, from the peculiar form of its buds and the richness of its dark red bractæas. All the kinds will grow in any common garden-soil, and they are increased by seeds or cuttings.

**EUPHORBIA.** — *Euphorbiæææ*. — Some of the kinds are British weeds, such as the Spurge Caper; but other kinds are thorny shrubs, requiring the heat of a stove in Britain, and producing flowers of a most brilliant scarlet. The most beautiful kind is *E. fulgens* Karwinski, *E. Jacquinæflora* Hort., which was introduced in 1836, by Mr. Rauch. The best plants are raised from seed; but cuttings may be struck by plunging them into the bark bed, and not covering them with a glass. The flowering plants should be grown in loam mixed with lime rubbish, or pounded brick.

**EUPOMATIA.** — *Anonæææ*. — A very remarkable Australian low shrub with yellow flowers. This plant is a very interesting one to a botanist, on account of the curious construction of its flowers, which were produced in this country in the Botanic gardens, Regent's Park, in March, 1856.

**EUTA'XIA.** — *Leguminosææ*. — Australian shrubs, with yellow and orange pea-flowers, which in England require a greenhouse. They should be grown in light peaty soil, and receive the general treatment of Australian shrubs. There are only two species.

**EUTOCIA.** — *Boraginæææ*. — Hardy annuals and perennials, which require the usual treatment of similar plants. (See ANNUALS and PERENNIALS.) They will grow in any common garden-soil, and the annuals should be sown in March or April, as, though they are natives of California, they are not injured by heat.

**EVENING PRIMROSE.** — See CENOTHERA.

**EVERGREENS.** — No garden should be without its due proportion of evergreens; and these plants are still more essential in small gardens than in large ones. Their advan-



tages are, that they afford a screen to secure privacy in winter as well as summer; that they preserve an appearance of verdure at all seasons; and that they do not disfigure the walks by falling leaves, which, where there is no regular gardener, render it very difficult to keep a place neat. They are also very useful in affording a rich background to those ornamental trees and shrubs which produce their flowers before their leaves; such as the double-blossomed Peach, the Almond, the snowy *Méspilus*, and *Magnolia* *conspicua*. It is the want of evergreens that gives the gardens in the neighbourhood of Paris, and most of the other continental cities, such an air of meagerness and poverty. But it cannot there be remedied, as few evergreens will resist the cold of their winters. This may appear strange to those who have experienced the heat of the continental summers; but the fact is, that their winters are as much colder than ours as their summers are warmer, and thus the average heat of the year is nearly the same. Alternate seasons of great heat and cold are favourable to deciduous plants, as the heat ripens their wood, and the cold gives them a season of complete repose when they have lost their leaves; but a moist temperate climate like that of Britain, is more suitable to evergreens, which continue in a growing state nearly all the year.

In street gardens, besides the evergreen trees and shrubs, it is advisable to select a few evergreen herbaceous plants, such as Pinks and Carnations, Wallflowers, &c., to give an agreeable effect to the beds during winter, when they are devoid of flowers.

EVERGREEN THORN.—The *Pyra-cantha*.—See *CRATÆGUS*.

EVERLASTING.—See *GNAPHALIUM* and *HELIOPSYCHUM*.

EVERLASTING PEA.—See *LA'THURUS*.

EXOGENS. — Dicotyledonous plants. The exogenous plants have received their name because the new wood of their trees and shrubs is deposited on the outside of the old wood, one layer being deposited every year. Thus the age of a tree may be counted by the number of its layers, shown by its wood when the trunk is cut down. The soil in which the tree was grown, and even the weather in the different years, may be guessed in the same manner; as the layers of trees grown in rich valleys are much thicker than those of trees grown in poor soils on mountains; and the layers deposited in damp cold summers are thicker than those of dry warm seasons. When trees have grown in a wood, with one side of the trunk fully exposed to the sun, and the other shaded by the other trees, a difference is very perceptible in the layers. These are always thickest on the side which has the greatest amount of healthy foliage. Exogenous trees have medullary rays in their wood, and leaves with reticulated veins. All the forest-trees of Britain, and other temperate climates, belong to this class.

FABIANA.—*Solanaceæ*.—*F. imbricata* is a very beautiful plant, a native of Chili, whence it was introduced in 1839; and, as Dr. Lindley observes in the *Botanical Register*, "it forms a small bright green shrub, with the habit of a Tamarisk, or rather of a *Thuja*, and when in flower is loaded with snow-white blossoms resembling those of some Heath." It is very nearly hardy, and will live and flower

abundantly in the open air, on a south wall, near London.

FAN PALM.—See DWARF FAN PALM.

FARFU'GIUM GRA'NDE. — *Asteraceæ*. — Introduced from China by Mr. Fortune. A remarkable foliaged plant. The radical leaves are large cordiform, of a brilliant green, with large bright spots and blotches of bright yellow. Hardy, but may be employed for the greenhouse with good effect.

FEATHER GRASS. — *Stipa pennata*. — A beautiful kind of grass, well worth growing to form tufts in flower borders, from its feathery lightness and graceful habit of growth. It should be grown in light rich soil; and it is propagated by seeds, or by dividing the roots.

FE'DIA. — *Valerianææ*. — Horns. — *F. cornucopia*, formerly considered to belong to the genus *Valeriana*, has red flowers and curious seed-pods, shaped like the figures we see of the Cornucopia, or Horn of Plenty. It is an annual, and the seeds only require sowing in the open border.

FENCES for flower gardens and shrubberies, are either such as are intended to be invisible, or, more properly, not acknowledged,—such as barriers of wire, or light iron rods, and sunk fences; or such as are intended to be acknowledged, and to form part of the landscape,—such as architectural parapets and hedges. Wire fences are commonly formed of light iron posts or stakes, through holes in which are stretched stout wires or slender iron rods. In forming wire fences of stakes and iron wires, there is no difficulty when the line of direction is perfectly straight, or consists of a number of straight lines joined together; but when the direction is curvilinear, some attention is requi-

site to fix the posts in such a manner as to permit the wires which pass through holes in them to be drawn quite tight. Iron or wire hurdles, are too well known to require description. When either hurdles or fences, composed of posts and rods of wire, are intended to keep out hares and rabbits, the lower parts of them, to the height of about two feet, require finer wires to be fixed to them, in an upright direction, at about three inches apart.

Architectural fences are used in small gardens, close to the house; and they should generally be low walls, of open work, in the style of the architecture of the building; and these walls may have piers at regular distances, terminating in vases, or other architectural ornaments, provided these are in harmony with the house. These walls, and indeed all other architectural fences, should be varied with shrubby plants planted against them, so as to harmonise them with the plants in the beds and borders within.

Hedges may either be of evergreens, neatly cut, so as to form living walls with standard plants at regular distances to imitate architectural piers; or they may be formed of a mixture of different kinds of flowering shrubs with evergreen standard low trees at regular distances. No plant makes a finer flower-garden hedge than the box, the standards in which may be formed of Cypressess, Junipers, or Arbor Vitæ. On a larger scale the Holly makes an excellent hedge, and the standards may be of the variegated kinds of holly. For a mixed hedge of evergreens and deciduous flowering shrubs, the Laurustinus, the Sweet-Briar, the Pyracantha, and the Cydonia japonica, with similar shrubs, may be used, with the lower kinds of American

Thorns (*Cratægus*), or the Chinese Crab (*Pyrus spectabilis*), as standards. A very excellent flower-garden hedge may be formed by training the Ivy, or any climbing plant, over a slight wire fence or trellis (fig. 14);




FIG. 14.—WIRE FENCE.

and its uniformity may be broken, if it is very long, by standards, at regular distances, either of Ivy trained on iron posts with umbrella tops, or of any kind of low deciduous or evergreen trees. The variegated species of Ivy, the *Ampelopsis*, and a number of other climbing shrubs, ligneous or herbaceous, also make beautiful hedges for shelter or separation in flower-gardens. The *Arbor Vitæ* and common Laurel alternating with the variegated variety, the narrow-leaved variety, and the Portugal Laurel, also make excellent flower-garden fences; as do the evergreen and variegated kinds of Privet, the variegated Holly, and the *Aticuba*. In short, there is scarcely any ornamental shrub that will not form a very suitable fence for a flower-garden, when carefully trained; and wire fences, in the summer season, may be covered with creeping or climbing annuals: such as the *Nasturtium*, the *Convolvulus*, &c., or even

the tall growing *Salvias*, *Petunias*, Sweet-Peas, and *Pelargoniums*. A very pretty fence of this kind may be formed by training the common *Mignonette* over a wire trellis; as it is well known that the *Mignonette*, if sown in autumn and kept during the winter in a greenhouse, may be trained the following season to the height of three or four feet. *Honeysuckles* also make delightful fences.

**FENNEL FLOWER.**—See *NIGELLA*.

**FERNs** are very ornamental in shrubberies, from their large and handsome leaves, and the curious manner in which these unroll when the plants first appear in spring. The most curious are the heart-shaped Mexican Ferns, (See *ALLOSURUS* and *NORTH CEVA*). Some of the other exotic ferns are very handsome, and hothouses have, in many cases, been set entirely apart for them. One of the most interesting of these is at the seat of W. Borrer, Esq., at Henfield, Sussex; the interior of which is formed into caves of freestone, in the crevices between which the Ferns grow. Ferns disposed in this manner would form a very elegant ornament for a grotto. Exotic Ferns are also the best plants for growing in the airtight glass plant-cases, now becoming so fashionable in large drawing-rooms. See *PLANT-CASES*. But the cultivation of Ferns is a growing fancy, and one which is being encouraged by the interest which ladies take in this tribe of plants on account of its elegant and graceful foliage, which is now very frequently introduced into nosegays; and it occupies an important place in the assemblages of vegetable productions for table ornaments, and other decorative purposes. This being the case, some remarks on Ferneries suitable for the growth of

hardy Ferns will doubtless be acceptable, especially as many very elegant species and varieties of them can be grown in a limited space, with a little care, and at small expense. As an example, we cannot do better than give some description of the Fernery at the Muséum d'Histoire Naturelle at Paris, constructed according to the ideas of Professor Decaisne. It is situated in an experimental square, with an Arbor Vitæ hedge, 10 feet high on the east and west sides; on the south there is an avenue of Chestnuts; its length is 30 feet, its width about 6 feet, its greatest height 4 feet; it runs north and south, and its sides present two slopes, one to the east, the other to the west. Its base is composed of an irregular mass of clinkers, such as may be obtained from the clearing out of furnaces, and this is covered with old peat soil thrown aside in repotting plants, and in this is placed pieces of freestone rock as irregularly as possible, with a view to effect and also to admit of the planting of the Ferns. A row of larger pieces of rock is placed all round the base, so as to prevent the sides from slipping. The Ferns are planted in the intervals between the stones, and in their crevices, the larger sorts being planted towards the top, and the smallest at the base. When planted, the soil was covered with a layer of moss in order to keep it moist. The creeping rooted sorts soon run into the moss, which serves to protect them, and also affords them nourishment. When much decayed a fresh layer is placed over the old without removing the latter. In dry weather, in summer, frequent watering is necessary. There is no danger from overwatering, the drainage, from the nature of the materials employed, being very good. In

autumn, when the fronds change colour, and become dry, they should not be removed, but left all the winter, and cleared away in the spring, when the new fronds begin to push.

During the summer, the same treatment will apply to the different species almost indiscriminately; and likewise during the winter if it is mild; but if after very wet weather severe frost should supervene, it will be advisable to give some protection by straw mats, or better, by a boarded covering, placed about eight inches above the Ferns. On this Fernery the following species have succeeded as well as could be desired:—

BRITISH FERNS. — *Adiantum Capillis-Veneris* (Common Maidenhair).

*Allosorus crispus* (Mountain Parsley Fern).

*Aspidium Thelypteris*.

*Asplenium Adiantum nigrum* (Black Maidenhair Spleenwort), *A. Halleri*, Do. var. *fontanum*, *A. lanceolatum*, *A. marinum* (Sea Spleenwort), *A. Trichomanes* (Black-ribbed Maidenhair Spleenwort), Do. var. *cristatum*, *A. viride* (Green Spleenwort), *A. Ruta-muraria* (Rue-leaved Spleenwort), *A. germanicum* (Alternate Spleenwort), *A. septentrionale* (Forked Spleenwort).

*Athyrium Filix-femina* (Lady Fern), Do. vars. *rheticum*, *depauperatum*, *crispum*, *multifidum*, *pumilum*, *Friselliæ*.

*Botrychium Lunaria* (Moonwort). *Cheilanthes odora*.

*Cystopteris fragilis* (Brittle Bladder Fern), Do. var. *Dickiana*, *C. obtusa*, *C. dentata*, *C. tenuis*, *C. regia*, *C. alpina* (Alpine Bladder Fern), *C. bulbifera*.

*Ceterach officinarum* (Spleenwort). *Dicksonia adiantoides*.

*Lastrea cristata* (Crested Buckler Fern), *L. spinulosa*, *L. dilatata*,

Do. vars. *tanacetifolia*, *nana*, *dumetorum*, *collina*; *L. Oreopteris*, *L. Filix-mas* (Male Fern), Do. vars. *pumila*, *cristata*, *polydactyla*, *L. rigida*.

*Lomaria spicant* (Hard Fern), Do. var. *cristatum*.

*Ophioglossum vulgatum* (Common Adder's Tongue).

*Osmunda regalis* (Royal or Flowering Fern).

*Polypodium calcareum* (Limestone Polypody), *P. Phegopteris* (Beech Fern), *P. Dryopteris* (Oak Fern), *P. vulgare* (Common Polypody), Do. vars. *serratum*, *auritum*, *acutum*, *bifidum*.

*Polystichium aculeatum*, *P. angulare*, Do. vars. *subtripinnatum*, *tripinnatum*, *cristatum*, *proliferum*, *P. Lonchitis*, *P. acrostichoides*.

*Pteris aquilina* (Common Brake or Braken).

*Scolopendrium vulgare* (Common Hart's Tongue), Do. vars. *multifidum*, *laceratum*, *crispum*, *palmatum*, *glomeratum*, *ramosum*, *ramosum majus*, *creno-lobatum*, *marginatum*, *simplex*, *fimbriatum*, *alcicorne*.

**HARDY EXOTIC FERNS.**—*Pteris cretica*, *P. serrulata*, *Adiantum pedatum*, *Cheilanthes odora*, *Doddia virginica*, *Lomaria alpina*, *L. chilensis*, *Onoclea sensibilis* (Sensitive Fern), *Onychium capense*, *Pycnopteris Sieboldii*, *Woodwardia angustifolia*.

**FERRA'RIA.**—*Irideæ*.—Cape tuberous-rooted plants with very curious flowers, and requiring the usual culture of similar plants.—See **CAPE BULBS**.

**FEVERFEW.**—See **PYRETHRUM**.

**FICA'RIA.**—*Ranunculaceæ*.—The lesser Celandine, or Pilewort.—A British perennial, with bright yellow flowers, differing from those of the common Crowfoot in their petals being pointed. It likes a moist

shady situation, and will thrive under the drip of trees.

**FIGUS ELA'STICA.**—The India Rubber tree.—A kind of Fig-tree, which yields the East India Caoutchouc; that used principally in making the waterproof clothing is, however, from Brazil, and is produced by *Siphona Cahuchu*, one of the Euphorbiaceæ. In both cases the trunk of the tree is wounded, and there flows from the wound a thick milky juice, which when hardened by exposure to the air, becomes the India rubber. *F. elastica* is a favourite stove-shrub in England, from its large size and curious leathery leaves; but it very seldom produces either flowers or fruit; and, when it does, they have no beauty. The plants should be grown in sandy loam, and they strike readily from cuttings.

**FIG MARIGOLD.**—See **MESEMBRYANTHEMUM**.

**FIGWORT.**—*Scrophularia vernalis*.—A British plant with yellow flowers, growing in moist places.

**FILICES.**—One of the natural orders which includes all the different genera of Ferns.

**FITNESS** in a garden, as in every thing else, is of the greatest importance in producing a good effect. By this term is meant the adaptation of plants to the situations fitting for them: for example, tall straggling growing plants, which have a very fine effect in a shrubbery when backed by evergreen shrubs taller than themselves, would entirely destroy the beauty of a small garden, laid out in regular beds. In the like manner, small plants, however beautiful they may be, are lost among others more robust growing. To avoid these incongruities, the best plan is first to ascertain, if possible, the habit of growth and general appearance of every plant before introducing it

into a flower-garden; and then carefully to consider the situation in which it is likely to look best. A little care and attention in this respect, with common plants, will have more effect in producing a beautiful flower-garden, than large sums laid out in the purchase of showy plants without it.

FITZ-ROYA. — *Coniferæ*. — *F. patagónica* is a noble hardy evergreen tree, with gracefully drooping foliage, introduced from Patagonia in 1850. When the plant is young the leaves have a glaucous hue; but when old they become of a deep green, and take somewhat of a triangular form.

FLAG-FLOWER, or Fleur-de-Luce. — English names for the *Fris*.

FLAX. — See LINUM.

FLORISTS' FLOWERS are those which it has been found may be grown to an extraordinary size and degree of perfection by taking great pains with their culture. The Dutch were the first who practised this art with their Hyacinths and Tulips; but their example has been followed by the florists of other countries, who, as they cultivate their flowers in the hope of winning prizes with them at flower-shows, may be said to use them as instruments for gambling. All the varieties of florists' flowers are named, and every year many new kinds are raised, which are eagerly sought for, and sell for enormous prices. It is thus desirable that all florists' flowers should either hybridise freely or vary very much from seed. The principal florists' flowers are the Hyacinth and Tulip, the Dahlia, the Auricula, the Polyanthus, the Carnation, and the Pink; but to these may be added the Ranunculus and the Anemone, and, of late years, the Geranium or Pelargoniums, the Heartseases, Calceolarias, Chrysanth-

mums, Fuchsias, Verbenas, Phloxes, Cinerarias, &c. Of all the kinds, the Dahlia is undoubtedly that respecting which there is most gambling and most rivalry. It may be observed, that the rules by which florists decide as to the merits of their respective flowers do not depend on any particular beauty of colour, and sometimes not even on form; but on certain arbitrary criteria which they have settled among themselves; as, for example, no Auricula or Polyanthus is admired that is what is called pin-eyed, that is, if the style projects beyond the stamens; and a perfect Dahlia should not show any green in the centre. Thus, as it requires to be a florist to know the full merits of florists' flowers, they are of comparatively little interest to amateurs.

FLO'S ADO'NIS. — See ADO'NIS.

FLOWER FENCE. — See CASALP'INIA.

FLOWER-BASKETS. — These may be constructed in many different ways; some being intended to appear as if set on the ground, and others to



FIG. 15 — WIRE FLOWER-BASKET.

be raised on pedestals. The former are generally constructed with curved pieces of iron furnished with sharp spikes for entering the ground, like the prongs of a fork; and these are placed so as to form a circle, with wires for climbing plants extended across it, like the handles of a basket. (See fig. 15.) The plants must be trained up a wire frame in the centre, and thence brought down the wires

to the curved pieces of iron forming the border of the basket. The basket may be filled up with flowers or not, at pleasure. Other receptacles for flowers may be wicker baskets, with the interstices stuffed with moss; or



16.—CHINA FLOWER-BASKET.

the jars in which grapes have been sent over; but when these last are used, or any other kind of vessel which is very deep in proportion to its breadth, the lower part should be filled with brickbats, pieces of freestone, and other similar materials, to within about a foot or six inches of the top. In all cases where flowers are grown in baskets and boxes, they should stand on a lawn, and the most luxuriant-growing kinds should be chosen, to hang down the sides of the vessel. Captain Mangles, whose taste in ornamental gardening is well known,

adopts the baskets *figs. 16 and 17*, for suspending from the roof of his greenhouse. The baskets are made of wire, with pots of earthenware or china inside. These baskets are alike suitable for the Creepers, Cè-



FIG. 17.—FLOWER-BASKET.

reus, Moneywort, and other common plants which produce their flowers on hanging stems, as for Epiphytes and orchideous plants. When the baskets are used for Epiphytes, the wire should generally be filled with moss, instead of having a pot placed in it.

FLOWER-GARDENS embrace a subject on which a volume might be written without exhausting it; but the present article will be confined to a few general observations, applicable in every case; and to a short notice of the different kinds of flower-gardens which have been, or are, in most general use.

All flower-gardens, to have a good effect, ought to be symmetrical; that is, they ought to have a centre, which shall appear decided and obvious at first sight, and sides; and all the figures or compartments into which the garden is laid out ought to be in some way or other so connected with the centre as not to be separable from it, without injuring the general

effect of the garden. All the beds and borders ought to have one general character of form and outline; that is, either curved, straight, or composite lines ought to prevail. The size of the beds ought also never to differ to such an extent as to give the idea of large beds and small ones being mixed together; and the surface of the garden ought to be of the same character throughout; that is, it ought not to be curvilinear on one side of the centre, and flat or angular on the other. In planting flower-gardens the same attention to unity ought to be kept in view. One side ought not to be planted with tall-growing plants, and the other with plants of low growth; nor one part with evergreens, whether ligneous or herbaceous, and the other part with annuals or bulbs. Flower-gardens which are intended to be ornamental all the year ought to have a large proportion of evergreen herbaceous plants distributed regularly all over them; such as Pinks, Sweet-williams, Thrift, Saxifrages, intermixed with some very low evergreen shrubs, such as Heaths, Whortleberries, Thyme, *Gaulthéria procumbens*, and a variety of similar plants. Flower-gardens which are intended to be chiefly ornamental in spring, ought to be rich in bulbs and early-flowering shrubs; such as the Mezereon, *Cydônia*, or *Pyrus japonica*, *Rhododendron dauricum atrovirens*, *Erica herbacea*, &c. Those that are intended to be chiefly ornamental in summer, should be rich in annuals; and those that are to be in perfection in autumn, in Dahlias. Flower-gardens on a large scale never look so well as when the spaces between the beds are of turf; but those on a small scale may have the spaces between the beds of gravel, and the beds edged

with box. It may be thought by some that a flowering plant would look better than box for the edgings to the beds; but no effect is ever produced without contrast: and as the box is always green, and seldom flowers, it forms a striking contrast to beds of flowers in which the leaves are nearly hidden by the blossoms. Gravel walks with stone edgings do not form a good contrast, as the colours of the gravel and the stone are too near that of the dry soil of the beds.

All the different kinds of flower-gardens may be reduced to the following:—

*The French garden, or parterre*, is formed of arabesques, or scroll-work, or, as the French call it, embroidery of box, with plain spaces of turf or gravel, the turf prevailing. The box is kept low, and there are but very few parts of the arabesque figures in which flowers or shrubs can be introduced. Those plants that are used, are kept in regular shape by cutting or clipping, and little regard is had to flowers; the beauty of these gardens consisting in the figures of the arabesques being kept clear and distinct, and in the pleasing effect produced on the eye by masses of turf, in a country where verdure is rare in the summer season. These embroidered or arabesque gardens originated in Italy and France, and they are better adapted for warm climates than for England: they are, indeed, chiefly calculated for being seen from the windows of the house, and not for being walked in, like English flower-gardens.

*The ancient English flower-garden* is formed of beds, connected together so as to form a regular or symmetrical figure; the beds being edged with box, or sometimes with flowering plants, and planted with herbaceous flowers, Roses, and one or two



other kinds of low flowering shrubs. The flowers in the beds are generally mixed in such a manner that some may show blossom every month during summer, and that some may retain their leaves during winter. This kind of garden should be surrounded by a border of evergreen and deciduous shrubs, backed by low trees; and in the centre there should be a sun-dial, a vase, a statue, or a basin and fountain.

*The modern English flower-garden* has the groundwork of turf, on which a system of beds is formed in such a manner as to constitute a symmetrical figure; or, if on a very large scale, groups of figures. The French flower-garden and the ancient English garden were chiefly calculated for being seen from an elevated situation, so as to show the whole at once; but the modern English flower-garden is calculated to be walked through, and seen by degrees. The beds are generally of roundish or curvilinear figures, and they should never be of figures with numerous narrow angles, or projecting points; because such parts can never be properly covered with plants, and therefore have always a bad effect. These beds are sometimes planted with a mixture of flowers alone, and sometimes with flowers and shrubs; but they are more generally planted, each bed, with one kind of flower or one kind of shrub, so as to produce masses of colour, or of shades of colour, which will harmonise with the masses in the other beds. The spaces between the beds should not be less than two feet, for the convenience of walking and mowing; and the surface of the beds should never be much higher than that of the turf, because, if it is, the beds will look like blotches on a lawn. Besides, the plants in the highest part of the bed (which should be in

the centre) being drier than those on the sides, they will grow with less vigour in dry seasons, and with too much vigour in moist seasons, if they are too much elevated; so that the plants in the garden will never produce a uniform surface throughout. Some beds in flower-gardens of this description are entirely filled with Roses which are often pegged down and kept low; and other beds are filled with low evergreen shrubs, or with deciduous shrubs which have conspicuous flowers, such as Rhododendrons, Azaleas, &c. For every garden of this kind there is, or ought to be, a basin of water, as well for effect as for watering the plants; and if the garden be on a large scale, there may be statues, vases, open and covered seats, rustic baskets, containing plants, rock-work, and a variety of other objects; but these require to be introduced with great caution, and afford an excellent opportunity for a lady to exercise her taste in their arrangement. In fact, these ornaments, if not well managed, destroy the simplicity and elegance of the garden, and do more harm than good. When flower-gardens are close to the house and are intended to be very highly kept, the beds are often surrounded with a low frame-work of wire or trellis-work, so as to give them the effect of baskets of flowers; and this has sometimes a very good effect. Very often handles of wire-work are appended to these baskets, over which are trained beautiful climbing plants, such as the Maurandyas and Lophospermums, which flower abundantly during the whole summer.

*The architectural flower-garden*, or Italian garden, always adjoins the house, and is bordered and separated from the rest of the pleasure grounds by an architectural parapet or wall.

—See FENCES. It consists of beds symmetrically arranged, with gravel or pavement between ; and the beds are bordered or edged with stone. In other respects, these gardens are treated like the old English flower-garden.

*Terrace gardens* are merely architectural-gardens, formed on platforms adjoining the house, on one or more levels, each level being supported by a terrace-wall ; but as they are chiefly adapted for mansions and places of considerable extent, where of course a regular gardener must be kept, it does not appear necessary to enlarge on them here.

FLOWERING FERN. — *Osmunda regalis*. — (Royal or Flowering Fern.) — A native of Britain, and one of the largest and handsomest of the British Ferns.

FLOWERING RASPBERRY. — *Rubus odoratus*. — A kind of ornamental Bramble, well-deserving of cultivation in flower-gardens.

FLOWERING RUSH. — *Butomus umbellatus*. — A British aquatic plant, producing pink flowers. When cultivated, the seeds should be sown in loamy soil at the bottom of the aquarium or pond where it is to grow, or in a pot plunged to a considerable depth ; or it may be increased by dividing the root.

FLOWER-POTS are commonly of a red porous kind of earthenware, which is much better for the plants than the more ornamental kinds sold in the china-shops ; which, from being glazed, and consequently not porous, are apt to retain the moisture so as to be injurious to the roots of the plants. When china flower-pots are used, they should have the bottoms pierced with several holes instead of one ; and they should be particularly well

drained, by being filled to at least a quarter of their depth with pieces of broken tiles. Glazed pots are most suitable for plants kept in balconies, where they are much exposed to the air, as they do not admit of transpiration from the sides, and consequently the earth contained in them does not so soon become dry. There are ten sizes of pots commonly in use in British gardens, varying from two inches in diameter to a foot and a half, which are distinguished as sixties, forty-eights, thirty-twos, &c., diminishing twelve every time, from sixties up to the largest size, which are called twos ; the same quantity of clay, called a cast, being used for the two large pots as for the sixty small ones. Besides these there are thumb-pots, about an inch in diameter and two inches deep, of which there are eighty to a cast ; square stone pots for raising seeds, or striking cuttings, and which are seldom used but by nurserymen ; and deep narrow pots for bulbous-rooted plants. Many other shapes have been invented to suit particular purposes, but the above are the only kinds in constant and regular use.

FLOWER-STANDS are generally constructed of wire, painted green ; and they are so contrived as to hold a number of flower pots. They are of various shapes ; some being only large enough to hold two or three flower-pots, and others, as *fig. 18*, consisting of several tiers, and holding almost as many plants as a small greenhouse. They vary very much in form, and may be designed to suit the taste. Though elegant objects in a garden or under a verandah, they are not well adapted for keeping plants in a healthy state ; as, from the pots in them being exposed to the sun and air on all sides, the roots

are liable to become withered by the alterations in temperature. It is therefore generally advisable to keep all the plants on flower-stands in



FIG. 18.—WIRE FLOWER-STAND.

double pots, or to fill the interstices between the pots in the stand with moss. Generally speaking, the observations already given respecting plants in balconies apply to plants kept on flower-stands.

**FLY HONEYSUCKLE.**—The upright shrubby species of Honeysuckle, such as *Lonicera xylosteum*, the common Fly Honeysuckle, and *L. tatarica*, the Tartarian Honeysuckle.—See **LONICERA**.

**FLY OROCHIS.**—See **O'PHRYS**.

**FORTUNE'A.**—*Juglandaceæ*.—*F. chinensis* is a most remarkable shrub, nearly allied to the Walnut-tree, with a cone like that of Fir, which the Chinese use to dye black. The genus is named after Mr. Fortune, who introduced the plant from China in 1849.

**FORFICULA.**—See **EARWIG**.

**FORGET-ME-NOT.**—*Myosotis palustris*.—A British plant worth cultivating for its blue flowers, as well as for its name. It is a marsh plant, and should be grown near water. *M. sylvatica* has smaller flowers, and of a paler blue. The other plants belonging to the genus *Myosotis* are known by the popular

English names of Scorpion-grass and Mouse-ear.

**FORKING.**—A mode of stirring the ground so as to admit air and moisture to the roots of plants, without disturbing or injuring them, which would be unavoidable if the ground were dug.

**FORSYTHIA.**—*Oleaceæ*.—*F. viridissima* forms a compact deep-green bush, with balsamic leaves, which, though smooth, are of a rich deep-green, without the slightest lustre. The flowers are of a bright yellow, and are produced in great abundance all over the tree. The plant is a native of China, whence it was introduced in 1847, and is a valuable acquisition to our early flowering hardy shrubs. It grows about eight or ten feet high in the north of China, and sheds its leaves in autumn.

**FOTHERGILLA.**—*Hamamelidææ*.—American dwarf shrubs, with large handsome leaves, and white fragrant flowers. The plants should be grown in a moist peaty soil, and they are injured by very severe frosts. The flowers appear before the leaves.

**FOUNTAINS** are of two kinds; jets, which rise up in a single tube of water to a great height, and then fall in mist or vapour; and drooping fountains which are forced up through a pipe, terminated by a kind of rose pierced with holes, called an adjutage, which makes the water assume some particular shape in descending. The principle on which fountains are constructed is, that if a large quantity of water be contained in a cistern, or other reservoir, in any elevated situation, and pipes be contrived from it to carry the water down to the ground, and along its surface, the water will always attempt to rise to its own level the moment it can find a vent.

When the orifice is large, this inclination is only shown in a kind of bubbling upwards, as the ascent of the water is prevented by the weight of the atmosphere above it; but where the orifice is small, the column of water will force its way through the air very nearly to the height of the large body of water from which it descended. The height to which a jet of water will ascend, therefore, depends on the height which the cistern that is to supply it is above the ground from which it is to ascend; and on the size of the orifice through which it is to issue. Something must however, be allowed for the resistance which even a slender column of water meets with from the air; and something is also lost by the friction of the water on the pipes it passes through, if the place from which the fountain is to play should be far from the supplying cistern. The time which the fountain will play depends on the quantity of water which the cistern contains; and the evenness and proportion of the ascending column of water on the diameter of the conducting pipe, which should be five times the diameter of the orifice. To explain this, we will suppose a cistern erected on a summer-house twenty feet high, and that a fountain is wished to play about a hundred yards from it in a right line. Then, if the diameter of the descending and conducting pipes be two inches and a half, and the diameter of the orifice for the jet be half an inch, the water will rise about eighteen feet high. It must be observed, that the water will rise to a less height in proportion to the distance which the fountain is from the cistern, the loss by friction being about a foot for every hundred yards; and also that if the pipes take any bend or curvature,

the loss by friction becomes greater. The time that the fountain will continue to play may be calculated by estimating the quantity of water the cistern will contain, as a jet of the size above described will discharge about sixty-five quarts a minute. The pipes should be of lead, a quarter of an inch thick; as, if they are too slight, they are very apt to burst and leak, from the great weight and pressure of the water; and they should be carried deep enough into the ground to be out of the reach of danger from frost. They should also be so contrived as to present an uniform slope towards the point from which the jet is to issue, to prevent an accumulation of air, or of sediment from the water in the pipes, either of which will prevent the fountain from playing.

Drooping fountains do not require the water to rise so high for them as for jets; and consequently the cistern need not be so much elevated. The beauty of fountains of this kind depends on the adjuncts, which are so contrived as to throw the water in many different forms. For example, some are intended to represent a dome, and others a convolvulus, a basket, a wheat-sheaf, and a variety of other devices. The water from these fountains is generally received in a shell, whence it forms a sort of miniature cascade to the basin below.

FOUR-O'CLOCK-FLOWER.—A kind of Marvel of Peru. See *MIRABILIS*.

FOXGLOVE.—See *DIGITALIS*.

FRAMES.—A frame in gardening may be described as a bottomless box with a cover of glass. The glass is fixed in a sash of convenient dimensions for being taken off and put on again at pleasure, and the sides of the box are of such a height as to admit of the growth of plants of a foot or more high. The

back of the frame or box is placed towards the north, and is generally about the height of two feet, and the frame being right-angled, the side towards the south is usually about one foot or fourteen inches in height. The ordinary width is from five feet to seven feet, and the length may be three or more times the width, divided into sashes of two and a half feet or three feet broad. The frame may be either set on a bed of the common soil of the garden, in which case it is merely used for the protection of plants from the weather, or it may be placed on a bed of fermenting manure, or other materials that generate heat, for bringing forward seeds or tender plants. Sometimes frames are placed against steeply sloping surfaces, or against walls; in which cases the object is to bring forward plants trained on the wall or sloping surface. Frames are of the greatest use in gardening: not only for protecting plants that are not quite so hardy as those usually planted in the open air, especially in the winter season (such as Alpines, and seedlings of hardy plants which are somewhat tender when young), but for germinating seeds. Frames on beds of dung are commonly called hotbeds, and are particularly useful for raising young plants from seeds, striking cuttings, and, in culinary gardening, for growing crops of such plants as Cucumbers, Melons, &c. As the air confined within the frame is apt to become suddenly heated by bright sunshine, or by the fermenting material when the open air is temperate, care must be taken to prevent the heat from being at any time greater than the plants will bear; and this is effected by raising the sashes, or lights, as they are technically called, by wooden wedges placed between them and the frame,

in the hinder or higher part of the frame, so as to admit of the escape of the excessively heated air. Hence it is desirable in all frames, where much delicacy of temperature requires to be attended to, to keep a thermometer within them; and in general, when the temperature within rises to 60°, to lift or tilt up the sash and to introduce the wedge between it and the back of the frame, so as to permit the heated air to escape. Frames are sometimes also set upon low brick walls, which may either be raised above the soil, if it should be naturally moist; or sunk into it, if it should be naturally dry. In such cases, instead of a box of boards, the box may be said to be formed of brick or stone, on the top of which is placed a framing of wood to receive the sashes. Such frames, or cold-pits, as they are called, are used to preserve half-hardy and greenhouse plants during the winter. All frames that are used in winter or spring should be covered during the night, especially when the weather is cold, to retain the heat generated by the sun, or the fermenting material, during the day. This covering is generally of bast-mats laid on the glass sashes; but it is rendered much more effective when the mats are kept an inch or two apart from the sashes, so as to retain between them a stratum of air, which, from its non-conducting power, greatly lessens the escape of heat through the mats. As mats are apt to absorb the rain instead of conducting it off, coverings of thatch formed of regularly drawn wheat-straw or reeds are considered preferable; though such roofings are scarcely worth attending to in a small garden, where there is perhaps only one frame. The best covering of all is composed of boarded shut-

ters, placed a few inches distant from the frame, and this species of shelter is at once neat and durable, and calculated to retain a stratum of air above the glass, while it effectually throws off the rain. They should be made light and of a portable size; and although they may be more expensive than mats in the first instance, they will prove ultimately cheaper.

FRANCISCEA. — *Scrophularinæ*. — Ornamental stove shrubs, generally with large, fragrant, dark purple flowers. *F. Hopeana* has violet flowers, changing to white, and they are very fragrant.

FRANCO'A. — *Francoacææ* or *Galacineæ*. — Handsome plants, most of which are nearly hardy, and may be treated either as annuals or perennials, and may be always raised from seed.

FRAXINE'LLA. — See DIOTA'MNUS.

FRENCH HONEYSUCKLE. — See HEDY'SARUM.

FRENCH MARIGOLD. — See TAGETES.

FRINGE-TREE. — See CHIONA'NTHUS.

FRITILLA'RIA. — *Tulipacææ*. — Hardy bulbous-rooted plants, which will thrive in any common garden soil; but which do best in sandy loam. There are several species. They are increased by offsets; and they may remain several years in the ground without taking up, and without receiving any injury.

FRITILLARY. — See FRITILLA'RIA.

FROGBIT. — *Hydrócharis morsus-rana*. — A very graceful British aquatic, with white flowers.

FROST is injurious to plants in proportion to their natural tenderness, and to their succulency, whether induced by art, by culture, or the season, or the accidental or natural moisture of the soil. Hence, to protect plants from frost, the first

step is the thorough drainage of the subsoil; and the next, the use of a soil composed of materials which will readily permit the escape of water, and which, of course, is always comparatively dry. On such a soil, if a frame covered with glass sashes be placed, and covered with mats, thatch, or boards, during severe nights, all half-hardy plants will be completely protected. But there are a great many plants in beds, and borders, and against walls, which cannot be conveniently protected by those means; and the roots or lower parts of the stems of plants thus situated may be covered with leaves, straw, litter, rotten tan, or any other dry non-conducting material which will retain air, and consequently prevent the escape of heat, and yet throw off water. In general, all herbaceous plants may be entirely covered during winter with such kind of materials; and all ligneous plants will be saved from being killed, if the root-stock, neck, or collar, be so covered. The branches and upper part of the stem, if left naked, may indeed be destroyed; but if the collar and the ground for two or three feet around it be thus protected, the life of the plant will be preserved, and the next spring, if the plant be cut down to the ground, it will spring up again from the collar. In general, the easiest ligneous plants to protect are those which throw up suckers; and the most difficult those which seldom shoot from the root or stool, such as the pine and fir tribe. The plants easiest to protect are those which are placed against walls; because the branches can be saved from the perpendicular cold by a projecting coping, and the roots by litter, leaves, rotten tan, &c. What are called Alpine plants, which in their native country are covered during

winter with snow, are best protected by being kept in pots and placed in what is called a cold frame; that is, a box covered with glass, placed on the common soil of the garden, and consequently without bottom-heat, but covered in severe weather with mats, thatch, or boards. Planting herbaceous plants and low shrubs in raised masses of soil covered with stone, technically called rock-work, is also a good means of preserving plants which are not quite hardy; because the mass of soil containing the roots is thus always more or less dry. One of the greatest enjoyments in gardening consists in growing the plants of warmer climates than our own in the open air; this, in the climate of Britain, is not so much to be effected by communicating artificial heat in the winter season, as by protecting them from frost and moisture. If all gardening were reduced to the mere growth of plants which were quite hardy, the art would lose half its interest. The nice point in this, as in many other cases, consists in overcoming difficulties; and the pleasure will be great in proportion as these difficulties appear at first sight to be insurmountable.

FUCHSIA. — *Onagrææ*. — The Fuchsias being all natives of South America, have till lately been generally treated as greenhouse plants, but the greater number are now considered to be among the more ornamental of our hardy exotics. They grow freely in the open air, and enliven our flower-gardens during the whole of the summer with their beautiful crimson flowers; and though they die down to the ground in winter, they spring up from the root the following May, and during summer flower profusely. They grow freely in a mixture of vegetable earth, or peat, sandy loam, and a

little well-rotted dung, which must be kept moist, but by no means sodden. All the species strike freely from cuttings of the young wood, without bottom-heat or a bell-glass; but they will do better with these assistants; and if planted round the edges of pots, in a rather more sandy soil than the mother plants have been grown in, and plunged into a slight hotbed and shaded, they will be fit to pot off in about a month or six weeks. Seeds are frequently ripened, and many very beautiful varieties and hybrids have been raised in this country. One of the finest of these hybrids is *F. Standishii*, raised between *F. globosa* and *F. fulgens*, and figured in the "Botanical Register" for 1840. Seeds vegetate freely if sown as soon as they are ripened in a rather sandy soil, on a little heat; and unlike most other perennial plants, they will, if grown strongly, flower the first year. *F. Chandlerii* is a splendid kind, and was raised by Mr. Chandler of Vauxhall, from seed of *F. fulgens*. The following kinds are the best, for growing in the open air, *F. globosa*, *F. discolor*, *F. virgata*, *F. microphylla* with small flowers, and *F. gracilis*; which last, though naturally a handsome shrub, about four feet high, may be trained to a single stem so as to form a small tree, in the following manner:—The first point is to select a healthy young plant that has a strong leader, and, taking it into a forcing-house, to remove its lateral branches and leaves to about half its height. The plant must then be kept constantly growing for two years, till it has attained the required height; during which period it must be frequently shifted into larger and larger pots, the lateral shoots and leaves being taken off as fast as they appear. When the plant has acquired the

height of eight or ten feet, it may be suffered to have a little rest; that is it may be taken out of the hothouse and placed in a greenhouse, when it will lose its leaves, and cease growing; for it must be observed, that while kept constantly growing by heat and moisture in the hothouse, it will retain its leaves during winter, contrary to the usual habits of the genus. The following spring, when the plant begins to grow, the top should be pinched off, when it will, in the course of a few months, produce a beautiful head, covered with flowers; and in this state, if set in the centre of a bed of Fuchsias on a lawn, or in a flower-garden, it will have a very pleasing effect. *F. fulgens* is a tuberous-rooted species, with herbaceous stems, which naturally die off after the plant has produced its seeds. When this is the case, the root requires to be kept quiet till the following spring, when it may be brought forward by putting it into a hothouse, or plunging it into a hotbed. Young cuttings of this species strike as freely as any of the other sorts; but they require care, as they are liable to damp off. In some cases a single leaf has struck the roots proceeding from the thickened part at the base of the petiole. *F. arborescens* forms, in its native country, a handsome low tree; but in England it proves much more tender than the other species, and succeeds best in the stove, where it deserves a place on account of its fine foliage and its terminal heads of lilac flowers. It grows very freely from cuttings, which often attain the height of five or six feet in one year. *F. discolor* is a very hardy species, a native of Port Famine, near the Straits of Magellan, but it is not very handsome, from the dingy colour of its flowers. *F. coccinea* is interesting from having been the

first Fuchsia grown in England, and the only one grown in this country for many years, it having been introduced in 1788; while the oldest of the others (*F. gracilis*) was not introduced till 1823. *F. coccinea* should be kept in the greenhouse. All the Fuchsias hybridise freely with each other, and vary very much from seed, which most of the kinds ripen every year. The fruit is a dark-purple berry, which when ripe is eatable. Among the Fuchsias that have been introduced within the last ten years may be mentioned *F. corymbiflora*, which is nearly hardy, *F. eximia*, *F. radicans*, a creeping or climbing plant like the Ivy, *F. macrantha*, *F. serratifolia*, *F. splendens*, *F. dependens*, and *F. spectabilis*, which last has been called the Queen of the Fuchsias; besides innumerable hybrids.

FUMARIA. — *Fumariaceæ*. — Pretty little plants with curiously-shaped flowers, which grow best in calcareous or sandy soils. The annual kinds should be sown with other annuals in March, April, or May; and the perennial species are increased by division of the root. Some of the kinds are now called Corydalis, and some Dielytra.

FUMITORY. — See FUMARIA.

FUNKIA. — *Hemerocallidaceæ*. — The Japan Day Lily. — Bulbous-rooted plants that were formerly considered to belong to the genus Hemerocallis. They are natives of China and Japan, and are grown in the open air in England. *F. cærulea* is quite hardy, and will grow anywhere, but *F. alba* requires a warm dry border, as do the newly introduced species. They are all very ornamental, and some of them are fragrant.

FURZE. — See ULEX.



**GAGEA.** — *Asphodelaceæ*. — Pretty little European bulbous plants, generally with small dingy yellow flowers. They should be grown in sandy soil, and will not require taking up in winter. The plants belonging to this genus were formerly considered to belong to *Ornithogalum*. *Gagea lutea* or *fascicularis* is a British plant.

**GALLIARDA.** — *Compositæ*. — Very showy herbaceous plants, natives of America, some of which are annuals, and others perennials. They grow best in peat soil. *G. Drummondii* or *picta*, and *G. pulchella*, or *bicolor*, as it is called in the seed-shops, are annuals; and their seeds should be sown on a slight hotbed in February or March; or in the open ground in the same months, and covered with a hand-glass, or a flower-pot turned over them, to preserve them if the weather should be frosty when they come up. It is necessary to sow the seeds of these plants in February or March, as they are a long time before they come into flower. The true *G. bicolor* is a perennial species, now called *G. lanceolata*, which should be grown in a peat border, and kept moderately moist; it is propagated by seeds or division of the root.

**GALEANTHUS.** — *Amaryllidaceæ*. — The Snowdrop. — The common British Snowdrop, *G. nivālis*, is well known both in its single and double state; but *G. plicatus*, the Russian Snowdrop, which has smaller flowers, is not so common. They both require a light rich soil, and they will thrive under the drip of trees. They are increased by offsets.

**GALEANDRA.** — *Orchidaceæ*. — Orchideous plants from Mexico and Guatemala. A variety of *G. Baueri* has very showy golden flowers.

**GALINSOGA.** — *Compositæ*. — *G.*

*trilobata* is a well-known showy Mexican annual, with rich orange-yellow flowers, which will grow in any common soil, and may be sown in March, April, or May. Like so many other plants, Professor De Candolle has changed its name; and it is now called *Sogalgina trilobata*.

**GARDENS**, in floriculture, may be described as separate scenes for the display of ornamental plants. The forms of these gardens or scenes are different; some being laid out in beds, the prevailing forms of which are curvilinear; and others in beds, of which the prevailing forms are rectangular, such as squares, parallelograms, octagons, polygons, &c. In some gardens, the beds have the forms of peculiar styles of architecture, such as of the Gothic, Grecian, Elizabethan, &c.; and these latter forms have given rise to what are called styles or manners in laying out Gardens. Hence we have gardens in the Gothic style, in which the forms of Gothic architecture prevail; others in which the Grecian forms prevail; and so on. In all these styles, the great art is to adopt such forms as are favourable to the cultivation and display of plants; and for this purpose, roundish beds, or such as have obtuse angles, are preferable to long narrow beds, or such as have acute angles; because the former are more convenient for stirring the soil, and the surface is more readily covered with plants, without, at the same time, causing the plants to spread over the boundaries. Hence, long narrow beds are generally covered to excess by the plants spreading over the outline on the walks or spaces between; and in acute-angled forms the angles are not sufficiently covered. See FLOWER-GARDEN.

**GARDENER.** — To keep a flower-

garden in perfection, it is necessary to have a good gardener, unless the amateur understands how the various operations of gardening are to be performed sufficiently well to be able to direct an indifferent gardener, or a common labourer, how to execute them. Thus, those persons who wish to have a show garden, will find it the best plan, if their grounds are large, to employ a good gardener, and to leave everything to his direction (for a really good gardener will not bear to be interfered with), allowing him to employ as many labourers as he may think proper; but if the grounds be small, this plan will be found too expensive; and it will be better to contract with a nurseryman to keep the garden constantly in order, and full of plants during the whole summer. The great enjoyment of gardening, however, in my opinion, is only to be obtained by the amateur who gardens himself, and who understands the principles or reasons upon which each operation is founded; and, therefore, I should recommend all persons fond of gardening, and especially ladies, who have sufficient leisure, not to attempt to have a show-garden, in which they can take comparatively little interest, but to manage their gardens themselves, with the assistance of a man to perform the more laborious operations. It sometimes happens that a manservant in the family, who is not overburdened with indoor duties, will answer this purpose; but it is generally preferable to employ a man who has been brought up as a gardener.

GARDENIA — *Rubiaceæ*. — The Cape Jasmine. — Greenhouse and stove shrubs, most of which are natives of the East or West Indies, with large and handsome flowers; which are generally white. *G.*

*florida*, the common Cape Jasmine, obtained its English name from its having been first brought to England from the Cape of Good Hope, where it was found cultivated in a garden, though it is really a native of China. *G. florida Fortuneana*, *G. andema*, *G. citriodora*, *G. Stanleyana*, *G. radicans*, are greenhouse species, highly to be recommended on account of the delicious fragrance of their blossoms. All the species should be grown in a compost of loam and peat, and they all require a moist heat. They are propagated by cuttings of the young wood, struck in sand, under a glass, and with bottom-heat. The cuttings may be put in about the end of July, and as soon as they are rooted they should be shifted into four-inch pots, placed in heat, shaded from bright sun till established, gradually exposed to plenty of light and air, so that they may be enabled to stand a temperature of from 50° to 55°. In February shift into five or six inch pots, according to the size of the plants, plunge in a hotbed with a bottom heat of 80°, and a top heat of 80° to 84°. Shift into larger pots as the roots require more room. By the end of June the plants will be of a good size, then place them in a cold frame or in a greenhouse to set their flower-buds. Syringe frequently, and keep the plants perfectly free from insects at all times. In the beginning of January remove some of the plants with the most forward buds to the stove or any forcing house, where their flower-buds will soon expand, the delicate white colour of the blossoms forming a beautiful contrast with the fine dark green foliage. Introduce other plants in succession; and thus a supply of Gardenia flowers may be kept up

for six months, affording the most fragrant luxury that can be imagined.

**GARDOQUIA.**—*Labiata*.—Half shrubby dwarf plants, mostly natives of South America and Mexico; one species of which, *G. Hookeri*, commonly called the Scarlet Thyme, which is a native of South Carolina, is very handsome. It should be grown in sandy peat and loam, in well-drained pots; and the plants should be plentifully supplied with water while they are in a growing state. It is nearly hardy, only requiring protection from frost, and it will continue flowering for several months. By frequent re-potting, and careful management, this plant may be greatly increased both in size and beauty; and it looks very well trained over a wire frame.

**GARLIC FLOWER**—See **ALLIUM**.

**GA'BRYA.**—*Garryaceæ*.—A hardy evergreen, introduced only a few years since, and which produced its very handsome long pendulous spikes of blossoms, or catkins, for the first time in England, in October, 1834. These spikes are produced in bunches of eight or ten together; and they are frequently above a foot long. It is quite hardy, and should be grown in a loamy soil, where it will continue flowering all the winter, in defiance of the cold. It is a most striking object, not only from the great abundance of its long, slender, graceful catkins, but from its dark-green, glossy and leathery leaves. It is readily increased by layers, or cuttings, struck in sand under a glass.

**GATES** are only necessary in flower-gardens, when they are inclosed by hedges, walls, or sunk or wire fences, and the gate ought always to bear some kind of relation to the fence. A wire or iron fence may have a wire or iron gate, but

it should be always of the simplest construction; a rustic fence should have a rustic gate; and a wall or a hedge commonly a close gate, or a boarded gate with stone or brick piers. Where a flower garden is surrounded by a sunk fence composed of a sunk wall and a fosse or ditch, the gate may in some cases be of iron between stone piers, and in others of light twisted wire. In all cases of this kind, the general harmony of the scene must be taken as a guide; and care taken that the gate neither appear too conspicuous, nor too insignificant.

**GATHERING FLOWERS** for bouquets or nosegays should always be performed when the plants are dry; otherwise, when tied together in a nosegay, the compressed leaves are liable to rot. The sprigs or shoots containing the flowers, or in the case of monocotyledonous plants, such as the Narcissus, the Hyacinth, &c., the flower-stems should always be taken off so as not to injure the leaves which remain on the plant; and in branching plants, such as the Rose, and all dicotyledonous herbaceous plants, the sprigs should be cut off at the back of a bud, otherwise in a short time an unsightly naked portion of the stem will remain on, which will at last wither, and disfigure the living plant. The branches should always be cut off, and not broken; as it is extremely difficult to break off a branch without injuring the portion that remains on the tree.

**GATHERING SEEDS** is an interesting operation; because it carries the mind forward to another year, and another generation. It should not be performed till the seed-pods are full-grown, which is easily known by the tendency of some of them to burst. It should always be done when the pods are perfectly dry,

and consequently, after the warmest part of the day rather than before it. The pods, after being gathered, should be laid in papers or in saucers, and exposed to the air in a dry place in the shade; and after being thoroughly dried they may either be tied up in papers without being opened, or the seeds taken out, the husks removed, and the clean seeds tied up and preserved in a dry place.

GAULTHERIA.—*Ericaceæ*.—Dwarf hardy shrubs, natives of North America, with flowers like the A'rbutus, and berry-like fruit, which is good to eat. Both the species should be grown in peat, or heath-mould; they are quite hardy, and will thrive under the drip of trees. They are propagated by layers. *G. Shallon* prefers a shady situation, where its roots may always be kept moist; and it will grow well and produce abundance of flowers and fruit in the closest parts of London.

GAU'RA.—*Onagraceæ*.—Curious hardy annual and biennial flowers, natives of North America, nearly allied to Clárkia, and requiring only the usual culture of their respective kinds.—See ANNUALS and BIENNIALS.

GAZ'ANIA.—*Compósitæ*.—Splendid herbaceous plants, of dwarf but vigorous growth; leaves deep shining green on the upper side, white and downy beneath. *G. elegans* is employed as a bedding plant; the flowers are produced in succession; they close at night and in dull weather, but when clear and sunny they expand and produce a very gay effect; they are bright orange yellow, marked inside on the base of each petal with a white and dark spot, the former giving the flower the appearance as if set round with pearls. Easily propagated by cut-

tings, and will grow in any good garden soil.

GEISSORHI'ZA.—*Iridæceæ*.—Tile Root. — Beautiful little bulbous plants, which were formerly considered to belong to I'xia. *G. Rochedana*, the Plaid Ixia, is particularly beautiful; and the whole plant is not above six inches high. The bulbs are not larger than a pea. All the species are natives of the Cape, and require a little protection during winter, though more from heavy rains than frost, if the bulbs are left in the ground at that season. If, however, they have been planted on a dry sandy bank, they may be left without any covering. All the species, from their low stature and the brilliancy of their flowers, look exceedingly well in pots. In this case they should be grown in sand and peat, or very sandy loam, and the pots should be well drained with cinders.

GELSE'MIUM.—*Apocýneæ*.—A pretty climbing evergreen shrub, generally kept in the greenhouse or conservatory, and generally known as *Bignônia sempervirens*, a native of South Carolina. It is grown in a compost of sand and peat, and it is propagated by cuttings struck under a glass.

GENE'TYLLIS.—*Myrtæceæ*.—A very showy little shrub from the Swan River. Introduced in 1854. A plant not quite three feet high had on it nearly two hundred heads of flowers, which look like miniature tulips; this gay appearance being however only the involucre or fleral leaves, which conceal the real flower. It is a hardy greenhouse plant.

GENI'STA.—*Legumindæ*.—There are above fifty distinct species of Genista, most of which will live in the open air in British gardens, but some of which are greenhouse shrubs. They all are very handsome, from

the profusion of their bright yellow pea-flowers. The greenhouse kinds should be grown in peat and loam, and are propagated by cuttings under a glass, which should be taken off frequently and wiped, or they will damp off. Most of the Genistas may be grafted on the Laburnum.

GENTIAN. — See GENTIAN'NA.

GENTIAN'NA. — *Gentianaceæ*. — Well-known plants, generally with pretty flowers and tonic properties. *G. acutis* is frequently used as an edging plant, and it is remarkable for the brilliant colour of its flowers, which are large, and of a deep mazarine blue. All the Gentians require abundance of free air, and will not grow well in the smoky atmosphere of a town. They should be grown in a light rich soil, and do best in a mixture of loam and peat, enriched with a little vegetable mould. *G. acutis* does best in peat alone. The perennial kinds are increased by dividing the root, and the annual ones by seeds, which should be sown as soon as ripe, as, if left till spring, they will not come up till the second year.

GEOMETRIC GARDENS. — This style of gardening is that in which the shape of the ground, of the beds, of the walks, and even of the shrubs, is regular or symmetrical; such as may be formed on paper by a rule and compass. The ground, if originally flat, is reduced to a general level surface, over which the beds, or borders, are distributed so as to form figures either simply regular, — such as squares and parallelograms, repeated one after another — or squares and parallelograms, and circles or ovals, or other curvilinear figures, — so arranged as to be symmetrical; that is to say, that one half of the figure formed by the whole shall correspond with the

other half. When the surface is naturally irregular, or on a slope, it is thrown into different levels, which are joined by steep slopes called terraces, generally covered with turf, and ascended and descended by stone steps. Each of the levels is laid out either regularly or symmetrically in the same manner as if the whole were only one bed; but the figures are of course smaller. Small trees or evergreen shrubs are distributed among the figures, and especially on each side of the main walks; and these trees or shrubs ought, in strict accordance with the style, to be cut or clipped into regular shapes; such as cones, pyramids, balls, candelabra, statues of men or animals, arcades, columns, or other architectural figures. In modern practice, this is generally neglected; but its omission is a defect, for cut trees are as essential to the geometric style, as having the ground cut or shaped into artificial surfaces. For the mode of cutting trees and shrubs into regular shapes, see TOPIARY; and for laying out the beds so as to form a regular figure, see PARTERRE.

GERANIUM. — *Geraniaceæ*. — There are few plants more easily grown, or that better repay the care of the cultivator, than Geraniums, or, as they are more properly called, Pelargoniums. All the half-shrubby kinds require a light rich soil, composed of well-rotted manure, leaf-mould, sand, and yellow loam, kept moderately moist. What is called rough potting, that is, filling the pots with chopped loamy turf, mixed with pieces of charcoal and with vegetable mould, is found to answer exceedingly well with Geraniums, as they never thrive so well as when they have abundance of air admitted to their roots. On this account also they thrive when treated according

to the one-shift system. A cool greenhouse, where the sashes can frequently be thrown off, and a balcony or window, not too much exposed to the sun, are the best adapted for them; and in such situations they may be kept during the whole year, only requiring, when in full flower, to be slightly shaded from the sun, to prolong the blossoming season. Geraniums are readily propagated at almost any season, by cuttings of the shoots, which will strike readily in the same soil as that in which the plants are grown, without either a glass or bottom-heat, but for fine specimens, June and July is the best time. The nurserymen, however, generally take their cuttings off the points of the shoots in the autumn, and plant them round the edges of pots filled with light rich soil, and plunged into a moderate hotbed. When the cuttings are sufficiently struck, which will be in about six weeks, they may be potted into single pots; or if there should not be room in the greenhouse for so many pots, they may be placed on a tolerably dry shelf, near the glass, till the following spring, when those that are wanted may be potted, and the rest reserved for planting out in the open ground, to bloom in the borders during the summer. Sometimes cuttings are made from the plants in the open air, by merely placing the cuttings in a warm border in face of a wall open to the south; and plants thus raised are much hardier than those struck in heat. If kept dry, they have been even known to survive a frost that has killed all their leaves, and indeed to live through the winter without protection. Gardeners and nurserymen who wish to raise show plants, put their cuttings in small pots in vegetable mould and sand,

and keep them in a cold pit till February or March, when they repot them in rich soil, after which the pots are plunged into a hotbed. As the side shoots grow they are tied to little sticks, to keep them apart; and to make the plant bushy, the tips of the shoots are taken off. As the plants grow they are usually shifted and re-shifted into larger and larger pots, the pots being filled up with loam, not too fine, and rotten dung. Immediately after the plants have flowered, they should be cut down nearly to the ground, or they will become drawn up, and will present an unhealthy appearance. By cutting them down, abundance of shoots will be obtained for propagation; and for this the strong-jointed shoots are to be preferred. The cuttings should be made about three inches in length, and inserted in well-drained pots or boxes filled with a mixture of fresh loam, leaf-mould, and silver sand. The old plants cut down after flowering should be repotted in October, and again in the end of January or in February. In this manner, good bushy plants are insured, and plenty of young plants provided for the next year. Many gardeners throw away the old plants as soon as they have done flowering, after cutting them down, and making as many cuttings as they can of the shoots; but others take the old plants out of their pots, and shaking the earth from them, hang them up by the roots, with the head downwards, till the time for repotting in spring. Geraniums may be thus kept quite dry in a cellar, hung up like plants gathered for their seed; or they may be laid in rows in a cellar, with their roots covered with dry sand. In both cases the plants should be repotted in February in a rich soil of loam and rotten dung, and the pots plunged

into a hotbed to excite the plants to grow. Many hundreds of beautiful varieties of Geraniums are cross-breeds raised from seed; that is, those raised from a plant, the stigma of which has been fecundated by pollen from the anthers of another variety of the same species. In this respect, cross-breeds differ from hybrids, which are raised from seed fecundated from a plant of a different genus, or, at any rate, a very different species. The use of cross-breeding is thus rather to improve plants, by crossing them with others having a better habit of growth, or more brilliant-coloured flowers, than to raise new and striking varieties; and, for this purpose, the plants chosen for the parents should be such as would be greatly improved by admixture with another. For example, a fine, bright-coloured flower, on a plant of a loose and bad habit of growth, might be crossed by a plant of a dwarf habit, the flowers of which were not beautiful, and so on. To judicious crossing as practised by the late Mr. Beaton, we owe many of the varieties of what are called *Bedding Geraniums*, by means of which our flower gardens are rendered so brilliant during the summer, and till frost sets in in autumn.

The following mode of grafting Geraniums is abridged from the "Floricultural Magazine" for May, 1840. The stocks should be of the strongest and healthiest kinds, about two or three years old, and rendered bushy by frequent transplanting, and pinching off the leading shoots. The year before they are wanted as stocks, they should be cut down in August to within three eyes (or buds) of the base of each shoot. In the following May the stocks should be transplanted into fresh pots, a

size larger than their old ones; and early in June, they should be "cut down to a clear grown part of the shoot, about two inches from the last year's wood." The stock should then be left two or three days to bleed, that is, to suffer the exuberant sap to escape; after which it may be grafted in the whip or side manner, without a tongue; care being taken to choose "well-ripened shoots, about three inches long, for scions." The principal difficulty arises from the succulent nature of the Geranium shoots; as, if the bark be bruised or wounded during the operation, the grafts will not take; and they are also very easily broken off afterwards.

Standard Geraniums are now grown by many gardeners, and have a striking and novel effect. They are produced like Standard Fuchsias, by keeping the plants constantly growing for two or three years, and as constantly depriving them of their side shoots. Geraniums thus treated should be planted out where the climate will permit, or where they can be protected; or, if kept in pots, it should be on the one-shift system, and the soil they are grown in should consist of large pieces of loamy turf, mixed with vegetable mould and pieces of charcoal. These plants look very well on a lawn.

The herbaceous and tuberous-rooted Geraniums require a much more sandy soil; and, when they have done flowering, they should be put on a dry shelf, near the glass, and very sparingly watered till the spring, when they may be repotted, and treated as above. These may be propagated by cuttings, or division of the roots, in rather dry and sandy soil, and they rarely perfect their seeds in our greenhouses.

The old genus *Geranium* has been

divided by modern botanists into fifteen genera; three of which are quite distinct, and have been already mentioned under the head of *Erodium*. The kinds usually grown in greenhouses belong to the genus *Pelargonium*; and of these there are nearly six hundred distinct species, besides innumerable cross-breeds, hybrids, and varieties.

GERMANDER.—See *TEUORIUM*.

GEROP'GON.—*Compositæ*.—Old Man's Beard.—The best known species of this genus, *G. glaber*, is a native of Italy, and is a very curious plant. It is an annual, having a smooth stem and leaves, and growing about a foot high. The flowers are fresh-coloured, and expand in the form of a star only when the sun shines upon them. The seeds are very curious, and it is from them that the plant takes its English name. They should be sown in the open border, in any common soil, in March or April, and the plants will flower in July and August.

GE'SNERA. — *Gesneriæ*. — Showy hothouse plants, generally with scarlet flowers. They require a light rich soil; and are propagated by cuttings struck in sand under a bell-glass with the aid of bottom-heat.

GE'UM. — *Rosæ*. — Avena, or Herb Bennet. — Perennial plants, natives of Europe and America, with very handsome flowers. *G. Quellyon* Swt. (*G. coccineum* Bot. Reg.) is a splendid plant, a native of Chili, with large orange-scarlet flowers. All the species are hardy, and require a light rich soil; they are propagated by seeds, or by dividing the roots. Some of the species are now called *Sieversia*; the seed vessels of *Geum* being hooked, and those of *Sieversia* ending in a straight feathery point.

GI'LIA. — *Polemoniæ*. — Beautiful annual flowers, natives of California, which only require sowing in spring or autumn in the open border. This genus is now (1857) united with *Leptosiphon*. See CALIFORNIAN ANNUALS, and ANNUALS.

GITHA'GO. — *Silenæ*, or *Caryophyllæ*. — The Corn Cockle. — A British weed, sometimes cultivated in flower-gardens.

GLADES are open spaces of turf among shrubs or trees of irregular shapes, without definite boundaries, so as to give the idea of something beyond them, of which the extent cannot be guessed. They should vary in width, and be of the most irregular shapes; the types being the open glades which appear in forest or copse-wood scenery. Their beauty in pleasure-grounds depends much on the smoothness or high keeping of the turf, and on the varied ground outline of the branches of the trees or shrubs which repose on it.

GLADI'OLUS. — *Iridæ*. — The Corn Flag. — The Gladioli or Corn Flags are bulbous plants with long spikes of showy bell-shaped flowers; and they are nearly all natives of the Cape of Good Hope. The bulbs, or rather corms, are solid, and do not require taking up if they can be kept dry during winter. The best mode of doing this is by fixing a frame with sashes over them, as this allows of giving them air when fine. When grown in pots the soil should be very sandy loam enriched with decayed leaves, and the bulbs should be kept entirely without water, from the time the leaves decay in autumn, till they begin to grow the following spring. Many cultivators take the bulbs out of their pots every September, and renew the soil; but others only take them up every third year. At Spofforth,



Yorkshire, where the soil is a rich yellow loam, there are clumps of Gladioli which have been left undisturbed in the open ground for more than twenty years, and which flower magnificently every summer. The only protection given, is covering the clump in autumn two or three inches thick with dry leaves, which are swept up from the neighbouring shrubbery, formed into a heap, rising highest in the centre, and sloping down on every side. Similar treatment is given to beds of Scarlet Gladioli in the garden at Blair Adam in Scotland, which are exceeding splendid. A great number of very splendid hybrid Gladioli have been raised by Mr. Cole, gardener to J. Wilmore, Esq., of Edgbaston, near Birmingham, principally between *G. cardinalis*, and *G. psittacinus*, or *G. natalensis*, which in the length of the spike, the size of the flower, and the brilliancy of the colours, surpass anything of the kind that I have ever seen.

GLASS CASES are of two kinds—those which are intended to cover plants in the open air, and those which are used for covering plants in rooms or on the outsides of windows, balconies, &c. Glass cases for the open air may be made of any convenient size or form so as to cover the plants to be protected; and sometimes they are glazed on every side, though at others they are placed against a wall, and only glazed in front and at the ends. The framework may be of wood, or of iron or zinc, so contrived as to separate into pieces, and join together in any temporary manner, in order that the gardener may be able to admit air, or to remove the case entirely at pleasure. A common hand-glass may be designated the smallest description of glass case, and a portable greenhouse the largest.

Glass cases for rooms consist of two parts—a body or box containing the mould and plants, and a hand-glass, or glazed case, for placing over it. This case, which may be square or oblong, two feet wide, and four or five feet long, should fit into a groove in the box containing the plants; and the plants, when planted and watered, will require no more attention for several weeks, or even months, according to the kind intended to be grown. Hyacinths planted in such a case in November, and placed in a room, will require no attention, except, perhaps a little water, till they have done flowering in the following March. Ferns and Cacti will require no attention for a year; but plants which come soon into flower, such as China roses, or indeed any plants which are coming into flower when planted, require to be removed when they have done flowering, and to be replaced by others. The glazed frames for such cases should be of mahogany or metal, and of neat and accurate workmanship: and plate, or German glass, ought to be employed.

GLASTONBURY THORN.—A variety of the common Hawthorn, (*Crataegus Oxyacantha præcox*) that blossoms about Christmas. The legend is, that Joseph of Arimathea having struck his staff into the ground to indicate where Glastonbury Abbey was to be built, prayed, that if he had fixed on the right place, the Holy Virgin would give him a sign of her approval, when instantly the staff (which was a branch of Hawthorn) struck root and shot forth leaves, flowers, and fruit. The original tree of this variety grows near Glastonbury; but plants, grafted from it, are common in all the nurseries.

GLAUCIUM. — *Papaveraceæ*. —

The Horned Poppy.—A British plant, common on the shore between Brighton and Shoreham, with glaucous or bluish-green leaves, and large yellow flowers. The pods are long and horn-like, whence the English name. The species are annuals or biennials, and should be grown in a chalky or calcareous soil. The seeds are common in all the seed shops.

GLECHOMA. — *Labiatae*. — The Ground Ivy.—There are two species; one with blue flowers, which is a British weed; and the other, the flowers of which are pink, which is a native of Hungary. They will both grow in any common soil; and, being perennials, are increased by division of the roots.

GLOBE AMARANTH.—See GOMPHRENA.

GLOBE FLOWER. — See TROILAEUS.

GLOBE THISTLE.—See ECHINOPS.

GLOBULARIA.—*Globularineae*. — The Blue Daisy.—Perennial and suffruticose plants, with round heads of blue flowers, most of which require a greenhouse in England. All the species grow freely in a mixture of loam and peat, and are propagated by cuttings under a glass.

GLOBOSA.—*Tulipaceae*.—*G. superba* is a magnificent plant which deserves cultivation in every hot-house. It is propagated by seeds, which ripen freely; or by dividing the roots, in January or February: the divisions should be potted in rather small but deep pots, and plunged into a bark-bed, where they should have very little water till they begin to grow. In March or April, the plants should be removed to larger pots; and, while they are growing, they should be abundantly supplied with water. The stems

will require to be supported by a stake or trellis; and if allowed sufficient heat and moisture, they will grow rapidly, and flower beautifully. When the stalks die down, the pots containing the roots should be removed to a dry stove, where they should be kept entirely without water till January or February, when the roots should be divided and repotted. The soil should be composed of one-fourth of peat, one-fourth of leaf-mould, and two-fourths of loam.

GLORY-PEA.—See CLIANthus.

GLOSSOLOGY.—A knowledge of the technical terms of botany.

GLOXINIA.—*Gesneraceae*.—Very handsome plants, with bell-shaped flowers, that require the heat of a stove; hybrids, have, however, been lately raised between this genus and *Sinningia*, which prove much harder than their parents. The commonest kinds of Gloxinia are *G. maculata*, which is apt to become so weak from the great number of its suckers, that unless they are removed as soon as they appear, it will seldom flower; and *G. speciosa*, which flowers abundantly. The former species is propagated by division of the root, and the latter by cuttings, which strike so freely without a glass, that even a leaf taken off with the base of the petiole entire, will take root, and make a handsome plant. All the species should be grown in a compost of loam, peat, and sand, or in very sandy loam and vegetable mould: and, when beginning to grow, the plants should be well supplied with heat and moisture. The pots should, indeed, stand in a saucer kept half full of water.

GLYCINE. — *Leguminosae*. — Climbing, tender plants, with pea flowers. The Linnæan genus *Glycine* has been divided by modern botanists

into eleven genera, the best known of which is *Wistària*. *Wistària Consequàna*, *chinènsis*, or *sinènsis*, sometimes called by its old name of *Glycine sinènsis*, is one of the most valuable climbing trees that will grow in the open air in Britain. This tree, though now so common, was only introduced in 1816 or 1818; it is a native of China, and appears to be quite hardy in the neighbourhood of London. Its large bunches of beautiful shaded lilac flowers, which are fragrant, are exactly like those of the common laburnum, except in colour; and they are produced most abundantly, the tree, in favourable situations, often bearing a second crop.

The *Wistària sinènsis* will grow in any common garden-soil; but it does best when the soil is light and rich, and the plants are abundantly supplied with water. It is often several years before it flowers, as it takes a long time to establish itself; but the period of its flowering may be hastened by watering it regularly with liquid manure, or by telling the housemaid to empty the slops and soap-suds on the ground near it—taking care to pour the liquid on the ground at a distance from the stem of the plant, as it would injure the collar if poured on it. All watering is, indeed, most effectual when it is given at some distance from the stem of the plant, as it is only the spongioles at the extreme points of the roots that can take up the moisture so as to be of any service; and water, if poured on any other part that is under ground, is in danger of rotting both the epidermis and the cellular tissue. When once established, the *Wistària* grows vigorously, and the plant in the Horticultural Society's garden at Turnham Green being checked in its height by that of the wall against

which it grows being only eleven feet, has spread so far on each side, as to cover a space of above three hundred feet in extent. It is easily propagated by layers, as the shoots, if laid down, will throw out roots at every joint. It may also be propagated by cuttings of the roots and branches, and even by leaves, which will take root if planted in sand and peat, and covered with a glass, provided care has been taken to break the petiole off the branch without wounding the protuberance at its base. Seeds of this plant are very rarely ripened in England; but when they are, they vegetate as readily as those of the common laburnum. The plant requires a wall or trellis-work to support it; but any aspect will do. Mr. Pamplin, of the Lavender Hill Nursery, has a plant which is trained against three sides of his house, viz. the north, the east, and the south; and the only difference he perceives is, that the flowers on the south wall expand first, but are the weakest and palest, and that those on the north, though they are the latest, are the darkest and most vigorous. The *Wistària sinènsis*, though so beautiful, is by no means dear, as a plant costs from 1s. 6d. to 2s. 6d. in the nurseries, according to its size—a plant of the latter price being the largest that can be transplanted with safety. There is a white variety, but it is very inferior in beauty to the species. It is, however, employed for contrast, and is usually propagated by grafting on the roots of the purple species, on which it grows more vigorously than on its own roots.

GLYCYRRHIZA.—*Leguminosæ*.—The liquorice. A perennial plant with small pale blue flowers, a native of the south of Europe. The liquorice is made by boiling the root (which resembles that of the ginger

in appearance) a long time, and letting the moisture evaporate from the sediment. The plant is not worth cultivating except from curiosity; but when it is grown, it requires a very rich mould.

**GNAPHALIUM.** — *Compositæ*. — Cudweed. This genus now includes only about half the number of species that it formerly did, six or seven new genera having been formed out of it. The British species are cottony-looking weeds, and very few, if any, of the foreign kinds are worth cultivating. The French *Immortelle*, of which such quantities are sold near the Cemetery of Père la Chaise, and which used to be called *Gnaphalium orientale*, is now removed to the genus *Helichrysum*. — See **HELICHRYSUM**.

**GNETIDIA.** — *Thymelææ*. — Very pretty greenhouse plants, which are rather difficult to cultivate, from the great delicacy of their roots. They should be grown in a mixture of sandy peat, or in what is called heath-mould; and they should never be suffered either to flag for want of water, or to stand in saucers full of it. All the species are rather difficult to propagate; but the best way is to take off the tips of the shoots when quite young, and to plant them in pure sand under a bell-glass.

**GOAT'S BEARD.** — See **TRAGOPOGON**.

**GOAT'S RUE.** — See **GALE'GA**.

**GOAT'S THORN.** — *Astragalus Tragacantha*.

**GODETIA.** — *Onagraceæ*. — The purple-flowered kinds of *Oenothera*, or Evening Primrose, have been divided from the others and formed into a genus under the name of *Godetia*, by Professor Spach, a German botanist, residing in Paris. Professor Spach formed thirteen other genera out of *Oenothera*, but only this one appears to have been generally adopted. The handsomest

species of *Godetia* are *G. rubicunda*, *G. vindsa*, and *G. ledipa*, all natives of California, introduced in 1835, and all of which may be sown in September, like the other Californian annuals. See **ANNUALS**. The other kinds are also all hardy annuals, which require no other care than sowing in March or April in the open border, in any common garden-soil, and thinning out when they come up, if they appear too thick. All the *Godetias* are rather tall-growing plants, and if not thinned out, they will become drawn up and weak. If the stalks appear weak, they should be tied to slender stakes. They bear transplanting well. The colours are most brilliant when grown in a poor soil; but the plants are smaller and less vigorous. A rich soil, however, sometimes makes them produce more leaves than flowers.

**GOLDEN-LEAVED CHESTNUT.** — This very curious and splendid tree is a native of California, but there is a specimen in the arboretum at Kew. It is a sweet chestnut, and its peculiarity consists in its leaves, which are of a bright gold hue on the under sides, and which give it a singular and brilliant appearance.

**GOLDEN ROD.** — See **SOLIDA'GO**.

**GOLDEN SAXIFRAGE.** — See **CHRY-SOSPLE'NIUM**.

**GOLDFU'SSIA.** — *Acanthææ*. — Stove plants, with handsome tubular flowers.

**GOMPHOLOBIUM.** — *Leguminosæ*. — Australian shrubs, which require to be kept in a greenhouse in England, and to be grown in very light loam, peat, and sand. All the species are very difficult to preserve; and they are all very tender delicate plants. They require to be trained to a frame; and they are easily killed, either by too much or too little water. They are propagated

by seeds, which ripen freely ; or by cuttings of the young wood, which must be struck in sand, under a bell-glass.

GOMPHRE'NA. — *Amaranthaceæ*.

—The Globe Amaranth. This is supposed to be the Amaranth of the poets, which, from the durability of its flowers, was considered to be the emblem of immortality. It seems to have been used at funerals in the time of Homer, as he describes it as worn by the Thessalians at the funeral of Achilles, and it is still used for the same purpose in various parts of the Continent. The plant is a tender annual, which should be raised on a hotbed or in a stove, and which, even when in flower, should be kept in the greenhouse. It should be grown in a light rich soil, and kept rather dry. Sometimes it is propagated by cuttings, struck in mould under a hand-glass; and plants grown in this manner are generally much hardier than those raised from seeds.

GONGO'RA. — *Orchidaceæ*. — Curious epiphytal plants, natives of the tropics, which require the usual treatment of orchideous plants, and are generally grown in a moist stove, or orchideous house, in baskets of moss, or on a piece of wood hung up to the rafters. Sometimes they are grown in pots, in peat and sand, mixed with pieces of broken stone or lime-rubbish. The flowers hang down from the root and require to be shaded from the direct rays of the sun. They are increased by division of the root; and when grown in pots, the pots should be half filled with potsherds.

GONO'LOBUS. — *Asclepiadaceæ*. — Climbing plants with dark red flowers, which require the heat of a stove. They should be grown in a mixture of loam and peat; and they may be increased by cuttings.

The flowers are more curious than beautiful.

GORDO'NIA. — *Ternstræmiaceæ*.

—The Loblolly Bay. This plant, though in its native country, the swamps of North America, it becomes a tree fifty or sixty feet high, is in England rarely more than a shrub-evergreen bush, the height of which seldom exceeds five or six feet. It is nearly allied to the Camellia, and it has large, white, showy flowers, and large handsome leaves. It should be grown in peat earth, kept moist, in a low sheltered situation; but it is quite hardy, and it has the great advantage of flowering abundantly when of very small size. It is generally propagated by layers; but when seeds are imported, they should be sown on wet moss, as they are said only to germinate well on that substance.

GOSSY'PIUM. — *Malvaceæ*. — The Cotton Tree. These plants, most of which are natives of the East Indies, require a stove in England. The flowers are large and handsome, resembling those of the Mallow, and the seeds are enveloped in a soft white woolly substance, which is the cotton. This substance is often produced in England. All the cotton plants are herbaceous, and most of them are biennials; and they all require a rich moist soil with abundance of heat. They are propagated by seeds and cuttings.

GRABO'WSKIA. — *Solanaceæ*. — The new name for *Lycium Boerhaaviaefolium*.

GRAE'LLSIA. — *Crucifera*. — *G. saxifragæfolia* is a native of Persia, whence it was introduced in 1844. It is a little perennial plant, with a great abundance of showy white flowers, and is very ornamental, but smells like garlic.

GRAFTING is the art of taking a

shoot from one plant and uniting it to another, in such a manner as that it shall grow and thrive as well as if it were planted in the ground. A grafted plant consists of two parts; the stock, which must have a root, and the scion, which is united to the stock, by the operation of grafting. The scion is commonly a shoot of the preceding year's growth; but in some cases, it may be a shoot of the same year's growth, or it may be of the growth of two or more years. The stock should be a well-rooted plant, fixed in the soil, with a stem of at least as great a diameter as that of the scion, but the stem may be much larger, and of several years' growth. Grafting is commonly limited to woody plants, and it is only within certain limits that it can be performed. To be united together by grafting, it is necessary that the plants be of the same nature, and, generally, that they be of the same genus or family; though, in some cases, all the genera of a tribe will graft on one another. Thus, any kind of *Caméllia* may be grafted on any other kind of *Caméllia* or Tea Tree, but not on any other genus; while any kind of *Pyrus* may not only be grafted on any other kind of *Pyrus*, but also on *Cratægus*, *Méspilus*, *Sórbus*, *Cydonia*, and perhaps several others.

The primary cause is probably to be found in the organisation of the respective tissues of the plants, those uniting which are alike; but as this can only be determined by microscopic observation, and only then by the most acute vegetable anatomists, the safe rule in practice is to limit our attempts at grafting to species of the same genus.

The uses of grafting are various. By grafting a weak-growing species or variety on a strong-growing kind, the weak-growing variety becomes

more vigorous; and, consequently, a large and handsome plant is much sooner produced than could be done by layers, cuttings, or seeds. On the contrary, by grafting a strong-growing plant on a weak, low, or slow-growing stock, dwarf plants are produced, and thus specimens of large trees may be obtained within a very limited space. Plants may be propagated by grafting that cannot be increased readily by any other mode: as is the case with common fruit-trees. The shoots of seedling plants grafted on a stock of several years' growth, will sooner produce blossoms and fruit than when left to grow on their own roots.

There are various kinds of graft-



FIG. 19.—WHIP, OR SPLICE-GRAFTING.

ing; but they are all founded on this essential condition, viz., that the inner bark of the scion should be closely united to the inner bark of the stock. Where the scion and the stock are of the same thickness, this may be done at both edges; but where the stock is thicker than the scion, it can only be done at one edge, which, however, is found

sufficient. The kinds of grafting best adapted for ladies, are the common splice, or whip-grafting; slit or cleft grafting; side-grafting; and inarching.

*Whip or splice-grafting*, is repre-



FIG. 20.—GRAFTING THE CACTI.

sented in *fig. 19*, in which *a* is the scion, and *b* is the stock. In this case both scion and stock are of the same thickness; both are cut slanting, so as exactly to fit; and there is a dovetail notch in the stock for




FIG. 21.—GRAFTING THE PEONY.

the scion to rest on. When the scion has been perfectly fitted to the stock, it is tied with a strand of matting, as shown in the figure, and afterwards covered with grafting-wax, or grafting-clay, the modes of making

which will be given hereinafter. There are different variations of this mode of grafting. Sometimes the dovetail notch is omitted, and at others a tongue is formed in the scion and a slit made in the stocks into which it is inserted; this tongue serving the purpose of the dovetail notch, viz., to keep the




FIG. 22.—GRAFTING THE PEONY.

scion in its place. When the stock is of so much larger diameter than the scion, the appearance of this graft is, of course, quite different, and the latter is put on at one side, in order that its inner bark may be closely united with that of the stock. This is the common mode of grafting fruit-trees in the nurseries.

*Slit, or cleft-grafting*, is performed by first cutting over the stock, and next making a slit or cleft in it; then paring the scion on both sides, so as to form a wedge, narrower at the inner edge; and

after inserting it in the cleft, tying it and claying it as before. This mode is well adapted for grafting one succulent plant on another; as, for example, in the Cacti tribe, grafting an *Epiphyllum* on a *Pereskia*, as shown in *fig. 20*, or for ligneous *Pæonies* on the tubers of




FIG. 23.—STOCK AND SCION PREPARED FOR SIDE-GRAFTING.

herbaceous ones, as shown in *figs. 21* and *22*. In *fig. 21*, *a* is the stock already notched; and, in *fig. 22*, *b* is the prepared scion, and *c* the grafted plant.

*Side-grafting* is shown in *figs. 23* and *25*, in which *f* is the stock, from which a portion is cut out, against which the scion *e*, also

somewhat thinned down, is to be applied and made fast, as shown in *fig. 25* at *g*. This being done, the graft is covered with grafting-wax or clay, as usual. It will be observed, that by this mode the head of the stock is not cut off, but is left on, in order to draw up the sap, and also to prevent the stock from being disfigured in the event of the death of the scion. There is another mode of side-grafting, as shown in *fig. 26*, in which it will be observed, that the lower end of the scion is inserted, in a bottle of water, to supply it




FIG. 24.—CLEFT-GRAFTING THE CAMÉLLIA.

with moisture; a practice which, though not absolutely necessary, is found advantageous. In another kind of side-grafting, the head of the stock is cut off, and the scion and the stock are cut, as shown in *fig. 23*. Formerly, *Caméllias* were very frequently grafted in this manner.

A new mode of grafting the *Caméllia* is shown in *fig. 24*. The head of the stock is cut off, and only a single leaf left; a cleft is then made in the stock, and the scion (*a*), with only a single leaf attached, is inserted (*b*). The pot with the



grafted plant is then plunged into a hotbed, and covered closely with a glass. This process is called in France *La greffe étouffée*.

*Inarching* differs from the other kinds of grafting, by preserving the




FIG. 25.—SIDE-GRAFTING WITH THE SCION BOUND ON THE STOCK.

scion attached to the parent plant till it has become united with the stock in such a manner as to derive its nourishment from it. For the mode of performing the operation, see *INARCHING*.

To graft with success, the operation is best performed in spring, immediately before the buds of the

scion begin to expand; and, in general, the stock ought, in this respect, to be in advance of the scion; a result which is obtained by cutting off the scions from the parent plant in the winter season, and inserting their ends in the soil in a cool shady place in the garden till they are wanted in spring. In



FIG. 26.—GRAFTING WITH THE END OF THE SCION IN A BOTTLE OF WATER.

performing the operation, it is necessary to have a very sharp knife; for if the slightest roughness is left on the parts of the scion and the stock which are to be united, their perfect union cannot be effected. The operation ought also to be performed with rapidity, so as to expose the naked sections of the scion and stock for as few moments as possible to the atmosphere. When the plants to be grafted are in pots,

they should immediately afterwards be placed in a gentle heat, and kept moist; and if covered with a bell-glass, so much the better. The latter practice may be considered as essential in the case of grafting Orange trees, Caméllias, Rhododendrons, Daphnes, Arbutus, Magnolias, &c. Grafts made in the open air, on very small plants, may sometimes be covered with hand-glasses, or slightly sheltered or shaded till they have begun to grow; and the soil may be covered with litter, or rotten tan, or leaves, to retain the moisture. Where no pains are spared, the soil may be warmed immediately after grafting, by watering it with a few pots of hot water. After the scion has made shoots a few inches in length, the clay may be removed and the matting loosened; but care must be taken not to do this too soon. The proper time may always be known by observing whether the edge of the scion exhibits a granulating process, closely uniting it with the stock. In general, in the course of the month of August all the matting from plants grafted in the open air may be removed; and with those under glass, this may be done much sooner.

*Grafting-clay* is made of clayey loam, or brick earth, mixed with about a fourth part of fresh cow-dung, free from litter, and a portion of hay cut into pieces about an inch in length, adding a little water, and beating the whole together for several hours. On a small scale, however, this preparation is not necessary; as either moist clay alone, or cow-dung, may be plastered over the graft, and covered with moss, or even with coarse paper; the moss, or paper, being tied on with matting. The use of the covering is to exclude the air, and consequently to retain the moisture

of the scion and stock, and also an agreeable degree of temperature, in order that the vessels of the two woods may be able to unite.

*Grafting-wax* is composed of bees'-wax and pitch, with some tallow and a little rosin; at first melted and mixed together, and afterwards heated as wanted. The proportions are of no great consequence. The mixture is kept in an earthen pot, in which it may be heated when wanted; and is laid on with a brush till it is a quarter of an inch thick; and if covered with dry sand while it is still soft and warm, it will not be likely to melt and fall off, which otherwise would probably be the case.

GRAINS OF PARADISE. — The berries of *Cocculus indicus*.

GRAPE HYACINTH. — See MUSCA'RI.

GRASSES. — There are but very few ornamental kinds of Grass that are worth cultivating in a garden; and the most remarkable of these are the Quaking Grass, *Briza media*, and the Feather Grass, *Stipa pennata*. The Italian Reed, *Arundo Donax*, and its variety, the Ribbon Grass, *A. D. versicolor*, are very ornamental; but they are Reeds rather than Grasses, though they belong to the same natural family, *Gramineæ*. For a list of the Grasses proper for laying down a lawn, or grass plat, and their qualities, see LAWN.

GRASS VETCH. — See NISSO'LIA.

GRAVEL is in universal use for forming walks in Britain; as sand is, for want of gravel, on the Continent. The grand desiderata in gravels are: the quality of binding, or forming a smooth compact body not liable to be disturbed by the feet in walking; and a good colour which shall harmonise agreeably with the grass and trees, &c.,

around it. It is a very common practice in forming gravel-walks, to use the gravel as it comes from the pit, and after it is laid down and rolled, to cover it with sand taken from the same gravel by screening or sifting; but unless this sand be of a binding nature, from its containing a good deal of iron, it soon separates from the rough gravel below, and is removed by sweeping. Gravel, whether consisting of large or small stones, or particles, if laid down when perfectly dry, very seldom can be made to bind; and, under such circumstances, it forms a rough, moving, and consequently a most disagreeable surface to walk on. A remedy for evils of this kind, which is sometimes successful, is to strew over the walk Roman cement in powder, then to rake it, so as to incorporate the powdered cement with the surface of the ground to the depth of two or three inches, and immediately afterwards to water it thoroughly, and roll it till it becomes quite hard and smooth. This is one of the best modes of forming a permanent and agreeable gravel-walk on a steep slope; it is also an excellent mode in small gardens, where the object is to save labour in keeping, and to prevent the growth of weeds. Sea-shore gravel, which is generally mixed with sand and shells, can only be rendered firm by this process, or by one which destroys its colour, viz., mixing it with tar or gas liquor. When so mixed, however, it forms a very durable walk, though it is of a dark and disagreeable colour. Next to these modes, the best means is to break a number of small stones, or pebbles, into fragments; and if this be done with about one-third of the quantity of gravel to be used, and the fragments intimately mixed with the round pebbles, the gravel, when

thoroughly rolled with a very heavy roller, will bind. The finest gravel in the world is composed of the débris of flints, such as the Kensington gravel; and this kind, which has hitherto been found in only a few parts of England, was sent to every part of the world.

It must always be remembered, that broken angular pieces of stone, whether large or small, will bind much better than round pebbles; and if with the broken stones be mixed a ferruginous clay, which is generally of a reddish, brownish, or yellowish colour, and the whole be rolled immediately after it is laid down, it will harden by exposure to the atmosphere, and will become quite firm and smooth. If, however, the rolling should be neglected for a few days, the particles of rusty earthy matter will become hardened individually in a loose state; and even if rolled afterwards, they will never become quite firm. It must also be observed, that large and small stones do not bind well together; and hence all gravel, as soon as it is taken from the pit, should be sifted through a wire screen, the wires of which are only sufficiently wide apart to admit stones of the size of a moderately large gooseberry, and all the larger stones should be thrown on one side to be broken. The gravel that has passed through the screen should then be examined, and if it be found mixed with too much earthy matter, it should be again sifted through a wire sieve, sufficiently fine to allow only the earth to pass through. Part of the earthy matter should then be well mixed with the gravel and broken stones, in the proportion of one-third of each, and the whole should be laid evenly on the walk, and rolled immediately.

When gravel walks have become

loose from time or frequent sweeping, or from the gravel being originally of a bad quality, they may be rendered firm by forking them over; and, after raking out the largest of the stones, and breaking them, mixing the gravel with equal parts of sand and ferruginous clay in a somewhat moist state, rolling the whole as soon as the materials have been equally spread over the walk. If, however, neither sand nor ferruginous clay can be easily procured, burnt common clay powdered may be mixed with the gravel; the clay having been burnt by spreading it on the furnace of a hothouse, or by mixing it with faggots, and then setting fire to the whole: but in this case also, care must be taken that the mixed clay and gravel are watered after they are laid down, and rolled immediately after.

There are various substitutes for gravel. Where colour is the object, as well as firmness and smoothness, there is nothing better than burnt lumps of clay, reduced to a very coarse powder, and slightly mixed with Roman cement. Where colour can be dispensed with, a most effective garden-walk, and one which will last for many years, may be formed of the scrapings of public roads, which have been made, or metalled, as road-makers term it, with granite, or other coarse stone, mixed with tar, laid down to the depth of six inches on a bottom of broken stone, and smoothly and firmly rolled. The different kinds of asphalte so laid down also make smooth and durable walks; but they are too expensive for general use. When no gravel can be procured, granite or other stone, broken very small, and firmly rolled, will make a very durable walk, though the colour is far inferior to that of

fine yellow gravel. For laying out walks, and the mode of preparing the foundation of gravel walks, &c., see WALKS.

GREEK VALERIAN.—See POLEMONIUM.

GREEN-FLY.—See A'PHIS.

GREENHOUSE.—A structure for growing those plants in (more particularly in the winter season), which will not endure the open air of British winters. It may be of any form, but the most convenient is a square or a parallelogram, with upright glass in front, sufficiently high to admit of walking upright under it immediately within the glass; and with a sloping roof, at such an angle as readily to throw off the rain. This roof, for the better receiving the sun's rays, should face the south, south-east, or south-west; and this is called the aspect. The front should seldom be lower than seven feet in height, and the height of the back should be about two-thirds of the width of the house. The space within is generally laid out so as to have a shelf in front, about two feet high from the ground, and two or three feet in width; and next there is a path two or three feet in width; the remainder of the floor, from the edge of the path to the back wall being occupied with a series of shelves rising one above another like the steps of a staircase, on which the pots of plants are to be placed. These shelves may be nine inches or a foot in width, and the height of one above another may also be nine inches or one foot. The mode by which artificial heat is communicated to such a house is by smoke flues, or hot-water pipes. The fire should be at one end, or behind the house, whichever may be most convenient; and the principal flue or hot-water pipe should be along the

front wall, under the shelf; or, in some cases, it may be under the path. The reason for this position of the flue or pipe is, that heat always ascends; and, consequently, if the source of heat were placed under the back of the house, the heat would ascend directly to the roof at the upper angle of the house, and would scarcely heat the lower or front part at all. In order to admit of ventilation, the front-sashes should open outwards, or slide along a groove; and the roof-sashes should also open by sliding the one over the other. Other minor details need not be here entered into, as they are perfectly understood by all constructors of greenhouses, whether of wood or iron. With respect to these two materials, iron admits of the greatest variety of shape, such as a curvilinear ground plan and roof, and it also admits most light; but the construction in wood is most generally understood, and is rather the cheapest. Very excellent and ornamental greenhouses are constructed in iron, and wooden houses may be made by any carpenter or joiner. A portable greenhouse has lately been constructed to place over plants in the open air, and which consists of a stand or frame in which some sash-frames are fixed, so as to cover a sloping trellis below, over which some tender or half-hardy ornamental climbers are trained. This apparatus can be put up at a very trifling expense, as glass is now very cheap, and as the frame may be made of wood rough from the saw.

The simplest kind of greenhouse is one only heated by manure, which, with the shelter afforded by the glass, is sufficient to grow grapes, and to force flowers, so as to have roses and lilacs, &c., at Christmas. The outer appearance of this house

is very plain (see *fig. 27*); and it may be constructed at very little expense. There is a wall in front (shown at *c* in *fig. 28*), within which a dung bed is formed, into which the plants to be forced (*d*)



FIG. 27.—GREENHOUSE AND VINERY, OUTSIDE.

are plunged. Inside the back wall are trained peach and nectarine trees, or vines; and on the outside, vines, or cherry trees. Part of the roof (*e*) is formed of boards, and these project so as to form a coping to the outer part of the wall. The




FIG. 28.—GREENHOUSE AND VINERY, INSIDE.

next advance to heating greenhouses with manure is using smoke flues; and these, after having been long out of fashion, are now being partially revived; hot water pipes,

however, are still generally substituted for them. A common greenhouse, heated by hot water, is shown in *fig. 29*, which contains a




FIG. 29.—A SMALL GREENHOUSE.

propagating shelf (a) for cuttings, as they must be near the glass. It is not usual in greenhouses of this shape to have any path except the front one (d); but, in this, a concealed path behind the pots is left at b, which may be hidden by *Thunbergia alata*, or some other climbing plant, so as to enable the gardener to reach easily to water the plants on the shelf (a). The stage may be composed of flag stones supported by brick piers (c). There is a front shelf for bushy ornamental plants at e; and the hot-water pipes are shown at f. It is evident in this greenhouse that smoke flues may be easily substituted for hot-water pipes, if they should be preferred. Portable greenhouses, of hotheds, have lately been invented by the French nurserymen, for the purpose of striking cuttings in very small pots, a rage for little plants of this kind having lately existed in Paris; and having apparently reached England, from the great number of plants in very small pots which are now seen in the shop windows in London. The French

portable greenhouses are of various forms and materials, but one of the best is shown in *fig. 30*, which was figured in the *Bon Jardinier* for 1844, and is a box made of wood, about two feet across, or any other convenient size, which may have handles fixed for moving it at a, and which is covered with a common hand-glass, fixed on a board, which covers the top of the box, and in which are numerous holes made for small flower-pots. Just below this board is a zinc or tin basin (b), which is filled with sand or sawdust, or even moss, in which the pots are plunged. Below this is an open tin or zinc trough (c), which is filled with water through the funnel (d). A lamp is shown at e, which is kept in its proper place by a little tin ledge; and which slides in and out by a door in the side, which is fastened when the lamp is in its place. There are some holes at f, to supply air, to support combustion; and two slanting pieces of zinc at g, to reflect the heat. *Fig 31* is a circular portable greenhouse, which was figured in the *Gardeners' Chronicle* for Dec., 1843. It consists of three pieces of earthenware; viz., the foot (a), on which stands the basin (b), which is surmounted by the plate (c). In the foot (a), is placed a tin or earthenware lamp (d). Three or four inches above the wick is placed a short iron cistern (e), supported by three feet, which rest on the bottom of the basin (b); it is three inches deep, seven inches in diameter, and is fed by a pipe and funnel (f), into which water is poured until it can be seen at the bottom of the funnel, which shows that the cistern is full. The plate (c) is formed of common red earthenware, and consists of two circular trenches, (g g and h h,) four inches broad, and as

much deep. These trenches are filled with sand, and in the trench (g,) are placed in two rows, eighty-six very small pots. In the trench




FIG. 30.—PORTABLE GREENHOUSE.

(h,) are forty more pots ; so that in | be struck at one time. In the foot the two, nearly 130 cuttings may | (a) is a door fastened by a button,




FIG. 31.—CIRCULAR PORTABLE GREENHOUSE.

to admit taking out the lamp, and | lamp is supplied with the air replacing it when needful. The | necessary for combustion, by eight

holes bored at *i*, by eight still smaller ones at *k*, and by eight or ten in the plate at *l*. There is a metal plate pierced with holes at *m*, through which the greater part of the heat rises; so that the troughs *h h*, are much hotter than the troughs *g g*, which are warmed principally by the hollow spaces at *n*. The difference of heat between the two troughs is so great, that it is said, hothouse plants may be struck in the trough *h*, and greenhouse ones in *g*. The frame is covered with the hand-glass *p*, which of course may be removed at pleasure. A new mode of heating without either pipes or fires has lately been discovered, but it has only been applied to hothouses. See POLMAISE HEATING.

GREENHOUSE PLANTS are those which will not bear the cold of a British winter in the open air, but that only require to be protected from frost. Many persons injure their greenhouse plants by giving them too much heat in winter, and too little air in summer, and are then surprised to find their plants die, or at least become sickly, and remain without flowering, notwithstanding all the care that has been bestowed upon them. No greenhouse ought to be kept at a greater heat at night than from 35° to 46° during winter; but the thermometer ought never to be suffered to fall below 35°. In the day, particularly if there be sunshine, it will of course rise higher; but the fire should be lessened accordingly, as the thermometer, even in sunshine, should not rise in winter above 50°, or at most 52° or 53°. A higher temperature will induce premature vegetation; and the plant will waste its strength in an abortive attempt to produce flowers and seeds at a season when its nature requires it to be

kept in a state of complete repose. The second fault, of giving too little air, is an equally serious one. Plants can no more live without fresh air than without water; and even in winter, the sashes of a greenhouse should be opened for an hour or two, say from twelve till two, in the middle of the day, whenever the sun shines, or the frost is not too intense. In the summer, say from the middle of May to the middle of September, the plants should be set out in the open air, the space on which they are to stand being covered two or three inches deep with small coal or slack, or ashes, to prevent the worms from creeping out of the ground into the holes at the bottom of the pots. In cold and damp seasons, the time for putting out the plants may be delayed till June; and previously to their removal, the sashes of the greenhouse should be left open for a week or ten days, night and day. Greenhouse plants should be watered regularly every evening in summer, and twice a day if the weather be very hot and dry. In winter, they should always be watered in the morning, when water is given; but this need not be every day. Some plants, indeed, do not require watering oftener than once a week. The general rule is, frequently to examine the pots, and to give water whenever the earth appears to have become dry on the surface. Greenhouse plants should never be suffered to stand in saucers during winter, as stagnant water is peculiarly injurious at that season; and whenever the earth in a pot looks black and sodden with water, the plant should be turned out of the pot, and after the black earth has been shaken from its roots, it should be repotted in fresh soil, well drained with broken crocks or cinders. In February or March, the plants should



be looked over and repotted where necessary; those that are too tall should be cut in, and cuttings made of their shoots. The young plants raised from cuttings made in autumn should be repotted in larger pots for flowering; and where the plants do not require fresh potting, but have the surface of their mould become green and mossy, the moss should be taken off, and the ground slightly stirred with a flat stick; taking care, however, not to go so deep as to injure the roots. When trouble is not an object, all greenhouse plants are the better for repotting once every year, either in spring or autumn; and when the ball is taken out of the pot for this purpose, it should be carefully examined, and all the decayed parts of the roots should be cut off. Sometimes when the ball of earth is turned out, nearly half of it will fall off almost without touching it; and when this is the case it will generally be found that there is a worm in the pot. Worms do a great deal of mischief to greenhouse plants in cutting through the roots, as their instinct teaches them to make their way through the earth straight across the pot and back again; and they cannot do this without tearing the roots asunder every time they pass. Another point to be attended to in the management of a greenhouse is, keeping the plants as near as possible to the glass; as unless this be done, the plants will become what gardeners call "drawn up," and unnaturally tall and slender, from the efforts they make to reach the light.

**GREVILLEA.**—*Proteaceæ*.—Australian plants with very curious flowers, which should be grown in a mixture of equal parts of sand, loam, and peat. They are increased by seeds, which ripen freely, or by cuttings of the old wood, in sand,

under a bell-glass. *Grevillea australis* with red and yellow flowers is very nearly hardy.

**GRINDELIA W.** (*DO'NIA R. Br.*)

—*Compositæ*.—Perennial and annual plants, with large showy yellow flowers. The leaves of some of the species are covered with a white glutinous matter, that looks like milk. Nearly all the species are natives of Mexico, and they should all be grown in a mixture of loam and peat. The perennial species require the protection of a frame during winter.

**GROTTOES** are covered seats, or small cells or caves, with the sides and roof constructed of rock-work, or of brick or stone, covered internally with spar or other curious stones, and sometimes ornamented with marine productions, such as corals, madrepores, or shells. A kind of grotto is also constructed of roots ornamented with moss. Perhaps the most generally effective grotto is one formed with blocks of stone, without ornaments either externally or internally, having the floor paved with pebbles, and a large long stone, or a wooden bench painted to imitate stone, as a seat. The roof should be rendered waterproof by means of cement, and covered with ivy; or a mass of earth may be heaped over it, and planted with periwinkle, ivy, or other low-growing evergreen shrubs, which may be trained to hang down over the mouth of the grotto. In some cases it answers to cover grottoes with turf, so that when seen from behind they appear like a knoll of earth, and in front like the entrance into a natural cave. As grottoes are generally damp at most seasons of the year, they are more objects of ornament or curiosity than useful as seats or places of repose. One of the finest grottoes in England is that

of Pain's Hill, formed of blocks of stone, with stalactite incrustations hanging from the roof, and a small stream running across the floor. Pope's grotto at Twickenham, the grotto at Weybridge, and that at Wimborne St. Giles's, which has cost 10,000*l.*, are also celebrated. A fountain or a gushing stream is a very appropriate ornament to a grotto; though, where practicable, it is better in an adjoining cave, when a person sitting in the grotto can hear the murmur of the water and see the light reflected on it at a distance, than in the grotto itself.

GROUND CHERRY. — *Cérus* *Chamæcérus*.

GROUND IVY. — See *GLECHO'MA*.

GROUNDSEL. — *Senécio vulgaris*. — I mention this troublesome weed, to enforce upon amateur gardeners the necessity of pulling it up as soon as it appears, without suffering it to open its flowers, lest it should ripen any of its seeds. The plant belongs to the Compositæ, and the seeds are each furnished with a feathery wing or pappus, by means of which they are distributed in all directions.

GROUNDSEL-TREE. — *Bácccharis halimifolia*. — A shrub with bluish green leaves, and rather pretty flowers, which are produced in autumn. It will grow in any common garden-soil, but it is killed in severe winters, if in an exposed situation. It may be propagated by cuttings, which will strike if planted in the open border in autumn; or by layers.

GUANO. — A new kind of manure, lately introduced from South America. It consists of the dung of sea-fowls, collected from the Guano Islands, on the coast of Peru; and it is so strong that a table-spoonful of it dissolved in water will go as far as three trowels-ful of horse dung. It may be used for Orange-

trees, Pelargoniums, Heart's-ease, Fuchsias, and any other plants requiring rich soil. In general, however, it is most efficacious to grass land, and it may also be used with advantage in a kitchen garden. In these cases the proportion is four ounces of guano to a gallon of water; but this is much too strong for greenhouse plants, and for them half an ounce of guano to a gallon of water will be as strong as it will be safe to give them.

GUA'VA. — See *PSY'DIUM*.

GUELDER ROSE. — See *VIBU'RNUM*.

GUERNSEY LILY. — *Nerine sarniensis* Ker. — See *NERI'NE*.

GUM ARABIC TREE. — *Acácia vèra*, or *arábica*. — See *ACA'CIA*.

GUM CISTUS. — *Cistus cypricus*, or *ladaniferus*. — See *CISTUS*.

GU'TTA PE'RCHA. — This is a kind of gum somewhat similar to the Caoutchouc or India Rubber, but which possesses the remarkable "physical property of becoming quite soft at the temperature of boiling water, without being in any way adhesive, and on cooling recovering its primitive hardness." The Niato or Gutta Percha tree of the Malay Peninsula, is said by some botanists to be a species of *Bássia*, but Dr. Lindley pronounces it to be a species of the genus *Isonándra*, both genera belonging to the natural order Sapotacæ. Mr. Low, however thinks that several trees in Borneo will produce a similar juice. The gum is said to be deposited in layers in the wood, and to be obtained only by cutting down the tree; but as it is also said to flow when numerous incisions are made in the bark, it is to be hoped that some less wasteful mode of procuring it than cutting down the tree will soon be devised. The words Gutta Percha belong to the Malay language, and signify "ragged gum"

—the *ch* in the word *Percha* being pronounced as in *perch*.

**GYMNOSTACHYUM.**—*Acanthaceæ*.—A Ceylon plant with inconspicuous yellow flowers, but showy leaves, with milk white midrib, and side veins on a dark green ground. Introduced in 1853.

**GYNE'RIUM ARGENTE'UM.**—*Gramineæ*.—Pampas Grass.—Native of South America, but hardy enough to withstand our ordinary winters, and even the most severe with a little protection. It forms a large tuft or bush; leaves of a glaucous green, sharply serrated. The flower stem pushes from amongst the leaves like a round, straight, thick reed, 6 or 8 feet high, terminated by a very large silky panicle, of a silvery white colour, and having a very light and graceful appearance. It will grow in any soil, but prefers a mixture of peat and friable loam. Propagated by seeds and by offsets after the plant is well established.

**GYPSOCALLIS** Sal.—*Ericaceæ*.—The Moor, or Cornish Heath, separated from the genus *Erica* by Salisbury.—For culture, see *ERI'CA*.

**GYPSO'PHILA.**—*Caryophyllaceæ*, or *Silenaceæ*.—Small-flowered creeping or trailing plants, annuals and perennials, which require a calcareous soil, and are well adapted for rock-work.

**GYPSUM.**—Sulphate of lime, commonly called plaster of Paris.

**HABENA'RIA.**—*Orchidaceæ*.—Hardy North American perennials, with tuberous roots, and very curiously-shaped flowers, which are generally yellow, but sometimes purple, and sometimes white. They grow best in a shady situation, and in a peat soil, kept rather moist than dry.

**HABRA'NTHUS.**—*Amaryllidaceæ*.—Bulbous-rooted plants (some of

which will thrive in the open grounds though others require a greenhouse, and others a stove), the culture of which exactly resembles that of the *Amaryllis*. The flowers are also similar, though very much smaller; and, as in the *Amaryllis*, they are produced before the leaves. The *Habranthus* appears to exemplify the doctrine of bulbs being underground stems; for we are told by the late Hon. and Rev. W. Herbert (*Bot. Mag. t. 257*) that the bulbs of this species, though round when imported, after having been potted a year, become gradually elongated. Plants of this genus are generally grown in a mixture of sandy loam and peat; and for the details of their culture see *AMARYLLIS*.

**HABROTHA'MNUS.**—*Cestraceæ*.—Very elegant Mexican shrubs, bearing a profusion of rose-coloured tube-like flowers in the middle of winter. A plant of *H. elegans*, planted in the free ground of the conservatory in the Botanic Garden in the Regent's Park, is splendidly in flower for at least eight months in every year.

**HÆMAN'THUS.**—*Amaryllidaceæ*.—Bulbous greenhouse plants, with large red flowers of very singular appearance, but no beauty. They are very coarse-growing, and take up a great deal of room. *H. multiflorus* is, however, an exception, as it is rather pretty.

**HÆMATOXYLON.**—*Leguminosæ*.—The Logwood. This tree, which grows about twenty feet high in its native country, is a stove shrub in Britain. It has yellow flowers, and should be grown in a mixture of peat and loam.

**HA'KEA.**—*Proteaceæ*.—Austrian shrubs, with flowers somewhat resembling those of the *Grevillea*, which are frequently sweet-scented. The plants are generally kept in the

greenhouse; they should be grown in peat and sand mixed with a little loam, and the pots should be well drained, and never suffered to become either too wet or too dry. See AUSTRALIAN SHRUBS.

HALESIA. — *Halesiæceæ*. — The Snowdrop-tree. American low trees, which generally form very handsome hardy shrubs in British pleasure-grounds. The reason of this is, that in North America the species all grow on the banks of rivers, in very poor rocky soil, whereas in England they are grown in dry places in rich soil; and too much nourishment to a tree which does not require it, has the same effect as too much animal food to a child—it makes it increase in width instead of height. The Snowdrop-tree flowers freely, and its stem droops gracefully over water. The flowers are white, and resemble those of the Snowdrop; and the seed is curiously winged. The species will grow in any soil or situation, but they all prefer a poor soil near water, and a sandy situation. They are generally propagated by layers, though they all ripen seed abundantly in England.

HALIMODENDRON. — *Leguminosæ*. — The Salt-tree. *H. argenteum* Dec. (*Robinia Halodendron* Lin.), is a Siberian hardy shrub, which will grow in any soil or situation. When grafted standard high on a Laburnum, it forms a very handsome drooping tree, with silvery leaves and purple flowers.

HAMAMELIS. — *Hamamelidæceæ*. — The Witch Hazel. A hardy shrub, a native of North America, which will grow freely in any soil that is not too rich, though it prefers a dry stony gravel. It has the peculiarity of flowering during winter, beginning to expand its rich deep yellow flowers just as its leaves are falling off, and dropping its flowers when its branches

begin to be re-clothed with leaves in spring.

HAND-BILL. — An instrument used in pruning hedges.

HAND-GLASSES. — Portable frames or covers, formed of iron, zinc, or wood, and glazed. These glasses differ from bell-glasses in being longer, and composed of numerous small pieces of glass, which are fastened together by narrow strips of lead. Hand glasses are generally square, but they may be made of an octagon, or any other shape that may be most convenient; and they are sometimes made with a pane to open to admit air, or with the upper part to take off. This is very convenient; for as hand-glasses are chiefly used for protecting half-hardy plants during winter, which it is necessary to give air to every fine day, it is found very troublesome to be obliged to lift the hand-glass off the plant, and to lay it on one side whenever this is done. Bell-glasses, on the contrary, being principally for preventing the evaporation of moisture from the leaves of cuttings, do not require any opening, as the plants seldom want any air till they have rooted.

HARDENBERGIA. — *Leguminosæ*. — A new name given by Mr. Benthams to *Kennèdya monophylla*, and five other species of that genus, which have small purplish flowers.

HARDY PLANTS are all those that will stand the open air in British gardens without the slightest protection; half-hardy ones are those that may be planted in the open ground, but require the protection of a mat or hand-glass; and tender, those that must be kept during winter in a hotbed or plant-house heated by artificial means. Greenhouse and frame-plants are those grown in pots, which require protection from the frost during winter;

and stove plants are those grown in a bothouse all the year.

**HAREBELL, or HAIRBELL.**—It is rather curious, that though few poets can write a sonnet without mentioning the Harebell, and though it is sure to be introduced in every eloquent prose description of country scenery, botanists cannot exactly decide what plant is meant by the name—some supposing it to be the beautiful little blue *Campanula rotundifolia*, and others, the wild Hyacinth, *Scilla non-scripta*. The fact is, that both plants are now known by the name in different parts of Britain; but as the original word is said to have been “air-bell,” it is most probable that it was the Campanula that was first so designated, and that is alluded to by the poets; as the tender blue of its flowers is so near the colour of the skies, as not to require any great exertion of poetic fancy to call it a bell of air, and as its slender stem has sufficient elasticity to rise again when lightly trodden on. There is some reason for employing such terms to plants as Hare’s-ears, Hare’s-foot, &c., from resemblance; but none whatever that we can imagine for that of Hare-bell. It is very probable that the designation was originally Hair-bell, or Hair-bells, on account of their being well adapted for garlands for the hair. In Miller’s *Gardener’s Dictionary*, Hair-bells occur in the index, and is referred to the common Hyacinth, *Hyacinthus non-scriptus*, or *Scilla non-scripta*, which Miller says, “grows plentifully in woods and near hedges, in lands which have lately been wood, so is seldom admitted into gardens; but the poor people, who make it their business to gather the wild flowers of the fields for nosegays, &c., bring great quantities of these to London

and sell them about the streets.” In Lee’s *Introduction to Botany*, 1799, *Hairbells* is given as the English name of *Hyacinthus non-scriptus*; and we find the same term and explanation in various dictionaries. From these facts it may be concluded that the name of Harebell is a corruption of the original and more applicable one of *Hairbell*.

Then, as to what plant is understood. In the south of England it appears to be the common Hyacinth; in the north of England and in Scotland it is the Round-leaved Bell-flower, *Campanula rotundifolia*. To this also the descriptions given by the poets in those parts apply. This Campanula is remarkable for its upright, graceful, slender stalks. Scott alludes to the plant as being slender and elastic:—

“A foot more light, a step more true,  
Ne’er from the heath-flower dashed  
the dew;  
E’en the slight hare-bell raised its  
head  
Elastic from her airy tread.”

*Lady of the Lake, Canto I.*

And again in *Canto II.*—

“‘For me,’—she stooped, and, looking  
round,  
Pluck’d a blue hare-bell from the  
ground,—  
‘For me, whose memory scarce con-  
veys  
An image of more splendid days,  
This little flower that loves the lea,  
May well my simple emblem be;  
And when I place it in my hair,  
Allan, a bard, is bound to swear,  
He ne’er saw coronet so fair.’  
Then playfully the chaplet wild  
She wreath’d in her dark locks, and  
smil’d.”

For this purpose the Hyacinth has not the requisite pliability; on the contrary, its stalk is rather thick, succulent, and brittle; nor is it, like the Campanula, a flower that “loves the lea;” still, repre-

sented by artificial flowers it has a good effect; and ladies may cultivate both sorts, the Hyacinth in a somewhat moist, shaded situation, and the Campanula in any soil, rather dry than otherwise.

**HARES AND RABBITS** do a great deal of mischief in flower gardens, as they are very fond of devouring many flowering plants—particularly Pinks and Carnations. They are also very fond of young plants of Laburnum in the shrubberies, and of Parsley in the kitchen-garden. The usual way of protecting Pinks and Carnations is, by an invisible wire fence, or by a net-work of black worsted, supported, at intervals by blackened wires; but the young plantations are generally protected by common netting, supported by notched stakes. Some persons sow Parsley near their Carnations, in the hope that the hares will eat that in preference; but it often proves injurious, as the smell of the Parsley attracts more hares than would otherwise discover the Carnations, and thus, the Parsley being soon devoured, the Carnations are destroyed.

**HARE'S-EAR.**—See *BUPLEURUM*.

**HARE'S-FOOT FERN.**—*Duvallia Canariensis*.—A very curious exotic Fern, the roots of which grow out of the pot, and closely resemble a hare's foot. It is a native of the Canaries, and should be grown in sand and peat.

**HART'S-TONGUE.**—*Scolopendrium officinarum*.—One of the handsomest of the British Ferns, from its broad tongue-shaped leaves. It grows in marshy places. It is called *Scolopendrium* from its roots bearing some resemblance to the little luminous insect *Scolopendra electrica*.

**HATCHET VETCH.**—*Coronilla Securidaca*, now called *Securigera Coronilla*.—A coarsely-growing hardy

annual which takes up a great deal of room from its large, rough, and widely-spread leaves and stems: while it can boast of little beauty in the single yellow pea-flowers. It will grow in any soil or situation.

**HAULM.**—The dead stalks and leaves of peas, potatoes, &c. It is generally gathered up, and carried to the rubbish heap to rot for manure, or burnt. It is also sometimes used for covering the ground over the roots of trees, &c., to keep out the frost.

**HAWKWEED.**—The plants properly called Hawkweed belong to the genus *Hieracium*; they have generally yellow flowers, and many of them are British weeds; the yellow Hawkweed of the gardens (*Tolpis Barbata*) and the red Hawkweed (*Borchausia rubra*) are, however, quite distinct. They are both hardy annuals, which only require sowing in the open border; and one of which (the yellow) will stand the winter in the open ground without protection, if sown in autumn. The red-coloured kind is very apt to become drawn up with long slender stems, and requires staking and tying to make it look well.—See *CREPIS*.

**HAWTHORN.**—*Crataegus Oxyacantha*.—*CRATEGUS*.

**HAZEL.**—*Corylus Avellana*.—The common Hazel is rather a fruit-tree than an ornamental shrub; but it is sometimes grown in pleasure-grounds and geometric gardens, to form a shady walk. Walks of this kind were great favourites in the time of Elizabeth, and also in the Dutch gardens laid out in the time of William III. They are therefore suitable in the gardens of Elizabethan houses, or of any mansions built in James I.'s style. They require no particular care but planting the young trees in a loamy

soil, giving them, if possible, a little of that rich yellow soil generally called hazel loam, for its peculiar adaptation to this plant, and clipping and training the branches so as to make the walk form one continued bowser.

**HEART'S-EASE, or PANSY.**—Most of the different kinds now in cultivation have sprung partly from the wild kind, *Viola tricolor*, hybridised by some other species; and as all the kinds, whether hybrids or species, vary very much when raised from seeds, and as these varieties and hybrids may be readily cross-bred with each other, the number of kinds that may be raised defies all calculation. The Heart's-ease must be grown in very rich soil, composed, if in pots or boxes, of four parts of rich loam, one of sand, and one of decayed leaves or rotten dung; and if in the open ground, of rich loam highly manured. It is propagated by seeds, or division of the root. The seeds should be sown, as soon as they are ripe, in a bed, where the young plants should remain till they flower, when the best should be taken up and replanted in another bed, or in well-drained pots or boxes, for flowering. The plants will require constant watering during the hot weather; but they are very apt to damp off, if the soil in which they grow has not been well drained. The best varieties are propagated by cuttings taken off from the points of the shoots, in the spring, cutting them clean across immediately below a joint. The cuttings should be struck in pure white sand, and covered with a bell-glass; they should not be watered when put in, and they should be shaded for several days. Heart's-eases are also propagated by layers, pegged down at a joint, but not slit, on ac-

count of their tendency to damp off.

**HEAT** is concentrated or produced in gardens in a variety of ways: by shelter from winds, which prevents the natural heat of plants from being carried off by currents of air passing over them; by exposure to the sun, which concentrates its rays; by covering a surface of soil or the roots and stems of plants with a non-conducting material, such as straw, litter, leaves, &c., which prevents its radiation; by fermenting substances, such as stable-dung, litter, leaves, tan, &c., which produce heat by their decomposition; and by the consumption of fuel, from which the heated air generated is conducted in flues, or by means of pipes of hot water or steam. Hotbeds are generally heated by a bed of horse-dung, or other fermenting material; and brick-built pits, or houses with glass roofs, are heated by furnaces and flues, or furnaces, boilers and pipes of hot water or steam. Stable-dung and hot water pipes are the two best modes of heating pits and glass-roofed houses. Heat when produced is retained by coverings which admit the light, such as glass sashes, or in some cases frames covered with oil-paper, or with very thin canvas or gauze.

**HEATH.**—See **ERICA**.

**HEATH-MOULD** is very frequently confounded with peat-bog by amateur gardeners; but the fact is they are materially different. Black peat, which consists of vegetable fibre, prevented from decomposing by a superabundance of water, is unfit for the growth of plants when in a pure state; but heath-mould, or peat mixed with sand, is admirably adapted for the growth of all Australian and American hair-rooted plants, as the mixture of sand with the peat prevents its

retention of water, and it is only the retention of water that prevents the decomposition of the vegetable matter it contains.—See PEAT-BOG.

**HEDERA.**—*Araliaceæ*.—The Ivy. This well-known plant is what botanists call a rooting climber; that is to say, its stems climb up and twine themselves round trees, or any other suitable object which presents a sufficiently rough surface for their roots to take hold of; as, unless this is the case, the Ivy, whenever it is rendered heavy by rain or snow, falls down. Whenever, therefore, Ivy is wanted to cover smooth, newly plastered walls, trellis work should be fixed against them, to which the Ivy should be nailed like any other plant. The Ivy is remarkable for undergoing a complete change in its leaves when it flowers. The barren or creeping Ivy, which trails along the ground, and roots into it, rarely flowers, and its leaf is deeply cut; but the tree Ivy, or flowering part, rears itself on high, so as to be fully exposed to the light and air, and the leaves become of an oval shape. *H. canariensis*, the giant, or Irish Ivy, as it is sometimes called, though it is a native of the Canaries, is hardier and grows much faster than the common kind; but the variegated kinds are more tender, and grow much slower. Ivy requires a deep and somewhat light soil, into which its roots can penetrate easily; and when grown for any purpose in pots or boxes, it should be abundantly supplied with water. Ivy is useful in all cases where a naked space is to be covered with green in a short space of time; and it is particularly valuable in town gardens, as it will bear the smoke and want of pure air in cities better than most other plants. It should, however, in all close and crowded situations, be abundantly supplied with water, and occasionally syringed over the leaves. The gold

and silver varieties are very beautiful, especially the former, when grown against the chimney of a dwelling-house or hothouse; but they require warmth to make them thrive.

**HEDGEHOGS.**—*Medicago minima*.—An annual plant, with small yellow pea-flowers, and curiously shaped capsules, which resemble hedgehogs. The plant is weedy-looking, and not worth growing.

**HEDGE MUSTARD.**—See **ERY'SIMUM**.

**HEDGE NETTLE.**—See **STACHYS**.

**HEDGES** for flower-gardens should be composed of ornamental plants, such as *Cydonia*, *Japónica*, Privet, *Laurustinus*, *Ribes sanguineum*, Roses, and double-blossomed Furze, or Ivy and other climbers, trained over iron trellis-work. The hedge to a flower-garden should never be stiff and formal so as to look like a mere barrier; but it should be so arranged, and should consist of plants which harmonise so well with the flowers in the garden as to make them appear part of it. For further details on this subject, see **FENCES**.

**HEDYCHIUM.**—*Scitamineæ*.—Garland-flower.—Largereed-looking plants with splendid flowers, but which are only suitable for large places, as they require the heat of a stove, and a great deal of room, to make them flower well. They are natives of the East Indies. *H. coronarium*, which is one of the commonest kinds, has large white flowers, which are exceedingly fragrant. All the kinds require a light rich soil, and are increased by dividing the roots.

**HEDYSARUM.**—*Leguminosæ*.—The French Honeysuckle.—The species are mostly hardy biennials and perennials, which require only the usual treatment of their respec-



tive kinds. They will grow well in any rich light soil, and they are increased by division of their roots and by seeds.

**HELENIUM.**—*Compositæ*.—The species are generally tall-growing perennial plants, with large yellow flowers. They are increased by dividing the root. There are two or three annual species which are quite hardy, and only require sowing in the open border. The handsomest of these is *H. quadridentatum*, which has bright orange-coloured flowers, like a *Rudbeckia*.

**HELIA'NTHUM.**—*Cistaceæ*.—The Sun-rose.—Low shrubs, generally used for planting on rock-work, and strongly resembling the *Cistus* or Rock-rose. As most of the species are rather tender, they require protection during winter. For this reason, they are either grown in pots, which are placed upon rock-work among the stones; or taken up and repotted in winter, to be planted out again in spring. The soil should be a compost of loam and peat. They are generally increased by seeds, which they ripen in abundance.

**HELIA'NTHUS.**—*Compositæ*.—The Sun-flower.—The annual plant of this name, though a native of Peru, is one of the hardiest of its kind, as it only requires sowing in the open border in any common garden soil. It is not, however, suitable for every situation, unless there be abundance of room, on account of the large size of its stalks and leaves. The perennial kinds are much smaller, and very ornamental; they are quite hardy, and will grow in any soil and situation.

**HELICHRYSUM.**—*Compositæ*.—The Everlasting.—The common yellow Everlasting, *H. bracteatum*, is a hardy annual that only requires

sowing in the open border; *H. bicolor* is a very slight variety, merely differing in having the outer petals tipped with copper colour; but *H. macranthum* has white flowers tipped with pink, and is very handsome. This species is a native of the Swan River Colony, and it should be grown in a light peaty soil. It may either be sown in the open ground in April, to flower in autumn, or in a hotbed in February, to plant out in May. *H. bracteatum incurvum* affords varieties of many different colours; and can be highly recommended as a late flowering annual in the open ground; and it also forms a good pot plant.

**HELICONIA.**—*Musaceæ*.—Splendid hothouse plants, which require a rich sandy loam, and plenty of room and heat, to bring them to perfection. They are propagated by division of the root. *H. metálica* has leaves 1½ to 2 feet long, velvety green above, and metallic purple beneath; flower handsome, in an upright spike, scarlet tipped with greenish white. It is propagated by cuttings, which strike easily.

**HELIO'PHILA.**—*Cruciferae*.—Beautiful little annual plants, natives of the Cape of Good Hope, generally with blue flowers, and very long slender stems. The seeds should be sown on a hotbed in February, and the plants planted out in a warm open situation in May.

**HELIOTROPE.**—See **HELIOTROPIUM**.

**HELIOTROPIUM.**—*Boraginææ*.—The Heliotrope is a favourite flower in most countries, from its fragrance, which, however, is overpowering, and very unpleasant to those not accustomed to strong perfumes. It should be grown in a light rich soil; and though it re-

quires protection during winter, it may be planted out in May, when it will flower splendidly in the open air, till destroyed by frost in autumn; and of all plants that succeed in the open air in summer, it is perhaps the most sensible to the least degree of frost. A new species of *Heliotrope* has been lately introduced, called *H. Voltaireanum*, which has very rich dark purple flowers. It requires the same treatment as the old kind.

**HELIX.**—The Snail.—Snails are so destructive to gardens, and particularly to those of small size, that too much care cannot be taken to destroy them. The best time for effecting this is in winter or early spring, when the snails are in a quiescent state, and when they will be found in great numbers sticking to the walls, under ivy, &c.; in box-edgings; or in the crevices of rock-work, &c. In spring the warmth and moisture induce them to leave their hiding places, and they commence their work of destruction. At this season, they should be sought for in the daytime, in the same kind of places as those they select for their winter retreats, and, if possible, destroyed before they lay their eggs, which they do in April or May. The eggs, which are buried in the earth in some rather moist and shady place, and which are whitish, and quite round and transparent, should be sought for and destroyed in May or June. By these means the ravages of snails may be in a great measure prevented; and there will be no occasion to resort to watering the beds with lime or tobacco water—remedies which, unless very judiciously practised, are in fact worse than the disease. Many persons place empty flower-pots in different parts of a garden infested with

snails, at night; and when this is done, a great number of them will generally be found either in the pots, or sticking to the outside in the morning. Cabbage leaves and slices of raw potatoes are also laid as traps for snails.

**HELLE'BORUS.**—*Ranunculaceæ*.—The Christmas Rose, *H. niger*, is one of the handsomest plants belonging to this genus, on account of its flowering in winter, or very early spring, before almost every other flower. It is a hardy perennial, which will thrive in any common garden-soil, and is increased by dividing the roots. There is a greenhouse species, *H. atrorubens*, which is very ornamental.

**HELMET-FLOWER.**—See **CORYANTHES**.

**HEMEROCA'LLIS.**—The Day Lily.—Handsome perennial plants, with yellow or copper-coloured flowers. They are quite hardy, and only require a moist soil and a shady situation. They are propagated by dividing the roots. For the white and purplish-flowered kinds, see **FUNKIA**.

**HEN-AND-CHICKENS.**—A kind of Daisy.—See **BE'LLIS**.

**HENBANE.**—*Hyoscyamus niger*.

**HENFREYA.**—*Acanthaceæ*.—*H. scandens* is a very handsome climbing stove plant, a native of West Africa, with whitish *Petunia*-like flowers, and dark green leaves.

**HEPATICA.**—*Ranunculaceæ*.—Pretty little plants, which flower very early in spring. They should be grown in a light sandy soil, and a shady situation; and as they have a propensity to raise themselves out of the soil, they should be taken up every two or three years in autumn, and replanted. If this be not done, the earth should be raked up or hoed up

round them, so as to cover the roots; as, if these are left exposed, they will wither, and the plants will probably die. The flowers of the Hepatica, unlike those of most other plants, possess their full colour from the first formation of the bud.

**HERACLEUM.** — *Umbelliferae*. — The Cow-parsnip. — The gigantic Siberian Cow-parsnips, *H. asperum* and *H. giganteum*, are probably two of the most magnificent herbaceous plants in the world. They are biennials, and are propagated by seeds, which ripen in abundance. The plants should be placed in a shady, moist situation, near a pond, if possible; and, where this is not practicable, they should have abundance of water. Thus treated, a plant has been known to attain the height of fourteen feet in a single summer, with a fluted stem six or eight inches in diameter; and a compound umbel of white flowers, measuring twelve feet in circumference. A plant of these dimensions, with leaves equally enormous, grew in the grounds of Bromley Hill in the summer of 1839; and another of nearly the same size grew in our small garden at Bayswater in the summer of 1840.

**HERBERTIA.** — *Iridaceae*. — A beautiful bulbous plant named in honour of the late Honourable and Reverend William Herbert, whose botanical labours are so well known. It is a native of Buenos Ayres, and it may be grown either in a pot, or in the open air, in a sandy loam, as it only requires protection from severe frost or long-continued rains.

**HERB-ROBERT.** — A kind of wild Geranium, very common by the road-sides throughout England and the north of France.

**HERON'S BILL.** — See *Erodium*.

**HESPERANTHA.** — *Iridaceae*. —

The Evening Flower. — A genus of Cape bulbs, nearly allied to *Ixia*, and requiring the same treatment.

**HESPERIS.** — *Cruciferae*. — The Garden Rocket. — These flowers, though very common, are rarely well grown, as they require a great deal of care to bring them to perfection. They are all perennials; and as soon as they have done flowering, they should be taken up, and transplanted into fresh and very rich soil, which must be of a light and friable nature. The best is, perhaps, that which has been used during the preceding summer for celery trenches. Thus treated, the double white and double purple varieties of *H. matronalis* will attain an extraordinary size, and will flower splendidly.

**HEXACENTRIS.** — *Acanthaceae*. — This genus has been separated from *Thunbergia*, principally on account of the shaggy anthers of the flowers. The name of *Hexacentris*, which signifies "six spurs," alludes to the spurs proceeding from the base of the anthers. This genus was little known till the exhibition of a splendid creeping plant called *Hexacentris mysorensis* at the May show at Chiswick in 1852. It was trained over an umbrella-shaped trellis, from which its beautiful crimson and yellow flowers hung down in long racemes, forming a kind of fringe. The pendulous racemes of flowers grow from a foot to two feet long, and they are covered with bunches of flowers and buds. The plant is a native of the East Indies, and of course requires a hothouse in this country.

**HIBBERTIA.** — *Dilleniaceae*. — Trailing shrubs with large yellow flowers, natives of New Holland, which require a greenhouse in England. They should be grown in a mixture of sandy loam and

peat, and they are propagated by cuttings.

**HIBISCUS.**—*Malvaceæ*.—Showy plants with large handsome flowers, of which the hothouse species, which are mostly from China, require a strong moist heat. *Hibiscus syriacus*, the *Althæa frutex*, is a hardy shrub, which will grow well in any common garden-soil, and of which there are numerous splendid varieties; some of the best being those raised by Mr. Masters, of Canterbury. The *Althæa frutex* is propagated by seeds or layers. Several of the different kinds of Hibiscus are marsh plants, which grow best in pots suspended in water from the side of a pond. *H. Huegelii quinquevulnera* is a handsome Swan River shrub, of erect habit with large rosy flowers like those of the *Althæa frutex*; the petals are each marked by a blood-red spot at its base.—See WATER-PLANTS.

**HINDSIA.**—*Rubiaceæ*.—A new genus, formed on the purple-flowered kinds of *Rondeletia*. *H. violacea* is a very splendid stove shrub, introduced in 1844.

**HIP.**—The fruit of the wild Rose.

**HIPPEASTRUM.**—A genus nearly allied to *Amaryllis*.

**HIPPOPHAE.**—*Elæagnaceæ*.—Sea-Buckthorn.—Handsome hardy shrubs, natives of North America, which will grow in any common soil, and are increased by layers.

**HIPPURIS.**—*Haloragaceæ*.—Mare's-tail.—A British aquatic; sometimes planted in ponds, &c., to hide their termination, and to give the water the appearance of a natural stream.

**HOE.**—There are many different kinds; but they may all be reduced to two classes: the draw-hoes, which have broad blades, and are used for drawing up the earth to the roots of plants, being pulled to the operator; and the thrust or

Dutch hoe, which are principally used for loosening the ground and destroying the weeds, and which the operator pushes from him.

**HOING** is an operation used for loosening the earth, and destroying weeds, where both digging and forking would be injurious to the roots of the plants forming the crop. It is also used to draw the earth up to those plants which send out numerous fibrous roots close to the surface of the ground. This last operation is called hoeing up, and it is generally practised with annual culinary crops.

**HOLLY.**—See *ILEX*.

**HOLLYHOCK.**—See *ALTHÆA*.

**HONESTY.**—See *LUNA'RIA*.

**HONEY DEW** is a clammy substance often found on the leaves of trees and shrubs in hot weather; and it is by some supposed to be produced by insects, and by others to be exuded by the tree. Whatever may be its cause, it does injury by stopping up the pores of the leaves; and it should be washed off as soon as it is discovered.

**HONEY-FLOWER.**—See *MELI'X-THUS*.

**HONEYSUCKLE.**—See *CAPRIFOLIUM* and *LONICERA*.

**HONEYWORT.**—See *CER'INTHE*.

**HOOP-PETTICOAT.**—A kind of Narcissus, *N. Bulbocodium*.

**HOP.**—See *HUMULUS*.

**HORN OF PLENTY.**—See *FE'DIA*.

**HORN-POPPY.**—See *GLAU'GIUM*.

**HORNS.**—See *FE'DIA*.

**HORSE-CHESTNUT.**—See *ÆSCULUS* and *PA'VIA*.

**HOTBEDS** are formed of dung, or any other vegetable fermenting material; but stable dung is in most general use, and is by far the best. When newly brought from the stables, it should be laid in a heap or ridge, five feet or six feet in width, and four feet or five feet in

height; and after lying three or four days, till a brisk fermentation has taken place, it should be turned over, taking care to place what was outside in the interior; and after a few days more, when a second fermentation has taken place, and the straw has become so tender as to be easily torn asunder with a fork, the dung may be made up into a bed. This bed should be formed on a platform of soil, six or eight inches above the general surface, to preserve it from wet; and it should be of such a length and breadth as to suit the frame or bottomless box which is to be placed upon it. For raising tender annuals, or striking cuttings, the depth of the bed of dung need not be more than two feet, if it be early in the season—for example, in February; but if the bed be not prepared till April, it need not be made above one foot in thickness. When the bed is formed, the upper surface should be perfectly level, or slightly sloping to the south; and it should be three or four inches wider than the frame on every side. After the frame is set, the surface of the bed may be covered with six inches of light soil, on which the seeds may be sown; or, what will generally be found preferable, the seeds may be sown in pots, and plunged in this soil, care being taken that the heat of the bed is not too great, and that the seedlings, when they come up, do not suffer for want of air. There are thermometers for trying the temperature of earth or dung by plunging them into it; and there are others for trying the temperature of the air; but a very little experience will render these unnecessary. The soil should not be warmer than 60°, or the air than 65° or 70°, even during bright sunshine; but if, during the night, it

falls as low as 45° or 50°, no bad consequences will ensue. In severe weather, the sashes may be protected at night with mats, boards, canvas, or hurdles, covered with thatch or reeds. Hotbeds should always be placed in a sheltered situation, open to the south, and, if possible, on dry soil. When the heat of the dung begins to fall low, it may be renewed by exterior linings, which are narrow masses of fermenting dung placed round the main bed of dung; but for raising flower-seeds this is seldom necessary.

HOTHOUSES differ from greenhouses in being kept at a higher temperature, so as to suit tropical plants; and in having a flat bed for the principal part of the plants to stand on, instead of a sloping stage of shelves. This bed is commonly surrounded by a narrow brick wall, two or three feet high, and filled with tan, in which the plants are plunged; but in some cases, instead of tan, or any other fermenting material, there is a cavity beneath the bed, in which flues or pipes of hot water are placed; and the surface of the bed is either covered with sand, or some other material calculated to retain an equality of moisture, in which the pots are plunged in the same manner as in the tan. Some cultivators do not use any materials in which to plunge the pots, but merely set them on the surface of the bed, trusting to the general heat of the air of the house, or the heat emitted through the bottom of the pit from the pipes or flues below, taking care to keep the surface of the bed on which the pots stand moist, by pouring water over it at least once a day. The heat of hothouses for ordinary tropical plants should at no period of the day or year be lower than 65°; but in summer, during bright sunshine,

it may be as high as 70°, 80°, or 90°. During winter it should never be lower than 60° in the daytime. In hothouses devoted to the growth of orchidaceous plants, a higher temperature is requisite than for the ordinary plants of the tropics, and also a proportionately greater degree of moisture; and in order to attain the latter object, the floor of the house, or the hot-water pipes, should be frequently sprinkled with water.

**HOTTO'NIA.**—*Primulacææ*.—The Feather Foil, or Water Violet.—An aquatic British plant, which produces a pretty effect, from its pink flowers, on the borders of ponds and ditches where the soil is gravelly.

**HOUND'S TONGUE.**—See *CYNOGLOSSUM*.

**HOUSELEEK.**—See *SEMPERVIVUM*.

**HO'VEA.**—*Leguminosææ*.—Beautiful dwarf shrubs, natives of Australia, which require a greenhouse in Great Britain. They should be grown in a mixture of sandy loam and peat; and they may be propagated by cuttings, which are rather difficult to strike; and which should, therefore, be put under a bell-glass, in pure sand, and plunged into a hotbed.

**HOY'A.**—*Asclepiadacææ*.—The most common species, *H. carnsæa*, has curious wax-like flowers, from which drops a sweet, honey-like juice. It is a hothouse climber, which requires a light rich soil, and is propagated by cuttings, which, however, will not strike without the help of bottom-heat. It is sometimes grown in greenhouses, if in a warm situation, exposed to the sun. In this case, it should be trained close to the glass, and a mat, or some other covering, thrown over the roof of the house in severe weather. *H. imperialis* is a very splendid climbing plant, with very

rich dark purple flowers, which are the more conspicuous from the ivory white of the central column. The flowers are sometimes three inches in diameter. It is impossible to describe the singular richness of the flowers of this plant to any one who has not seen them. *H. picta aurea* is also very handsome. *H. bella* can scarcely be called a climber, as its general appearance resembles a myrtle. The corolla of the flowers is of a pure white, and the crown of a deep purple, "resembling an amethyst set in frosted silver." It was introduced in 1848. The flowers are very small, but very abundant.

**HU'MEA.**—*Compositææ*.—Elegant biennial plants, which should be sown on a slight hotbed in spring; then potted off, and kept in the open air during summer, and in the greenhouse during winter, to be finally planted in the open border in May the second year. If the plants are re-potted three or four times during the course of the first summer, always into only a little larger pots, they will become so much stronger before they are finally planted out as amply to repay the additional trouble.

**HU'MULUS.**—*Urticacææ*.—The Hop.—This plant, though generally grown for the purpose of making beer, is a very ornamental climber, and very suitable for covering bowers, &c., from the great rapidity of its growth, and the deep shade afforded by its large and numerous leaves. It should be grown in a rich and deep loamy soil, and it is increased by dividing its roots.

**HYACINTH.**—See *HYACINTHUS*.

**HYACINTHUS.**—*Liliacææ*.—The common garden Hyacinth, *Hyacinthus orientalis*, is one of the most beautiful as well as the most fragrant of flowers; and, to a certain

extent, is almost one of the easiest of culture for the amateur gardener. The reason of this is, that the bulbs are generally to be purchased at an easy rate in the seed-shops, and the leaves and flowers being prepared in the bulb during the previous year, it is only necessary to place the bulbs in soil of any kind, or even on the surface of vessels of water, to produce a very fine flower. But this will not insure a bloom in the following year, because that depends not only on the plant being placed in circumstances where it will flower freely, but also where it will produce abundance of healthy leaves, and bring these to maturity. This is only to be done in beds properly prepared for the purpose, and under a proper system of management. We shall first speak of the most common mode of growing Hyacinths, viz. — in miscellaneous borders; next, of the most perfect mode of growing them, viz. — in beds of properly prepared soil; in glasses of water; in moss or sphagnum; and in pots of soil.

*Growing Hyacinths in miscellaneous borders, among other flowers.*

—Fix on the spots where they are to be planted, and loosen the earth to the depth of a foot with the spade, breaking it fine, and taking care that the roots of the adjoining plants are cut off, so as not to interfere with those of the Hyacinths. Remove three or four inches of the soil, and then deposit three or four bulbs, one in the centre and the others round it, so as to form a circle not more than six inches in diameter. Press the bulbs firmly into the soil, and cover them, three or four inches deep, with the soil, if it is a common garden loam, and five or six inches if it is a light sand. Plant only bulbs of one colour together, and put in a stick

to mark the spot, that they may not be interfered with before they come up, when the bed is being dug over in spring. The season for planting Hyacinths is October or November; but even December is not too late in mild seasons, and in favourable situations. In general, no protection from frost is requisite; for the Hyacinth is very hardy, and chiefly suffers from too much water, from snails, or from a disease called the canker. In heavy clayey soils, a small cone of soil may be raised over the roots to throw off the rain; but when this is done, the cone ought to be levelled down in February, before the plants come up: or a small gutter may be formed round each circle of bulbs, to drain off the wet. Where borders have a sloping surface, both these precautions are unnecessary; and hence, in the garden of the Zoological Society in the Regent's Park, Hyacinths are planted in the sloping borders, though the soil is a strong clay, in autumn, and flower vigorously every spring. Hyacinths thus treated will produce very fine flowers the first spring; and, even though not taken up, if they are not injured by canker, or slugs, or the roots of adjoining plants during summer, they will flower tolerably well the second, and even sometimes the third year; after which their flowers will become every year weaker and weaker, till at last the plants are not worth the room they take up in the border. If it is wished to preserve the roots in a vigorous state, they ought to be taken up after flowering when the leaves have faded, and kept in a dry airy shed, with the neck of the bulb turned down; and then planted in a properly prepared bed in autumn, where, after remaining two years, they will have recovered their vigour,

and be fit to plant again in the border. Planting Hyacinths in miscellaneous borders is the most convenient mode for amateurs, and in general it produces the most agreeable effect in a private garden; for beds of Hyacinths have more the appearance of being cultivated for sale by a florist, though it must be confessed that stronger flowers are produced in this way, and the effect, considered by itself, is far more splendid.

*Beds of Hyacinths.*—The most convenient width is five feet; and the length may be greater or less, at pleasure. Five feet in width will admit of four rows for the four colours of red, white, blue, and yellow, which should be six inches apart between the rows, and the bulbs may be placed at the same distance from each other in the row. The arrangement of the colours may be according to fancy, but the common mode is never to have two of a colour together. To prepare the bed, dig out the soil to the depth of three feet, and fill it up to one foot above the surface with very sandy loam, mixed with leaf-mould, cow-dung, or hotbed dung thoroughly rotten. This may be done in September, and in October six inches of the soil may be removed, and the bulbs planted; after which the soil must be replaced. To protect the bulbs from too much wet during the winter, the surface of the bed should be gently sloped to each side; and during rainy weather it may be covered with reeds or thatch, in such a manner as to throw off the rain. Thus treated, the plants will bloom with great vigour; and to have the colours in the greater perfection, the bed ought to be covered in the flowering season with a tent or an awning. But for amateurs the most conve-

nient mode is, to form the bed of such a size as to be contained in a common cucumber frame with glass sashes, which may be put on during heavy rains, and also during sunshine; tilting them at both ends to admit a free circulation of air, and covering the glass with mats to exclude the sun. Care must be taken to remove the glasses entirely during cloudy weather, in order not to draw up the plants: and, for the same reason, to take them off every night when the weather is dry. A common cucumber frame, twelve feet long, and four feet wide, will contain a very handsome collection of Hyacinths; which may thus be grown to the highest degree of perfection, and protected from every exterior injury. As soon as the plants have done flowering, the frame and glasses may be removed; and when the leaves have become yellowish, the bulbs may be taken up, and each kind kept by itself, and placed in an airy situation in the shade till they are quite dry. After this they should be cleansed from any soil that may stick to them, and the fibrous roots, which will have withered up, should be rubbed off. The bulbs should then be laid on a shelf of lattice-work, with the neck of the bulb downwards, or placed in shallow wicker baskets, and hung up in an airy shed or room till wanted for use. If decay or canker makes its appearance, the parts injured, if small, should be cut out, and the bulb laid aside to dry; but if the parts injured are extensive, the bulb should be thrown away at once, as the disease is infectious, and will communicate itself to healthy bulbs lying near the diseased ones. Hyacinth bulbs are generally fit for putting in baskets in the course of the month of July, and the bed being



partially renewed with fresh soil, they may be planted again in September or October. A third part of the soil being taken away, and replaced by fresh soil every year, the bed may continue to be used for an unlimited period. Young bulbs or offsets will be produced more or less every season, and these may be taken off when the bulbs are taken up, laid by themselves, and planted in a nursery-bed for a year, when they will have grown sufficiently large to be fit for planting in the flowering-bed. In an excellent lecture on the Hyacinth, delivered before the Royal Horticultural Society in April, 1861, it is stated that in Holland, in order to induce the formation of young bulbs, the old ones are cut crosswise, and sprinkled with sand to absorb any superfluous moisture that may exude from the incisions. After a time they are planted and numerous small bulbs are formed on the edges of these incisions. At the expiration of one season they are again lifted, and the small bulbs, still only partially developed, are separated from the parent root and planted out again and again, year after year, for three or four years before they become flowering bulbs of fine market quality. Single-flowered Hyacinths, whether in mixed borders or in beds, will generally have a tendency to produce seeds; but as these weaken the bulbs, the flower-stalks should be cut off as soon as the flowers have faded, or the capsules ought to be stripped off the flower-stalks with the hand as soon as they appear; unless, indeed, it is wished to raise new sorts—in which case the seeds may be allowed to ripen, and they should be sown under glass as soon as they are ripe. They will come up the following

spring, and, if carefully transplanted and properly treated, will produce flowers in from three to five years.

*Flowering Hyacinths in glasses of water* is a very simple operation, and may be effected by filling the glass with water up to the neck; and then placing the bulb in the cup-shaped part of the glass intended to receive it, and renewing the water from time to time, when it begins to get muddy. Rain water only should be used for filling the glasses. When the water is changed the bulb should not be taken out, unless the roots are short and few, but the hand should be put over the top of the glass so as to retain the bulb in its place, and the water carefully and slowly poured off. This is done to prevent any injury being done to the long roots, as they are very brittle and easily broken, and the plant is seriously injured by their being in an imperfect state. When one of the long roots is broken, it should be cut off with a sharp knife close to the bulb.

When Hyacinths are to be grown in water-glasses, some persons think it advisable first to plant the bulbs in soil, and when they have made roots of an inch or more in length, to take them up, and wash the roots before putting them in glasses; but planting in a flower-pot generally makes the roots spread, instead of descending perpendicularly; and thus, they can scarcely be put into the glass without breaking. To avoid this danger the bulbs should be planted in loose sandy soil, and a very deep pot. When the bulbs are put into the water, without previously planting them in the ground, the glasses may be kept in the dark, and in a temperature of about 50°, gradually raising it to 55° till the

roots begin to grow; but as soon as this is the case, the glasses should be placed in a room near the light, with a temperature of about 60°, when the plants will grow rapidly. They will, however, in ordinary cases, do very well without any other care than putting them in the glasses, and letting the water at first just touch the bulb. As soon as the roots begin to grow, however, the water should be lowered; as, if water is retained round the bulb after it has been excited into a growing state, it is very apt to rot. For the same reason great care should be taken not to let any water penetrate into the heart of the plant when the leaves begin to open, and the flower-stalk to arise. Should the flower-stem appear weak, it may be supported by a slender prop fixed in a disk of wood, on which the glass may be placed at its base; or by any more elegant or convenient means. In choosing Hyacinths for water-glasses, the red and blue flowers are preferable to those which are white or yellow; the latter two having a fragrance too powerful for rooms, and, besides, they generally flower weaker in glasses than the others. Which-ever kind of Hyacinth is preferred, the largest and primest bulbs of the sort should be selected for glasses. In the windows of seed-shops we sometimes see Hyacinths or Narcissi with their flowers inverted in a glass of water appearing as if they had grown in that position. They are, however, grown in the usual manner, with the glass inverted over the pot in which the flower is grown, and only turned and the glass filled up with water after the flower has expanded, the flower-pot being removed, and the bulb wrapped in wet moss. Sometimes another flower appears grow-

ing from the other end of the glass; but this is grown in another flower-pot in the usual way, and only removed to the glass when it is wanted to produce the proper effect. Deceptions of this kind cannot be considered in good taste, particularly at the present day, when people are so much better educated than formerly. Hyacinths flowered in water are seldom of much use afterwards; nevertheless, if the leaves are carefully preserved, and the plants, immediately that they have done flowering, are planted in a nursery-bed, they will recover their vigour in two or three years. It is also said that sinking the bulb entirely in water after it has done flowering invigorates it, and will enable it to flower the second year; but I have never had an opportunity of proving this.

*Flowering Hyacinths in Moss or Sphagnum.*—Fresh moss can be disposed so as to have a very good appearance; but it smells disagreeably in rooms; therefore Sphagnum, well washed, is to be preferred. It can be placed in pots, baskets, boxes, or vases, and kept moist. The bulbs should be planted in the moist Sphagnum as in soil, and covered with a dry layer of the same substance till they begin to push. The surface of the Sphagnum may then be made to have a gay appearance by covering it with lycopods.

*Growing Hyacinths in pots of soil* requires particular care. To insure a vigorous growth, the pots ought to be deeper than usual, and they need not be much wider at the top than at the bottom. The soil ought to be a sandy loam, mixed with rotten leaves or cocoa-nut fibre, or dung so thoroughly decayed as to have become a kind of mould, and the pots ought to be well drained. In planting the bulb,

make a hole in the soil large enough for it, sprinkle in some silver sand, and then place the bulb, fill in the soil so as to leave about a third of the bulb exposed. When first planted, which ought to be in September, or any period between that month and February, the bulbs may be kept in a cool place, and covered with soil, coal ashes, and sand, till the buds have begun to move; when the pots may be taken to the greenhouse or the windows of a warm room, and if the soil be watered with warm water, they will grow so much the faster. As soon as the plants begin to grow, they will require constant watering, but great care should be taken not to let any water stand round the roots. When the plants have done flowering, they may be turned out of the pots with the balls of earth unbroken, into the common soil; and the bulbs may be taken up and dried when the leaves have decayed. Bulbs which have flowered in pots seldom flower vigorously the second year; and unless the amateur has abundance of room for a nursing-bed, and leisure to manage it, it is better to throw away at once bulbs which have been flowered either in pots or in water-glasses.

HYBRIDS are plants raised from seed produced by fecundating the stigma of one plant with the pollen of another, and the following is the mode of performing the operation:—The plant that is intended to bear the seed should be carefully watched, and, just before the pollen bursts, the stamens should be cut off. The operator must then wait till the stigma becomes covered with moisture exuding from it; and then, but not before, the pollen from the other plant must be applied with the point of a penknife, or the hairs of a camel's hair pencil. Should the cells of the anthers of the one plant burst

before the stigma of the other becomes moist, the pollen may be collected, and kept in paper till the stigma is ready to receive it. In some cases pollen has been kept good in this manner for two years; but the moisture of the stigma should be taken advantage of as soon as it appears, as it soon dries up, and cannot be restored artificially. The best time for performing the operation seems to be about the middle of a bright sunny day; and as soon as it is done, a bit of string, or a strand of bast-mat, should be tied round the stem of the flower, that the seed-pod may be known. As soon as the seeds are ripe, they should be sown immediately in shallow pans of light sandy soil, and set on a greenhouse shelf, where they may be suffered to remain during the winter. Many of the young plants will come up by spring, when they should be immediately potted off into single pots, and treated as before recommended for cuttings. Great care is necessary in selecting the plants proper for hybridising. The object to be kept in view, is to produce in the hybrid a better plant than either of the parents, and this cannot be done when the parents are widely dissimilar; as when they are, their progeny will follow one parent almost to the exclusion of the other. One of the most skilful hybridisers I have met with (Mr. Cole, nurseryman, of Birmingham) proceeds on this plan, choosing the finest plants to raise the seed from, and the result is perfectly successful.

HYDRANGÆA.—*Saxifragdææ*.—There are several kinds of Hydrangæa, most of which are American shrubs, which are quite hardy in British gardens. The kind best known however, and which is called the Hydrangæa, *par excellence*, is a

Chinese shrub, only half hardy in England. Some botanists call it *Hydrangea hortensis*, the garden hydrangea; but Decandolle and the French, *H. Horténsia*, the specific name being given in honour of a French lady, whose Christian name was Hortense. Although the plant is now so common, it has not been introduced much more than seventy years; the first one of it grown in Britain having been imported from China by Sir Joseph Banks, in 1789 or 1790, about the same time as the Tree Pæony. The Hydrangea, though nearly hardy, is generally considered as a greenhouse or window-plant; it is admirably adapted for the latter situation; and it is scarcely possible to give it too much water, though water may be withheld from it for several days without killing it—the plant reminding its possessor of its wants by its conspicuously drooping its leaves, and reviving rapidly when water is given. It should be grown in a rich soil, and its branches should be cut in every year when it has done flowering; as, otherwise, the branches are apt to become unsightly from losing their leaves near the base.

Blue Hydrangeas are very much admired; partly, perhaps, from the difficulty of obtaining them, for no plants can be more capricious. Sometimes they come without any trouble at all; sometimes applying any one of the numerous recipes recommended will change the colour, either directly or gradually; and sometimes no care nor any recipe has the slightest effect, and the flowers remain pink, in spite of all that can be done to turn them blue. Water impregnated with alum, steel filings, sheep's-dung, wood-ashes, peat-ashes, nitre, carbonate of soda, or common salt, are all recommended,

and all succeed—sometimes. The flowers are occasionally turned blue by removing the plants to a loamy soil, and sometimes by planting them in peat. It is generally allowed that the fine yellow loam found in some parts of Hampstead and Stanmore Heath, and the peat of Wimbledon Common, are sure to produce the desired effect: as is also the peat of the bogs near Edinburgh, and that of the neighbourhood of Berlin and St. Petersburg; or any soil that contains a large proportion of iron. Water in which tan has been steeped is also very often successful; though, like the other recipes, it cannot always be depended on.

**HYDROCHARIS**—*Hydrocharitaceæ*.—Frogbit.—A pretty little British water-plant, with white flowers

**HYDROPIPER**.—Water Pepper.—See POLYGONUM.

**HYGROMETER**.—An instrument for measuring the dryness, or in other words the moisture of the air. There are various kinds, but that which is the simplest, and which is now most universally used, is formed of two delicate thermometers, the bulb of one being naked and kept dry; the other covered with muslin and moistened with a little water. If the air is not completely saturated, evaporation from the wet bulb immediately takes place, cold is thereby produced, and that thermometer exhibits a lower degree of temperature than the one with the dry bulb. If the difference is 10°, the dryness is great; if as much as 15° it is excessive, and with that degree of dryness neither plants nor animals can long be healthy. Living rooms it is well known are generally too dry for plants; and also for human beings. If the wet bulb thermometer indicate three or four degrees lower than the one with

the dry bulb in the same apartment, there is no danger from that apartment being too damp.

**HYPERICUM.** — *Hypericaceæ*. — St. John's Wort. — The pretty yellow-flowered shrubs and herbaceous perennials known by this name at the present day, were formerly in high repute for driving away evil spirits; and on this account were generally planted near dwelling-houses. They were also highly valued for their medicinal properties, being believed to have a powerful effect in stopping blood and healing wounds. The most common kind, the Tutsan, or Park Leaves, is now made into another genus, under the name of *Androsæmum*; but the botanical distinction is very trifling. All the kinds will thrive under the drip of trees; and they will grow in any soil and situation, though they prefer moisture and the shade. They are found in almost all the temperate climates of the world; and they are propagated by seeds and by dividing the roots.

**HYPOCALY'MMA.** — *Myrtaceæ*. — The Peach Myrtle. — This is a beautiful little Swan River shrub, with peach-coloured flowers. It is a greenhouse plant, requiring the usual treatment of half-hardy Australian shrubs. The leaves when bruised smell of lemon; and the flowers closely resemble those of the peach-tree, except that they are much smaller.

**HYPOCYRTA.** — *Gesneraceæ*. — *H. gracilis* is a pretty creeping stove plant, with cream-coloured flowers, growing like an epiphyte, on trees in the moist forests of South America. *H. scabrida* has very brilliant red flowers.

**HYPOXIS.** — *Hypoxidaceæ*. — A native of Natal with bulb-like tubers, broad leaves, and a profusion of golden-yellow star-like flowers.

**IBERIS.** — *Cruciferae*. — Candytuft. — Most of the kinds of Candytuft are well-known annuals, which received their name from *I. umbellata*, the first species grown as a garden flower, having been brought from Candia. The seeds should be sown in a rich light soil in autumn, where they are to remain, and kept rather dry during winter. They should be repeatedly thinned out, and in spring they should be watered with liquid manure, taking care not to let the liquor touch the plants. When the plants are about to flower, those of the common kind should be six or eight inches apart every way at least; and those of *I. coronaria*, the Rocket Candytuft, should be from one to two feet apart; and thus treated, the flowers will be very large and fine. When it is not thought advisable to take so much trouble, the seeds may be sown very thin, either in autumn or early in spring; either alone, or mixed with mignonette; and in either case they will look very well in the flower borders. *I. umbellata atropurpurea* is a fine variety for beds and ribbon borders. The perennial and suffruticose kinds are well adapted for rock-work; and they are easily propagated by cuttings, or by dividing the root.

**ISLAND MOSS.** — *Cetraria islandica*.

**IOE PLANT.** — See **MESEMBRYANTHEMUM**.

**ICHNEUMON FLY.** — A very elegant slender creature, somewhat resembling a gnat, which generally deposits its eggs in the living body of a caterpillar. Great numbers of caterpillars are thus destroyed every year; and as the grub of the Ichneumon does not feed upon vegetable matter of any kind, it may be regarded as a friend to gardeners, and

it should be spared accordingly. There are several kinds of Ichnemomones, some much larger than others, but the habits of all are the same.

**ILEX.**—This name is frequently applied in common conversation to the *Quercus Ilex*, or evergreen oak; but it is properly the botanic name of the Holly.

**ILEX.**—*Aquifoliaceæ*.—A genus of evergreen shrubs or low trees, of which the most interesting is *Ilex Aquifolium*, or the common Holly, a native of Britain, with fine dark green prickly leaves, and scarlet or coral-coloured berries. There are a great many varieties of this shrub, some of which have leaves variegated with cream-colour, white, different shades of yellow, and slight tinges of red; and others have white, yellow, and even black fruit. They are all beautiful, and, being evergreen and quite hardy, are reckoned among the most ornamental of British shrubs. They grow slowly, but as they are always erect and compact, they are very valuable for small gardens, where the plants require to be kept within bounds. The species are propagated by seeds, which are kept a winter in a rot-heap before they are sown; and the varieties are propagated by budding or grafting on the species, and sometimes by cuttings. As, however, the operation of propagation, whether by seeds or otherwise, is slow, and, in the case of budding and grafting, somewhat difficult, amateurs will always find it preferable to purchase plants from the nurserymen. Hollies will grow in any soil in an airy situation, but they do not thrive in smoke. They prefer a loamy soil, but they will grow in sand, and also in strong clay; and, though not so well, on chalk or limestone. They make beautiful and permanent hedges,

elegant single trees, and picturesque groups; and from the closeness of their foliage, they are very useful in shutting out any unpleasant object. A Holly hedge is also well adapted for a street or roadside garden; as, while it serves as a screen, it has a cheerful look, both in summer and winter. Among the rarer kinds of Ilex may be mentioned *I. latifolia*, a hardy evergreen tree from Japan, remarkable for the large size and deep green of its leaves, and its numerous clusters of red berries. Another very handsome species is *I. platyphylla*, a native of the Canaries, with large white flowers and scarlet berries more than twice the ordinary size.

**ILLICUM.**—*Winteraceæ*.—Half-hardy shrubs, with very dark strongly scented flowers, which smell like aniseed; and hence the popular name applied to the genus of Aniseed Tree. Most of the kinds come from China, and are tender in British gardens; but *I. floridulum*, an American species, is very nearly hardy, only requiring protection in severe winters. They should all be grown in peat; and they are generally increased by layers, though cuttings will strike in heat under a bell-glass.

**IMANTOPHYLLUM.**—*Amaryllidaceæ*.—A very splendid plant, with a large head of bright scarlet and yellow flowers. It has somewhat the habit of the *Agapanthus*, and is a native of Natal.

**IMPATIENS.**—*Balsaminaceæ*.—*Noli me tangere*. There are several annual hardy species of this genus, most of which are natives of Europe and North America, and have yellowish flowers; but some have lately been introduced with beautiful pink flowers from India. They are all distinguished by the seed-vessel springing open when it is

touched, and discharging the seeds. All the kinds require a light soil, and abundance of water; and they are generally large, erect, strong-growing plants. Several very beautiful species have been introduced within the last few years from the Himalayan Mountains, most of which have pinkish or rose-coloured flowers; and lately a creeping plant (*I. repens*) has been introduced, the first creeping plant of the genus seen in Europe. It has yellow flowers, and it is a native of Ceylon. Another very curious kind of balsam is *I. Jerdoniae* with very showy green, red, and yellow flowers, and tuberous stems, which send out roots at intervals. It was found growing on trees among the Indian mountains.

**INARCHING.**—A species of grafting, in which the scion is only partially separated from the parent plant; in such a manner, that while it is uniting with the stock, it derives a portion of its nourishment from the plant to be propagated. For this purpose the stock is either planted near the parent, or if in a pot it is placed near it, in such a manner that a branch from the scion can be readily joined to the stock. The stock is sometimes cut over immediately above its point of junction with the branch joined to it; but more frequently the stock is left at length. The stock may either be united to the scion by notching the one into the other, as in notch-grafting; or simply by paring a portion of the bark and wood from both scion and stock, and splicing them together, as in side-grafting. In either case the scion is made fast to the stock by tying them together with strands of matting, and the graft so formed is covered with moss tied on, or with grafting-clay, or grafting-wax.

After a certain period, the scion and stock unite, when the former is separated from the parent, and the stock is cut over a little above the graft. After some further time, when the scion begins to grow vigorously, the stock is cut close over above the point of union, and the section left becomes in time covered with bark. April is the best season for inarching, as unless the sap is fully in motion, the wounds dry instead of uniting; and hence, if the operation be performed too soon, when the stock and the scion are examined at the end of the time when it is expected they will be united, it will be found that they do not adhere at all, and that, indeed, the wounds have healed separately.

Inarching is only adopted in the case of woody plants that grow with difficulty when grafted in the usual manner. The conditions of growth are the same as in independent grafting—viz. that the inner layer of bark of the scion must be placed exactly on that of the stock, to insure their union. Inarching is generally applied to Camellias; and any person who has visited any of the great Camellia growers in April or May, must have seen some of the large old plants of the superior kinds, surrounded by a number of pots of the common single red, supported at different heights, for the convenience of reaching the different branches to which they have been united by inarching. One of the modes shown of grafting has all the advantage of inarching, the scion being nourished by the water as it would be in inarching by its roots.

—See GRAFTING.

INDIAN CORN.—See ZE'A.

INDIAN CRESS.—See TROPÆOLUM.

INDIAN FIG.—See OPUNTIA.

INDIAN SHOT.—See CA'NNA.

INDIGO'FERA.—*Fabaceæ*; subtribe, *Indigofereæ*.—Several species afford the indigo dye of commerce, especially *I. tinctoria* and *I. cœrulea*. *I. decora* is a pretty flowering plant from China, nearly hardy, and which forms a good greenhouse plant; and it may also be grown out of doors in a sheltered situation.

I'NGA.—*Leguminosæ*.—Beautiful plants, nearly allied to the genus *Mimosa*, with silky tassel-like flowers.—All the species are stove shrubs, and should be grown in a mixture of loam and peat. They are propagated by cuttings taken off at a joint, which are struck in pure sand, under a bell-glass, and plunged in a hotbed, or tan, to afford them bottom heat.

INSECTS are extremely destructive to flower gardens, particularly those belonging to the order Lepidoptera, which includes the butterflies and moths. Some of the Coleoptera, or beetles, are also very injurious, while in the grub state. It would take too much space, in a work like the present, to give even the names of all the insects which injure flowers; but some of the most destructive are mentioned by their popular names as they occur in the alphabetical series, and a few words said on each. Entomology should, however, be studied by every one who loves flowers; as it is of great service to the florist to know these destructive creatures under all their changes. It is true, that insects are, in most cases, only injurious in the caterpillar state; but often, by destroying a chrysalis, or a moth, or butterfly, before it has had time to lay its eggs, the mischief which would have been done by the brood which would be raised from them may be prevented.

I'NULA.—*Compositæ*.—Elecampane.—Some of the foreign species of this genus are very showy plants, all with orange-yellow flowers, and large coarse stalks and leaves. They are only suitable for large gardens or shrubberies.

IONOPSI'DIUM.—*Crucifereæ*.—*I. acutale* is a pretty little annual plant found wild on the Basaltic hills near Lisbon, and consequently very suitable for rockwork. Its flowers, which, though small, are very abundant, are white when they first appear, but turn to lilac before they fade. When first introduced in 1845, it was supposed to be a *Cochlearia*.

IPOMŒA.—*Convolvulaceæ*.—Beautiful climbing plants, herbaceous and shrubby, which should be brought forward in a stove or hotbed; though when they have formed their flower-buds, many of them may be planted out in May to flower in the open air. All the species should be grown in a light soil, well manured with decayed leaves, or the very rotten part of an old hotbed. Two beautiful kinds are *I. rubro-cœrulea* a half-hardy annual, which, if planted out in a warm border, will flower beautifully in the open air; and *I.* or *Pharbitis* *Lealii*, which will only flower in a stove. Both these kinds produce an astonishing number of flowers, though each flower lasts only one day, and sometimes, if too much exposed to the sun, only a few hours; and both grow with great rapidity and vigour. *I. Lealii* is, however, a shrub, and is propagated by cuttings, which strike rapidly with the aid of a little bottom-heat. *I. ficifolia* resembles these species, but it has darker flowers, which will expand in greenhouse-heat, and which live two or three days. It is shrubby, and



continues flowering till autumn. *I. Horsfalliae* is also a most splendid climber. It should be grown in a moist stove, in rich light loam, and allowed plenty of water while growing. It thrives best when grafted on *I. insignis*, and when grown on its own roots it should be cut down every year to within a few inches of the ground. Another species, *I. tyrianthina*, has very rich dark flowers, which it produces in great abundance.

IPOMOPSIS. — *Polemoniaceae*. — Beautiful biennial Peruvian plants, with splendid scarlet flowers, which Professor Don and some other botanists classed with the *Gillias*, and which were formerly called *Cántua*. They are free-growing plants; but as they are supposed to require protection during winter, they are generally grown in pots in England, and kept in a greenhouse. In America, however, it appears that these plants are found in a wild state in Georgia, and that they are left in the open ground all the winter, without any protection, in the neighbourhood of Boston, whence the plants attain a size (seven feet high), and the flowers a brilliancy of colour, quite unknown in Europe. They should be grown in a light and somewhat rich soil; and care should be taken to prevent their roots from becoming sodden with water, as when this is the case, they are very apt to damp off.

IRIS. — *Iridaceae*. — There are three distinct kinds of Iris, besides innumerable species, hybrids, and varieties. These are, the fibrous-rooted kinds, which grow best in a fine sandy loam, and which increase rapidly every year by suckers from the roots; the tuberous-rooted kinds, which are very apt to be destroyed by snails, or to rot from too much wet; and the bulbous-rooted kinds, which

should be taken up and replanted every second or third year, as the new bulbs, which are formed every season, are always directly under the old bulb; and thus in the course of a few years the bulbs descend so low as to be out of the reach of the air, and consequently incapable of vegetation. Thus it will be generally found that persons in the habit of growing Irises are always complaining of losing their plants, while the real fault rests with themselves for not taking up their bulbs at the proper time. The bulbous and tuberous-rooted Irises succeed best in sandy peat, or in any light and dry soil. The splendid Chalcædonian Iris is one of the tuberous rooted kinds; and it not only requires a dry soil during winter, but to be allowed plenty of pure air during the whole period of its growth, or it will be very apt to damp off.

IRISH IVY. — The Giant Ivy, *H. canariensis*, which, though called Irish, is in fact a native of the Canary Islands.

IRISH YEW. — The upright-growing Yew, which forms a flame-shaped tree, like the upright cypress, or the Lombardy poplar, instead of spreading like the common kinds. When young, it makes a very handsome shrub, from the fine colour and luxuriance of its foliage.

IBATIS. — *Cruciferae*. — *I. tinctoria*, the Woad, is a British plant, used for dyeing blue, and which looks well in a miscellaneous border or shrubbery. Some of the species are dwarf plants, very suitable for rock-work.

ISOLEPIS. — *Cyperaceae*. — *I. gracilis* is a pendulous grass-like plant, very ornamental in a conservatory, greenhouse, or in apartments. It grows in tufts of numerous capillary flexible stems, which are very grace-

ful when planted so as to hang down over the sides of vases, pots, or suspended baskets.

ISONA'NDRA. — *Sapotaceæ*. — *I. gutta* is the tree which is said to produce the Gutta Percha. It is a native of the Malay Peninsula and Borneo, and has only very lately been introduced into Great Britain. In the autumn of 1848, there were, however, two or three healthy plants of it at Kew.

ISOPO'GON. — *Proteaceæ*. — Australian plants, with very curious leaves and flowers, nearly allied to *Banksia*. They should be grown in peat and sand, mixed with a little turfy loam, and the pot should be a third filled with potsherds broken small. These plants are very difficult to cultivate, as they are very apt to damp off; the cuttings also are extremely difficult to strike.

ISO'TOMA. — *Lobeliaceæ*. — Annual and biennial plants which may be sown in the open ground, or brought forward in a hotbed, and planted out in May. *I. axillaris* is a most beautiful and elegant plant, the flowers of which look like a large lilac jasmine.

I'TEA. — *Ericaceæ*. — A little hardy American shrub, which requires peat soil in British gardens.

IVY. — See HE'DERA.

IXIA. — *Iridaceæ*. — Bulbous-rooted plants, with very beautiful flowers, which vary exceedingly in colour and form. They are all natives of the Cape of Good Hope, and they are generally grown in pots in greenhouses; but as, when thus treated, their slender stems are apt to become etiolated, and consequently very weak, they do much better in the open garden, treated in the following manner, in the climate of London:—A bed of any length and breadth that may be required, should be dug out to the depth of two or

three feet, according to the nature of the soil, a retentive clay requiring to be dug deepest. This bed should have a third part of its depth filled with pebbles, brick-bats, or any other draining material. A stratum of fresh turfy loam, should be laid on this, and above it a stratum of rotten cow-dung, so as to fill the bed to within about a quarter of its depth from the surface of the ground. The bed should then be filled with a mixture of light turfy loam and sand, the loam being broken or chopped small, but not sifted. The surface of the bed should be raised two or three inches above the level of the surrounding border; and it is most desirably situated, if backed by a south wall, and sloping from the gravel-walk. In this bed the *Ixia* roots should be planted in quincunx; and if they are protected by a thatched covering raised on a slight wooden frame during winter, they may be left in the ground several years without sustaining any injury. In the north of England, or in any cold wet climate, the *Ixias* may be planted in October in pots, well drained, with a layer of cow-dung over the drainage, and filled up with a mixture of turfy loam and sand. The *Ixias* should be planted three in each pot; and the pots should be plunged into a hotbed, and covered with a glass frame during winter. In spring, the glasses may be gradually removed, and when the flowers are nearly ready to expand, the pots may be removed to the greenhouse, or the window of a sitting-room. Where the soil of a garden is a fat yellow loam, on a chalky or other porous subsoil, and the situation dry and yet sheltered, the bulbs may frequently be planted in the open ground, and left there for years, without any other care than covering

them with a heap of dead leaves during winter.

**IXORA.** — *Rubiaceæ*. — Splendid stove plants. The history of *Ixora coccinea*, the best known species of the genus, is rather curious. It is a native of China, and of some of the East India islands, where it is worshipped as a sacred plant, and where it is said to form a small tree about six feet high, rising with a single stem, and having its head formed entirely of clusters of bright scarlet and yellow flowers, whence it has received the names of *Flamma Sylvarum*, and the Tree of Fire. This plant was first introduced in 1690; but it was soon lost, and its existence was even doubted, till it was re-introduced about a hundred years afterwards by the celebrated Doctor Fothergill. After this, seeds were obtained by several nurserymen, and the plant was so much admired that it was sold for several years at five guineas each. It is now common in collections, but it is rather difficult to keep; as, though it requires a moist heat, it will die if its roots are suffered to retain any stagnant moisture among them, and it must not be plunged either in tan or in a hotbed. It is also very liable to be attacked by insects. *Ixora javanica* is a very handsome plant, with bright red branches, orange flowers, and large deep-green leaves. It is a native of Java, and in this country it requires a warm moist stove; as, unless it has abundance of heat and moisture, it is apt to be infested with insects.

**JACA, OR JACK TREE.** — A species of *Artocarpus*, or bread-fruit.

**JACOBÆA.** — The plant usually called by this name is a species of *Senecio*, or Groundsel. It is also called purple Ragwort. — See *SENECIO*.

**JACOBÆA LILY.** — A splendid bulbous-rooted plant, formerly called by botanists, *Amaryllis formosissima*, but the name of which is now changed to *SPRECKELIA*, which see.

**JACQUI'NIA.** — *Myrsinææ*. — West Indian trees and shrubs, with showy flowers, requiring a stove in England. They should be grown in loam and sand, and are propagated by cuttings.

**JALAP.** — The plant producing Jalap was formerly supposed to be a kind of Marvel of Peru; but it is now discovered to be a kind of *Convolvulus*, or *Ipomœa*.

**JA'MBOS, OR THE ROSE APPLE.** — A kind of *Eugénia*, belonging to the order *Myrtacææ*.

**JASMINE.** — See **JASMINUM**.

**JASMINUM.** — *Oldenææ*. — The Jasmynes are shrubs remarkable for their fragrant flowers; and the common species, *Jasminum officinale*, is one of our most vigorous-growing wall-climbers, though a native of India. There are several species hardy in British gardens, but the greater number require the greenhouse or stove. The principal hardy species is that already mentioned. It well deserves a place against the wall of a house, or the piers of a verandah, which it will cover in a very short time; or, if planted against trellis-work, or against the frame-work of a bower, it will soon afford an agreeable shade, and produce its long, graceful, deep-green shoots in such quantities as, after covering the bower, to hang down to the ground all round it, and require to be separated like a curtain by a person entering. This plant and the common Ivy, when trained up a single post, with a spreading umbrella top of framework, form two of the finest objects in small gardens by their pendant branches,

which not only hang down from a height of from fifteen or twenty feet to the ground, but trail along it to a considerable distance. Both plants may be called evergreens; as, though the Jasmine is not so from its leaves, it is so from the deep-green colour of its shoots. The flowers are white and very fragrant, and yield an oil similar to that produced by *J. grandiflorum*. *J. revolutum* is a native of Nepal, with yellow blossoms, and thrives against a wall, where it grows with great vigour, covering a large space in a short time. *J. nudiflorum* is a very beautiful species introduced from China by Mr. Fortune in 1844. It has large yellow flowers, which appear before the leaves, and it is quite hardy. It is a very valuable plant, as it flowers in January, when so few plants are in flower in the open air. *J. fruticans* and *J. humile* are upright border shrubs, with yellow flowers, deciduous leaves, and deep green shoots. *J. grandiflorum* is a hothouse shrub that bears a strong resemblance to the common Jasmine, and yields the Oil of Jasmine of the shops. *J. odoratissimum*, from the Azores, has yellow and very fragrant flowers and broad evergreen leaves. *J. azoricum*, a native of Madeira, requires the greenhouse, has white flowers, and is very fragrant; and *J. Sambac*, a stove species, of which there is a variety with double flowers, is most fragrant during the night. It is to this species that Moore alludes in his beautiful lines on the Jasmine. There are several other species, but all are climbers, except *J. fruticans* and *J. humile*, already mentioned. They will all thrive in any common garden soil, mixed with leaf-mould; and they may be all propagated by cuttings planted in sand, and covered with a hand-glass.

JERUSALEM SAGE.—See PHLO'MIS.

JET D'EAU.—A fountain, which consists of a single column of water, rising straight up out of the ground. —See FOUNTAINS.

JONQUIL.—A kind of Narcissus.

JUDAS TREE.—*Cercis Siliquastrum*. — A low tree, producing numerous racemes of beautiful purplish pink flowers, from the old wood of the trunk and branches. It grows freely in any common garden-soil, but prefers a warm and sheltered situation; and it flowers best against a wall. The flowers have an agreeable and slightly acid taste; and they are eaten in France, fried in batter as fritters. There are several varieties, but the only other species is *C. canadensis*, a native of North America. As these plants bear abundance of seed, and grow rapidly, they are often raised from seed; and hence the great number of varieties. They may also be propagated by layers.

JUJUBE TREE.—The lozenges called Jujubes are made from the fruit of *Zizyphus vulgaris*, which ripens abundantly in the neighbourhood of Paris; but the real Jujube-tree is *Z. jujuba*, a native of the East Indies, which requires a stove in Europe. Both are nearly allied to *Paliurus*, or Christ's Thorn.

JULIBRI'SSIN. — This beautiful tree, which is a kind of Acacia, is called the Silk-tree, from the abundance and silkiness of its long, fine, tassel-like blossoms. It is rather tender in England, but it grows freely in Italy. —See ACO'VIA.

JUNIPER.—See JUNIPERUS.

JUNIPERUS. — *Conifera*, § *Conpressina*. — The Juniper. — Evergreen shrubs, natives of different parts of the world, but most of which are hardy in British gardens. They all thrive in common soil

mixed with sand, or in heath-mould; and they are generally propagated by seeds, though they will all root from cuttings. *J. communis*, a native of Britain, of which there are several varieties, is a very common hardy evergreen, sometimes found in the form of a low bush, and at others in that of a conical tree, like the Cyprus. It bears clipping, makes excellent garden hedges, and was formerly cut into a great variety of shapes. The fruit is used throughout Europe to flavour ardent spirits (the spirit called Holland being flavoured with it), and the wood is burned in ovens or kilns to flavour dried beef, hams, or fish. *J. virginiana*, the Red Cedar, is one of the most common of small evergreen trees, or large shrubs. It is raised from seeds, and the male and female plants being of different sizes, the individuals vary exceedingly in their form and manner of growth; so that a number of plants of this species may exist in a shrubbery or pleasure-ground, and yet not two of them be alike. *J. excelsa* is a tall Cypress-like shrub, or low tree, very hardy and very ornamental. *J. recurva*, a native of Nepal, is a very elegant plant, with drooping shoots, well adapted for cemeteries. It is one of the hardiest of the species, and thrives even in the smoke of London. *J. Sabina*, the common Savin, is one of our most ancient garden shrubs, being almost the only coniferous evergreen planted in the time of Queen Elizabeth; and there are several varieties of this species, all of which are beautiful. The fragrance of all the Junipers is resinous and refreshing, and many of the kinds are used in medicine. The wood used in making lead pencils, is generally that of the red cedar; or of the Barbadoes Cedar, *Cedrela*

*odorata*, which last is a stove plant in England.

**JUSTICIA.**—*Acanthaceæ*.—Stove plants, with showy and curious flowers. They require a rich light soil, or a mixture of loam and peat, and flower freely with moderate care. They are propagated by cuttings, which strike readily in sand, under a hand-glass, and with bottom-heat. *Justicia bracteolata*, now called *Thyrsacanthus bracteoides*, is an extremely handsome plant, as when grown in a stove it produces its pretty lilac flowers all the winter.

**KALMIA.**—*Ericaceæ*.—The Calico Laurel.—Low shrubs with beautiful flowers; natives of North America. They may be grown with perfect safety in the open air, or they may be kept in a greenhouse and forced, so as to flower in February. They are generally grown in peat earth, on account of their numerous hair-like fibrous roots; and they may be removed even when in flower, without injury, if sufficient care be taken. They are propagated by layers, or by seeds, which are received every year in large quantities from America. The seeds should be sown in pots, in sandy peat, or heath-mould, as it is called; and they should be very thinly covered. When the plants come up, they should be transplanted into other pots, putting three in each, and they should not be removed to the open ground till they are five or six inches high. They should be planted out in spring.

**KALOSANTHES.**—*Crassulacæ*.—Mr. Haworth's name for *Crassula coccinea*, and some of the allied species.—See **CRASSULA**.

**KAULFUSSIA.**—*Compositæ*.—A beautiful little annual, with bright

azure blue flowers, resembling an Aster, the ray florets of which curl curiously back after they have been expanded a short time. This plant was formerly considered half-hardy; but it is found only to require sowing in the open border in April, to flower in May or early in June. Its beauty is, however, very short-lived, as its flowers have generally all faded and its seeds ripened before the end of July. It was named *Charëis* by Professor De Candolle, but the name has not been generally adopted. *K. rosea* has rose-coloured flowers, with mauve centre.

KEEL.—The lower part of the flower of a pea-flowered plant, consisting of two petals, so closed together as to resemble a little boat.

KENNE'DYA.—*Leguminosæ*.—A genus of well-known plants, with showy flowers, which has been lately divided by Baron Hügel into four new genera, viz. :—the *Hardenbergias*, comprising those with small bluish or lilac flowers on slender branches, the type of which is *K. monophylla*; the *Zichyas*, having bunches of broad reddish flowers, with very short keels, as for example, *K. coccinea*; the *Kennedyas*, with large scarlet or crimson flowers, having long keels; and the *Physalobiums*, having flowers a good deal like those of the *Zichyas*, but with bladdery capsules. All the *Kennedyas* are Australian climbing or trailing shrubs, which require a greenhouse in England, and should be grown in heath-mould, or very sandy loam, mixed with peat. They are propagated by cuttings, which strike readily in sand, under a bell-glass.

KE'RRIA.—*Rosæcæ*.—By some mistake, *Kerria japonica* was at first supposed to belong to *Córchorus*, a genus of *Tiliacæ*, and of course nearly allied to the Lime-tree, to which

it bears no resemblance, though it is still called *Córchorus japonicus* in the nurseries. It is also singular that though the double-flowered variety was introduced into England in 1700, the species was not introduced till 1835. It is a delicate little shrub, too slender to support itself in the open air; but when trained against a wall, flowering in great profusion. It should be grown in a light rich soil, and it is propagated by cuttings.

KIDNEY VETCH.—See *ANTHYLLIS*.

KNAPWEED.—*Centaurea Scabiosa*.

KNAU'TIA.—*Dipsacæ*.—One species is a very pretty little flower, requiring only the usual treatment of hardy annuals.

KNIGHT'S STAR.—A kind of *Amaryllis*, considered by some authors as forming a separate genus called *Hippeastrum*.

KNIPHOFIA.—*Asphodelæ*.—A most striking plant, with large massive flower spikes of scarlet and yellow flowers. It is a native of the Cape of Good Hope; but it will flower profusely all the summer, if planted in the open garden, and it has a very good effect in rockwork; the foliage is also ornamental. The genus was formerly called *Tritoma*.

KNIVES are used in gardening for pruning and also for budding and grafting. Pruning knives were formerly characterised by hooked blades; but straight-edged blades are now preferred, as making a cleaner cut. The best description of budding knife has a straight blade, the upper half of the back having also a cutting edge, and the handle is terminated by a rounded end. Sometimes a knife is made to serve as both a budding and grafting knife, as shown in fig. 32.

KNOWLTONIA.—*Ranunculacæ*.

—Half-hardy perennial plants, na-

tives of the Cape of Good Hope, nearly allied to *Addis vernalis*. They should be grown in peat, mixed with a little loam; and they are increased by dividing the roots.



FIG. 32.—GRAFTING KNIFE, WITH THE PORTION OF THE BACK OF THE BLADE FROM + TO + GROUND TO A CUTTING EDGE, SO AS TO MAKE IT SERVE ALSO FOR A BUDDING KNIFE.

**KÖLREUTERIA.**—*Sapindaceæ*.—A middle-sized deciduous tree, a native of China, but quite hardy in British gardens, and very ornamental from its large variously-divided foliage, and its conspicuous terminal

compound spikes of rich yellow flowers. These are freely produced in the climate of London, and are often succeeded by bladdery capsules, which contain seeds; and from these, or cuttings of the roots, it is readily propagated. It will grow in any soil, and does not altogether dislike coal-smoke.

**KONI'GA.**—*Cruciferae*.—The Sweet Alyssum.—A pretty little annual, with white sweet-scented flowers, often used as an edging-plant to beds and borders. It only requires sowing in the open ground in March.

**L**ABELS are pieces of wood, parchment, or metal, bearing the name of the plants, and tied to them. When the names are affixed to a piece of wood or metal, stuck into the ground, they are called tallies; and of these there are many kinds.—See TALLIES.

**LABLA'VIA.**—*Leguminosæ*.—The Egyptian Bean, formerly called *Dolichos Lablab*, but now *Lablavia vulgaris*. A half-hardy climbing annual, or biennial plant, which only requires the usual treatment of similar plants. It has a very showy flower.

**LABU'RNUM.**—See CY'TISUS.

**LACE BARK.**—See LAGE'TTA.

**LACE LEAF.**—See OUVIR'ANDRA.

**LACHENA'LIA.**—*Asphodelææ*.—Cape bulbs, with very showy flowers. They will not need taking up in winter; but must be grown in pots in a greenhouse, and allowed very little water at that season. They are generally grown in loam and peat, mixed with a little leaf-mould.

**LA'DANUM, or Labdanum.**—A gum produced by some of the kinds of *Cistus*, used in laudanum, which is prepared from opium, made from the heads of the Poppy.

LADIES' BEDSTRAW.—See GALIUM.

LADIES' MANTLE.—See ALCHEMYLLA.

LADIES' SLIPPER.—See CYPRIPEDIUM.

LADIES' TRACES.—See SPIRANTHES.

LADY BIRD.—See COCCINELLA.

LÆLIA.—*Orchidaceæ*.—Very beautiful epiphytes for winter blooming, and which may be grown with its roots wrapped in moss, and fastened on a piece of wood; or in the husk of a cocoa-nut. The flowers are extremely beautiful and very delicate. *L. superbiens* is a magnificent orchid; flowers deep rose, variegated with dark red, lip crimson striped with yellow; they are produced on spikes five or six feet long, with upwards of fifteen flowers three or four inches across on each spike. *L. A'nceps*, *L. Perrinii*, and *L. Turneri*, are very fine species; the latter is quite new. See ORCHIDEOUS EPIPHYTES.

LAGENA'RIA.—*Cucurbitaceæ*.—The Bottle Gourd.—An East Indian species of Gourd, which is sometimes grown on account of its curious shape; but the pulp of which is poisonous.

LAGERSTRÆ'MIA.—*Lythraridæ*, or *Salicariæ*.—The Pride of India.—Beautiful trees, with flowers something like those of the *Clarkia* in form, but much more brilliant in colour. *L. indica*, flowers deep rose, is generally grown in the stove, but the other species succeed if planted in the open ground in a conservatory.

LAGETTA.—*Thymelæææ*.—The Lace Bark Tree.—A shrub or low tree, a native of Jamaica, remarkable for its liber, or inner bark. This inner bark slips off the wood without difficulty; and its fibres, which are extremely fine, are so tough that

they will admit of being spread out without breaking or separating, till the bark becomes lace-like in its texture. Charles II. had a collar and ruffles made of it. In England the plant requires a stove, and to be grown in a mixture of loam and peat. It is propagated by cuttings, which are rather hard to strike. The flowers are white, and in shape they resemble those of the *Mezereon*; but instead of being produced in clusters round the stem, they grow on a kind of spike, far apart from each other.

LANTA'NA.—*Verbenacææ*.—Greenhouse and hothouse plants, with pretty flowers, nearly allied to the *Verbenas*; and the half-hardy ones requiring the same treatment. Of these there are many very pretty varieties.—See VERBENA.

LAPAGE'RIA.—*Smilacææ*.—The genus was named after the Empress Josephine, whose maiden name was Lapagerie. *L. rosea* is a very showy climbing plant, with large bell-shaped white flowers tinged with rose at the base. It is a native of Chili, but it flowers freely in a greenhouse. It must have a well-drained, highly porous soil, consisting of peat and loam, and which will admit of the plant, while growing, being deluged with water without the latter remaining stagnant; and after the blooming season is over, which lasts a long time, moisture should be gradually withdrawn, in order to induce the plant to ripen its wood. Under this treatment, which is that practised by the Messrs. Veitch, it flowers in a greenhouse most profusely, each shoot forming a wreath of gay blossoms for several feet in length. With the above *L. alba* contrasts very well.

LAPEYROUSIA.—*Iridacææ*.—Cape bulbs, with pretty flowers,



which may be planted in a warm border, and left in the ground during winter, if protected during that season by a hand-glass, &c., from frost or heavy rain.

LARKSPUR.—See DELPHINIUM.

LASIOPE'TALUM.—*Byttneriaceæ*.—Australian low shrubs, which require a greenhouse in England, and are grown in loam and peat, and propagated by cuttings.

LASTHE'NIA.—*Compositæ*.—Californian annuals with bright yellow flowers; which require the usual treatment of Californian plants.—See CALIFORNIAN ANNUALS.

LA'THYRUS.—*Leguminosæ*.—A genus of vigorous-growing, very ornamental perennials and annuals, of which those best known are *L. latifolius*, the Everlasting Pea, with pink flowers, and a variety with pure white flowers, both growing to the height of six feet or eight feet when supported by sticks, in the manner of common Peas, or trained to a trellis; *L. grandiflorus*, a perennial, remarkable for the large size of its flowers; *L. odoratus*, the common Sweet Pea, an annual remarkable for the fragrance of its blossoms, which are of various colours; and *L. tingitanus*, the Tangier Pea, a tall-growing plant, the flowers of which are dark purple. Another very interesting species is Lord Anson's Pea, *L. magellanicus*, a perennial plant, interesting from the beauty of its foliage and its blue flowers, and not nearly so much cultivated as it ought to be: against a wall it is a rare, and at the same time a very elegant species. There are many others, both annuals and perennials, all of which are more or less showy, and being of vigorous growth are well adapted for broad borders. They will grow in any common soil; the annuals are propagated by seeds,

and the perennials by division of the root.

LAUREL.—See CH'RASUS.

LAU'RUS.—*Laurææ*.—The Sweet Bay, *L. nobilis*, is a very handsome evergreen shrub or low tree, with dark-green leaves. It is somewhat tender, and requires a sheltered situation. The male and female flowers are on different plants; and the former, which are of a rich yellow, are by far the most showy. It will grow in any common soil, and it is propagated by layers. The leaves are used to flavour custards; but as they contain prussic acid they should not be used for that purpose, nor in any way in connection with articles of food. A number of French soldiers were poisoned in the Peninsula in consequence of using laurel wood for skewers. The fruit of the female plant is a round, dark purple berry, produced in abundance in fine seasons; but it is seldom seen, as the male plant is by far the most common. There are several other kinds of *Laurus*, most of which are stove shrubs.

LAVA'NDULA.—*Labiata*.—The Lavender is a low suffrutescent bush, well known for the fragrance of its flowers, and for an oil which they yield by distillation in water. *L. Stæchas*, the French lavender, is a more ornamental plant than the common kind, but somewhat tender. Both require a dry calcareous soil, and an open airy situation. The common Lavender is cultivated on a large scale at Mitcham, and also at Henley-on-Thames. At both places it is propagated by cuttings of the young wood planted in autumn; and seeds are sold in the seed-shops.

LAVA'TERA.—*Malvææ*.—A very showy annual, common in flower-gardens, which only requires

sowing in the open border in March or April. There are two other species which are shrubs.—See **TREE MALLOW**.

**LAWN**.—Smooth mown turf, when of any extent in pleasure-grounds, is called a lawn; and its chief beauties are the uniformity of its surface, and uniformity in the kinds of grasses which cover it, and which produce an uniform tone of green. These objects are produced by first preparing the soil, which should be a sandy loam, or a loam slightly inclining to sand, of a foot or more in depth, and equally drained throughout, so as everywhere to retain the same degree of moisture. Next, the same mixture of grasses should be sown throughout, and lastly they should be mown at regular intervals, say of a fortnight during the summer months, and a month during spring and autumn. Whenever coarse grasses, or broad-leaved plants of any kind appear, they should be taken out with the spud; and whenever any spot becomes bare, the soil should be renewed and pieces of fresh turf introduced, or seeds sown. When worms disfigure the surface, the castings which they throw up should be scraped off; and if the surface be watered with lime-water all the worms will be destroyed; but the propriety of this proceeding is very doubtful; for the common earth-worm pierces the soil perpendicularly to the gravel, rendering the compact substratum somewhat like a sieve, and thus affording the most ready drainage imaginable; and were it not for them, lawns would long continue swampy after heavy rain. In general, it is impossible to produce a fine lawn, except in an open, airy situation, with a soil which will retain moisture during summer; for in close pent-up places, surrounded by walls or hedges, and

under the drip of trees and shrubs, no kind of grass will grow. In such places, all that can be done is to encourage the growth of moss; which will spring up naturally wherever the soil is kept sufficiently moist; but where it is very dry, the branches of the trees and shrubs should be allowed to trail on the surface, so as completely to cover it. In some situations, where the branches of the trees and shrubs do not lie close to the surface, or where they are chiefly of deciduous kinds, the surfaces may be clothed with Ivy or Periwinkle. In very small gardens, grass-plots are generally formed by rolls of turf, taken from the surfaces of some adjoining pasture-field or meadow, and this forms the most permanent lawn; for generally all the artificial grasses ultimately disappear, except the natural grass of the locality; but turf in many places cannot be easily obtained, and grass-seeds must then be sown. The following kinds are considered the best:—Fox-tail Meadow grass, *Alopecurus pratensis*, which should form one-fourth of the whole; the Sweet-scented Spring-grass, *Anthoxanthum odoratum*, which gives the fragrance to new hay; and *Poa pratensis*, the common Meadow grass. To these may be added the Crested Dog's-tail-grass, *Cynosurus cristatus*; and the hard Fescue-grass, *Festuca duriuscula*, with about the proportion of two pounds of white clover-seed to four bushels of the other mixture; and this quantity will suffice for an acre of ground.

**LAYERING** is a mode of propagating used both in the case of ligneous and herbaceous plants, and the operation is performed by choosing a young shoot of the current or the preceding year, bending it down to the ground, and covering a portion of it near the extremity of the shoot with an inch

or more of soil, previously fixing it there with a hooked stick. In general, layers of woody plants




FIG. 33.—LAYER OF A CARNATION.

made in autumn may be taken off about the same season the following year ; but some trees and shrubs, such as Magnolias, the Tree Ivy, &c., require to remain on the tree



FIG. 34.—LAYER OF A DECIDUOUS PLANT.

for two years. Roses layered in the summer season with shoots of the same year's growth may be taken

off the following spring ; but the general practice is to layer them in autumn or winter, and allow the layers to remain on the plants for a year. Layers of herbaceous plants, such as Carnations, Pinks, Double Sweet Williams, and Chrysanthemums, made in the beginning of summer, will have made roots by the autumn ; and the layers of Chrysanthemums so rooted will flower the winter of the same year. To facilitate the rooting of all layers, whether ligneous or herbaceous, a notch or slit is made in that part of the shoot which is buried in the soil ; or it is twisted, and a portion of the bark taken off, or it is in some other way wounded, bruised, or injured, so as to check the return of the sap by the bark, when the sap, accumulating at the upper lip of the wound, forms a callosity there of granulated matter, from which roots are soon after emitted. In layering herbaceous plants, and more especially Carnations, the slit is made on the under side of the shoot, and in the case of woody plants, on the upper side. In both cases, the knife is entered immediately below a bud or joint ; roots being always more freely protruded at the joints of plants than in the intervals between them. The cut is generally made half through the shoot, and continued up half an inch or an inch, and to keep it open a small splinter of wood, or a small flat stone, or a piece of slate, or a potsherd, is put in between the divided parts to irritate the wound and cause it to protrude granulous matter. See *fig. 33*. In layering herbaceous plants, it was formerly the custom to shorten the leaves remaining on the layer, but in modern practice this is considered unnecessary, and even injurious, by lessening the powers of the leaves to elaborate the sap. The leaves are always

stripped off that part of the layer which is buried in the soil ; as shown in the layer of a deciduous plant, *fig. 34*. In layering some woody plants, such as certain kinds of *Roses*, *Tree Pæonies*, &c., the entire shoot is laid down, and the knife entered immediately below each eye ; and the wounds being kept open by splinters of wood or stones, the whole shoot is covered with earth to the depth of half an inch or an inch, according as the soil is sandy or loamy, and a shoot is afterwards sent up from each eye, so that a shoot thus laid down produces nearly as many plants as it has buds. This practice is much more successful with some kinds of shrubs and trees than with others, but it is not at all applicable to herbaceous plants. Some shrubs, such as the *Honeysuckle*, *Técoma*, *Wistaria*, &c., which produce long shoots, and continue growing throughout the summer, may be pegged down as they grow, and a slit made behind each bud, or every other bud, covering the joint so treated with soil. A great many plants are thus produced from a single shoot in one season, more especially in moist warm summers, or in a warm situation, where water is applied artificially. Layers of every description root most freely in sandy soil, in an open airy situation ; and those which are difficult to root succeed best where the soil is almost a pure sand. The layering of *Carnations* is an operation particularly suitable for ladies, more especially when the plants are in pots, as they can be placed on a table or bench, and there will be no occasion for stooping.

#### LAYING IN BY THE HEELS.—

When plants are taken up for removal, if they cannot be planted immediately, they are generally laid

together horizontally in a trench made for that purpose, and the roots covered with earth. This is done to prevent the roots from becoming dry and withered, which they would do if they were left exposed to the open air for any length of time.

#### LEADWORT.—See PLUMBA'GO.

LEAF-MOULD is formed of decayed leaves, and is one of the most useful materials in the culture of flowers. All plants whatever will grow in leaf-mould, mixed with loam and sand, and many plants will grow in leaf-mould alone. It is particularly useful for growing plants in pots, especially *Pelargoniums*, *Fuchsias*, *Petunias*, *Brugmansias*, &c. ; and in many cases it may be used as a substitute for heath-mould. Leaf-mould is formed by sweeping up the leaves of trees and shrubs in autumn and winter, and laying them in heaps in a convenient place to rot, turning them over occasionally, so as to expose continually a new surface to the action of the air. At the end of a year, a considerable portion of the leaves will have become mould, and may be separated from the rest by sifting ; and, at the end of two years, the whole will have become one mass of mould. If it were required to grow any kind of herbaceous plants to the largest possible size, within a given time, I do not know how it could be better done than by placing the plant in the centre of a bed, of three or four cubical yards, of leaf-mould mixed with coarse sand, thoroughly drained by a stratum of stones at the bottom, and amply supplied with water. *Pine-apples* in France, and melons in Holland, are grown to an enormous size in only leaf-mould and rough sand. The best substitute for leaf-mould is heath-mould, that is to say, peat

and sand, mixed with very rotten dung sifted. Or rotten dung and sand may be used, if the dung has become so thoroughly decayed as to form a kind of mould. Of late years, when destructive fungi have so much abounded, it has been necessary to abstain from using leaf-mould in many cases. Plants that are being grown in it should therefore be carefully watched, and shifted into fresh materials if attacked with fungi. The roots should be washed; and it would also be advisable to mix a little flowers of sulphur with the soil in which the plants affected are repotted.

LEATHER WOOD.—See *DI'ROA*.

LEAVES are, next to roots, the most important parts of plants. With a root a plant will begin to grow, but unless the leaves which it produces are allowed to come to maturity, it will soon cease to live, because it is in the leaves alone that the moisture imbibed by the roots is elaborated into the sap or vital juice of the plant. Nothing so decidedly shows the ignorance or knowledge of a gardener, as the manner in which he treats the leaves of plants. Those of bulbs many gardeners will, if not prevented, cut off, as soon as the plants have done flowering; and, in general, gardeners wish to perform the same operation on all herbaceous plants after they have flowered. When a man of this description makes a layer or a cutting of a shoot that has the leaves on, he either takes them off entirely, or cuts off their tips, not knowing that it is by means of the leaves alone that such cuttings can produce roots. (See *CUTTINGS*.) Leaves through their petioles return sap to the general circulation of the plant, and hence the growth both of the roots of the plant and its shoots

depends entirely on the number of its healthy leaves. Leaves perform their office of elaborating the sap by exposure to the light and air, and more especially to the direct influence of the sun; therefore it is not sufficient to preserve the leaves which a plant produces, it is also necessary to prevent them from being darkened by adjoining plants or other objects, or from darkening other leaves. This, in some cases, requires thinning both of leaves and shoots; but more generally it may be effected by placing the plant in an open airy situation. As the progress of a plant, therefore, after it is once originated, and planted in a proper soil and situation, depends entirely on the leaves and on their treatment, it follows that the growth of the plant may be in a great measure checked by the removal of the leaves, either before they have burst from the bud or immediately afterwards. In this way Mr. Beaton has reduced the shoots of the most vigorous-growing fruit-trees without ever once using the knife. The same principle may be applied in the case of every other description of plant.

Leaves are also occasionally used instead of manure or tan for hotbeds; and very frequently for what are called linings to old hotbeds, the heat of which has decreased, as very great heat is generated by leaves while undergoing the process of decay.

LE'DUM.—*Ericaceæ*.—The Labrador Tea.—American low shrubs, with pretty white flowers, which require to be grown in peat and sand, heath-mould, or very sandy loam. *Lédum buxifolium*, the Sand Myrtle, is frequently called *Ammyrsine buxifolia* in the nurseries. It is a very pretty, compact-growing, little plant, with box-tree

leaves, and clusters of white flowers, which have a pink tinge on the back of the petals. It is very suitable for beds in a geometric flower-garden, or for rock-work; but it requires a slight protection during severe frosts.

**LEGUMINOUS PLANTS.**—Plants that produce their seed in a pod or legume, like the common Bean and Pea; some of them have pea-flowers, and others have tassel-like flowers, like those of the Acacias.

**LEIOPHYLLUM.**—Another name for *Ledum buxifolium*.

**LE'MNA.**—Duckweed.

**LEMON.**—See **CITRUS**.

**LEONOTIS.**—*Labiata*.—Lion's-ear.—Shrubby plants, from the Cape of Good Hope, with scarlet or orange flowers, which are produced in whorls round the joints of the stems. The flowers are produced in autumn, and the plants require a light rich soil.

**LEOPARD'S BANE.**—See **DORONICUM**.

**LEPERIZA.**—*Armyllidaceæ*.—A very handsome South American bulb, nearly allied to *Pancratium*, but with yellow flowers tipped with green. The plant requires a greenhouse.

**LEPTODACTYLON.**—*Polemoniaceæ*.—A Californian shrub nearly allied to *Gilia* and quite hardy in British gardens. Its flowers are pink, and they are produced in such great profusion, as frequently to conceal entirely the leaves and branches.

**LEPTOSIPHON.**—*Polemoniaceæ*.—Pretty Californian annuals, now united to *Gilia*; they will bear a moderate degree of cold better than too much heat.—For their culture, see **ANNUALS**.

**LEPTOSPERMUM.**—*Myrtidææ*.—Very pretty Australian half-hardy shrubs, with white flowers, which

are generally kept in a greenhouse in England, but which may be grown in the open air, with a slight protection during winter. They require a sandy loam, mixed with peat in nearly equal quantities; and they are generally propagated by cuttings, as the plants which are raised from seed are a long time before they flower.

**LESCHENAULTIA.**—*Goodeniaceæ*.—The two best known species of this genus are both natives of New Holland, and both conspicuous for the great abundance of their dark scarlet flowers. *L. formosa* is very common in windows, greenhouses, and small balconies; but though it is so general a favourite, few people can keep it long. The fact is, that though it does not belong to the same natural order as the Heath, it very much resembles it in habit, and is even more easily killed. The *Leschenaultia* should be grown in heath-mould mixed with a little loam, and treated exactly like a Heath; that is, never suffered to become too dry, and never saturated with water. It should be potted high, so as to leave the collar above the mould in the centre of the pot; and when kept in a balcony, the pot in which it grows should be placed within another pot, so that the roots may not be injured by the outside of the pot becoming heated by the sun. The most important point, however, is to allow the plant plenty of air, as it will not live without abundance of both air and light. *L. Baxteri* is a very beautiful variety of the old species, the flowers being much larger and more brilliant, but it requires the same treatment. It was once supposed that the flowers of all the species of the *Leschenaultia* were of a bright scarlet; but this is found to be a mistake. In 1842, *L. biloba*, a blue-

flowered *Leschenaultia*, was introduced from the Swan River, and since that period several other species have been introduced; one of which, *L. arcuata*, has flowers with three large yellow segments, and the other two of a dark purple or crimson. It is a prostrate greenhouse plant, with the branches spreading and curved downwards, and very large flowers. *L. splendens* is another very beautiful species, the flowers of which are scarlet and yellow.

LESPEDEZA. — *Leguminosæ*. — Pea-flowered perennial plants, nearly allied to the French Honeysuckle, which only require to be planted in any common garden-soil, in the open borders.

LESSE'RTIA. — *Leguminosæ*. — *L. pulchra* is a pretty little half-shrubby plant, with purplish-red pea-flowers, which are produced in May. It is a native of the Cape of Good Hope, and it is generally kept in a greenhouse.

LEUCOJUM. — *Amaryllidaceæ*. — The Snow-flake. — Beautiful bulbous-rooted plants, natives of Europe, as hardy as the common Snowdrop, and requiring the same treatment, except that they do not succeed quite so well under the drip of trees. Some of them are now placed in a new genus called *A'cis*.

LEUCOPO'GON. — *Epacrideæ*. — Australian half-hardy shrubs, with spikes of feathery white flowers. They are very abundant in the temperate regions of Australia, and only require a slight protection in England during winter.

LEVELLING is an operation which is required on a large scale in laying out gardens, and on a smaller scale in digging uneven ground. In either case, care should be taken to keep the best soil on the surface; so that when a hill is to be lowered in order

to fill up a hollow, the first operation is to take off the surface of both, and reduce the ground to an uniform inclination or level, by removing the subsoil, and replacing the surface-soil afterwards evenly over the whole. In practice, it is seldom, if ever, desirable to reduce a surface to a perfect level, because in that case the rain which fell on it would not readily run off. An inclination should generally be given from one side to the other; or, when the plot is a square, from the centre to all the sides; and this inclination may be so gentle as to render it quite impossible to be detected by the eye alone. A piece of ground fifty feet broad may have an inclination of three inches, if the soil be loamy and retentive; but if it be sandy and absorbent, an inch and a half will be sufficient. In levelling lawns, no part whatever of the surface ought to be on what is called a dead or perfect level; because, as the grass retains the water on the surface like a sponge, if the soil be loamy, it will soon become mossy and unpleasant to walk on during the whole of the winter and spring. All flat lawns, therefore, on clayey soil, ought not only to have a gentle inclination, but frequent drains, the stones in which ought to be brought up to within a few inches of the surface. In arranging the inclination of dug surfaces, care should be taken that the water is not thrown on the gravel-walks; for which purpose drains are requisite in the marginal borders; though, in general, dug soil, if the stratum be not retentive, is sufficiently absorbent to render such drains unnecessary, the superfluous water of the subsoil finding its way to the drains of the walks.

LEYCESTERIA. — *Caprifoliaceæ*. — *L. formosa* is a very handsome

plant, with long spikes of reddish flowers, which will not only thrive but grow more luxuriantly in the immediate neighbourhood of the sea, than in any other situation. It is a native of Nepal, and was introduced in 1824. It was, however, soon lost through injudicious treatment—probably through keeping it too warm; but it has been lately reintroduced, and it is now found to grow vigorously in the open ground. It is propagated by cuttings and seeds.

**LIBOCEDRUS.**—*Conifera*.—This is a magnificent tree from the coldest part of South America. *L. tetragona* is quite as hardy as the *Araucária imbricatá*, and as curious and ornamental. There are several species, all natives of South America.

**LICHEN.**—*Cryptogamia Lichenes*.—Moss-like plants, generally found on old walls, desert heaths, or the bark of old trees; also frequently on dead wood.

**LIGHT** is as essential as air and water to plants; and without abundance of light, plants are neither vigorous in themselves, nor properly coloured. When greenhouse plants are kept in imperfectly lighted plant-houses, or in half-darkened rooms, it is really painful to witness the efforts they make to catch as much light as they possibly can; their stems become weak, from being unnaturally elongated, or drawn up and twisted, in their efforts to reach the light, and their flowers are pale, and of very little value. In those towns where the atmosphere is thickened by coal-smoke, the light never has the same beneficial effect as in the open country, where there is nothing to prevent it from exercising its full influence over the plants.

**LIGNUM VITÆ.**—*Guaiacum officinale* is a tree, a native of the West

Indies, remarkable for the hardness and extraordinary heaviness of its wood. It has blue flowers, which are produced in succession all the summer. It requires a stove in England, and should be grown in a mixture of peat and loam; but it is very rarely met with.

**LIGUSTRUM.**—*Oleaceæ*.—The Privet is one of the most common, but at the same time most useful, of garden shrubs. The plant, in its wild state in Britain, is deciduous; but there is a variety, obtained originally from Italy, which is evergreen, and which forms hedges for shelter of every size, from those of six inches in width and one foot in height, to hedges ten feet high and two or three feet in width. These hedges afford an excellent shelter to exposed flower-gardens, and also when planted on the south side of a border, shady situations for particular kinds of plants, such as Primroses, Polyanthus, the rarer kinds of Ranunculaceæ, Trilliums, Cypripediums, Bog Orchideæ, and a great variety of others. The Privet is preferable to all other plants for garden-hedges, on account of the rapidity of its growth and the nature of its roots, which are chiefly fibrous, and never extend to a great distance from the plant. The tree Box has the same properties, but then it is of much slower growth. The Evergreen Privet is also one of the best plants for verdant architecture and sculpture; because it grows compact, is of a deep green colour, bears the shears well, and the leaves being small, they are not disfigured by clipping, like those of the Holly or the Laurel. The Box equals it in the smallness of the leaves, but it grows more slowly; and though the Juniper and the Yew surpass it because they never show the mark of the shears,



they grow much more slowly still. The Privet grows in any soil and situation, even in narrow courts amid coal-smoke, and it is readily propagated by cuttings. It also grows under the shade of trees, and is therefore admirably adapted for thickening and darkening narrow shrubberies, and for screening plantations. As a single object, the Privet is very ornamental, whether covered with its white flowers or its dark-purple berries; and there are varieties with green, white, and yellow berries, and variegated leaves. *Ligustrum lucidum*, and *L. spicatum*, are very ornamental sub-evergreen shrubs or low trees, natives of China and Nepal; but they are liable to be injured by very severe winters. These two species are propagated by budding or grafting on the common Privet.

LILAC.—See SYRINGA.

LILYUM.—*Liliaceæ*, or *Tulipaceæ*.—The lily is the most splendid genus of bulbous plants. All the species are beautiful, and most of them are hardy. *Lilium candidum* grows from three feet to five feet high, and its pure white flowers, which appear in June, are well known from being placed by painters in the hands of the Virgin. *L. bulbiferum*, a native of Italy, has orange flowers, which appear in June and July, and the plant is equally high with the preceding species. *L. philadelphicum* grows five feet or six feet high, and produces its fine scarlet flowers in August. *L. Pomponium* is a splendid species with scarlet flowers, produced in May and June; and *L. tigrinum* grows six feet high, and produces its black-spotted orange flowers in August and September. There are many other hardy species in cultivation; and *L. cæmium*, *L. japonicum*, *L. longiflorum*, and some others eminently beautiful and

chiefly with white flowers, require the protection of the greenhouse, or a cold frame. The species which are natives of America thrive best in sandy peat kept moist when the plants are in a growing state; but the others grow freely in common garden-soil. They are all readily propagated by offsets, which they produce in abundance. The bulbs of all the species are probably edible when cooked, for those of *L. Pomponium* are used in Kamtschatka in the same way as potatoes are in Britain; and they all belong to what are called the scaly bulbs, which may remain several years in the ground without taking up, and which when they are taken up, should be planted again as soon as possible. The beautiful Japan Lilies (*L. lanceolatum* and its varieties) are now frequently planted in the open air during the flowering season, and are certainly some of the most beautiful plants that can be imagined of the Lily tribe in the open air. Numerous hybrids have also been raised between the greenhouse and hardy kinds, some of which are very handsome. *L. auratum*, introduced from Japan by Mr. Fortune in 1862, and considered the greatest acquisition of the season; it is a large hardy bulb, with very large white flowers, spotted with chocolate purple, with a golden bar down the centre of each segment.

LILY.—See LILYUM.

LILY OF THE VALLEY.—See CONVALLARIA.

LILYMAX.—This is the scientific name for the slug, one of the most destructive creatures in existence to a garden. The slug differs from the snail in having no apparent shell, though it has the rudiments of a shell buried in the upper part of its body. Like the snail also, it can only crawl when the earth is moist with rain or

dew : as when the ground is dry it absorbs too much of the slime which both slugs and snails are obliged to discharge from their bodies to enable them to glide along. There are many kinds of slugs, nearly all of which are destructive to vegetation ; the only exception being the shell-slug (*Testacellus*), which lives on earth-worms. These creatures are by no means common ; but they are found in the earth near hothouses, in the neighbourhood of London, and they may be known by their dirty yellow colour, and by their having a little scale-like shell, which naturalists call the shield or buckler, on the outside and on the highest part of the body, near the breathing-hole, which it is probably intended to protect. Slugs may be destroyed in the same manner as snails.—See *HE'LI'X*.

**LIME.**—A kind of Citrus, rarely grown in England, but requiring the same treatment as the orange and the lemon.—See *CITRUS*.

**LIMNANTHES.**—*Limnanthaceæ*.—One of the Californian annuals, the flowers of which are yellow in the centre, with a deep border of white. For the culture, see *ANNUALS*.

**LIMNOCHARIS.**—*Hydrocharideæ* or *Butomeæ*.—These plants, which are natives of Brazil, are either annual or biennial, and the seed should be sown in a layer of rich, loamy soil, at the bottom of a cistern or tub, which should be kept very moist ; and as the young plants grow, the tub or cistern should be gradually filled with water. They require the heat of a stove.

**LINA'RIA.**—*Scrophularinæ*. — Toad-flax. — Hardy annuals, suitable for borders and rock-work ; they only require sowing in March, April, or May, in the open border. They will grow in any soil or situation ; but they prefer a rather stiff, poor soil, and an open, exposed situation.

Several of the kinds have been removed from the genus *Antirrhinum* (Snapdragon), to which they are very nearly allied.

**LINNÆA.**—*Caprifoliaceæ*. — A slender trailing plant, named after the celebrated Linnæus ; well adapted for rock-work, or pots ; its flowers are small, but sweetly fragrant. It should be grown in loam and peat, and it may be propagated by cuttings, which should be struck under a hand-glass. It is a native of Britain, and of course hardy ; nevertheless it should be covered with moss in winter.

**LI'NUM.**—*Linaceæ*.—The Flax. —The common Flax, the fibres of the stalk of which are used to make linen, has pretty blue flowers ; but there are other species of the genus with showy yellow flowers. Some of the perennial kinds are rather tender, and require to be protected during severe winters ; they are also liable to damp off if kept too moist. They should be grown in light soil, consisting principally of vegetable mould ; and the dwarf kinds are very suitable for rock-work. *L. grandiflorum rubrum* is one of the finest annuals ; its stems are branching, 18 inches high, and bear a succession of large rich crimson flowers. They are generally propagated by cuttings or seeds, which they ripen abundantly.

**LION'S-EAR.**—See *LEONOTIS*.

**LION'S-TAIL.**—*Leonotis Leonurus*.

**LIQUID MANURE** may be described as a solution of any description of putrescent manures, such as guano, stable-dung, pig's-dung, pigeon's-dung, sheep's dung, &c. It may be used with great advantage in the kitchen-garden, but is seldom required in the culture of flowers ; and indeed many of the finer kinds have been injured by it, though some few, such as the Hydrangeas, the com-

moner Pelargoniums, Chrysanthemums, Cock's-combs, Balsams, Auriculas, &c., have been benefited. Liquid manure ought not to be applied to plants till they have obtained a considerable degree of strength and vigour.

**LIQUIDAMBAR.** — *Amentaceæ*. — Though too large a tree to come within the scope of this work, it may be mentioned for its ornamental appearance when quite young, from the brilliant purplish-red assumed by its leaves in autumn. It is quite hardy, and will grow in any common garden soil that is tolerably moist.

**LIQUORICE.** — See *GLYCYRRHIZA*.

**LIRIODENDRON.** — *Magnoliaceæ*. — The Tulip-tree grows to a still larger size than the Liquidambar; but it is very ornamental from its flowers, which somewhat resemble those of the Parrot-tulip, and its curiously-shaped leaves. It seldom flowers till it has become a large tree. The seeds, which are imported from America, often lie two years in the ground before they come up.

**LISIA'NTHUS.** — *Gentianeæ*. — Ligneous, perennial, and biennial plants, natives of the West Indies, which require a hothouse or greenhouse in England. *L. Russellianus* has handsome purple flowers; but it is very difficult to cultivate. The following method is said to be the best. The seed should be sown in March, in a compost of three parts loam, two parts vegetable mould, and one of silver sand, and the pots placed in a hotbed at a temperature of about 70°. The frame should be shaded till the young plants have expanded their fourth leaf. In June the young plants should be potted separately in 60's, and then returned to the frame, and shaded for about ten days. They should remain in the frame till September, being gradu-

ally hardened so as to be ready to take out of the frame about the end of that month, when they should be removed to a warm dry shelf in a greenhouse; here they should remain till February, having no more water than will be sufficient to keep them from flagging. The first week in February they should be put into a cucumber frame, and well supplied with water. As soon as the plants begin to grow they should be repotted, and placed in a frame heated to 75°, in which they should be plunged in charcoal dust. They should be watered twice a week till May, and then every alternate day with rain-water and liquid manure alternately. Early in July they will come into flower, and may then be removed to the greenhouse or drawing-room. One plant has been known to have 300 blossoms exposed at one time. *L. acutangulus* has no beauty to recommend it.

**LISSA'NTHUS.** — *Epacrideæ*. — The plants should be grown in a greenhouse, in peat and sand; and they are propagated by cuttings of the tips of the shoots, like heaths.

**LITTÆA** or **LYTTÆA.** — *Bromeliaceæ*. — Handsome plants, nearly allied to Agave, with spreading leaves and long spikes of flowers. The fine plant formerly known as *Buonaparteæ juncæa*, is now called *Littæa geminiflora*. They should be grown in sandy loam, and are increased by suckers from the roots.

**LOAM.** — Clay is one of the primitive earths, of so close and compact a texture as to be almost unfit for vegetation, unless mixed with some lighter material; but combined with sand and decayed vegetables, it forms loam. What are called sandy loam, and yellow loam, are two kinds of soil very conducive to vegetation; and sandy loam is perhaps the best of all soils for a garden.

LOA'SA. — *Loasaceæ*. — Stinging annual and biennial plants, with showy flowers. The splendid climbing plant, *L. lateritia*, or *aurantiaca*, is now discovered to be *Caiophora punicea*, the difference between the genera consisting in the *Caiophora* having a twisted seed-pod, while that of the *Loasa* is plain. The species are all nearly hardy, but they do best when raised on a slight hotbed, and planted out in May.

LOBELIA. — *Lobeliaceæ*. — Nothing can exceed the beauty of the plants retained in this genus, some of which are tender, requiring a stove, and others of which are quite hardy, growing freely in the open ground. Some also are quite dwarf, and others tall plants; some are blue, others scarlet, and others yellow; and some are annuals, and the others perennials. *L. Erinus speciosa*, the Crystal Palace var., is of a deep blue, and is one of the best and most useful annuals for bedding and for ribbon borders. All the *Lobelias* require a light rich soil, and plenty of moisture. The large, tall-growing kinds, with scarlet or pink flowers, are now frequently called *Tûpa*.

LOBLOLLY BOY. — See GORDO'NIA.

LOCUST TREE of the Americans, or Cobbett's Locust. — *Robinia Pseud-Acacia*. — See ROB'NIA.

LOGWOOD. — *Hæmatôxylon campechianum*. — A leguminous stove-shrub, which grows best in loam and peat, and is propagated by cuttings.

LONDON PRIDE. — *Saxifraga*, or *Robertsonia umbrosa*. — See SAXI'FRAGA.

LONGERA. — *Caprifoliaceæ*. — The upright or Fly Honeysuckle. — Great confusion exists in botanical works respecting the scientific names of the different kinds of Honeysuckle. Generally speaking, however, the

climbing species are called *Caprifolium*, and the upright, erect shrubs *Lonicera*. The latter kinds are all quite hardy, and will grow in any common soil; and they are propagated by cuttings planted in the open ground in autumn. *L. tatârica*, the Tartarian Honeysuckle, and *L. Xylôsteum*, the common Fly Honeysuckle, are the commonest kinds. *L. auro-reticulata* is a beautiful hardy, climbing shrub from Japan; leaves ovate, beautifully marked with golden yellow.

LOOSE STRIFE. — See LYSIMA'CHIA.

LOPE'ZIA. — *Onagræceæ*. — Annual and biennial plants, hardy, half-hardy, and tender; but with light, feathery, pink flowers, and pretty ball-like fruit, which is produced on long stalks, and is very ornamental. For the culture, see ANNUALS and BIENNIALS.

LOPHOSPE'RMUM. — *Scrophularinæ*. — Beautiful climbing plants, with pink bell-shaped flowers, which grow luxuriantly in the open border, covering a trellis-work or a wall in an incredibly short space of time. As the plants are killed down to the ground in winter, cuttings should be taken off in autumn, and kept in a greenhouse or frame during winter to plant out in spring. The plants will grow in any common garden soil, provided it is tolerably light, and that they have abundance of space for their roots.

LOQUAT TREE. — See ERIOBO'TRYA.

LORA'NTHUS. — *Loranthæceæ*. — A kind of Mistletoe, generally found on the Oak; common in Germany, but not yet introduced into England.

LORD ANSON'S PEA. — *Lâthyrus magellanicus*. — See LA'THYRUS.

LOUDO'NIA. — *Haloragææ*. — *L. aurea* is a Swan River shrub, the flowers and seed-vessels of which

vary from a rich golden yellow to an orange red. *L. florëscens*, discovered by Mr. Drummond in 1843, has flowers which are of a very pale yellow or lemon colour. Both require the usual culture of Australian shrubs. The genus was named by Dr. Lindley in compliment to Mr. Loudon.

LOVE APPLE.—The Tomato.—See LYCOPE'SIUM.

LOVE LIES BLEEDING.—*Amarantus caudatus*.—See AMARA'NTUS.

LO'WEA.—The new name for *Rdea berberifolia*.

LUOU'LIA.—*Rubiaceæ*.—*L. gratissima* is a remarkably fragrant plant, with large flowers, something like those of the Hydrangea. It is grown in a greenhouse, in a mixture of light turfy loam and peat; and it is propagated by cuttings, which require bottom-heat. *L. Pinceana* is a new species which was introduced in 1843. It is a very handsome plant, with large white flowers, which are exceedingly fragrant.

LUNA'RIA.—*Crucifera*.—*Honesty*.—Hardy annual and perennial plants, which will grow in any common garden soil, and only require the usual treatment of their respective kinds.—See ANNUALS and PERENNIALS.

LUPINE.—See LUPINUS.

LUPINUS.—*Leguminosæ*.—The Lupine.—A genus of herbaceous annuals and perennials which contains some of our most beautiful border flowers; yellow, blue, white, and pink Lupines are among the oldest border annuals; *L. nanus* is a beautiful little annual, with dark-blue flowers, a native of California, and requiring the usual treatment of Californian annuals. *L. mutabilis*, and *L. Cruckshanksii*, are splendid plants, growing to the height of four or five feet, and branching like miniature trees; *L. polyphyllus* and

its varieties are perennials, and they are splendid and vigorous-growing plants, with spikes of flowers from one foot to eighteen inches in length; *L. nookatensis* is a handsome dwarf perennial, and *L. arborescens* when trained against a wall will attain six feet in height, and in sheltered situations it will grow with equal vigour trained as a bush tied to a stake; *L. latifolius* is a perennial from California, with very long spikes of blue flowers. All the species will thrive in common garden soil: the annuals are propagated by seeds sown in February or March, and the perennials, by division of the root.

LYCA'STE.—*Orchidaceæ*.—A genus of orchideous plants, which varies considerably in the different species, some of the kinds being extremely ornamental, and others very much the reverse. *L. Skinneri* is the most ornamental species. The plants comprised in the genus were formerly included in the genus *Maxillaria*, and they belong to that class of stove orchids, which grow best in a pot or basket, or leaf-mould, mixed with lime rubbish, or potsherds. The species are generally natives of Guatemala.

LY'CHNIS.—*Silenaceæ*, or *Caryophylleæ*.—Beautiful flowers, nearly allied to the Pinks; some of which, such as the Ragged Robin (*Lýchnis Floscuculi*), grow wild in the hedges in England. *L. Senno* is a fine new showy hardy perennial, from Japan, with large, deep crimson flowers, upwards of two inches across. *L. Haageana*, and *L. viscaria splendens*, are very beautiful varieties for the flower garden. They are nearly all hardy, and may be grown in any common garden soil.

LY'CIUM.—*Solanaceæ*.—Boxthorn.—The species are mostly hardy shrubs with long slender shoots, which trail on the ground or ascend

among the branches of larger shrubs or trees, according as they may be circumstanced. *Lycium barbarum*, the Duke of Argyll's Tea Tree, is one of the most vigorous-growing hardy shrubs, producing, when established a year in good soil, shoots ten or twelve feet long; *L. europæum* is almost equally vigorous; and *L. Treviànum*, in a warm sheltered situation, will grow to the height of twenty feet. Scarcely any shrub will cover a bower, or naked wall, or trellis fence in so short a time, and the fruit, which is of a coral colour, is ornamented as well as the flowers. The species mentioned have only one disadvantage, which is, that their roots run to a great distance, and throw up numerous suckers; and this peculiarity renders the plant unfit for small gardens, though well adapted for confined court-yards or narrow passages, the side walls of which are to be covered with verdure. A single plant on a lawn trained with a stem to the height of ten or twelve feet, and then allowed to spread on every side over frame-work in the form of an umbrella, will not only cover this frame-work, but produce shoots which will hang down to the ground on every side, and thus form a complete curtain, which may be drawn aside like that of a window or bed, and will close again of itself on the spectator. These species are easily propagated by cuttings of the roots or shoots in any common soil rather dry than moist. *L. àfrum* is a very beautiful species, with large violet-coloured flowers, but it requires the protection of a wall; and *L. Boerhaaviaefolium*, recently changed to *Grabówska*, is remarkable for the singularity of its leaves, which are covered with a mealy whiteness; it also requires the protection of a wall.

LYCOPE'RSICUM. — *Solanaceæ*. — The Tomato, or Love-apple (*L. escu-*

*lèntum* Don; *Solanum lycopersicum* Ten.), is generally grown for its fruit, which is eaten as a sauce, &c. It is, however, very ornamental when the fruit is ripe, from its large size and brilliant colour. There are several kinds, varying in the size and the colour of the fruit. Nearly all the kinds are annuals, which should be raised on a hotbed, and planted out in May against a wall or an espalier railing, to which they should be trained; they all require a rich soil, and abundance of sun and air to bring them to perfection.

LYCOPO'DIUM. — *Cryptogamia Lycopodiaceæ*. — Club-moss. — A curious kind of moss, common in Europe and America, some of the kinds of which are very ornamental. *L. helveticum*, which is very handsome, is generally grown in pots in greenhouses. It should be grown in peat and loam, and allowed abundance of water. *L. cæsiu*m is a new species lately introduced from China, which is extremely ornamental from the beautiful glaucous bloom which appears to be on the fronds. A variety of *L. c. arboreum* is exceedingly handsome.

LYSIMA'CHIA. — *Primulaceæ*. — Loose-strife. — Herbaceous plants with yellow flowers, chiefly perennials, and of which one species, *L. Nummulària* (Moneywort), is a well-known ever-green trailer, which, when kept in a pot of moist soil, will produce shoots of two or three feet in length, which hang down on every side. *L. verticillàta* is an upright-growing plant, with abundance of showy yellow flowers, which look very well planted in the borders of a large garden. They will grow in any common garden soil. The most showy species of the genus is, however, *L. nutans*, with dark red flowers, a native of South Africa, but flowers freely in the open air during

summer ; and only requires protection from frost in the winter.

LYTHRUM.—*Lythraceæ*.—A genus of very ornamental hardy perennials, which grow in any common soil kept moist, and are propagated by division. *L. Salicària* is a native of Britain on the banks of rivers, and grows to the height of four feet ; *L. diffusum* grows to the height of one foot ; and both these species produce their purple flowers in July or August, when flowers are comparatively rarer than they are in June and September. *L. virgatum* grows three feet high, and produces its purple flowers from June to September.

LYTTE'A.—See LITTE'A.

MACLURA.—*Urticaceæ*.—The Osage-orange. — A handsome deciduous tree, with small shining yellowish green leaves and many thorns. The flowers are white and rather small ; but the fruit, which is as large as an orange, and of a brilliant golden yellow, is very ornamental. These trees are as yet rare in British gardens, but they have borne fruit in the Jardin des Plantes in Paris. The male and female flowers are on different trees. The leaves of this plant abound in a milky juice which is very tenacious ; and they may be employed for feeding silk-worms. The Maclura is tolerably hardy, yet suffers in our very severe winters ; but in Ireland it may be grown as hedges, and may be turned to account when silk-worm culture is properly and more generally understood than it is at present, and when, by means of the Black and White Mulberries, the Maclura, and Ailantus glandulosa, any lady might produce more silk than she could ever possibly wear out. We have fed silk-worms with

leaves of the two Mulberries above mentioned, resorting occasionally to those of the Maclura ; the deaths of the insects were only two or three per cent., and the silk produced was very fine and beautiful. The Maclura succeeds better in rather a poor soil ; as where the soil is too rich, the plant makes shoots more luxuriant than it can ripen ; and thus the tips of the young wood are often killed by frost.

MADDER.—See RU'BIA.

MA'DIA.—*Compositæ*. — *M. sativa* is a weedy-looking plant, grown in Germany for crushing its seeds to make oil. *M. elegans* (*Madària elegans* Dec.) is a coarse growing annual, with woolly leaves and very pretty yellow flowers, which are brown in the centre. The seeds should be sown in the open air in February, or as soon as the weather will admit, in rich deep soil ; or in sheltered situations, the seeds may be sown in autumn, and the young plants left to stand the winter. When the plants begin to attain a considerable size, they should be staked and tied up, or they will have a very untidy and disagreeable appearance. The kind called *M. splendens* is only a variety of *M. elegans*.

MAGNO'LIA. — *Magnoliaceæ*. — This is a genus of singularly ornamental trees, mostly of small size, and some of them shrubs. *M. grandiflora*, the evergreen Magnolia, the most desirable variety of which is *M. g. exoniensis*, is a well-known highly prized tree, generally planted against a wall. Though it will only flower freely in favourable situations, yet it is very hardy, not having been killed anywhere by the severe winter of 1837-8. In every villa, whatever may be its extent, one or two plants of this Magnolia ought to be placed against the house, or on a conservative wall. It will thrive in a loamy soil,

rather rich ; but it will grow still better in peat, and it requires no attention but training the branches, and nailing them against the wall. It produces its large flowers, which are from six inches to a foot in diameter when fully expanded, from August to October. *M. g. præcox* is a comparatively rare variety, with broader leaves than *M. g. exoniensis*, and still larger flowers, and they appear in July and sometimes in June. In purchasing both kinds in the nurseries care should be taken to select plants which have been raised from layers ; as seedlings, which are now sometimes imported from France, are often ten or fifteen years before they come into flower : whereas the others will flower the first or second year. *M. conspicua* is a deciduous tree, which produces abundance of white flowers about the size of lilies, in April and May, and sometimes even in March. It is quite hardy, but as its flowers appear so early, they are liable to be injured by spring frosts ; they also appear before the leaves, and for these reasons the tree should be planted against a wall, and if possible near *M. grandiflora*, so that the branches may intermingle, in which situation it produces a splendid effect. It never grows out of bounds, and therefore requires no pruning. It will thrive quite well as a standard in any common soil, and planted among evergreens in sheltered situations forms a splendid object when in flower. *M. c. Soulangiana* is a hybrid between this species and *M. purpurea*, equally splendid in its flowers ; and this hybrid, *M. conspicua*, and *M. grandiflora*, ought never to be omitted in any garden, where ornamental flowering trees are required. *M. purpurea* is a shrub which will thrive in the open border, but it flowers best against a wall,

and no plant is better deserving a place there. *M. acuminata*, with bluish flowers, and *M. cordata*, with yellowish ones, are as hardy as most flowering trees, and the former will attain the height of thirty or forty feet in fifteen or twenty years ; both deserve a place as standards. *M. auriculata* is a beautiful hardy tree, with mahogany-coloured bark, and smooth shining leaves with reddish veins ; it ought also to have a place in every collection of trees. The flowers of this and of the two preceding sorts are not fragrant like those of *M. grandiflora* and *M. conspicua*. *M. triptala* has leaves so large, that in America it is called the Umbrella-tree ; the flowers are white and fragrant. It requires a peat soil kept moist, and forms a splendid object on a lawn. *M. macrophylla* is a comparatively rare species with white flowers, the petals of which have a purple spot at the base, and the leaves are of an enormous size. It thrives best in this country in deep sand. *M. fuscata* is a greenhouse shrub with brown-coloured flowers delightfully fragrant, which well deserves a place in every conservatory, and which, in very warm situations, will live through the winter against a conservative wall. In general, the Magnolias may be designated the aristocratic trees of a garden, whether we regard the large size and fragrance of their flowers, or the length and breadth of their enormous leaves. The bark and wood of all of them are fragrant, and may be used as a substitute for those of the Cinchona.

MAHA'LEB.—The Mahaleb Plum or Cherry.—See CRÆSUS.

MAHONIA.—*Berberidea*.—The Ash Berberry.—Very handsome evergreen shrubs with pinnate leaves, and bearing abundance of brilliant



yellow flowers, which are succeeded by purplish berries. All the Kinds grow freely, and are very ornamental; but *M. Aquifolium*, the leaflets of which somewhat resemble the leaves of the Holly, and are of a brilliant shining green, is by far the handsomest and hardiest species. It is very ornamental as an evergreen at all times of the year; in spring by its numerous yellow flowers, and in summer by its grape-like clusters of glaucous purple berries. The *Mahonias* will grow in any common garden soil, and are increased by layers. *M. fascicularis* is rather tender, and should have some slight protection during severe frosts.

MAIDEN-HAIR.—See ADIAN'TUM.

MALACHODE'NDRON.—*Ternstroemiaceæ*.—A handsome bushy shrub, which may be trained as a low tree, with large white flowers. It should be grown in sandy peat, and it is propagated by layers or cuttings, the latter of which, however, require sand, a bell-glass, and bottom-heat, to make them strike root.

MALCO'MIA.—*Cruciferae*.—The Virginian Stock.—A pretty little annual which only requires to have its seeds sown at almost any season, to grow freely and to flower abundantly. Sow in autumn for spring flowering; in March and April for summer; and in June and July for a succession, to continue flowering till frost sets in. As nearly all the seeds are sure to come up, it may be sown as an edging plant instead of Box or Thrift; and in fact it is often used for this purpose in cottage gardens; and it has also a very good effect in rock-work. If the flower stalks be cut off, the plants will flower a second time. There is a white-flowered variety; and the two may be planted side by side in parallel lines.

MALE FERN.—*Aspidium Filix-mas*.—A very handsome species of Fern for growing in shrubberies.

MALESHE'RBIA.—*Malesherbiaceæ*.—A very pretty Chilian half-hardy annual, with blue flowers, the seeds of which should be sown on a hot-bed in February, and the young plants planted out in May.

MALLOW.—See MA'LVIA.

MA'LOPE.—*Malvaceæ*.—Annual plants with very handsome flowers. *M. trifida*, of which there are two kinds, one with crimson and the other with white flowers, is rather dwarf; but *M. grandiflora* will grow four or five feet high in a good soil and an open situation, bearing very large and showy brilliant crimson flowers. All the kinds are quite hardy, and only require sowing in March or April in the open border, and thinning out and transplanting, when the young plants are three or four inches high.

MALPI'GHIA.—*Malpighiaceæ*.—The Barbadoes Cherry.—A trailing plant, a native of the West Indies, which requires a stove in England. It should be grown in a light loamy soil, and it is propagated by cuttings of the ripe wood.

MA'LVIA.—*Malvaceæ*.—The Mallow.—A great number of different species are grown in British gardens, tender, half-hardy, and hardy perennials and annuals. They are all of the easiest culture according to their respective kinds; and the hardy species may be grown in any soil or situation.

MAMMILLA'RIA.—*Cactaceæ*.—Succulent plants, with almost globular stems covered with prickles, but without leaves; the flowers growing out of the stem without any stalk. These plants are natives of the high table-land of Mexico, where they are subject to very few variations of temperature; and they should therefore

be kept in greenhouse heat all the year in England. In their native country they grow in rich loam, and therefore require a better soil in this country than the different kinds of *Cereus* and *Echinocactus*, which grow among calcareous rocks, in the mould formed by the deposition of vegetable matter in the fissures. By attending to these particulars, the *Mammillarias* may be easily grown in any situation where they can be preserved from frost. When kept in a room they should be allowed as much air as possible; and the dust which lodges among their spines should be frequently blown off with a small pair of bellows, but the plants themselves should never be watered overhead.

**MANETTIA.**—*Rubiaceæ*.—Climbing plants some of which require a stove in England; though one species (*M. cordifolia* Hook; *M. glabra* Dec.), which has very handsome bright scarlet tube-like flowers, is generally grown in a greenhouse. It is a native of Buenos Ayres, whence it was introduced in 1831, and, like many plants from that country, it will very probably stand the summer in the open border in England. It should be grown in a mixture of sandy peat and loam; and when kept in a pot, it should be allowed plenty of room for its roots, and abundance of fresh air as often as possible. *M. bicolor* has tubular flowers, red at the base, and yellow at the top, which produce a very good effect. The *Manettias* are propagated by cuttings, which must be struck in sand, with bottom-heat. To have fine flowers, the plants should be pruned back to the old wood.

**MANGIFERA.**—*Terebinthaceæ*.—The Mango Tree.—A native of both the East and West Indies, with white flowers, which requires a stove in England. The fruit is said to be of

remarkably fine flavour in its native country. The plant in England should be grown in very sandy loam, and the pots well drained, as it is very apt to damp off.

**MANGO TREE.**—See **MANGIFERA**.

**MANGOSTEEN.**—*Garcinia Mangostana*.—This celebrated fruit, which is so highly spoken of by travellers in Java, &c., belongs to the same genus as the Gambogetree, and both require a stove in England. They are, however, very seldom grown in this country.

**MANTISIA.**—*Scitamineæ*.—*M. sallatidia*, the Opera Girl, is a plant, the flowers of which appear before the leaves, and which really look something like dancing figures fantastically dressed. The plant requires a stove in England, and it should be grown in a mixture of turfy loam, peat, and sand, kept rather moist, but well drained. It is increased by dividing the root.

**MANURES**, in Floriculture, are little wanted, and in general leaf-mould, or hotbed dung, or any kind of fermentable material, consisting chiefly of vegetable matter, is to be preferred.—See **LEAF-MOULD**. Thoroughly decomposed stable-dung is produced by turning it over every three or four weeks in summer, when fermentation is active, or three or four times in winter, when it is more slow; and in either case it is fit for use when it can be passed through a coarse sieve. It is to be mixed with the soil in proportions dependent on the nature of the plant to be cultivated. In general, rapid-growing plants, such as bulbs of every kind, require the thoroughly decomposed manure, but strong vigorous plants which grow all the summer, such as Dicotyledonous annuals and perennials, may be manured with materials in a less decomposed state. All

manures should be preserved in compact masses, so as to present as small a surface to the action of the atmosphere as possible, and a shaded situation is consequently preferable to one exposed to the free action of the sun and air.

**MARANTA.** — *Cánnea*. — The Indian Arrow-root. — Stove-plants, with tuberous roots and small white flowers. The powder called Arrow-root is made from the tubers. *M. Zebrina*, Sims; *Caláthea zebrina*, Lind., is much admired for its foliage, which is striped with pale and deep green above, the under side being a rich violet. It is sometimes called the Zebra plant.

**MARE'S-TAIL.** — See HIPPO'RIS.

**MARICA.** — *Irideæ*. — Fibrous-rooted plants, with very ornamental flowers, greatly resembling those of the Cape bulbs; natives of Africa, some of which require a stove and others a greenhouse in England. For culture, see AMARYLLIS.

**MARIGOLD.** — See CALE'NDULA.

**MARJORAM.** — See ORI'GANUM.

**MARSH MARIGOLD.** — *Caltha palústris*. — A British marsh or aquatic plant, sometimes introduced in ponds and other artificial pieces of water, in garden scenery, to give them a natural appearance, or to hide their termination. The plants only require to be planted in the muddy banks of the water, if it be a pond; but if it be a river, they should have a stone or two laid on their roots to prevent them from being washed away by the stream.

**MARSH PLANTS** are of different kinds: those which grow in common soil, saturated with moisture throughout the year; those which grow in soil, saturated or covered with water during winter and spring; and those which grow in peat-bogs. A few of them are ornamental; such as *Menyanthes trifoliata* and *Cómarum pa-*

*lústre*, which are proper Marsh Plants; *Damasdnium vulgáre*, and *Ranúnculus Língua* and *Flámmula*, which grow in soils sometimes dry during summer; and *Parnássia palústris*, which grows in peat-bogs and springy soils. In gardens, bogs are easily imitated, by placing the soil in pots, or sunk boxes, with retentive bottoms and sides, so as to retain water. Where there is an aquarium, or pond for plants, it is very often surrounded with a broad border or margin of soil, raised a few inches above the level of the water in the pond, and which is kept moist by the exudation of the water. To prevent the exudation from extending farther than the border, the bottom and the other margin are formed of masonry lined with clay. A very common mode, and one of the best, is to place the plants in pots or tubs, and to set these on supports in the water, so that the bottom of the pot or tub may be only a few inches covered by it. In this way the soil about the plant is kept sufficiently moist without the risk of any excess. Among Marsh Plants may be reckoned the different kinds of Sedge, some of which are very ornamental; the Buck-bean, the Water Violet, the Sweet-scented Rush, the Forget-me-not, the Marsh Bedstraw, and many others.

**MARTAGON LILY.** — Those Lilies which have the segments of the perianth so completely turned back, as to form no bad representation of a Turk's cap. In the midland counties these flowers are called Turnagain-gentlemen. For their culture, see LI'LIUM.

**MARTY'NIA.** — *Pedalíneæ*. — Half-hardy annuals, with very oily seeds, which require to be raised on a hot-bed, but which may be planted out in May. *M. frágrans* is the most beautiful.

**MARVEL OF PERU.**—See MIRA'BILIS.

**MASTIC TREE.**—A kind of Pistacia tree, producing the gum mastic.

**MATTHI'OLA.**—*Cruciferae*.—The Ten-week Stock is an annual which should be raised on a hotbed, and transplanted into a very rich sandy loam in May. The remains of celery trenches which have been made in a sandy or calcareous loam form the best soil for Stocks of all kinds; but where this kind of soil cannot be obtained, sand or chalk, enriched with vegetable mould, will do extremely well. The finest Stocks I ever saw were in a garden at Greenhithe, the soil of which was chalk, and in Mrs. Humphrey's garden at Shenstone, the soil of which was a loamy sand; and though both these were biennial Stocks the same soil would have grown the annual ones equally well. Some of the finest Stocks in British gardens are from seed raised in Germany and Russia; and the plants raised from this seed are called German and Russian Stocks. For the culture of the biennial species, see BROMPTON STOCKS.

**MAURA'NDYA.**—*Scrophulariæ*.—Elegant climbing plants, with beautiful dark blue or purple flowers, which are rather tender, and are generally killed in winter, if planted in the open ground. They do not require much room for their roots, and generally flower best in a pot, as their roots are so weak and delicate as easily to be killed by having coarse-growing plants near them. *M. Barclayana* thrives best in a pot with wires fixed in the rim for it to run over (see fig. 35); and thus treated, it forms an extremely beautiful object in a balcony garden. All the Maurandyas should be grown in a light rich soil; and

they are increased by seeds or cuttings.

**MAXILLA'RIA.**—*Orchidaceæ*.—A very extensive genus of Epiphytes, some of which have their flowers hanging down from their roots, and




FIG. 35.—POT FOR TRAINING THE MAURANDYA.

are grown in baskets of moss, the husks of cocoa nuts, or on pieces of wood with the bark on, or hung by wires to the rafters of the damp stove or orchideous house. Some of the species have upright flower-stems, and are grown in pots in brick rubbish, mixed with sand, or heath-mould, and a little

loam. Most of the kinds are handsome, and some have splendid flowers.

**MAY APPLE.**—See *PODOPHYLLUM*.

**MAY'TENUS.**—*Celastrineæ*.—An evergreen shrub, a native of Chili, with yellowish flowers, which are produced in great abundance in May. It is nearly hardy, and only requires a slight protection during severe frosts.

**MEADOW SAFFRON.**—The popular English name for *Colchicum*.

**MECONOPSIS.**—*Papaveraceæ*.—The new name for the Welsh Poppy, *Papaver cymricum* L. This plant, which has yellow flowers, is a native of mountainous places in Wales; and it is easy of culture in any soil which is poor rather than rich.

**MEDINE'LLA.**—*Melastomaceæ*.—This is a very splendid genus of shrubs from the Malay Peninsula, and the Eastern Archipelago. Most of the species inhabit damp forests, and Dr. Blair states that he has seen some of them climbing up trees from sixty to eighty feet high. The most beautiful species is probably *M. magnifica*, introduced about 1850, and sometimes called *M. bracteata* in the nurseries. The bracts of the flowers of this species are rose-coloured and very ornamental. In Great Britain, it requires a moderate stove or warm greenhouse. *M. Sieboldiana*, syn. *M. eximia*, has white wax-like flowers, with a yellowish-brown calyx, and deep rose-coloured stamens.

**MELALEUCA.**—*Myrtaceæ*.—Australian shrubs, with very singular tassel-like flowers, which the first settlers in New Holland called the Tea Trees, and which are nearly allied to *Metrosideros*. One species, *M. nerifolia*, which has yellow flowers

with petals, has been removed to the genus *Tristania*; *M. Cajuputi*, from which the Cajeput oil is made, and *M. Leucadendron*, the Black and White Tree, are natives of the East Indies, and require a stove in England; but all the Australian species are greenhouse plants. One of the handsomest of these, *M. fulgens*, has its flowers in a long spike, which looks like a bottle-brush. All the kinds should be grown in a compost of sand, loam, and peat; and they are all propagated by cuttings.

**MELANTHIUM.**—*Melanthaceæ*.—Pretty little plants with bulbous roots and blackish flowers, mostly natives of the Cape of Good Hope, and requiring the usual treatment of Cape bulbs.

**MELASTOMA.**—*Melastomaceæ*.—Very handsome stove shrubs, with large showy flowers. The leaves are also large and strongly ribbed. The fruit is eatable, and filled with a black pulp; whence the name of *Melastoma*, or Black-mouth, is said to be given to it, because it stains the mouths of those who eat it. All the species are natives of Ceylon and other parts of the East Indies; and they all require to be grown in peat, and kept rather dry during winter.

**MELIA.**—*Meliaceæ*.—The Bead Tree.—*M. Azedarach*, the common Bead Tree, is a half-hardy shrub, or tree, with lilac flowers and yellow berries, the pulp of which is poisonous; but the hard stone in the centre is used to make rosaries. There is another species, *M. semper-vivens*, which is a native of the West Indies, where it is called the Indian Lilac, or Pride of India. Both kinds are generally kept in the stove in England, where they will ripen their seeds; but the first kind does very well against a conserva-

tive wall, and it has flowered in the open air at Bayswater and other places. It will grow best in loam and peat, and it is propagated by cuttings.

**MELIANTHUS.**—*Rutaceæ*.—The Honey-flower. — A half-shrubby greenhouse plant, with bluish-green, or rather gray, leaves, sometimes called Sicilian Ragwort. If planted in the open air, and slightly protected from frost, it will grow ten feet high, and produce its large spikes of brownish-red flowers abundantly. It is a native of the Cape of Good Hope. It should be grown in a light rich soil if it be wanted to attain a large size; or in sand, mixed with a little loam and lime rubbish, if it be wanted to flower while yet of a small size. It looks very well trained against a south wall.

**MELISSA.**—*Labiataæ*.—The Balm. —None of these species are particularly ornamental, but they are worth growing for the fragrance of their leaves. They are all hardy perennials, which will grow in any soil or situation, and which are propagated by dividing the root.

**MELON THISTLE.**—*Cactaceæ*.—The Melon Thistle.—All these plants have a sort of crown of cottony substance, which sometimes grows to an enormous size. The flowers are generally red, and are produced around this crown. They are natives of the hottest parts of the tropics, and should be kept in a dry stove in England. They should be grown in a little sandy loam, mixed with two-thirds of lime rubbish; and the pots in which they grow must be well drained with cinders, as they are very liable to damp off or rot, if any stagnant water be suffered to remain about the roots. They are very much improved by plunging the pots in which they

grow into tan, and thus affording the plants bottom-heat.

**MELON THISTLE.**—See **MELON CACTUS**.

**MENISPERMUM.**—*Menispermaceæ*.—Handsome climbing shrubs, natives of Europe and North America, with curiously shaped leaves, racemes of yellowish or greenish-white flowers, and red or black berries, which have somewhat of an intoxicating quality. *M. canadense*, which is the commonest species, is a hardy free-growing climber, admirably adapted for covering a wall or arbour in a very short time, and in a very ornamental manner. It is well deserving of general cultivation, and yet it is comparatively little known, perhaps on account of the modest colour of its elegant little drooping racemes of flowers, which are generally hidden from common observers by the leaves. Its English name of Moonseed is derived from the shape of the seed, which resembles a crescent or half-moon. It will grow in any soil or situation; and it looks very well on a lawn trained up a single pole, and with the extremity of its branches left to spread themselves at pleasure. It also looks very well trained to form a pillar, or to a frame with an umbrella top, &c.

**MENYANTHES.**—*Gentianaceæ*.—The Buck-bean.—The European kinds have white flowers, but some of the exotic species, now called *Villarsia*, which are natives of Australia and the Cape, are very handsome, with very showy yellow flowers. They are all marsh plants, and should be sown or planted in the mud or soft ground left by the water. Some of the kinds are only half-hardy.

**MENZIESIA.**—*Ericaceæ*.—Little heath-like plants, formerly included in the genus *Erica*, natives of

Europe and North America. The commonest kind (*M. polifolia*), St. Dabeoc's Heath, is found wild in Ireland. The flowers are larger and more globular than those of the common Heaths, and much handsomer. They are quite hardy, and only require to be grown in sandy peat or heath-mould.

**MESEMBRYANTHEMUM.** — *Ficoides*.—The name of Mesembryanthemum signifies mid-day flower; and this name admirably expresses the habit of the plants, their flowers only expanding in the brightest sunshine. The English name of Fig Marigold alludes to the fruit, which is shaped like a fig, and which is eaten by the Hottentots; and to the flower, which resembles that of a Marigold in shape, and sometimes in colour. There are two kinds of Mesembryanthemum which are called the Ice plant, *M. glaciale* and *M. crystallinum*, the former being an annual, and the latter a biennial—and they take their English name from the little globular protuberances, or rather blisters (which botanists call papulæ), filled with a soft watery matter, which glisten over the whole of the plants, and make them look as though they were covered with ice. The flowers of these plants are white; but there are other Mesembryanthemums with pink or purple flowers, and those of the commonest and hardiest kind, *M. pomeridianum*, are of a brilliant yellow. This kind is an annual, the seeds of which should be sown on a hotbed, and the young plants transferred to the open ground in May; and they should be always planted out in the open border, as they never flower well in a pot. *M. tricolor* is a charming variety, which should be treated in the same way as the preceding. The perennial kinds may be grown either in

pots, or in the open ground; but in the latter case they should either be taken up or carefully protected during winter, as they are killed by the slightest frost. They should be grown in sandy or gravelly soil, which, for the larger-growing species, may be mixed with a little loam; but even of these, the poorer and more sandy the soil, the more brilliant will be the colour of the flowers, though the leaves and stems will become small and weak. All the species should be kept quite dry when in a dormant state, and abundantly supplied with water when they are about to flower; and all the perennial kinds are propagated by cuttings, which should be kept dry for several days after they are put into the ground till they begin to wither, when they should be supplied with a little water, and they will directly begin to throw out roots. The pots in which these plants are grown should be well drained with cinders; and when planted out in the open air, it should be on a dry, open, sunny bank.

**MESPIIUS.**—*Rosaceæ*.—This is one of those genera which have been dismantled and almost annihilated, by modern botanists. A few years ago, almost all the flowering shrubs and low trees included in the order Rosaceæ, were referred to Mespilus. All the Cratæguses, a great number of the Pyruses, the Arónias, Amelanchier, Eriobótrys, and many other allied genera, were all considered to belong to Mespilus. Now, however, the genus Mespilus is confined to the two kinds of Medlars; and even of these, *M. grandiflora* seems rather doubtful. *Méspilus germanica*, the common Medlar, and its varieties, are now, therefore, the sole support of this once extensive genus; and they are not only trees of considerable

size, but trees that, notwithstanding their large white blossoms, are too coarse growing to be called ornamental.

**METROSIDE'ROS.** — *Myrtaceæ*. — Australian and Cape shrubs, with tassel-like flowers, nearly allied to *Melaleuca*. One species (*M. verus*), the Ironwood, is a tree and a native of the East Indies. The most beautiful of the Australian shrubs formerly considered as belonging to this genus, are now removed to the genus *Callistemon*; and these have generally crimson flowers. The remaining species are generally kept in a greenhouse in England, but they may be grown in the open air, if they are slightly protected during winter; and in sheltered situations they will often stand several years without any protection whatever. They should be grown in a mixture of sandy loam and peat, but any common garden soil will do; and when grown in the open air, they should be trained against a wall. They are propagated by cuttings of the ripened wood, which cannot be struck without the help of sand, bottom-heat, and a bell-glass.

**MIGNONETTE.** — *Reseda odorata*. — This well-known plant is generally considered as an annual, and sown every year as such; but it is, in fact, a shrub, and if preserved carefully through the winter, in two or three years its stem will become quite woody. In this state it is called the Tree Mignonette, and is supposed by many to be a different species. It is a native of Barbary, and grows wild on the sandy shore of Algiers. The name, Mignonette, which is French for "the little darling," is supposed to have been given to it on account of its seeds having been first sent to England from Paris. It is rather singular, however, that it should be known

by a French name in England, while in France it is called by its Latin name of *Reseda*.

Mignonette should always be sown in light sandy soil, if possible; as when grown in a rich loam, it loses its fragrance. With a little management, it may be contrived to have Mignonette in flower every month during the year, without the aid of either a regular gardener or a hot-house. In order that the plants may flower in winter, the seeds should be sown in the open border in July. Or, if it be more convenient, the seeds may be sown in pots in that month, placing the pots in a balcony, outside a window, or in any situation where they will have abundance of light and air. In September the plants should be removed to the pots in which they are to flower, and only a sufficient number left in each to make the pots look full, without the plants being so crowded as to occasion them to be drawn up. This number must, of course, vary according to the size of the pot; but it should never exceed eight, or be less than three. The pots should then be taken into the house, and placed in any convenient situation in a room without a fire, till they have formed their blossom-buds, which will be the latter end of October, when they should be removed to a window in a room where there is a fire; when they will throw out abundance of branches, and will continue flowering beautifully during November, December, and January; and if they are regularly watered every day, till the following March. Theseeds of the plants which are to come into flower in March to succeed them, should be sown in pots at the latter end of August, and the pots may be placed in a spare bedroom, or in any open shed, or other situation



under cover, where they will have plenty of light, and can have air occasionally. Early in November they should be thinned out, or transplanted, so as to leave only six or eight plants in a pot, and these pots should be plunged into a shallow box or packing case, half filled with coal-ashes, and placed in a cellar, or back-kitchen, or, in short, any place where they will not have much heat, and yet be protected from frost. While in this situation, they should be regularly watered once or twice a week; and as no light is better than only a little, they may be covered with a piece of old carpeting, or an old ironing-blanket supported by a few sticks stuck in the earth, so as to prevent it from crushing the plants by its weight. In this situation, though they will become quite blanched, they will grow freely, and be well-shaped plants; while, on the contrary, if they had not been covered, as they could not be put in a window on account of the danger from frost, they would have become etiolated, or drawn up, with weak, ill-shaped stems, in the efforts they would have made to reach the light. Besides, the blanket will save them from being injured by frost. About a fortnight before they are wanted to flower, the blanket may be taken off, and the box removed to the window of the kitchen, or some place where there is a constant fire: when the plants will soon become quite green, and will form flower-buds. The pots may then be taken out of their box, and removed to the room where they are to flower, having been first put into other pots, somewhat larger than themselves, and the interstices between the two being stuffed with moss, which may also be laid on the surface of the earth in the inner

pot; or, if moss cannot be easily obtained, double pots will suffice, the outer one being only just large enough to admit the inner one. A third crop may be sown in February, in pots which may be kept under shelter till all danger is over from frost, and which may be then set out on window-sills or in any other situation in the open air, and which will flower in May, June, and July, continuing in flower till they are succeeded by a fourth crop sown in April, in the open ground, or in pots in the open air, which will come into flower in July, and continue till November.

When it is wished to obtain a plant of Tree Mignonette, a healthy vigorous plant of Mignonette sown in April should be placed at the proper time for transplanting in a pot by itself, and the blossom-buds should be taken off as fast as they appear. In autumn, all the lower side-shoots should be cut off, so as to shape the plant into a miniature tree, and it should be transplanted into a larger pot, with fresh soil, formed of turfy loam broken small, but not sifted, and sand. It should then be removed to a greenhouse, or warm room, and by being regularly watered every day, and kept tolerably warm, it will remain in a growing state all the winter, and by spring its stem will begin to appear woody. It should be treated in the same manner the following year, all the side branches being cut off as they appear, except those that are to form the head of the tree; and by the third spring it will have bark on its trunk, and be completely a shrub. It may now be suffered to flower, and its blossoms, which will be delightfully fragrant, will continue to be produced every summer, for a great many years in succession.

Many persons save their own seed of the common Mignonette; but it is hardly worth while to do so, as it is generally both good and cheap in the seed-shops.

The variety *R. odorata grandiflora* has a more vigorous habit of growth than the common kind, and the flowers are larger; but care is necessary in saving the seeds, as the large variety is not uniformly reproduced. Seeds from plants having the appearance of degenerating to the original species should not therefore be gathered when the large variety is wished to be perpetuated.

**MILDEW.**—Rose-trees and many other plants are very apt to be affected in autumn with a white or brownish appearance on the leaves, which is sometimes called the blight, but more properly rust or mildew. The cause of this appearance was long unknown; and some supposed it to be produced by unhealthy wind, and others that it was the work of insects: it is now, however, satisfactorily, proved to be a parasitic plant or Fungus growing on the leaves, as Lichens and other Fungi grow on the bark.

The parasitic Fungi, known by the general name of mildew, are of different kinds; some grow on the surface of the leaf, some form under the epidermis or outer skin, others attack the root, whilst there are kinds that pervade the whole plant, as in the case of the Potato disease, and Vine mildew. The destructive character of the last two are well known, and they, like the other kinds, have attacked plants in vigorous health. Doubtless, as a preventive, it is well to keep plants duly supplied with all the elements of nutrition, and with properly regulated supplies of heat, air, and moisture, with light; but beyond

attention to these particulars, the only preventive appears to be flowers of sulphur; this proves effectual in the case of the Vine, Roses, &c., and generally in that of all plants under glass, *if applied in time*; for although it will kill the mildew at any time, yet the disorganization of the tissues caused by the parasite often proves an irreparable injury.

**MILFOIL.**—See *ACHILLEA*.

**MILKVETCH.**—See *ASTRA'GALUS*.

**MILKWORT.**—See *POLY'GALA*.

**MI'LLA.**—*Asphodelææ*.—A Mexican plant, with flowers of the most brilliant and purest white, which continue expanded day and night, till they fade, instead of closing at night, as is usual with plants of the same family. They will grow in any common soil, and only require a slight protection from frost, such as covering with dead leaves, &c., during winter.

**MILTO'NIA.**—*Orchidæææ*.—A very beautiful epiphyte from Brazil, with its flowers on erect stems, like those of the *Cattleya* which this plant somewhat resembles. Though an epiphyte, it is generally grown in England in a pot, in loam, mixed with sand and rubbish, and it requires the same treatment as other orchidaceous epiphytal plants which will bear being grown in pots.

**MIMOSA.**—*Legumindææ*.—To this genus belongs the Sensitive Plant, of which there are three species, the leaves of all of which shrink at the touch; *M. pudica* is the Sensitive Plant most cultivated in hothouses, though *M. sensitiva* is also very generally cultivated; the former, however, is a shrub, and the latter an annual or a biennial. Both may be raised on a hotbed in spring, with the tender annuals, and either kept in pots throughout the summer, or turned out into the open

border about the end of May. Many species formerly included under the genus *Mimosa* are now removed to *Acacia*; the principal distinction between the genera being that *Mimosa* has a jointed seed-pod, which *Acacia* has not. Several other genera have also been formed out of *Mimosa*. Some of the kinds are stove-plants; others thrive in a greenhouse; and *M. marginata* Dec., (the *M. prostrata* of the nurseries,) is sufficiently hardy to stand ordinary winters against a conservative wall. They should be all grown in a mixture of loam and peat; and they are propagated by seeds or cuttings. See SENSITIVE PLANT.

**MIMULUS.** — *Scrophulariæ*. — The Monkey Flower. — The first *Mimulus* introduced into Britain was *M. ringens*, in the time of Miller, and *M. glutinosus*, a shrubby species, with orange flowers, was the second. Since then, numerous species have been introduced from North and South America, principally annuals and perennials. All the herbaceous kinds of *Mimulus* cross freely with each other, and thus a great number of showy plants have been raised, particularly by Mr. James M'Nab, of the Royal Botanic Gardens, Edinburgh. They should all be grown in a compost of peat and loam, and supplied abundantly with water; indeed, when grown in pots they should be kept constantly standing in saucers full of water. They are all very nearly hardy; and *M. roseus*, *M. cardinalis*, and *M. moschatus*, commonly called the Musk Plant, will grow in the open air, for several years without any protection, dying down to the ground in winter, and springing up and flowering abundantly every spring. The shrubby kinds are now separated from the others, and formed into a new genus,

under the name of *Diplacus*. (See *DIPLACUS*.) The name of Monkey-plant alludes to the seeds, which are marked so as to bear some resemblance to the face of a monkey.

**MIRABILIS.** — *Nyctagineæ*. — The Marvel of Peru. — These plants, though generally treated as annuals, have fusiform tuberous roots, which may be taken up every year and replanted, like those of the *Dahlia*. They require a rich soil.

**MIRBE'LLA.** — *Leguminosæ*. — An Australian shrub, with pretty pea-flowers; which is generally kept in a greenhouse in British gardens. — See AUSTRALIAN SHRUBS.

**MISTLETOE.** — See *VISCOUM*.

**MOLUCCE'LLA.** — *Labiata*. — Mol-davian Balm. — A hardy annual, which only requires sowing in March or April in the open border, in any common garden soil. — See ANNUALS.

**MO'LY.** — A kind of garlic, with very pretty yellow flowers. — See *A'LLIUM*.

**MOMO'R'DICA.** — *Cucurbitaceæ*. — The Squirting Cucumber. — An annual gourd-like plant, with woolly leaves and yellow flowers, the fruit of which resembles a small Cucumber; and which, when ripe, bursts the moment it is touched, scattering its seeds and the half-liquid pulpy matter in which they are contained to a considerable distance. This quality made it a favourite in gardens a century ago, when some people were yet in a state of sufficient barbarism to find amusement in the annoyance of others; but it has now deservedly fallen into disrepute, and is seldom grown.

**MONACHA'NTHUS.** — *Orchidaceæ*. — The Monk Flower. — An orchidaceous epiphyte from Demerara and Brazil, requiring the usual treatment of similar plants. — See ORCHIDEOUS. EPIPHYTES.

**MONA'RDA.** — *Labiata*. — Hardy

herbaceous plants, with showy flowers, natives of North America, they grow best in a rich light soil; and they are increased by dividing the root. *Monarda didyma* produces the Bergamot.

**MONEY WORT.** — *Lysimachia Nummularia*. — A trailing plant, with yellow flowers, which should be grown in peat, or some other light soil, and kept moist. Its long trailing shoots look very well hanging over the sides of a rustic basket or vase, supported on a pedestal, or rock-work; and in such situations, if kept moist, it will flower abundantly; while the same plant removed into the shade will not produce a single flower, and is easily killed if watering be neglected.

**MONK FLOWER.** — See *MONACHANTHUS*.

**MONKEY FLOWER.** — See *MIMULUS* and *DIPLODENDON*.

**MONK'S HOOD.** — See *ACONITUM*.

**MONOCHLAMYDEAE.** — Plants having only a calyx and no corolla; in opposition to *DICHLAMYDEAE*, which are the plants which have both a calyx and a corolla.

**MONOCOTYLEDONOUS PLANTS** are those, the seeds of which send up only one cotyledon or seed-leaf when they vegetate, and have leaves, the veins of which are in parallel lines. The ligneous or woody plants belonging to this division increase very little in thickness during the whole period of their existence; and their wood consists of fibrous matter, fresh quantities of which are deposited every year within the stem.

— See *ENDOGENS*.

**MONECIOUS PLANTS** are those which have the male and female flowers separate, but still on the same plant; while *DIOECIOUS* plants are those which have the male and female flowers distinct, and on different plants.

**MONO'SPIS.** — *Lobeliaceae*. — A very beautiful little trailing plant, having dark-blue flowers with conspicuous yellow anthers, and the flowers on long footstalks. It is a native of the Cape of Good Hope, and it should be grown in sandy peat. It is suitable for rock-work.

**MONSO'NIA.** — *Geraniaceae*. — Very beautiful herbaceous plants, nearly allied to the *Geraniums*, but with much larger flowers, and named in honour of Lady Anne Monson. They are now rarely seen, but well deserve cultivation. They should be grown in a mixture of vegetable mould and loam, and kept in a greenhouse. They are propagated by cuttings, or by dividing the roots. They are natives of the Cape of Good Hope.

**MOONSKED.** — See *MENISPERMUM*.

**MOON TREFOIL.** — *Medicago arvensis*.

**MOOR HEATH.** — The English name of *GYPHOSOLIS*.

**MORE'A.** — *Irideae*. — Bulbous-rooted plants, with very handsome flowers, nearly allied to *Ixia*, from which genus they have been removed. They are generally grown in pots, in a mixture of sandy loam and vegetable mould; and when they have done flowering they should be kept dry till they begin to grow in spring. When planted in the open ground, they should be protected from frost and heavy rains.

**MORICA'NDIA.** — *Cruciferae*. — A very pretty hardy annual, which should be sown in the open border in March or April. *M. Ramburii* is a native of Spain, introduced in 1856.

**MORMO'DES.** — *Orchidaceae*. — An orchideous epiphyte, with dark-purple flowers, from the Spanish Main. It should be grown on a piece of wood. — See *ORCHIDEOUS EPIPHYTES*.

**MORNA.** — *Compositae*. — Beauti-

ful half hardy annuals, with everlasting flowers, which should be raised on a hotbed, and planted out in May.

MOSSHOUSES are constructed of wood lined with rough boards, to which moss, generally of several different kinds, is attached by cord or wire, and nails. The roof is also covered with boards, to which is fixed sometimes thatch, and at other times heath, or the mossy bark of oak, pine, birch, or other old trees. The floor is generally paved with blocks of wood, or sometimes with small pebbles, or any other material, according to fancy. The ceiling is generally lined with moss in the same manner as the side walls, and both may be formed into panels, according to the taste of the designer. There are a great many kinds of Moss and Lichens which may be used for lining moss-houses. Of terrestrial Mosses, those which are most common are the *Dicranum glaucum*, which is of a whitish green, and *Bryum hornum*, which is of a yellowish green; *Sphagnum acutifolium* is of a pinkish colour, and *S. obtusifolium* is of a yellowish white. The commonest Tree Moss, or technically Lichen, is *Cenomyce rangiferina*, the Reindeer Moss, which is found on the Ash, and on many other trees, and is white. This Moss also grows in great abundance on poor gravelly soils, among heath; for example, on Bagshot Heath, near London. Any quantity of the green mosses, and also of the yellow kinds, may be purchased in Covent Garden Market: and the Reindeer Moss, if ordered from local nurserymen adjoining heaths, may be collected by the same persons who supply them with the other Mosses. Almost everything in an affair of this kind must be left to the fancy of the

designer. Some of the handsomest mosshouses in England have been erected in Bagshot Park, the seat of the late Duchess of Gloucester, by Mr. Toward, now gardener to Her Majesty at Osborne. Mosshouses must not be confounded with root-houses, which are formed with fantastic roots, or with wood houses, which are formed with branches of trees with the bark on. When a mosshouse is to be erected, the first thing to be done is to make a drawing of the effect that it is intended to produce, and then to prepare the frame. If the mosshouse is to be only a kind of alcove open in front and without windows, it will be easy to get some wood, and any man-servant who can use a saw and a hammer can put it together; but if it is to have a door and windows, a regular carpenter must be called in. In the first case, young Pine and Larch trees that have been cut down in thinning plantations will do very well. When the framework is completed, laths must be nailed across the compartments, between which the moss is thrust with a wooden knife, or blunt chisel, the root end being lowest. The great art consists in arranging the moss so as to form a pattern: and this is accomplished by sorting the moss into heaps of the different colours, tracing the pattern rudely on the laths, and keeping a coloured copy of the design before the operator. The moss should be so contrived as completely to hide the laths, and it should also be pushed in to a sufficient depth to be quite firm. The lines of the figure should be quite distinct, and the colours clear and well contrasted.

MOTH.—Moths are distinguished from butterflies by flying at night instead of during the day; and by their antennæ, which are pointed

and sometimes feathery, instead of terminating in a knob, like those of the butterflies. Moths are more difficult to entrap in their perfect state than butterflies, as they are rarely seen by day; but a diligent search should be made for their eggs, and their caterpillars should be destroyed as soon as they are hatched if possible, while they are quite small.

**MOULD.**—Thoroughly decomposed leaves or putrescent manure, mixed with sand or other light soil, is called mould, which is chiefly distinguished from soils by its containing but a small portion of earthy matter; hence we have leaf-mould, composed chiefly of rotten leaves; dung-mould, of dung reduced to a dry powdery matter; and heath-mould, consisting of the black vegetable soil found on the surface of heaths, and always more or less mixed with sand. The two first kinds of mould are used for growing plants which in cultivation are considerably removed from a state of nature, such as Pelargoniums, China Roses, Fuchsias, Balsams, Petunias, and a great many others; and the heath-mould is used in the culture of Heaths and of Ericaceæ, and more or less in most New Holland and Cape shrubs and bulbs. In general, all plants whatever, from the Oak to the Moss, will grow in heath-mould alone, and therefore it is a particularly useful soil in which to raise seedlings; and in this respect it differs materially from leaf-mould and dung-mould, in which they will not grow. Garden-mould is composed of decayed vegetables and manure mixed with the finer part of the soil, thoroughly pulverised by repeated digging, raking, and hoeing.

**MOUNTAIN ASH.**—*Pyrus aucuparia*.—A well-known tree, very ornamental in shrubberies for the

abundance of red berries with which it is covered every autumn. It is quite hardy, and will grow in any soil and situation.

**MOUSE.**—Mice are sometimes troublesome in gardens in country places, particularly where there are many bulbs planted, as they eat the solid bulbs or corms. To prevent their ravages chopped furze is sometimes buried with the bulbs, or the clippings of thorn hedges or rose briars are laid over the bed.

**MOUTAN.**—The Tree Peony is generally called the Moutan, or Botan, in China; and several new and splendid kinds have been introduced by Mr. Fortune since the year 1846. Some of these kinds are a pure white, others scarlet, others salmon colour, and others purple of various shades. One was reported to be yellow, but it proves to be only straw colour of a very faint tint. All the kinds are very ornamental; and some of them in their native country, Japan, acquire a woody stem eight or ten feet high in a single season.

**MOVING PLANT.**—*Desmodium gyrans*, a native of the East Indies, which requires a stove in Great Britain. It has pea flowers not remarkable for their beauty, and it derives its name of Moving Plant from the singular motion of its leaves, which, when the sun is shining full upon them, begin to turn and quiver in a most extraordinary manner. Sometimes only one or two leaves will move slowly up and down, as though each turned on a pivot, but at other times the whole tree appears in a violent state of agitation, every leaf trembling as though it were shaken by some invisible hand.

**MOWING** is an operation performed with the scythe, and in ornamental gardening it is used for the purpose

of keeping the grass quite short and smooth. It is the most laborious operation which falls to the lot of the working gardener, and in large places, there are generally a set of labourers, who are not gardeners, who are kept on purpose for it. Mowing machines require far less skill and exertion than the scythe, and answer very well where the surface of the soil to be mowed is perfectly smooth and firm, as all lawns should be made. Mowing machines are particularly adapted for amateurs, affording an excellent exercise to the arms and every part of the body; but they should be of small dimensions, otherwise they require too great exertion, and can only be worked by strong labourers. This is the case when they exceed sixteen inches in width; with a twelve or fourteen inch machine a boy will easily mow a well kept lawn; but two boys would not be sufficient for a machine of twice that width. A few inches wider than that which a boy could easily work would require the strength of a man; a few more than the latter would require the strength of a horse; so much is the loss of effective power occasioned by increase of size. Where a lawn is varied by numerous small beds or single trees or bushes, the scythe is required, in addition to the machine, for mowing up close to the branches or stems of the plants; but where an amateur mows his own lawn with a machine, a better instrument than the scythe for the purpose mentioned is a pair of common hedge-shears, with which the grass may be clipped as short as it can be mown. When a lawn is newly formed, and the soil is rich, it will require to be mown every eight or ten days for the first and second summers; but afterwards, when the soil becomes ex-

hausted, and the grass grows with less vigour, once a fortnight for the three summer months will suffice, and once every three weeks or a month for the autumn.

MUCU'NA.—*Leguminosæ*.—Cow Itch.—*M. pruriens* is a stove plant with large drooping racemes of very beautiful dark-purple pea-flowers. The legumes or seed pods are covered with long brittle hairs, which cause an intolerable itching if applied to the skin. The species is a native of the West Indies, but other kinds are found in the East Indies, where the pods are skinned and eaten, cooked like kidney beans. The seeds, which are large, round, and flat, with a scar running all round them, are sometimes called asses' eyes.

MULCHING is seldom used in flower-gardens, though it may be applied advantageously to Camellias and Magnolias, and any other half tender shrubs. It consists in laying a quantity of straw, or litter, round the stem of the plant, so as to cover the whole of the roots during winter, and either removing it or forking it into the ground in spring.

MULLEIN.—See VERBA'SCUM.

MU'SA.—*Musacæ*.—The Plantain, or Banana.—Stove plants, grown generally for their fruit, but very ornamental from their large leaves and curious flowers. Most of the species require a great deal of room, as they will neither flower nor fruit till they attain a large size. They should be grown in a rich loam kept moist, and they are increased by suckers. The new kind, *Musa Cavendishii*, flowers when of a much smaller size than any of the other kinds.

MUSCA'RI.—*Asphodèleæ*.—The Grape Hyacinth.—Bulbous-rooted plants, that only require planting in any common garden-soil, where

they may remain several years, flowering every year in succession, without any care being necessary in taking them up, &c. The Starch Hyacinth (*M. racemodsum*) takes its name from its flowers smelling like starch.

**MUSK PLANT.**—There are two plants known by this name, viz. *Mimulus moschatus*, a dwarf plant with yellow flowers; and *Aster argophyllus*, a tall plant with blue flowers.

**MUTI'SIA.**—*Compósitæ*.—Curious plants, with tendrils at the extremity of the leaves. They are natives of Brazil, and require a stove in England. They should be grown in peat and loam, and they are propagated by cuttings.

**MYANTHUS.**—*Orchidææ*.—Flywort.—An Orchideous epiphyte from Demerara, which should be grown in a moist stove on half-rotten wood.—See ORCHIDEOUS EPIPHYTES.

**MYGINDA.**—*Rhamnææ*.—Handsome shrubs, nearly allied to the Holly; natives of the West Indies. They are generally stove plants in England, and they should be grown in sandy loam.

**MYOSOTIS.**—*Boraginææ*.—*M. palustris*, the Forget-me-not, delights in moist places on the border of running streams. *M. sylvatica*, which is found in woods, resembles it, but the flowers are very inferior.

**MYRICA.**—*Myricææ*.—The Candleberry Myrtle and the Sweet Gale belong to this genus, and they are both interesting to the botanist. They should be grown in loam and peat, and they are propagated by cuttings.

**MYRTUS.**—*Myrtææ*.—A genus of beautiful evergreen shrubs, natives of Europe, Asia, South America, and some of them of New Holland. The common Myrtle, *M. communis*, of which there are

eight or ten very distinct varieties, is too well known to require any description. Myrtles are not surpassed in beauty of foliage by any other exotic shrub; the flowers are of a pure white, and like the leaves, fragrant. The fragrance arises from an oil which is secreted in little cells, which appear as dots when the leaves are held up to the light. The handsomest varieties of the common Myrtle are the Roman, or broad-leaved, the broad-leaved Dutch, and the narrow-leaved and double-flowered. They will grow in any common soil, somewhat




FIG. 36.—A CUTTING OF A MYRTLE PREPARED FOR PLANTING; THE DOTTED LINE SHOWING THE GROUND.

loamy, and are propagated with most facility by cuttings of the current year's wood, when it is just beginning to ripen, cut across at a joint and then planted in sand, and covered with a bell-glass. Cuttings will root, however, taken off at any season, and treated with common care. When cuttings are made of the old wood they should be planted to the depth of half the space between the buds, as shown in fig. 36. Myrtles may also be raised from seeds, which are produced freely by the broad-leaved kinds.



*M. bullata* is a native of New Zealand, and has blistered leaves. Its native name is Rama-Rama. *M. tomentosa* is a native of China, with woolly leaves and purple flowers, which appear in June and July. *M. Pimenta*, now made *Pimenta vulgaris*, is a native of the West Indies, requiring a stove, and is the plant producing the common Allspice of the shops. The common broad-leaved myrtle will stand the winter against a conservative wall, in dry soil, in most parts of England, and also in Scotland, more particularly in low situations, near the sea. At Nettlecombe, in Somersetshire, there are large trees covered with flowers. In some parts of Ireland it is as hardy as the common Laurustinus is in the climate of London. Garden hedges are made of it at Belfast, and also at Cork.

**N**AILING half hardy shrubs against a wall is an operation that should be performed with great care; and as the sole object of growing the shrubs is on account of their being ornamental, nothing should be shown which tends in the slightest degree to injure this effect. For this reason the nails should be small and round-headed, and strips of leather or black tape are preferable to list. Leather is sometimes preferred to list, even for fruit trees, because it does not harbour insects; but it is too expensive to be used on a large scale. In nailing ornamental shrubs, the branches should not be kept so close to the wall as fruit-trees, as half their beauty would be lost if they were deprived of their loose shoots. All that is required is to train the trunk and main branches.

NAPOLÉON'A. — *Belvisiæ*. — *N. imperialis* is a very singular

plant, with flowers which, when fresh, are apricot-coloured and crimson, but which, when dying, assume a bluish tint. The whole appearance of the genus is so remarkable as to render it necessary to constitute a new order for it between *Cucurbitaceæ* and *Passifloraceæ*. *N. imperialis* was first brought to England in 1848.

NAPOLÉON'S WEEPING WILLOW. — This willow differs from the common kind in several respects, and it is probably the male variety of *Salix babylonica*, of which only the female was formerly known in England. It is of much slower growth than the common kind, and therefore much better adapted for planting in a shrubbery.

NARCISSUS. — *Amaryllidaceæ*. — The genus Narcissus is a very extensive one, embracing as it does, the Jonquils, the Polyanthus Narcissus, the little Hoop Petticoat, the Poet's Narcissus, and the Daffodils, besides numerous others. The late Mr. Haworth paid great attention to this genus, and divided it into thirteen new genera, none of which, however, have been adopted by other botanists, though their names have been preserved in the sections into which the genus Narcissus is now divided. All the Narcissi are quite hardy, and will grow in any common garden soil; and they are all increased by offsets. They may be left in the ground several years without sustaining any injury; the only care necessary in their culture being not to shorten or cut off the leaves after the plant has flowered, but to leave them on till they wither naturally, as their assistance is necessary to mature the new bulb, which forms every year in the place of the old one. It is the more necessary to attend to this, as many gardeners, from a mistaken idea

of neatness, cut off the leaves of the Narcissi as soon as the flowers have faded, and in this way first enfeeble, and finally kill the plants.

NASTURTIIUM.—See TROPÆOLUM.

NAVELWORT.—See COTYLEDON.

NECK of a plant.—The collar, collet, neck, or vital knot, is the point of junction from which spring the ascending stem and branches, and the descending roots. This point has been called the heart of the plant, because any injury done to it causes instant death.

NELUMBIIUM.—*Nymphaeaceæ*.—

The Indian Lotus, or Sacred Bean of India. A stove aquatic, generally with white or pale-pink flowers; rather difficult to flower in this country, as it requires great heat and abundance of room; the seeds, also, which are sent over from India, rarely vegetate. The seeds should be sown in rich loamy soil in the bottom of a large tub, which should be kept full of water while the plants are growing, but which may be allowed to become dry when the flowers have faded. The plants are increased by dividing the root, or by seeds. There are two West Indian Nelumbiums; one of which has pale-blue, and the other pale-yellow flowers. It must be observed, that the Nelumbium, or Indian Water-Lily, differs essentially from the Egyptian Water-Lily, which flowers freely in a stove aquarium.—See NYMPHÆA.

NEM'ESIA.—*Scrophulariæcæ*.—Free-flowering half hardy annuals, about nine inches high, allied to the Linarias. Flowers various coloured, pure white, blue, violet, or pale rose. Succeeds in any ordinary soil.

NEMOPA'NTHES.—*Celastineæ*, or *Aquifoliæcæ*.—The new name for *Ilex canadensis*.

NEMO'PHILA.—*Hydrophyllæcæ*.

—Beautiful little annual plants, natives of California, that require the usual treatment of similar plants.—See CALIFORNIAN ANNUALS and ANNUALS. The most beautiful species is probably the common blue kind, *N. insignis*; but there are four others, viz. *N. atomaria*, the flowers of which are white with black spots; *N. phacelioides*, the flowers of which are almost black; *N. maculata*, introduced in 1848, the flowers of which are white, with a dark purple spot on each petal; and *N. discoidalis*, with petals rich purplish-black edged with white.

NEP'ENTHES.—*Cytineæ*.—The Chinese Pitcher Plant. There are two species in common cultivation; one a native of China, and the other of Ceylon; both of them being marsh plants, and requiring the pot in which they grow to stand in a saucer full of water. *N. distillatoria* grows above eight feet high, and it shows a tendency to curl its tendrils round other plants, or any object within its reach, so as to support its pitchers, which are at the extremity of its tendrils. Both species should be grown in a peaty soil, and they both require the heat of a stove. Neither the flowers nor the fruit have the slightest beauty to recommend them. Some new Pitcher-plants, which are said to be distinct species, have been recently introduced.

NE'PETA.—*Labiataæ*.—Catmint. —Hardy herbaceous plants of no beauty, which grow freely in any common soil.

NERI'NE.—*Amaryllidæcæ*.—Showy bulbous-rooted plants, the type of which is the Guernsey Lily, and which are natives of the Cape of Good Hope, China, and Japan. The Guernsey Lily is a native of Japan, and the reason why it has obtained its English name is said

to be, that a ship laden with these bulbs and other plants from China, was wrecked on the coast of Guernsey; and that the bulbs being washed on shore, took root in the sandy soil of the beach, and flourished there so remarkably as to be supposed to be natives of the island. Whether this story be true or not, it is quite certain that for nearly two hundred years these bulbs have been cultivated in Guernsey with the greatest success, growing freely in the open air, and producing abundance of offsets every year, from which the English market is supplied. In England the bulbs are generally planted in spring, in pots of very sandy loam, and placed in some window or other situation where they will have plenty of light. They flower in September and October; and as soon as they have flowered, the bulbs are generally thrown away, as they are said never to flower well the second year. This is, however, entirely the fault of the grower; as, if they were planted in a well-drained sunny border in the open ground, and allowed to mature their new bulbs every year by the agency of their leaves, there is no doubt but they would live as long as any of the kinds of Narcissi, and flower as freely. The bulbs might be protected in winter by a layer of dead leaves, or litter from a cow-house; and the bed, which should be of light sandy soil, should be occasionally manured in spring by a layer of old cow-dung.

NERIUM. — *Apocynææ*. — The Oleander, or Rose Laurel. — There are three distinct species of Nerium, besides several varieties. The first of these is the common Oleander, a native of Italy, but which is generally kept in a greenhouse in England; the second, which is called

*N. Flavescens*, has yellow flowers; and the third, *N. odorum*, which is a native of India, is a stove plant. The greenhouse species and their varieties (to which may be added *N. splendens*, supposed to be a hybrid between *N. oleander* and *N. odorum*) all require a soil composed of one half loam, one quarter peat, and one quarter vegetable mould, or rotten dung; or, if this soil cannot be obtained, equal parts of peat, loam, and sand. They should be regularly watered every day; but as no water should ever be allowed to remain in a stagnant state about their roots, the pots in which they are grown should either have no saucers, or if they have, no water should be allowed to stand in them. The plants should also be repotted at least once every year, and the soil shaken out from the roots, as they throw out a great deal of excrementitious matter, which poisons the soil in which they grow. This repotting should take place in spring; and, after it has been performed, the plants should be watered and set in the shade for a day or two. As soon as they begin to grow they should have plenty of light and air, and they should be regularly watered twice a day. Thus treated, the Oleander will grow rapidly, and throw out such large bunches of flowers as to form a truly splendid object. The stove species is generally grown in rather a moist heat; but it may be removed to the greenhouse, or even to the open air, during the hottest months of summer, if care be taken to water its roots twice a day, and syringe it every evening overhead.

NEW ZEALAND TEA. — *Leptospermum scoparium*.

NICA'NDRA. — *Solanæææ*. — The Alkekengi, or Kite-flower, a strong and vigorous annual, growing five or

six feet high, and throwing out numerous branches. The flowers are blue, and the fruit is in an inflated capsule, like that of the Bladder-nut or Winter-Cherry. It is a native of Peru, and its seeds should be sown in March or April, in a shrubby or border, where the plants may have plenty of room, the seeds being put into the ground singly, and at least three feet apart.

NICOTIANA.—*Solanææ*.—The Tobacco.—All the different kinds of Tobacco have showy flowers; but the handsomest species are *N. Tabacum*, the Virginian or common Tobacco, *N. noctiflora*, *N. multivalvis*, and *N. longiflora*. All these are annuals, and their seeds should be raised on a slight hotbed or warm border; and the plants, when in their second pair of leaves, should be transplanted to a bed of light rich soil, where they should be planted three feet apart every way. While the plants are young, the joints of the leaves should be frequently examined, in search of a caterpillar which is frequently found there, and which, if not removed, will eat off the points of the shoots, and consequently destroy the beauty of the plant. *N. rustica*, the common, or English Tobacco, the leaves of which are generally used for making tobacco-water, &c., should never be grown in a garden, as the flowers are of a dirty greenish-yellow, and the whole plant is covered with clammy hairs, extremely disagreeable to the touch. It may, however, be very usefully employed in gardens for the destruction of the green-fly, and for this purpose it may be grown in any out-of-the-way spot, the leaves and stalks dried, moistened, and packed up for use when again sufficiently dry. The powder sprinkled on the moistened

foliage will effectually destroy the green-fly and other insects.

NIEREMBERGIA.—*Solanææ*.—There are several species of Nierembergia, all natives of South America. *N. gracilis* is a pretty little half-hardy plant, with white flowers veined with lilac. Its slender, very graceful habit renders it well adapted for pots, borders, small beds, or suspended vases. It should be sown in gentle heat, pricked out in pots or boxes, and planted out in warm soil in May; or it may be sown in August, and potted off in September for the greenhouse and conservatory. It may also be propagated by cuttings on a hot-bed.

NIGELLA.—*Ranunculææ*.—The Fennel-flower, or Devil in a Bush.—Annual plants, with showy flowers, which are, however, almost hidden by their leafy involucre. *N. hispánica* is the handsomest species. They only require sowing in March or April in the open border; or they may be sown in autumn, as they will stand the winter without protection, and will thus be ready to flower early in summer.

NIGHTSHADE.—See SOLANUM.

NISSOLIA.—*Legumindææ*.—The Grass Vetch.—A rare British plant, with grass-like leaves and bright crimson single flowers, which looks very well on rock-work, where it can be kept moist.

NITRARIA.—*Ficoideæ*.—Low shrubs with white flowers, which are very hardy, and will grow well in situations exposed to the sea. In gardens, the ground in which they grow should be occasionally watered with water in which saltpetre has been dissolved.

NITRATE OF SODA.—This substance, which is found in great abundance as a natural production of the

earth in South America, is a very powerful manure; but it must be applied carefully, or it will make the leaves look brown and shrivelled. It should always be mixed well with the soil in which plants are to be placed, and not laid on the surface of soil in which plants are already growing. When it produces its proper effect, it gives great vigour to the plants, and renders the leaves of an intensely deep green.

**NOISSETTE ROSE.**—Roses which bear their flowers in bunches, and which were named from a nurseryman of the name of Noisette, in Paris, who raised the first from seed of the common China.—For the culture, see Ro'sa.

**NOLA'NA.**—*Nolánaceæ*.—Trailing annual plants, with pretty blue flowers, that only require sowing in March in the open border. *N. atriplicifolia*, the handsomest species, strongly resembles the minor *Convólulus*. Suitable for borders, hanging baskets, and rockwork.

**NOLITA'NGERE, or NOLI-ME-TA'NGERE.**—See IMPA'TIENS.

**NORFOLK ISLAND PINE.**—*Araucária excelsa*.—One of the largest trees in the world in its native country, but which can only be grown of small size in England, from its requiring protection during winter.

**NOTHOLÆ'NA.**—*Filices*.—A beautiful genus of ferns, with cordate leaves, from Mexico; which will grow in any cool greenhouse or fernery.

**NU'PHAR.**—*Nymphædæcæ*.—The yellow Water-Lily.—A British plant, common in stagnant water. The popular name is Brandy Bottle, from the flowers smelling like brandy. They look very well in ponds, or even cisterns, where they will grow freely if the seeds are sown in a layer of loam at the bottom. The

plants may also be increased by division.

**NUTTA'LLIA.**—*Malvæcæ*.—Beautiful poppy-like perennial plants, which may be planted out in summer, but which must be protected during winter in a frame or greenhouse. They should be grown in light rich soil, consisting principally of vegetable mould, with a little loam; and when in flower, they are very beautiful.

**NYOTA'NTHEE.**—*Jasminæcæ*.—The Indian Jasmine. This plant, which is generally grown in a stove in England, gives out its odour only by night, and is the plant alluded to by Moore in the following well-known lines:—

“The timid Jasmine buds, that keep  
Their odour in themselves all day;  
But, when the sunlight dies away,  
Let the delicious fragrance out  
To every breeze that roams about.”

The plants should be grown in loam and peat, and would probably succeed in a greenhouse, as it is found that they do not flower well if they are kept too hot.

**NYCTER'NIA.**—*Scrophulariæcæ*.—*N. Selaginoides* is a small, neat, half hardy annual, about four inches high, covered with star-like white or pink flowers, admirably adapted for edgings, small beds, baskets, and rockwork, or pots. Sow in pots in heat in March, and plant out in May in light rich soil.

**NYMPHÆ'A.**—*Nymphædæcæ*.—The Water Lily.—One species of this beautiful plant grows wild in England; but there are others which must be grown in the aquarium of a hothouse to induce them to flower in England. They should be grown in a rich loamy soil, and kept in the warmest part of the stove. Among the Eastern kinds, perhaps the most interesting are the blue Lotus, *N.*

*cærulea*, and the crimson lily of India, *N. rubra*. *N. dentata* is very handsome, and *N. pygmæa* is valuable for the small size of its flowers, and for being almost hardy. *N. elegans* is a Mexican species, with pale violet, sweet-scented flowers, and *N. scutifolia*, the largest blue-flowered water-lily known, is from the Cape of Good Hope.

**O**BELISCARIA.—*Compositæ*.—

Hardy perennials from Texas.

*O. pulcherrima* grows about two feet high, has rich crimson flowers, the petals edged with yellow; very showy. Any ordinary soil.

*O'Cymum*.—*Labiata*.—Basil.

Some of the East Indian perennial species are ornamental, and worth cultivating in the stove, where they should be grown in sandy loam.

*ODONTOGLOSSUM*.—*Orchidaceæ*.

—A splendid genus of Mexican epiphytes, requiring the usual treatment of similar plants.—See ORCHIDEOUS EPIPHYTES.

*ENOTHE'RA*.—*Onagraceæ*.—

The Evening Primrose.—Perennial, biennial, and annual plants, with large flowers. The yellow and white-flowering kinds, which are the true Evening Primroses, are now the only ones left in the genus, the purple-flowered ones having been removed to the genus *GODETIA*. The Evening Primroses have the peculiarity of only opening their flowers in an evening, or when the sun is overcast; as, contrary to the habits of most other flowers, they seem unable to bear much light. They are all of the easiest culture, and will grow in any common garden-soil, without any other care than occasionally taking up and replanting the perennial kinds, and sowing the annual and biennial ones every year in March or April. Of the biennial kinds,

*Æ. nocturna*, and *Æ. villosa*, both natives of the Cape of Good Hope, are rather tender; and of the perennials, *Æ. rosea*, *Æ. cæspitosa*, and *Æ. anisobloba*, require a slight protection during winter. *Æ. acutis*, which is a native of Chili, though a common border flower, should have a flower-pot or hand-glass turned over it in severe frosts; *Æ. cæspitosa* and *Æ. anisobloba*, both splendid plants, should also be protected during winter, particularly from heavy rains, as they are very apt to damp off if they are exposed to too much moisture. Paxton recommends removing the damp soil from the roots of these plants when growing in the open ground in October, and after replacing it with dry soil, covering the plant with dry saw-dust, and setting a flower-pot over it, the hole in the bottom having been first stopped to keep out the snow and rain. In this state it should remain till March, when the sawdust should be removed, and the plant covered with a hand glass till it can bear exposure to the cold. Both kinds should be grown in a mixture of peat and loam; and both are propagated by dividing the root into pieces about an inch and a half long in autumn, and planting them. *Æ. Lamarckiana* is a hardy annual or biennial, three or four feet high with splendid bright yellow flowers, upwards of three inches across. Sow in the open ground in April.

OFFSETS are a natural means by which plants propagate themselves. In bulbs, the offsets are small bulbs which form by the side of the principal one, from which they should be broken off when the bulbs are taken up and replanted. In shrubs and perennial plants, the offsets either spring from the collar of the old plant, or from an underground stem;

and in both cases, as they are provided with roots of their own, though they draw a part of their support from the main stem, they only require dividing and replanting to form new plants.

OILED PAPER, calico, or silk, is often used as a substitute for glass in hotbed frames, for raising seeds or striking cuttings; and it is peculiarly adapted for the latter purpose, as it radiates the enclosed heat more slowly than glass does.

OLD MAN'S BEARD.—See GEROPOGON.

OLEANDER.—See NER'IUM.

ONCIDIUM. — *Orchidaceæ*. — Well-known orchideous plants, with very curious flowers. *O. papilio*, the Butterfly-plant, is certainly as much like a butterfly as it is possible to imagine a flower to be; and as it is borne on a long slender stem, which quivers with every breeze, it forms no bad representation of a beautiful insect fluttering over the neighbouring flowers. *O. altissimum* has a spike of flowers which is sometimes ten or twelve feet in length. All the kinds are very handsome, and some of them are splendid. They are all natives of South America, Mexico, and the West Indies; and as they will thrive in a much lower temperature than the Dendrobiums, and some of the other *Orchidaceæ*, they are very suitable for a small hot-house. All the kinds may be grown in pots, though some of the smallest appear to thrive most tied to pieces of wood and hung from the rafters. The soil should be turfy peat, mixed with sphagnum and potsherds. The pots should be large, and filled a third of their depth with broken potsherds, rather larger than those mixed with the peat. Great care should be taken in re-potting any of the *Oncidiums*, as

the roots will be found to adhere strongly to the sides of the old pot, and thus are easily broken. To prevent this, the plants should be shifted as seldom as possible; and when shifting is inevitable, they should be kept without water for several days beforehand, so that the plants may be in a flagging and feeble state, and their roots have less power of adhesion. All the *Oncidiums* should be regularly watered during the growing season, but afterwards very sparingly, especially in winter.

The following are some of the more commonly grown, and finest kinds of *Oncidium*: *O. flexuosum*, a very beautiful species, with a long, much-branched panicle of bright-yellow flowers; *O. crispum*, the flowers of which are of a copper colour, and much undulated or curled; *O. altissimum*, with a very long flower-stem, somewhat branched, and with yellow flowers spotted with brown; *O. papilio*, the flowers of which are borne singly, on long, simple, and naked stalks; and there are also some dwarf species, such as *O. triquetrum*, and *O. pulchellum*, a very beautiful species, with white flowers tinged with pink; *O. triquetrum* has also white flowers blotched with purple. *O. Barkerii* is dwarf, with large flowers, rich brown, transversely barred with yellow, and is produced in the winter; *O. Lanceanum*, bright yellow, spotted with crimson, very fragrant; *O. raniferum* should be grown on a piece of wood hung from the rafters; and *O. papilio*, and some of the other species, may be treated in the same manner.

ONOBRYCHIS. — *Leguminosæ*. — Saintfoin. Hardy perennial plants, some of the species of which are pretty and suitable for rock-work.

ONO'NIS. — *Leguminosæ*. — The Rest Harrow. — Little herbaceous and shrubby plants, some of which are natives of Britain, and which have generally yellow or pink flowers. Most of the kinds should be grown in peat, or in very sandy loam; and they are all suitable for rock-work. Some of the kinds from the south of Europe are rather tender; but they will all live in the open air, if they have a slight protection during hard frosts.

OPERA GIRLS. — See MANTISIA.

O'PHRYS. — *Orchidææ*. — Dwarf plants belonging to the terrestrial Orchidææ, with very curious flowers, which always look as if an insect were nestling in them. One of these, *O. aptifera*, looks as though a bee were buried in the flower; another, *O. aranifera*, has the lip in the form of a spider; and in the third, *O. muscifera*, the whole flower resembles a fly. — For the culture of these plants, see O'RHIS.

OPUN'TIA. — *Cactææ*. — The Prickly Pear. — This is the hardest of all the genera of Cacti, as there are some species which will live in the open ground in England, with only a slight protection from frost during winter; and they grow freely in the south of Europe. The hardest kind is *Opuntia vulgaris*, of which there are forests on Mount Etna, growing in chinks and crevices in the rocks, where there appears scarcely soil enough to contain their roots. They are equally abundant in the rocky districts of Spain, where they grow so vigorously and so apparently in a state of nature, that a doubt has arisen whether they are not natives of Spain transported at a very early period to South America, instead of being, as is generally supposed, natives of Peru, introduced by the first Spaniards who visited that country, into Spain. The fruit,

which we call the Prickly Pear, but which is called Tuna in Spain, is so great a favourite in that country, that Karwinski tells us, in September hundreds of vendors sit in the streets of the Spanish towns, busily employed in stripping the fruit off the branches which have been gathered loaded with it; their hands and arms being fearfully swollen with the spines, which they have not leisure to avoid, so great is the impatience of the purchasers to obtain the fruit. He adds that many Spaniards will eat above a hundred Prickly Pears in one day; and that some indulge to such an excess, that they bring on cholera, which is often attended by death, especially if the sufferer attempts to mitigate his disease by drinking brandy. The cochineal insect is bred on *Opuntia cochiniifera*, or the Nopal tree, a native of Mexico, and much more tender than the common kind. A white woolly substance appears on the leaf-like stems of the tree, like the American blight on Apple-trees; and this substance conceals the female cochineal insect, which is a kind of coccus or scale, resembling that on the Pine-apple and the Vine. The male insect is winged, and it is only the female that produces the dye. When fully grown, the insects are brushed off the plant with the tail of a squirrel or deer; and they are killed by drying them in ovens, which makes them curl up, and in this state they are ready for sale. It is on account of the value attached to the cochineal as an article of commerce, that a branch of the Nopal tree is introduced into the arms of the republic of Mexico.

All the kinds of *Opuntia* require abundance of dry air and intense solar light, and on this account they do best in the open air on a sunny bank sheltered by a wall facing the



south. In a stove, especially if other plants be grown in it requiring a moist temperature, the *Opuntias* never produce either flowers or fruit; and, indeed, often die without any apparent cause. It is hardly possible for any situation to be too hot and dry for these plants, as, like all the plants destined to live in burning sands, they are furnished with very few stomata or breathing pores, whilst they have abundant organs of absorption to draw as much moisture as possible from the soil; and thus they are enabled to sustain heat that would dry up and wither any plants not succulent. On the other hand these very qualities render them easily injured by a superabundance of moisture, as they have no means of getting rid of it; and it soon occasions them to damp off, or, in other words, to rot. The best soil to grow *Opuntias* in, is a mixture of very sandy loam with broken bricks and rubbish from old walls; they require but little water at any season except when going into flower, and then less than any of the other kinds of *Cacti*. They are propagated by cuttings, which must be taken off at a joint and laid on a shelf for two or three days to dry before planting, in order that the superfluous moisture may escape. When planted they should not be watered; and when young plants are raised from seed, they also should not be watered when they are transplanted. — See *CACTUS*.

**ORANGERY.**—A house intended only for Orange trees may be opaque at the back, and even the roof, with lights only in front, provided the plants be set out during summer. In fact, so that the plants are preserved from the frost, they will do with scarcely any light during winter; and in many parts of the Continent they are kept in a cellar.

**ORANGE THORN.**—*Citriobatus*.—Spinous shrubs, belonging to *Pittosporaceæ*, natives of Port Jackson and other parts of Australia, which, from bearing small orange-coloured fruit, are called Orange Thorn by the colonists.

**ORANGE TREE.**—See *CRÆTUS*.

**ORCHIDACEÆ, TERRESTRIAL.**—The terrestrial *Orchidaceæ* are, as their names import, those plants belonging to this extensive order which grow in the ground, in contradistinction to the *Epiphytes*, or those which grow with their roots exposed to the air. The terrestrial *Orchidaceæ* are of four kinds, viz. those from the tropics, which require a stove in England; those from the Cape of Good Hope, which require a greenhouse; those from the South of Europe, which only need a slight protection during winter; and the hardy kinds, most of which are natives of Great Britain. The stove species require nearly the same treatment as the *Epiphytes* (see *ORCHIDEOUS EPIPHYTES*); and the greenhouse species only differ from other greenhouse plants in requiring particular care to be paid to their drainage. For this purpose the pots should be filled one quarter of their depth with broken potsherds or cinders, and the soil should consist of turfy peat broken into pieces, and sand mixed with about a third of vegetable mould. The half-hardy and hardy kinds may be grown either in pots or in the open ground. — See *ORCHIS*.

**ORCHIDEOUS EPIPHYTES.**—The plants thus designated should, properly speaking, only be those which in their native countries are found hanging from the branches of trees, with their roots exposed to the air, as these only can be called air-plants. It is, however, very difficult to draw a line of demarcation, as regards

culture, between these plants and the terrestrial Orchideæ of the tropics, as several of the Epiphytes may be grown to great perfection in pots; and others, though in a state of cultivation they can only be grown well on branches of trees, are found growing naturally on exposed rocks. All the true Epiphytes, which in their wild state are found with their roots hanging down in the air, grow in dense forests, where shade, moisture, and excessive heat, seem essential to their existence; and these plants in a state of culture should generally be grown in baskets, either of earthenware or china, or in husks of Cocoa-nuts half filled with moss, or tied on pieces of wood, hung up from the rafters of a damp stove, and in the shade. This rule, however, though apparently so reasonable, is not without its exceptions in practice; probably because, as it is impossible to imitate the natural climate of the plants exactly, their wants are changed by the different situation in which they are placed. Thus, the West Indian *Dendrobiums* and *Epidendrums*, both of which in their natural state are generally found on the branches of trees, in a state of culture thrive best potted in turfy peat or chopped moss, left sufficiently loose to allow the points of the roots to protrude occasionally, and to hang down over the side of the pot. The flowers of the *Dendrobiums* are generally produced in long pendant racemes; but those of the *Epidendrums* are erect, like those of the *Oncidium*s. Most of the East Indian species should always be grown on wood, particularly *Rennathëra coccinea*, and all kinds of *Vanda* and *Sarcanthus*; and the East Indian *Dendrobium*s, and the different species of *Eria*. The species of the genera *Aérides* and *Calogyne*, however, though both

are always found on trees in their native country, may, in England, be grown in pots, in turfy loam or chopped moss, or in baskets of moss. The *Stanhopeas* and *Catasetums* should be grown in baskets of moss, or in pots hung from the rafters of the house, as their flowers proceed from the roots, and hang downward; but the *Cattleyas*, which have erect flower-stems, are always grown in pots. Where it is not convenient to have pots hanging from the rafters, the *Stanhopeas* must have a pile of pieces of turfy peat raised at least six inches above the rim of the pot, and the pseudo-bulbs must be placed on the top; as, unless this is done, the flower-stem, when protruded from the root, will bury itself in the earth contained in the pot, and the flowers will be unable to expand, though they will easily make their way through the loose pieces of turf. Where this mode of potting is adopted, slender pieces of wood are generally passed at regular distances through the pile of turf, to keep the pieces in their place. The *Catasetums* grow in open parts of the woods of the tropical regions of South America, and one species is the celebrated Wourali Vine. They all require great heat and moisture, and when grown on wood it should be on that of soft-barked trees.

Various expedients have been devised to produce the shade supposed necessary for some of the Orchideous plants. The Orchideous-house has been in some cases glazed with dark-green or brownish glass, double sashes have been used, and creeping plants trained over the roof. None of these plans, however, have proved successful; as, though the plants thus treated have grown rapidly, it has been to produce leaves rather than flowers. Whether it be that

the plants in an artificial state require more light than in their native woods, or whether the British sun is so much feeble than that they have been accustomed to, as to render shading unnecessary, it is certain that the Orchideous Epiphytes in England require plenty of light, and that they never flower well if kept in comparative darkness.

Another point that has puzzled cultivators is to find out what kind of wood is most suitable for those kinds that are to be grown on hanging branches. Mr. Henchman, who collected Orchideæ on the Spanish Main, asserts that he never found an Orchideous plant on a dead tree, whether standing or fallen, though he found many species of *Oncidium*, *Catasetum*, &c., growing on the ground, as though they had been accidentally dislodged from the trees on which they had grown. He even observed that the colour of the *Oncidium papilio* was much darker on the ground than it was in its natural situation, on the branches of a lofty tree. From his finding no Orchideæ on dead trees, he was led to suppose that the plants draw some kind of nourishment from the trees on which they live; and he also remarked that rough and soft-barked trees were their favourite abodes. He found *Oncidium papilio*, and a kind of Schomburgkia, called by the Indians the Spread Eagle, on the upper branches of trees which were exposed to the air, and at least from twenty to thirty feet from the ground, and *O. lividum*, and the *Catasetums*, on branches fully exposed to the sun; while the *Gongoras*, *Rodriguezias*, and *Corysanthes* were on the soft and young wood, not more than seven or eight feet from the ground, in the most dense and

thickest parts of the forest. These hints, and the observations of other collectors, have been of great service to cultivators; and, in consequence, they generally grow their Epiphytes on rough-barked trees (that of the *Robinia Pseud-Acacia*, Cobbett's Locust, for example), and some growers prefer forked portions of plum or apple trees, half covering them with moss to retain the moisture, and to imitate the soft woolly bark of some of the trees of the tropics. These logs are hung from nails in the rafters, or from rods suspended across the roof; and the pseudo-bulbs, or rhizomas, of the plants are bound on them with fine wire, and covered with sphagnum or some other kind of moss. Messrs. Loddiges use living plants of *Lycopodium stoloniferum*, which have the advantage of looking better, as well as of retaining more moisture than any kind of dead moss. Mr. Beaton made a ball of moss, which he suspended in the hollow formed by the branches of a three-forked stick, which he hung up from the rafters till the plants were established; and then he placed the stick in a pot, taking care that the length of the stick below the fork was sufficient to hold up the ball of moss with the plant attached, just above the rim of the pot—after which he filled up the pot with pieces of turfy peat. When the Orchideous plants are grown in wire baskets, the baskets should be made of copper wire, or, if of iron, they should be painted with anti-corrosive paint. They should be formed shallow, and wide at the top, with the bars sufficiently apart to allow the flower-stems of the *Stanhopeas*, and other plants sending out their flower-stems from their roots, to push their way through, and to hang down between

the bars. For this reason, baskets which are narrow at the base, are not suitable for any Orchideous plants but those that send up their flower-stems from their pseudobulbs. The baskets for Stanhopeas, and other root-flowering plants, should be from three to six inches deep, and from six to ten inches wide; and they should be filled with moss, or with strips of turf two or three inches wide, and placed on end round the inside of the basket, so as to stand nearly upright, with a large flat piece in the centre. The plant should be placed in the middle, and the basket filled up with broken pieces of turf, mixed with crocks or cinders, if the plant be very delicate, and easily affected with too much moisture. These baskets are very convenient for Orchideous plants, as they may either be suspended from the roof, or placed on an inverted pot; or if the plant requires bottom-heat, the basket may be placed on the surface of a pot plunged in the hot-bed. The basket also looks better and more elegant than a flower-pot when the plant is in flower, and is brought into a drawing-room. When Orchideous plants arrive from abroad, Mr. Beaton first put them into water; and after having been thoroughly washed, he put them into a heap, covered with a damp mat, where they remained for several days; after which he planted them in baskets, or tied them on moss supported by a forked stick, as above described.

ORCHIDEOUS HOUSE. — A hot-house intended for growing tropical Orchideous Epiphytes, and furnished with contrivances for keeping the interior moist. The roof is generally glazed with ground or green glass, to diminish the light, as the Orchideous Epiphytes, in

their native forests, always grow in the shade.

O'RHIS. — *Orchidaceæ*. — Most of the species of the genus *Orchis* are natives of Europe, and a great number of them are found wild in Britain. With respect to culture, they may be divided into two classes: those which grow naturally in peat or heath-mould, such as *O. maculata*, *O. morio*, *O. mascula*, &c.; and those which grow in dry chalky soils, such as *O. simia*, *O. militaris*, *O. fusca*, *O. tephrosanthos*, and *O. ustulata*. In general, little can be done in the way of propagating Orchises, excepting by seed; but they may be taken up in their native localities when in flower, with a ball of earth about three inches square to each, and being planted in suitable soil in an open situation in the garden, they will live and flower for several years. Seeds, if collected when ripe, and sown immediately, will come up freely; and if the soil and situation be suitable, they will flower freely the second or the third year. The same observations will apply to *O'phrys*, *Herminium*, *A'ceras*, *Goodyera*, *Platanthera*, *Gymnadenia*, and several other genera formerly included in the genus *Orchis*. Most of the British Orchises grow well in pots, and they may be forced as easily as the common Hyacinth. The kinds of *Orchis* which bear flowers resembling insects, are now included in the genus *O'PHRYS*.

ORDER. — The necessity of order is strongly evinced in a flower-garden, as the plants in it lose half their beauty unless they are placed according to some regular plan or order of arrangement: thus they may be either in masses of one colour, or of one kind; or they may be arranged according to

size, or according to some botanical system, at pleasure. But whatever mode of arrangement may be adopted, it will be found that not only the interest excited by the garden, but its beauty will be greatly increased by some regular order being followed throughout.

In a botanical point of view, the word Order signifies a number of genera, which coincide in several important particulars. As for example, according to the Natural System, the order Cruciferae includes all the plants that have the petals of their flowers disposed so as to resemble a Greek cross, and, according to the Linnæan system, the order Trigynia includes all the plants, the flowers of which have three styles, &c.

ORIGANUM.—*Labiatae*.—Marjoram.—*O. vulgare*, the common Marjoram, is plentiful on chalky soils in various parts of England; and it may be planted in patches in gardens or shrubberies where bees are kept, for the fragrance of the flowers, and the delight which the bees appear to have in them. The sweet Marjoram, *O. Majorana*, a native of Portugal, is cultivated in England as a pot-herb; and for the Hope Marjoram, or Dittany of Crete, *O. Dictamnus*, see DITTANY OF CRETE.

ORNITHOGALUM.—*Asphodelææ*.—The Star of Bethlehem.—Bulbous plants with white star-like flowers, some of which are frequently kept in the greenhouse, but all of which may be grown in the open ground if the bulbs are planted in a tolerably dry soil, four or six inches deep. Some of the handsomest kinds are *O. pyramiddle*, a native of Spain, the unopened flower-stalks of which are sold in the market at Bath and other places in the West of England for the table, under the name of

Prussian Asparagus; *O. latifolium*, a native of Egypt; and *O. caudatum*, from the Cape of Good Hope. The latter two are generally considered greenhouse plants, but they only require protection from severe frosts. *O. umbellatum*, a native of France, is quite hardy; and also *O. arabicum*.

OROBANCHÆ.—*Orobanchææ*.—Broom-rape.—Parasitic British plants growing on the roots of other plants, which they destroy. They have erect stems, somewhat scaly and bulbous at the base, and terminating in a spike of rather large purplish or brownish flowers. They are almost incapable of culture, as their seeds will lie dormant in the soil for years, till they meet with a plant to the roots of which they can attach themselves; but if it should be wished to grow them, a few seeds of *O. major* may be sown on the roots of any kind of broom or furze, and of *O. caryophyllacææ* on the roots of any kind of bramble or of *Galium Mollugo*, and they will probably germinate. *O. rubra*, which is very fragrant, may in the same manner be sown on the roots of wild thyme; and *O. elatior* on those of the *Centaurea Scabidosa*, or greater Knap-weed.

O'ROBUS.—*Leguminosææ*.—The Bitter Vetch.—Pea-flowered, perennial plants, some of which are very ornamental; natives of Europe and North America, which should be grown in peat and loam, and are increased by dividing the root.

ORYZA.—*Graminææ*.—Rice.—This plant is occasionally grown as an object of curiosity in England, though the climate is not hot enough to ripen the grain. It is a marsh plant, and requires to have its roots constantly supplied with water at a very high temperature.

OSAGE ORANGE.—See MACLU'RA.

OSBECKIA. — *Melastomaceæ*. — Handsome stove plants, remarkable for their showy flowers, and strongly ribbed leaves. They should be grown in peat, mixed with one-third of sandy loam, and kept moist. They are propagated by cuttings.

OSMU'NDA. — *Filices*. — The Flowering Fern. This is by far the handsomest of the Fern family. A native of Britain, which produces a fine effect in a shrubbery, or among trees; and which should be grown in peat, or other light soil, and kept moist.

OSY'RIS. — *Osyrideæ*. — The Poet's Cassia. — A pretty little shrub, with white flowers, a native of the South of Europe; which should be grown in loam and peat, and which is propagated by cuttings.

OURISIA. — *Scrophulariaceæ*. — A beautiful hardy perennial, with erect scapes bearing drooping scarlet tubular flowers. Introduced from Chili by Messrs. Veitch.

OUVIRA'NDRA. — *Juncaginaceæ*. — A most remarkable aquatic plant, the leaves of which are like open net-work, consisting only of the veins, without any of the fleshy part. A native of Madagascar.

O'XALIS. — *Oxalidæ*. — Wood Sorrel. — Mostly perennial and tuberous rooted plants, from the Cape of Good Hope; but some few of which are natives of Britain, and others of Mexico and other parts of South America. They have showy flowers, and are easily cultivated in sandy peat kept moist. All the Cape species require protection during winter, and are generally grown in pots.

PACHYPHY'TUM. — *Crassulaceæ*. — A very curious and ornamental plant, with pale bluish succulent leaves, and dark red flowers,

with bright yellow stamens. There is a most striking contrast between those bright-looking flowers and the glaucous hue of the large calyx and bracts, which surround them; they cover the stems, and look like spikes of flowers. The plant is a native of Mexico, and requires a greenhouse in this country.

PÆONIA. — *Ranunculaceæ*. — The herbaceous species are well-known showy flowers, which thrive in deep sandy soil, and are propagated by division; and the suffrutescent or shrubby kinds, of which there are several varieties, thrive in similar soil, and are propagated by laying down the shoots, cutting behind each bud, and covering them throughout their whole length by an inch or two of sand or sandy soil. Each bud thus treated will throw up a shoot and emit roots, and after a year may be cut off so as to form a distinct plant. The tree Pæony, as it is called, is quite hardy in the climate of London; but as the flowers and leaves come out early, they are liable to be injured by spring frosts, and it is therefore desirable to protect them by a horizontal covering a foot or two above the plant, which, by reflecting back the heat radiated from the soil, keeps up such a temperature as prevents the plant from freezing. There are many very handsome varieties of the tree Pæony, both double and single, but that which is most common is the *P. Moultan papaveracea*, a single variety in which the petals are large and white, with a dark purple mark at the base. Both the herbaceous and shrubby Pæonies seed freely; and as by fecundating the flowers of one species with those of the others, new varieties may be easily procured, raising seedling Pæonies forms a source of interest for amateurs. For some

account of the newly introduced kinds of the Pæony, see MOU'TAN.

**PALAVIA.**—*Malvaceæ*.—An elegant annual plant, generally raised on a hotbed, and planted out in May; but which may be sown in the open border in April.

**PALIURUS.**—*Rhamnaceæ*.—Christ's Thorn.—A curiously bent thorny shrub, with very oddly-shaped flat fruit, which has given rise to the French name for the plant of *portechapeau*. It is a native of Asia, and will grow in any common garden soil.

**PANCRA'TIUM.**—*Amaryllidaceæ*.—The Sea Daffodil.—Splendid lily-like bulbous-rooted plants, some of which require a stove, and others the greenhouse. They should be grown in light loam and vegetable mould; and should be allowed a season of rest, by being kept without water when not in a growing state.

**PANSY.**—See HEART'S-EASE.

**PAPAVER.**—*Papaveraceæ*.—The Poppy.—Showy annual and perennial plants, which will grow in any common garden-soil; and which, being quite hardy, only require the common treatment of their respective kinds.

**PAPYRUS.**—*Cyperaceæ*.—An interesting marsh plant, which requires a stove in England, and which is worth growing, from its pith having been the only paper used by the ancients. It should be planted in loam at the bottom of a tub or cistern; or it may be grown in an aquarium.

**PARASITES** are plants which root into other plants and differ from epiphytes in that circumstance, the latter only growing on the outside of the branches of trees, and deriving nourishment partly from the decay of the outer bark, and partly from the moisture which its porous corky nature enables it to retain. The

only ligneous parasite which is grown in this country is the Mistletoe, which is propagated by bruising the berries, and causing them to adhere to the bark (see VISCOUM), and the chief epiphytes are some of the stove Orchidaceæ. The British herbaceous parasites are *Cuscuta Epithymum* and *C. europæa* upon Clover and Hops, and *Orobánche mājor* and *Lathræa Squamaria* on the roots of forest-trees. The hardy epiphytes of Britain are the Lichens and Mosses, which grow on the bark of old trees, or stunted young trees in moist shady situations, and some species of Ferns, such as *Polypodium vulgare*, which is often found growing on the bark of old pollards in the central districts of England, and in great abundance on trees in the moist climates of Devonshire, Lancashire, Cumberland, &c. It is very abundant on old Oaks in the grounds of some of the villas, on the banks of the lake of Ambleside. Almost the only herbaceous parasite which can be conveniently cultivated in gardens is the *Cuscuta europæa*, the seeds of which, when gathered on Heaths or in Hop-grounds, may be sown at the roots of almost any herbaceous plant in gardens, when they will spring up, twine round it, and perhaps ultimately strangle it. *Cuscuta verrucosa* is sometimes grown in greenhouses on Geraniums, and is noted for the fragrance of its blossoms.—(See CUSCUTA.) *Orobánche mājor* is very common in clover fields in Norfolk, and greatly injures the crops of that valuable forage plant. It also grows on the roots of Broom and Furze.—See OROBANCHÆ.

**PARASOL ACACIA.**—*Robinia umbraculifera*.

**PARTERRE.**—The French term for what in England is called a flower-garden, but which in France

in former times, when the word was originated, was most frequently a figure formed on the surface of the ground by turf, box, and gravel or sand, with occasional flowers or low shrubs. In these parterres, flowers and shrubs were altogether secondary objects, the main features being the compartments of turf and the curious scroll-work of box. The French divided their parterres into three kinds: parterres of embroidery, which consisted chiefly of scroll-work or arabesque figures of box kept low by clipping; *parterres de compartiments*, which consisted chiefly of beds of turf of different forms, varied by small shrubs clipped into regular shapes; and *parterres anglais*, which consisted of turf in large masses, with beds of flowers surrounded by box. Parterres of embroidery are now rarely to be met with, either in France or England; they have been totally destroyed at Versailles and Fontainebleau; and in England, though we have old French gardens at Levens near the Lakes of Westmoreland, at Wroxton near Banbury, and other places, yet almost the only parterres of embroidery are those of long standing at Wentworth Castle, Yorkshire, and Holland House, Kensington, and the more recently formed ones at Wrest, Bedfordshire, and Trentham Hall, Staffordshire. Parterres of compartments among the French generally consisted of one square, round, or parallelogram plot of turf, in the centre, surrounded by a border of narrow beds planted with flowers and low shrubs, and these are at present common both in France and England. *Parterres anglais* may be considered as included in the parterres of compartments; because the French do not now cut up the ground into so many beds as

formerly, and they plant a great many more flowers than they did in the time of Le Nôtre. In all the French parterres of former times, and also in most of those imitated in England, the groundwork, or, in other words, the little walks on which the arabesques of box appeared to be planted, were of different-coloured sands, gravel, shells, powdered stones, or brick, so as to exhibit different colours in the same parterre; but that practice is now left off both on the Continent and in Britain. In a word, parterres are now assemblages of flowers in beds or groups, on a ground of either lawn or gravel; in the former case the beds are dug out of the lawn, and in the latter they are separated from the gravel by edgings of box or stone, or of some plant, or durable material. The shape of the beds in either case depends on the style of architecture of the house to which the parterre belongs, or on the taste and fancy of the owner. Whatever shapes are adopted, they are generally combined into a symmetrical figure; for when this is not the case, the collection of beds ceases to be a parterre, or a flower-garden, and can only be designated as a group or collection of groups on a lawn. Hence it is, that all parterres and regular flower-gardens ought to be separated from the scenery by which they are surrounded, by a line of demarcation, such as a low architectural wall, with a balustrade and piers and vases; a low evergreen hedge, a canal, a ridge of rock-work, a sunk fence with the sides of turf or of stone, a raised fence with the ridges and top of turf, or a raised terrace-walk of grass or gravel.

Fig. 37 will give an idea of a regular flower-garden; which may be made architectural by laying the



walks with flag-stones, and placing fountains and statues in the circles; and fig. 38 is a plan of the flower-garden at Dropmore, certainly one of the most beautiful in England. Other designs may easily be made

bed so as that each bed shall be a mass of one colour, and the other is to plant flowers of different colours in the same bed. It is almost needless to state that the former system is by far the best for general and striking effect; but as a parterre is frequently a kind of botanic garden, and as in this case it is desirable to




FIG. 37.—FLOWER GARDEN.

on paper, and transferred to the ground, by dividing the space to be laid out into squares with chalked strings, and making corresponding squares over the plan.

In planting parterres there are two different systems; one is to plant only one kind of flower in a




FIG. 38.—DROPMORE GARDEN.

keep all the species of a genus together, flowers of all colours must occasionally occur in the same bed. In general, botanical parterres should not be mixed with parterres for effect, because the one kind never fails greatly to injure the other.

In planting parterres for general effect, the colours should be arranged so that those which are adjoining

each other should be contrasts; and those which occupy corresponding parts of the same figure should be the same. For example, suppose a bed on one side of the centre to be planted with yellow flowers, the corresponding bed on the other side (the figure being symmetrical) should also be planted with the same kind of yellow flowers, for the sake of preserving the symmetry. Sometimes the corresponding bed of colours may be planted with a different species, having flowers of the same colour which appear at the same time, but in general this cannot be done successfully, partly on account of the different shades of colours, but chiefly because it is scarcely possible to get two plants of different species, even though they are of the same colour and flower at the same time, that will prove so exactly alike as to have the same aspect. The colours which contrast with one another are generally well known, particularly to ladies; such as blue and yellow, orange and purple, red and green, &c.; and in practice any two colours which do not contrast well naturally, may be brought together or near each other by the intervention of white, or of a very dark colour approaching to black. There are many low compact growing plants, with white flowers, very suitable for planting out in flower-beds, such as *A'rabis álvida*, or any of the white *Verbenas*; and *Lótus jacobæus* forms the nearest approach to black. *Nemóphila discoidalis* is also very nearly black. As the prevailing colour in garden scenery is green in all its different shades and mixtures, so the prevailing colour in parterres ought to be red, and all its various shades and mixtures. Next to red, yellow, orange, and all their various shades

and mixtures ought to prevail, as contrasting with the blue of the sky, and with that of water, should there be any near the flower-garden. In choosing the colour for any particular flower-garden, it is necessary to consider what colours are to be placed adjoining it; and in choosing the colour for plants to be placed in vases or pots, it is necessary to consider the background against which they are to be seen. For example, an elevated vase with the sky for a background, should never be planted with either blue or purple flowers; but orange or red flowers in such a vase will have an admirable effect. In botanic parterres, only one plant of a species or variety is planted; and that ought to be kept perfectly distinct from every other by a space an inch or two in width, being left all round it; but in parterres for effect, the whole surface of the bed ought to be covered with the same kind of flower, and no part of the soil should be seen. Hence, for this kind of parterre, low-growing plants and trailers, or creepers, such as *Nierembergias* and *Verbenas*, are most desirable; and free-flowering tall plants, such as *Petunias* and *Dahlias*, ought to be pegged down. One of the most useful plants for producing white in parterres of effect is the common *Petunia*, and for red the different kinds of scarlet *Pelargonium*, or *Verbena Melindres*.

The laying out and planting of parterres should always be attended to by the ladies of the place, because it requires a degree of taste and artistical feeling which is very seldom to be found among some gardeners to a sufficient extent; and which, indeed, can hardly be expected in many of them.

PASQUE FLOWER. — See ANEMONE.

PASSERINA.—*Thymelæa*.—Sparrow-wort.—Most of the species are Cape shrubs, which require a greenhouse in England, and should be grown in sandy peat; but one species, *P. hirsuta*, is a native of the South of Europe, with small yellow flowers. They are all more curious than beautiful.

PASSIFLO'RA. — *Passiflora*. — The Passion Flower.—The common Passion Flower, *Passiflora cærulea*, is a very ornamental climber, which will live in the open air in the climate of London, flowering abundantly, and ripening fruit every year. It requires a good and somewhat loamy soil; and where the soil is light and sandy, a pit two feet deep and two feet square should be dug out and filled with a mixture of loam and peat. This pit may appear large for a plant with such a slender root and stem as the Passion Flower, but it will not thrive unless plenty of room be allowed for its roots; and, on this account, only the dwarf species can be grown in a pot. There are several kinds of Passion Flower which require a greenhouse, and some very splendid ones that cannot be grown without a stove. Of the latter, the most beautiful is *P. Loudoni*, the flowers of which are of a most brilliant crimson. Nearly all the kinds ripen seed freely; and the fruit, which is a kind of berry, is eatable but insipid. All the kinds hybridise freely, and thus many new kinds may be raised. Some of these hybrids are very beautiful, particularly those raised from *P. racemosa*; and some of those raised between the stove kinds and *P. cærulea* are nearly hardy. *P. Neu-mani* is a very hardy and free-flowering species. They are all easily propagated by cuttings, which should be made of the young shoots, and

struck in sand, in heat, under a bell-glass.

PASSION FLOWER.—See PASSIFLO'RA.

PATERSON'IA. — *Iridea*. — A fibrous-rooted genus of very beautiful plants, natives of New Holland. They should be grown in sandy loam and peat, and increased by dividing the roots, or by seeds. They require a little protection during winter; and, on this account, they are generally grown in pots, and kept in a frame or greenhouse.

PAULO'WNIA. — *Scrophulariaceæ*. — A suffruticose tree which grows with great rapidity to the height of 30 ft. or 40 ft., and produces large racemes of beautiful shaded lilac flowers. The leaves are very large and handsome, and the whole bears considerable resemblance to a Catalpa. It is a native of Japan, and it has not yet flowered in England, though it has in the Jardin des Plantes in Paris. It only requires to be planted in a dry open situation, exposed to the sun. It is propagated by seeds, which it has ripened abundantly in France, and which should be raised on a hotbed; and it is also propagated very readily by cuttings of the roots. The name of the plant being a Russian word, it should be pronounced Paulófnia. It flowers well at Florence.

PA'VIA. — *Hippocastanææ*, or *Esculææ*.—The American Horse-chestnut or Buck-eye. — These plants differ from the Common Horse-chestnut in their fruit, which is in a smooth husk, while that of the Horse-chestnut is in a rough husk. They derive their American name of Buck-eye from the large brown spot on the side of the seed, the botanical name of which is the hilum. Several of the Pavias are shrubs, and one of them, *P. rubra*, is almost prostrate. They are all

very handsome, particularly the dark-red and yellow-flowered kinds, and *P. macrostachya*, which has long feathery white flowers. They will grow best in loamy soil; and they are all propagated either by seeds or layers, or by grafting or budding them on the common Horse-chestnut.

PEACH MYRTLE.—See HYPOCALY'MMA.

PEAT BOG consists entirely of vegetable matter decayed by being saturated with moisture, but which requires to be decomposed or mixed with some earthy matter to render it fit for vegetation. As it is the tannin which abounds in the liquid part of peat bog which prevents the decomposition of the vegetable fibre it contains, it is only necessary to drain it of its superabundant moisture to convert it into peat earth; in which state it is used in gardening for the growth of large American plants, such as Rhododendrons, &c., in the open ground. Heath-mould is peat mixed naturally or artificially with a large proportion of fine white sand; and in this state it is used in greenhouses for growing Heath, and other Cape and Australian shrubs, with fine hair-like roots in pots. When greenhouse shrubs are directed to be grown in peat, it is always understood to mean a mixture of peat and silver sand, and not black peat alone.

PEGS.—Pieces of forked stick (see fig. 39) used for keeping down plants that are wanted to cover a bed in a regular flower-garden, and for other similar purposes. When hooked sticks are not easily to be procured, bent wire or tin pegs are sometimes used, or even hair-pins. Some persons recommend the pins of whalebone.

PELARGONIUM.—See GERANIUM.

PELLITORY, COMMON.—*Pyrethrum Parthënum*.

PELLITORY OF SPAIN.—*Anthemis Pyrethrum*.—See ANTHEMIS.

PELO'RIA.—A curious variety of the common Toad-flax.—See LINARIA.



FIG. 39.—HOOKED STICK FOR PEGGING DOWN PLANTS IN FLOWER GARDENS: ONE END OF WHICH SHOULD ALWAYS BE MUCH LONGER THAN THE OTHER.

PENTAPTERYG'NIUM.—*Vacciniaceæ*.—This beautiful little shrub was found among the hills of North Eastern India. The flowers are formed like those of many kinds of Heath and Vaccinium, but they are of a golden yellow, a very unusual colour in this order, with the pedicels and margins of the calyx red. It flowered in England in 1856.

PENTSTEMON.—*Scrophulariaceæ*.—The two genera *Chelone* and *Pentstemon* are often confused together, but they are quite distinct, and when seen together may be easily distinguished from each other, as the flowers of *Chelone* are short and inflated, and crowded together; while those of *Pentstemon* are long and funnel-shaped and far apart. The Pentstemons are generally hardy

or half-hardy plants, suffering less from cold than from damp during winter; and as they all are very apt to damp off at that season, it is a good plan to take cuttings of all the kinds grown in the open ground in autumn, and to strike them in a sandy peat, keeping them in a greenhouse or some dry place till spring, when they may be planted in the flower-border. All the Pentstemons are beautiful North American perennials, growing from one foot to two feet in height, with white, pink, blue, or purple flowers, produced from March to October. Most of them will grow in common garden soil, and the rest in loam and peat: and they are all readily propagated by division of the roots, or by seeds or cuttings. *P. campanulatus* grows a foot and a half high, and produces its light purple flowers from March to October, and *P. roseus* produces its red flowers during the same period; *P. pulchellus* grows a foot and a half high, and produces light purple flowers in June and July; *P. speciosus* grows two feet high, and produces its beautiful blue flowers in August and September. *P. Murrayanus* (the handsomest of the genus) grows about two feet high, and produces its brilliant scarlet flowers in August, but it is rather tender. *P. Cobaea* grows about a foot and a half or two feet high, and produces its large light purple or pinkish flowers in August, and it is also rather tender. *P. Scouleri*, which grows three feet or four feet high, and produces its purple flowers from May to July, is suffrutescent, and succeeds either in the open border, or forms a beautiful object against a conservative wall. On the whole, all the species are beautiful, and none of them are of difficult culture.

PERA'DO.—The name for a kind

of Holly, a native of Madeira, *Ilex Perado*; which is only half-hardy in England. It makes, however, a beautiful tree, which will stand without protection in the open air if it is grafted standard high on a tree of the Common Holly.

PERENNIAL PLANTS are those permanent plants which are not woody, but which generally die down to the ground every year, and spring up again the year following. There are some, however, which are called evergreen perennials, which never die down to the ground, such as Pinks, Carnations, several kinds of Saxifrage, &c. Perennials have the great advantage over annuals and biennials, that they do not require renewal from seed, but are propagated by division of the root or by cuttings of the stem. Bulbous plants are perennials, and they are propagated by separating the offsets, which may be considered as a kind of division of the root. Tuberous-rooted plants are propagated by separating the tubers; and when these tubers are furnished with eyes like the potato, they may be cut into pieces, preserving an eye to each; but when they are without eyes or buds, excepting at their upper extremity, as in the case of the Dahlia and the garden Ranunculus, each tuber must be separated from the parent plant entire with its bud. The great majority of plants which ornament the miscellaneous borders of a flower-garden are herbaceous perennials, including under this term bulbs and tubers. All the hardy bulbs in a flower-border, except those of the Hyacinth and the Tulip, should be kept as dry as possible during winter, as they are more liable to be injured by wet than cold; and when they are taken up to remove their offsets, &c., it should be in autumn when

the leaves have withered, and they should be planted again as soon as practicable, as they are very apt to be injured by damp, &c., if they remain long out of the ground. Tubers, on the contrary, such as those of the Garden Ranunculus, and the Dahlia, must be taken up every year as soon as they have done flowering, and only replanted just before the growing season commences, as, if left in the ground, they are very apt to rot; the bulbs of the Hyacinth and the Tulip thrive best when treated in the same manner. The fibrous-rooted perennials should be taken up and divided when they are growing too large; and even when division on this account is not necessary, most of the kinds are benefited by taking up and replanting in fresh situations occasionally, on the principle of the rotation of crops. This is, that all plants throw out excrementitious matter, which is poisonous to themselves, though wholesome for other plants; and thus, in the course of a few years, the ground in which plants grow becomes unfit for them. Nature has provided a remedy for this by elongating the roots of all perennial plants, whether ligneous or herbaceous, every year; and this is sufficient to prevent trees and shrubs in permanent plantations from being injured; but from the constant digging, &c., in a garden, perennial herbaceous plants are very seldom permitted to extend their roots to a sufficient distance to find suitable soil; and they are therefore benefited by taking up and replanting, or laying down decayed leaves or fresh soil over their roots. The season for taking up and replanting perennial plants should be either in autumn, after they have done growing, or in spring, before they begin to grow; and if the soil

about the roots looks black and saturated with moisture, or, as the gardeners express it, "sour," the roots should be washed quite clean before replanting. Where the roots are to be divided, it may be done, if they are large, with the spade, or if they are small, with a knife; and, at all events, they should be cut smooth, and trimmed (that is, all the bruised parts removed) with a sharp knife, before replanting. — See PLANTING.

PERGULARIA. — *Asclepiadaceæ*. — *P. odoratissima* has, perhaps, a sweeter fragrance than any other plant known. The flowers are green, and of no peculiar beauty, but they are most valuable for their delightful fragrance, which is chiefly perceptible at night. The Pergularia is a stove-climber which should be grown in a large pot (a 12) with holes in the sides, which should be plunged into the centre pit of the stove and kept moist. The soil should be sandy loam or chopped turf mixed with leaf-mould; and the plant is propagated by cuttings struck in sand with bottom-heat, and covered with a bell-glass. It should be cut back every year when it has done flowering; and it will shoot out vigorously in spring.

PERILOCA. — *Asclepiadaceæ*. — *P. græca* is a handsome hardy climber, with velvet-like flowers of a very singular colour, being a dark purplish maroon. It will grow in any light rich soil, and it is very suitable for covering arbours. It is said to be fatal to flies, and that a number of dead flies may be swept up every day in bowers covered by it. It is a native of the Canary Isles, and it is propagated by layers or cuttings, both of which grow freely.

PERESKIA. — *Cactaceæ*. — The Barbadoes or West Indian Goose-

berry. This plant bears very little resemblance to the other kinds of Cacti, as it has thin leaves and a round stem like any other ligneous plant. *P. aculeata*, the commonest kind, has white flowers; but the flowers of *P. Bilo* are of a beautiful pink. The fruit resembles a gooseberry, and is very good to eat. The Pereskias are quite hardy, growing in the same temperature and requiring nearly the same treatment as the Opuntia or Common Indian Fig (see OPUNTIA); and *P. aculeata* is frequently used as a stock for grafting on it the more tender kinds of Cacti.

PERILLA. — *Labidatæ*. — *P. nan-kinensis* is an important annual plant for bedding purposes on account of its foliage, which is of a purplish black, affording a very marked contrast with the bright green of other plants, and especially with the silvery hue of such as the Cineraria maritima. It should be sown in heat, in March or April, and planted out in May.

PERISTERIA. — *Orchidaceæ*. — The Dove Flower. — Beautiful Peruvian epiphytes, which should be grown on wood. — See ORCHIDEOUS EPIPHYTES.

PERIWINKLE. — See VINCA.

PERNETTIA. — *Ericaceæ*. — A pretty little evergreen bush, a native of Terra del Fuego, with white heath-like flowers. It is quite hardy, and only requires to be grown in a bed of peat soil.

PERSICARIA. — See POLYGONUM.

PETREA. — *Verbenaceæ*. — *P. volubilis* is a climbing plant, with long and beautiful racemes of dark-purple flowers, and large dark-green leaves. It is a native of Vera Cruz and Martinique, where it ascends to the summit of lofty trees, hanging from branch to branch in graceful festoons, and producing its flowers

in great abundance. In England, though it has been introduced since 1733, it is rarely seen in flower for want of proper management; but to make it flower freely, it only requires to be pruned like a common grape-vine—that is, to have the leading shoots stopped at the second joint to make them throw out side shoots, and to have these stopped in the same manner, in order to have what the gardeners call spurs distributed over all the branches; for it is on these spurs only that the flowers are produced. The plant is called in the Antilles the Easter flower, because it flowers about Easter; and it is used for decorating the Spanish churches at that season. In England it generally flowers in August. It should be grown in chopped turfy loam, mixed with a little peat to keep it open; and it is propagated by cuttings struck in heat.

PETTY WHIN. — *Genista anglica*.

PETUNIA. — *Solanaceæ*. — Perhaps no plants have made a greater revolution in floriculture than the Petunias. Only a few years ago they were comparatively unknown, and now there is not a garden, or even a window, that can boast of flowers at all, without one. *P. nyctaginigiflora*, the common white Petunia, was first brought from Brazil in 1823: and as it was thought very nearly to resemble the common Tobacco, it was called Petunia, from *Petun*, which is the Brazilian name for that plant. This plant was cultivated but sparingly, and only in greenhouses, as a perennial, till 1830, when *P. violacea* or *P. phænicea*, as it is sometimes called, was introduced from Buenos Ayres by Mr. Tweedie; and from this species, hybridised with *P. nyctaginigiflora* and *P. bicolor*, most of the innumerable hybrids now in our

gardens have been produced. All these kinds are found nearly hardy, and they may either be treated as half-hardy annuals, being raised on a slight hotbed and planted out in May, or they may be sown in the open ground as soon as the seed is ripe, or in March or April, or suffered to sow themselves; care being taken in all cases in the open air to choose a sheltered situation, and to lay a few dead leaves over the bed if the weather should be severe. When treated as greenhouse plants, these Petunias all become shrubby, but they will not live more than two or three years, and they should be cut down as soon as they have done flowering. When they are wanted to grow to a large size, and to cover a trellis, &c., like climbing plants, they should be planted in the free ground, in the conservatory, or in the open air, in a light rich soil; or, if they are kept in pots, allowed plenty of room for their roots; as, unless this is done, they will become drawn up with long weak stems, bare of both leaves and flowers to a considerable height. When they are wanted to form strong bushy plants for setting in a window or keeping in boxes under a verandah, the end may be attained by planting them first in very small pots and shifting them into others, gradually becoming larger and larger, always pinching off the flowers, and tips of the shoots, till the plants have attained the desired form and size, when they may be allowed to flower, and will form splendid objects. When Petunias are wanted to cover a bed in a regular flower-garden, they are not cut in at all; but their long rambling shoots being pegged down all over the bed, a number of side shoots will be sent up, which will soon become covered with a mass of flowers. The hybrid *P. splendens*, treated

in this manner, as it was in the flower-garden at Dropmore, is, when the sun shines upon it, almost too brilliant to be looked at. *P. intermedia*, sometimes called *Salpiglossis linearis*, is a dwarf shrub, a native of Panama, introduced in 1832, which requires to be kept in a greenhouse in England.

A great confusion has arisen about the name of the purple-flowered Petunia, as, when it was first raised at Glasgow from the seeds sent home by Mr. Tweedie, it was supposed by Sir W. J. Hooker to be a *Salpiglossis*; and it was figured and described by him under the name of *Salpiglossis integrifolia* in the Botanical Magazine, t. 3113. It was afterwards figured and described by the late Professor Don, in *Sweet's British Flower-Garden*, second series, t. 172, under the name of *Nierembergia phænicea*; and, lastly, by Dr. Lindley, in the *Botanical Register*, t. 1626, as *Petunia violacea*. It is very remarkable that there should have been so many doubts among botanists as to the genus of the purple Petunia, as it appears to common observers to differ from the white only in colour; and it is also remarkable that it should have been first called *phænicea*, which signifies crimson, when it is decidedly of a violet-coloured purple. The flowers of the white Petunia, and of all the hybrids raised from it, are fragrant, particularly at night; while the few hybrids raised between *P. violacea* and *P. bicolor*, and the numerous seedlings of the former species, have no fragrance. *P. bicolor* does not hybridise so freely as the other kinds, and it is more tender; but all the dark-mouthed and streaked kinds are raised partly from it, and they are generally hybrids between it and the white Petunia; the latter



kind producing the seed, as *P. bicolor* rarely ripens seeds. No plants are more easily trained than the Petunias; and, with a little care and attention, they may be made to cover trellis-work or wire frames of various different forms.

**PHÆDRANASSA.**—*Amaryllidaceæ*.—A very curious bulb, found by Mr. Hartweg in Peru, and which consequently requires a greenhouse in this country. The bulbs should be potted in rich, light, sandy loam, and kept very moist while they are in a growing state, but quite dry during their season of rest. The name of *Phædranassa* signifies a gay and beautiful queen.

**PHAIUS.**—*Orchidaceæ*.—*P. albus*, which is an exceedingly beautiful East Indian epiphyte, is remarkable for the dry and withered appearance which it presents when it enters into its dormant state. At this period it sheds its leaves, and its stems become covered with a dry brownish skin, which makes them look exactly as if they were dead. It should then be removed to a cool situation, where the heat is not greater than 40° or 45° of Fahrenheit, and kept with only enough water to prevent it from dying. In the course of a few weeks, a young shoot will begin to push out from the crown of the root, and as soon as this is perceived, the plant should be re-potted in sandy peat (the pot being first nearly half filled with potsherds), and removed to the orchideous house, where it should be exposed to a strong heat and syringed twice a day with a copious supply of water to the roots till the appearance of the flowers, when it should be removed to a cooler atmosphere, say that of a drawing-room, and be no longer syringed.

**PHALÉNOPSIS.**—*Orchidaceæ*.—The White Butterfly Plant.—This

beautiful plant, which certainly resembles a white butterfly, as much as *O. papilio* does a tortoiseshell one, should be grown on a piece of wood with the bark on, hung from the roof of the hothouse, the roots being wrapped in moss and tied on the branch. It flowers profusely, but it is very difficult to propagate. The White Butterfly Plant, *P. amabilis*, is remarkable for the great length of time it continues in flower; *P. grandiflora* closely resembles it, but the flowers of *P. rosea* are pinkish.

**PHARBITIS.**—*Convolvulaceæ*.—The new name given by M. Choisy to *Convolvulus major* and some few other species. The difference between this new genus and the genus *Convolvulus* consists in the shape of the stigma, and in the number of cells in the capsule.

**PHASEOLUS.**—*Leguminosæ*.—The Scarlet-runner, *P. multiflorus*, was cultivated at its first introduction as a garden flower; and it is still often grown for ornament in small street-gardens, by sowing the seeds in the ground, and training the plants up pieces of pack-thread, fastened to a hook or nail in the wall, at one end, and to a peg stuck in the ground at the other. There is a variety with red and white flowers, sometimes called Painted Ladies, which is very ornamental.

**PHILADELPHUS.**—*Philadelphææ*.—The Syringa, or Mock Orange.—North American hardy shrubs, common in shrubberies, the flowers of which smell like those of the Orange, and the leaves taste like Cucumbers. It is rather remarkable that one of the English names of these plants is Syringa; which is the botanic name of the Lilac, to which they have not the slightest affinity. There are many species; some of which have very large and

handsome flowers, and some bear flowers without any fragrance. They are all quite hardy, and will grow in any soil or situation; and they may all be propagated by seeds, layers, cuttings, or division of the root.

PHILESIA. — *Smilacææ*. — A beautiful little shrub, with bright crimson flowers and box-like leaves; which is called Pepino in its native country. It is found along the Straits of Magelhaen, and the west coast of Antarctic America. It is supposed to be quite hardy.

PHILIBERTIA. — *Asclepiadacææ*. — A very curious twining plant, a native of Buenos Ayres, which requires a greenhouse in this country. It should be grown in very sandy loam, with the pots well drained, and be kept nearly dry during the season of rest. It is propagated by cuttings.

PHILLYREA. — *Oleinaæ*. — Evergreen bushy shrubs, natives of Europe, and some parts of Asia, which are very useful in British gardens, from their shining dark-green leaves and small fragrant white flowers. They are often confounded with the Alaternus, from which, however, they are botanically quite distinct, as that shrub belongs to Rhamnacææ. The Phillyrea is generally found in the shrubberies of old mansions, as, from the time of Gerard, till Evelyn so warmly patronised the Holly, the Phillyrea and the Alaternus were the principal evergreens planted in British gardens; and both were great favourites for topiary work, as no plants are clipped more easily into figures of animals, &c. All the kinds are quite hardy, and will grow in any soil or situation: and they may be all propagated by seeds, layers, or cuttings.

PHLOMIS. — *Labiataææ*. — The Je-

rusalem Sage. — Perennial and shrubby plants, with large coarse-growing glaucous leaves, greatly resembling those of the common Sage, and yellow or purple flowers, disposed in a whorl round the joints. All the species will grow in any light rich soil: and they are propagated by layers or cuttings, or by dividing the root.

PHLOX. — *Polemoniadacææ*. — A genus of beautiful North American perennials and one annual, of which there are some species in flower almost every month in the year. They thrive best in sandy loam and peat, but many of the species will grow in any common soil. *Phlox setacea* is a low trailing perennial, which produces its flesh-coloured flowers in April and May. *P. nivâlis* is of equally low growth, and it produces its white flowers at the same period. *P. subulata* seldom exceeds three inches in length, and it produces its beautiful flesh-coloured flowers from April to June. *P. canadensis* has blue flowers, which are produced in April and May, and it grows almost a foot in height. *P. divaricata* produces light-blue flowers from April to June, and grows about the same height as the former species. *P. ovata* and *P. ovata Listmiana* grow about one foot high, and produce purple flowers from May to August; and *P. pilosa* grows about one foot in height, and produces its pink flowers in May and June. There are above a dozen other species, equally low in growth and prolific in flowers in spring or in the beginning of summer; and there are a number of species which grow from two to four feet in height, and flower in July, August, and September. Of these may be mentioned *P. paniculata alba* and *paniculata rubra*; *P. acuminata*, which grows four feet high, and produces pink flowers from May to August. *P.*

*pyramidalis* and its several varieties, *P. latifolia* and *P. maculata*, grow four feet high, and produce pink or red flowers from July to September; and *P. multiflora*, which has a long spike of white flowers about a foot and a half high, flowers nearly all the summer. The varieties raised of late years, by crossing, from *P. decussata*, *P. paniculata*, and *P. pyramidalis*, are exceedingly numerous and beautiful; and some of them are approximating the desideratum of a dwarfer habit of growth than that of the species from which they have been produced. The only annual species is *P. Drummondii* and its varieties, which are plants of surpassing beauty, raised annually from seeds or cuttings in light sandy soil, and admirably adapted for covering flower-beds or growing in pots. When raised from seeds, this species should be treated like a tender annual; and after being raised in a hotbed in February or March, it should be turned out in the open ground about the middle of May; or it may be sown in April or May in the open ground. In fine seasons it ripens seeds; but where it does not it may be preserved through the winter by striking cuttings in autumn, and preserving them in pots placed on the front shelf of a greenhouse or in a frame. The varieties vary from purple to light-rose, and generally come true from seed. On the whole, the genus *Phlox* is one of the most beautiful of herbaceous plants, and a garden ought to be no more without some of the species than it ought to be without *Roses* or *bulbs*.

PHOENIX. — *Palmæ*. — *P. dactylifera*, the Date Palm, is a well-known stove plant, which should be grown in a sandy loam. Young plants may be raised from the

stones of the dates sold in the shops, and if kept in sufficient heat they will grow freely; though the trees must be of considerable age and size before they bear fruit.

PHO'RMIUM. — *Asphodèleæ*. — *P. tenax*, the New Zealand Flax, is a very singular plant, with large bunches of orange flowers, and very long, broad, lily-like leaves, the fibres of which are so strong, that they are used in New Zealand for making baskets, and various other articles in their coarse state, and in the same manner as flax for making sails, &c. In England, the plant is at present rare, but it may be grown in a very rich sandy loam, frequently watered, or even in a border in front of a south wall if protected from severe frosts; or if sheltered from these it may be grown in a pot, and planted out with good effect among other foliage plants during the summer. The principal objection to its culture is the great size of its leaves, which occupy too much space for it to be grown in a small house.

PHOTINIA. — *Rosacææ*. — A very beautiful evergreen shrub or low tree formerly called *Crataegus glabra*, which is nearly hardy, but thrives best when trained against a wall in a sheltered situation. The soil should be sandy loam, and the plants are propagated sometimes by cuttings of the ripened wood, but more frequently by grafting or inarching on some of the hardy kinds of *Crataegus*.

PHYGELIUS. — *Scrophulariaceæ*. — A splendid suffruticose plant from the Cape, somewhat resembling a *Pentstemon*, with bright scarlet flowers. It flowers in the open ground, but will probably require a greenhouse in winter.

PHY'LICA. — *Rhamnaceæ*. — Pretty little heath-like plants, natives of

the Cape of Good Hope, with narrow leaves, and little terminal heads of fragrant white flowers, which begin to appear in autumn, and continue during winter and early spring. They are generally grown in a greenhouse, and require the same treatment as the Cape Heath.

**PHY'SALIS.** — *Solanaceæ*. — The Winter Cherry. Dwarf, shrubby and herbaceous plants, with showy flowers. The fruit is a bright-red berry in a bladdery calyx; and when the calyx has been macerated by soaking it in water, it has a very pretty effect. Some of the species are shrubby, but the greater part are annual plants; they are generally only half hardy, and they succeed best when grown in sandy loam.

**PHYSIA'NTHUS.** — *Asclepiadææ*. — A climbing plant from Mexico, which has proved hardy in the Royal Horticultural Society's garden. It has small whitish flowers, and very large and handsome fleshy seed-vessels, which look like oval gourds, and which, when opened, are found to contain the seeds enveloped in a quantity of fine silky substance, which looks like the cocoons of silkworms, after the fine silk has been spun off. The *Physianthus* will grow in any common soil; but it should always be trained against a wall, as otherwise the large fruit will be too heavy for the slender branches. There are two species.

**PHYSOSTEGIA.** — *Labiataæ*. — *P. imbricata* is a beautiful plant, with pale purple flowers, nearly allied to *Dracocéphalum*, which only requires the usual treatment of hardy perennials. *P. truncata* is an annual species, with pale pink flowers. Both are natives of Mexico, and will grow in the open ground, in any common garden soil.

**PHYTELEPHAS.** — *Cyclanthaceæ*.

—The Vegetable Ivory, or *Tagua*, plant, is nearly allied to the Screw Pine family, and its fronds resemble those of the Cocoa-nut tree. There is no proper stem, but the fronds or leaves sometimes measure nearly twenty feet in length, and are of a pale green colour, and delicate texture. "The singular heads of the fertile inflorescence grow round the base of the plant, often six clusters at one time, and the heads rest on the ground, or are wedged between the leaves, and borne on a buried footstalk, of which the fibre is exceedingly tough. These clusters are of an imperfectly rounded form, covered with strong protuberances, about an inch and a-half long. On dissecting one of these compact heads, it will be found to consist of many distinct clusters, each containing about four seeds, closely knitted together. Hence the popular name of this palm, *Cabesa del Negro*, or the Negro's Head, is by no means an inapt comparison, for the style-like projections resemble a black man's rigid hair. Enclosing the seeds is a yellow sweet oily pulp, which is collected in the month of October, and sold under the name of *Pepa del Tagua*. A spoonful of it, with a little sugar and water, makes the celebrated *Chiche de Tagua*, said to be the most delicious beverage of the country." The *Phytélephas* generally inhabits dense shady woods, at an elevation of from one to three thousand feet above the level of the sea. The fruit is large and very heavy, and the vegetable ivory, which is the albumen of the seed, is as hard, or nearly so, as the ivory of the elephant's tusks. The plant is a native of tropical South America, and has only lately been introduced into Great Britain; but there are now plants at Kew, in the Botanic Garden in the Regent's

Park, and other places. The one at Kew flowered in 1855, but did not ripen fruit.

**PHYTEUMA.**—*Campanulacæe*.—Herbaceous plants, generally with dark-blue flowers, which will grow in any ordinary soil, and which are increased by dividing the roots.

**PHYTOLOCCA.**—*Chenopodiaceæ*, or *Phytolacæe*.—*P. decandra*, the Virginian Poke, is a fine vigorous-growing plant, which is ornamental from the abundance of its black berries, but which, from its large leaves and spreading habit of growth, requires a great deal of room. It should be grown in a very rich soil, and it is increased by seeds or cuttings. There are several species, all of which have black berries, containing a deep-red juice, which is said to be used in Portugal to colour Port wine.

**PICOTEE.**—A kind of Carnation, with a narrow dark-coloured margin to the petals, or with the petals covered with small brown or dark purple dots. For the culture, see **DIA'NTHUS**.

**PILEWORT.**—See **FICA'RIA**.

**PIMELE'A.**—*Thymelacæe*.—Australian shrubs, which require a richer soil than most other plants from that country. They should be grown in a greenhouse in England, in a soil composed of sandy peat and loam, mixed with vegetable mould, or part of an old hot-bed. They should have plenty of light, and they should be kept regularly watered. They are propagated by cuttings. *P. discussata*, *elegans*, *Hendersoni*, *rosea*, and *spectabilis* are most esteemed species.

**PIMPERNEL.**—See **ANAGA'LLIS**.

**PINK.**—See **DIA'NTHUS**.

**PIPIINGS.**—Cuttings of Pinks and Carnations are called pipings, because these plants have tubular

stems, and when separated at a joint, the parts are pulled asunder, instead of being cut. This is done




FIG. 40.—PIPING OF A CARNATION.

in autumn, by taking a shoot that has nearly done growing, in one hand, and pulling the upper part of it off just above a pair of leaves, so as to separate it at the socket formed by the axils of the leaves, leaving the part pulled off with a tubular or pipe-like termination. Some florists then cut off the tips of the leaves, but others leave them entire, as shown in fig. 40, and in both cases the pipings must be struck in sand with a hand-glass fixed firmly over them. It may be here observed, that the herbage of Pinks and Carnations is called the grass; and that when a plant is in a vigorous state of growth, it is said to have the grass fine.

**PIPTA'NTHUS.**—*Leguminosæe*.—A handsome half-hardy tree, with large yellow pea-flowers. It will grow in any common soil, but it

requires a slight protection during winter.

**PISTACIA.**—*Terebinthaceæ*.—The Pistachia Nut-tree.—Very handsome trees, which abound in turpentine in their native country, but which produce very little in England.

**PITS** are structures, either sunk in the ground, or raised above it with brick walls on all sides, and with a glass cover, for the purpose of preserving plants from the frost. They do not require flues, beds of tan or dung, or any other artificial mode of heating; but they do require artificial heat when they are employed for preserving greenhouse plants, for growing hothouse plants, or for forcing hardy herbaceous flowers or shrubs into premature bloom. They are also used as a substitute for hotbeds in bringing forward tender annuals, and in raising seeds. For all these purposes some mode of artificial heating is required; and this may either be accomplished by smoke flues, the circulation of hot water in pipes of iron or earthenware, or by the introduction of beds of fermenting materials, such as tan or dung. The most convenient mode of heating is unquestionably by hot water, because by this mode there is less danger of producing excessive heat; and the heat is more congenial to vegetation than the dry heat of smoke-flues. Where hot water pipes cannot be conveniently procured, or in the given locality are more expensive than smoke-flues, then the latter may be adopted; taking care to supply moisture to the atmosphere of the pit by placing pans of water on the flues; or by keeping the surface of the soil, or the path if there be one, moist by a supply of water from time to time. The construction and the heating of pits are so well known to gardeners, builders,

and ironmongers, that very little need be said on the subject. They may be of any convenient length—six feet, eight feet, or ten feet in width, three feet high above the surface of the ground behind, and of such a height in front as that the slope of the glass may form an angle with the horizon of between 20° and 30°. The depth to which the pit is sunk in the soil will depend on the uses to which it is to be applied. When it is merely to preserve plants from the frost of winter, it need not be sunk into the soil at all; but when it is to contain a bark-bed, the depth of that bed, which may be between two and three feet, should be excavated from the soil. When the pit is to be entered by the gardener, in order that he may walk upright, there should be a path immediately under the back wall; and this will require the pit to be at least seven feet in depth. In this, as in all other cases, sufficient drainage must be provided; and if the walls and floors are built and laid hollow, the entrance of moisture and the escape of heat will be prevented. In general, the pits which are heated by tan or dung have the material placed in the beds inside; but in some cases it is placed around the pit, in what are called linings, between two feet and three feet inside, and as high as the walls of the pit outside, so that the heat penetrates through the wall to the dung or soil within; and to facilitate this, the lower parts of the walls are built with open brickwork. Pits of this kind are called Mac Phail's pits, and are admirably adapted for growing hothouse plants, and for every description of forcing.

**PITCAIRNIA.**—*Bromeliaceæ*.—Handsome herbaceous stove-plants, with pineapple-like leaves, and very singular scarlet or pinkish flowers.

They should be all grown in sandy peat and rich loam.

PITCHER PLANT.—See *NEPENTHES* and *SARRACENIA*.

PITTO'SPORUM.—*Pittosporæ*.—Handsome evergreen bushy shrubs, which require a slight protection during winter. *P. Tobira* is a native of China, which has been known to live out of doors for several years in a sheltered situation, but which should be protected from very severe frosts; it produces umbels of white flowers, which have the perfume of orange flowers. *P. undulatum* is a native of the Canaries; leaves aromatic; flowers white, with the scent of Jessamin. *P. flava*, introduced in 1854, has bright yellow flowers. All the species are easily propagated by seeds, cuttings, or layers; and they succeed best in light rich soil.

PLANTAIN TREE.—See *MUSA*.

PLANT CASES.—See *GLASS CASES*.

PLANTING is the operation of inserting plants in the soil, either in the free ground or in pots. The simplest kind of planting is that which consists in removing small seedling plants, or such as have been struck from cuttings or layers; and this is commonly performed by making a round hole with a dibber, and putting in the root of the plant to the same depth as it had been covered with earth before, and making it fast by thrusting the dibber into the firm earth beside the hole and pressing it to the root. In this operation the great art is to make the root fast at its extreme points. Thus, in planting common seedlings of annuals, or even cabbage-plants, if the earth be pressed close to the root at the upper part, and not at the extreme points, the success will hardly be complete; and in tender plants, or in a dry season, a failure will be the result.

In planting plants of a larger size, a small pit should be opened by the spade or the trowel; the bottom of the pit having been formed into a cone or small hill, the plant should be placed in the centre, and the roots spread out equally over it on every side. The roots are then to be covered with soil, gently pressed over them; and the operation must be finished by watering, so as to consolidate the soil equally, without making it firmer on one part of the roots than another. If the soil should have been previously dug, trenched, or loosened to the depth of a foot or probably two or three feet, the pit should not be made so deep as to throw the neck or collar of the plant below, or even on a level with the surface, when the soil is consolidated by watering. On the contrary, it must be left of such a height above it, as that when the soil is finally consolidated by its own gravity, influenced by the weather, the neck shall still be above the general surface of the ground, and the plant stand on a small hillock. This condition of planting cannot be too strongly attended to; for nothing can be more injurious to transplanted plants than having their necks buried more than they were in a natural state. Nothing is more common than too deep planting; and the temptation to it is greater because plants that are deeply planted from having the roots more accessible to moisture, are more certain of growing the first year, and are less in want of mulching to exclude the heat and draught, and of staking to prevent them from being moved by the wind. Hence, in planting trees or shrubs, it is of the greatest importance, not only with a view to their future growth, but also to their

natural appearance above the surface, to have them planted on little hillocks, greater or less in height according as the soil may have been moved to a greater or less depth, either in the operation of digging the pit in firm soil, or of planting in soil which has been moved by digging or trenching, or otherwise. In small gardens it is generally desirable, for the sake of producing immediate effect, to plant plants of considerable size; and in this case, in addition to the precautions which have been already mentioned, it is desirable to plant by what is called fixing with water. This operation is performed in the following manner:—the hole being properly prepared, the plant placed in it, and the roots spread out on every side, and extended as far as they will go, one person holds the plant upright, a second sprinkles earth over the roots, and a third supplies water from a watering-pot with a rose on if the plant be small, and without a rose if it be a tree of six or eight feet in height, holding the pot as high above his head as his arms will reach. The weight of the water coming down from such a height consolidates the soil about the roots, and fixes them in such a manner as to render the plant, if it has been carefully taken up, almost in the same state as it was in before the removing. Large trees or shrubs, if planted in this manner in the autumn, and staked, where there is danger from high winds, will grow, and even flower and fruit the following year, as well as if they had not been removed. In this kind of planting with large plants, the hillock left after the operation is finished should not be less than a foot above the surrounding surface; and to lessen evaporation during the ensuing summer, the hillock

should, if possible, be covered with short litter, moss, turf turned upside down, or even small stones for the first year. In staking large plants of this kind, the stakes should be placed close to the stem of the plant, in which position they are much less likely to injure the fibrous roots than when placed at a distance from the tree; and the stakes should be made fast to the stem of the plant by a piece of straw or hay-rope, or by a piece of twisted matting, or any kind of cord; the part of the stem to which the stake is tied having previously had a small handful of straw, or moss, or mat, bound round it to prevent the tie from galling the bark of the stem, and preventing its increase during summer. These stakes should remain for a year, or sometimes two years, according to the size of the plant and its facility of making roots. In this matter much must be left to the discretion of the planter, who must always bear in mind that a staked plant is in a most unnatural position; and also, that if the tree should lean somewhat to one side for some years after planting, it will ultimately become more or less erect, if guarded from the action of strong winds. In the case of planting trees with stems three or four inches in diameter in exposed situations, two or three stakes may be used, placed at a short distance from the base of the stem, and leaning towards it; and where they are made fast, they should be joined by matting, hay-ropes, or some other soft material, so as not to injure or confine the bark. Before transplanting trees of a timber size, the main roots are frequently cut at the distance of five or six feet from the stem a year previously to transplanting; in consequence of which they send



out fibres, which in the course of the summer become small roots, so that the tree, instead of drawing its principal nourishment from spongioles at the distance of twenty feet or perhaps thirty feet from the stem, is enabled to draw it from the distance of six or eight feet, and thus to continue growing, though not with the same degree of vigour as if it had not been transplanted. But it is necessary to observe that although young fibres are abundantly formed in the first season after the shortening, yet they are too tender to bear the pressure requisite for the removal of large trees; and most of them are so much bruised in course of the operation that they subsequently rot. It is therefore better in the case of large trees not to remove them for at least two years after their roots are cut in. Some kinds of trees, when of large size, such as the Sycamore, the Lime, the Horse-chestnut, and a few others, may be transplanted without this precaution; but in this case the operation must be performed in autumn as soon as the leaves have dropped, in order to give the roots time to form some fibres during the winter; and the greater the distance from the stem at which the roots are cut, the greater will be the success. Large trees with wide-spreading roots, when transplanted, seldom require to be staked, because the roots form a broad base, which prevents the stem from being blown to one side. Where there is danger anticipated from high winds, the trees may be secured by three guy-ropes tied to the upper part of the stem, and made fast to stakes driven into the ground at such a distance from the tree as that the ropes may form an angle with the ground of  $45^{\circ}$ ; or

the stronger roots may be kept in their position by stakes driven into the ground with their heads beneath the surface of the soil; the main roots being made fast to them by cords.

In all cases of transplanting deciduous trees, with the exception of the Beech and the Hornbeam, some pruning should be given to the top, so as to lessen the number of branches and leaves which are to be supplied by the root. The quantity of branches that are required to be removed will depend partly on the kind of tree, and partly on the intention of the planter, but mainly on the climate and soil. Beech trees, as already mentioned, are injured when transplanted by having many branches removed, and often die in consequence. Sycamores and all the A'cer tribe, having numerous fibres near the main stem, require but little pruning of the head. The same may be said of the Yew and the Holly, the Lime and the Elm. When the object of the planter is to produce immediate effect by a bulky head, all the branches may be left on, whatever may be the kind of tree; but in that case the tree will produce only leaves for a number of years, or if it produce shoots they will not exceed a few lines in length. Ultimately, if the soil be poor and dry, the tree will probably perish; but if the soil should be good and moist, and the climate also moist, the tree will in time become vigorous, and produce shoots. Where the climate is moist, and the soil good, and also moist, any tree may be transplanted without pruning the branches; because the fibres it will produce in such a soil and climate will be sufficient to supply the moisture transpired by the leaves. But where the climate is dry and the soil also dry, no large tree

can be safely transplanted with all its branches; because the transpiration by the leaves will be much greater than the moisture which can possibly be absorbed by the roots. Hence, in the dry climate of the Continent, all trees with stems above an inch or two in diameter have their branches entirely cut off, always excepting the Beech and the Hornbeam, the Yew, and all the Pine and Fir, and Cypress tribes. Even in this country, in Evelyn's time, this was the practice; and the late Sir Joseph Banks, when he planted groups of trees with stems of five inches or six inches in diameter on a portion of Hounslow Heath which was allotted to his residence there, planted only stumps ten feet or twelve feet high, which stumps became finely-headed trees, conspicuous from the road in passing Spring Grove. Much has of late been written on the subject of transplanting large trees, by Sir Henry Steuart and others; and the practice has been recommended of leaving on the whole of the head. Experience, however, has proved that this can only be done with advantage under certain circumstances.

Planting in pots, when the plants are of the very smallest size, may be effected by a small dibber, as in planting in the common soil; but it is more frequently done on the principle of planting in pits; that is, the pot being properly drained by a few potsherds being placed over the hole in the bottom of the pot, and an inch or two of soil placed over them, according to the size of the pot, the young seedling or newly-struck cutting is held with one hand, and soil sprinkled over the roots by a trowel with the other. When the pot is filled, the soil is consolidated by lifting the pot with both hands a few inches high, and setting it down

once or twice with a slight jerk; afterwards supplying water so as to moisten the whole of the soil in the pot. The thumb, or a potting-stick should previously be passed round the inner edge of the pot, so as to firm the soil round the rim; otherwise the water is liable to run down round the edge of the pot, without moistening the soil in the middle. Immediately after planting, the pot should be set in a position where it can be shaded during sunshine; but on no account should tender plants be shaded during cloudy weather, or covered with an opaque covering during night, unless for the purpose of protecting them from cold. Of course the after treatment of every plant in a pot must depend on its nature; all that it is necessary at present to treat of is the manner of planting.

Transplanting plants which have already been grown in pots is either effected by removing the ball or mass of earth containing the roots entire, or by gently breaking the ball in pieces and stretching the roots out on every side. When the ball is not broken, the operation is called shifting. Plants are often reared in pots on account of their tender nature when young, or for the convenience of transporting them to a distance, though they are intended ultimately to be planted in the open ground. In almost all cases of this kind, the ball should be broken, and the pit having been prepared with the greatest care, as in common planting, the fibrous roots should be stretched out in it as far as they will go on every side. Hence, a plant which has been grown in a very small pot, when it is to be transplanted into the open garden, may often require a pit three feet or four feet in diameter. There is not perhaps an operation in the whole

science of gardening that affords a higher gratification to the planter than transplanting plants from pots when the pits and soil are properly prepared, and the roots carefully stretched out without being bruised or broken. In consequence of the extraordinary sources of nutriment which are thus afforded to the plant, and of the greatly increased power given to the roots, the shoots which it makes the first year are extraordinary, and evince a degree of vigour which none but a gardener of experience could believe possible. On the other hand, when a plant in a pot is turned out into a pit, however well the soil may be prepared, if the roots are not stretched out, it may remain for many years without growing much faster than it previously did in the pot. This is often the case with the more rare species of the Pine and Fir tribe, and with Magnolias and other plants kept in pots by nurserymen; and it is further attended by this evil, that the plants are easily blown to one side by the wind. In the case of surface-rooted plants, such as Pines, if they have been some years in the pot, they never send out roots sufficient to keep them upright; and hence the Pinaster and Stone Pine, which are almost always kept in pots in British nurseries, are generally found leaning to one side in plantations in this country. It is necessary, however, to make the distinction between plants newly planted in pots, and those which have been in pots for two or three years; for the former may perhaps have few roots which have reached the sides of the pot, as in the case of China Roses struck and potted early in the season and planted out the same summer, and which, of course may be planted out without breaking the ball. The same observation will apply to all

other plants in pots that have not their fibrous roots somewhat woody; and also to all air-rooted plants, such as Heaths, Rhododendrons, Azaleas, A'rbutus, and in general to all the Ericææ, which having at no age large woody roots, may always be transplanted from pots with the balls entire.

It may here be observed that large shrubs of almost all the Ericææ may be transplanted at almost any age with less danger than most other plants, as, from the slender and fibrous nature of the great mass of their roots, they are less liable to injury than woody-rooted plants. All that is required is that they should be taken up with a large ball of earth, and that when replanted they should be abundantly supplied with water.

Hitherto nothing has been said especially applicable to evergreens, whether in the open ground or in pots. These being at every season of the year more or less in a growing state, it is always desirable to transplant them with balls; and it is only young plants of evergreens, such as seedling Hollies, Portugal Laurels, and young cuttings or layers of the common Laurel, *Laurustinus*, Sweet Bay, *Phillyræa*, *Alatérnus*, Junipers, &c., which can be sent at any distance with a certainty of growing without balls. The common Holly, when it is above three or four feet in height, requires to be taken up with a ball, and that ball carefully preserved by being tied up in a mat—or, according to the Dutch practice, put into a basket of wickerwork. The same remark will apply to *Arbor Vitæ*, Junipers, A'rbutus, Rhododendrons, Box, *Phillyreas*, and even the common Laurel.

The best season for transplanting all deciduous trees and shrubs is the

autumn; because the plant has time to produce some fibres, and to accommodate itself to its new soil and situation during the winter, so as to be prepared to grow freely the following spring. Evergreens may also be transplanted in autumn, or at any time in open moist weather during autumn, winter, or early spring. In dry or frosty weather it is always dangerous to remove them, because the sap in an evergreen is more or less in motion at every season of the year, and the plant is never so completely dormant as in the case of deciduous trees. Formerly it was thought that the best season for removing evergreens was in the latter part of summer, shortly after they had completed their year's growth; but this doctrine was only acted upon in the time of Miller and before, when there were comparatively few species of evergreens in British gardens; and it has been recently found by Mr. M'Nab (see his *Treatise on Transplanting Evergreens*) that evergreens may be transplanted with much greater safety in mild weather in autumn or winter, than at any other period of the year. Herbaceous plants may in general be transplanted at any season when they are not in flower or coming into flower; but the safest time for perennials is in autumn, after they have ripened their seeds, and are going into a dormant state. Biennial and annual plants are best transplanted when quite young, or after they have obtained their second or third pair of leaves; and seedlings in general may be treated in a similar manner. In all cases of planting (excepting with Cacti and other succulents) the plants should be watered as soon as they are fixed in their new situations; and, when practicable, they should be shaded

for a few days from the heat of the sun.

**PLATYC'ODON.**—*Campanulaceæ*.—Hardy verbaceous perennials, with large flowers,  $2\frac{1}{2}$  inches across, of a fine blue. *P. grandiflorum* is a native of Siberia; *P. sinensis* was introduced by Mr. Fortune from China; it is more dwarf than the preceding, flowers later, and is a very showy plant for flower borders.

**PLATYLOBIUM.**—*Papilionaceæ*.—Handsome Australian evergreen shrubs. *P. formosum* has beautiful orange yellow flowers, spotted and rayed with carmine, margined with dark red. Propagated by seeds, which should be soaked in hot water before sowing, and by cuttings.

**PLATYSTEMON.**—*Ranunculaceæ*.—One of the Californian annuals, with cream-coloured flowers and woolly glaucous leaves. For the culture, see CALIFORNIAN ANNUALS.

**PLATYSTIGMA.**—*Papaveraceæ*.—A very curious little plant, with the petals alternately white and yellow. For the culture, see CALIFORNIAN ANNUALS.

**PLEASURE-GROUND** is that portion of a country residence which is devoted to ornamental purposes, in contradistinction to those parts which are exclusively devoted to utility or profit, such as the kitchen-garden, the farm, and the park. In former times, when the geometrical style of laying out grounds prevailed, a pleasure-ground consisted of terrace-walks, a bowling-green, a labyrinth, a bosquet or small wood, and a shady walk, commonly of nut-trees, but sometimes of taller trees, with ponds of water, fountains, statues, &c. In modern times the pleasure-ground consists chiefly of a lawn of smoothly-shaven turf, interspersed with beds of flowers, groups of shrubs, scattered trees,

and, according to circumstances, with a part or the whole of the scenes and objects which belong to a pleasure-ground in the ancient style. The main portion of the pleasure-ground is always placed on that side of the house to which the drawing-room windows open; and it extends in front and to the right and left more or less according to the extent of the place; the park, or that part devoted exclusively to pasture and scattered trees, being always on the entrance front. There is no limit to the extent either of the pleasure-ground or the park, and no necessary connection between the size of the house and the size of the pleasure-ground. A small house and a large garden was the wish of the poet Cowley; and the largest parks are sometimes attached to very small houses and small pleasure-grounds, and the contrary. A pleasure-ground in modern times differs from that prevalent at any former period, in including all the scenes and sources of enjoyment and recreation of the ancient style as well as the modern. For example, adjoining the drawing-room front there is a terrace or terraces, with or without an architectural flower-garden, decorated with statues, vases, fountains, and other sculptured or architectural objects. Beyond this, or connected with it to the right and left, there may be a lawn with flowers, shrubs, groups of trees, ponds, lakes, rock-work, summer-houses, or greenhouses, an orangery, and sometimes a botanic garden. Walks may stretch away on either, or on both sides, to a shrubbery, which, in the present day, is commonly formed into an Arboretum and Fruticetum, containing all the hardy trees and shrubs which the extent of the scene will admit of; and in the course of the walk

through this scene there may be rustic structures; such as woodhouses, mosshouses, roothouses, rockhouses, or Cyclopæan cottages; Swiss cottages, common covered seats, exposed seats of wood or stone, temples, ruins, grottoes, caverns, imitations of ancient buildings; and, in short, there is scarcely an architectural object capable of being rendered ornamental, and a shelter from the sun, the wind, or the rain, which may not find a place. To know all the different scenes which may be introduced in a pleasure-ground in modern times, it is only necessary to visit such a place as Alton Towers, in Staffordshire, where, in addition to the objects mentioned, may be seen pagodas, hermitages, an imitation of Stonehenge, and of other Druidical monuments, shellwork, gilt domes, and huge blocks of mossy rock, ridges, viaducts, and many other curious objects. In small places of an acre or two, the most interesting objects which may be introduced in a pleasure-ground are collections of trees, shrubs, and herbaceous plants, which may always be arranged to combine as much picturesque beauty and general effect as if there were only the few kinds of trees and shrubs planted which were formerly in use in such scenes. Where a small place, even of a quarter of an acre, is to be made the most of, there should seldom be more than one or two trees, shrubs, or plants of exactly the same kind, and the ornamental plants immediately adjoining the house may be combined with the verandah, portico, or porch, conservatory, greenhouse, or hothouses, terrace flights of steps, balustrades, vases, statues, fountains, walks, rockwork, and a great variety of similar objects, according to the taste of the designer, the peculiarities of the situation,

and the expense which the proprietor is disposed to incur.

**PLERO'MA.**—*Melastomaceæ*.—*P. elegans* is a very handsome green. house shrub, with large dark-purple flowers. It is a native of the Organ Mountains of Brazil, whence it was introduced in 1846. *P. Benthamiana*, flowers purplish-violet, from the same country, is also very ornamental.

**PLUMBA'GO.**—*Plumbaginaceæ*.—Lead-wort.—Greenhouse plants, remarkable for their vigorous growth and abundance of flowers. *P. capensis* has pale blue flowers, which are produced in succession from July till November. *H. Larpéntæ*, nearly hardy, from China, flowers rich cobalt-blue, autumn, suitable for growing in suspended baskets in the greenhouse or conservatory, or it may be placed out in the open ground in May. *P. rósea* requires abundance of water during the growing season, the pot then may even be placed in a pan of water. The last two are propagated by offsets, *P. capensis* by cuttings.

**PODO'LEPIS.**—*Compositæ*.—Very pretty Australian plants, which should be grown in a compost of loam and peat. They are all nearly hardy; the perennials are increased by dividing the root, and the annuals (*P. grácilis*, &c.) by sowing on a hotbed in February or March, and transplanting into the open border in March.

**PODOPHYLLUM.**—*Podophyllaceæ*.—The May Apple, or Duck's Foot.—An American herbaceous marsh plant, which should be grown in a light rich soil kept moist, and which is increased by seeds or dividing its creeping roots. The flower is white, and the fruit, which is eatable, is green and about the size of a plum.

**POET'S CASSIA.**—See **OST'RIS**.

**POINCIA'NA.**—See **CÆSALPI'NTIA**.

**POINSE'TTIA.**—*Euphorbiaceæ*.—*P. pulcherrima* is a most splendid plant, not for its flowers, which are small and white, but for its large bright scarlet bractæas, which, at a little distance, have a superb appearance. There is a variety with white bractæas, but it is very inferior to this species. This plant requires a stove, in which it should be grown in a compost of loam and peat. After it has shed its leaves, it should be pruned and allowed a season of rest, during which it should be kept nearly dry. It is increased by cuttings, which, when taken off, should be dried for a few days, and then plunged into the tan of a pine-pit or stove.

**POI'VREA.**—*Combretaceæ*.—This new genus, established by Professor De Candolle, includes all those species of the genus *Combretum* which have ten stamens and five-angled seeds; the type being *Combretum purpureum* (*Poiræa coccinea*. Dec.). For the culture, see **COMBRETUM**.

**POLEMO'NIUM.**—*Polemoniaceæ*.—Greek Valerian.—The common wild species, *P. cærúleum*, is very abundant on the dry sandy banks in the lanes near Shenstone, in Staffordshire, where it is called Churity, though its common name in other parts of England is Jacob's Ladder. All the kinds succeed best in gravelly or chalky soil, and they are all increased by dividing the roots.

**POLIA'NTHES.**—*Hamercallidææ*.

—The Tuberose.—A bulbous-rooted plant, a native of the East Indies, remarkable for its highly odoriferous white flowers. The bulbs are imported from Italy, where they are grown for exportation as Hyacinths are in Holland. They require to be brought forward in a frame or

pit ; and when coming into flower, they should be removed to a greenhouse or any cool airy apartment, where they will diffuse a powerful fragrance, which to some is grateful and to others oppressive. They should be potted in sandy loam ; and if the bulbs are intended to flower the second year, the plants should be replaced in heat close to the glass, and kept there till the leaves begin to decay ; after which the bulbs may be treated like those of the Hyacinth. It is rarely, however, that this can be done with success, and it is therefore better to throw the plants away when they have done flowering, and purchase fresh bulbs every year. In pleasure-grounds of limited extent, a few plants of the Tuberose in flower, distributed over them at distances of fifty or one hundred yards plant from plant, will diffuse a most delightful fragrance in the summer and autumnal evenings ; a circumstance well understood in the public gardens in the vicinity of Paris.

**POLMAISE HEATING.**—The principle of this mode of heating is to imitate the natural atmosphere of a hot climate by allowing the plants a constant change of heated air ; and it differs from Penn's system, with which it has been compared, in supplying a constant current of fresh air, instead of merely allowing the same air to circulate through the house again and again. This mode of heating was first used in a stove erected at Polmaise, in Stirlingshire ; but afterwards the stove was very much improved by the late Mr. Meek ; and various modifications of the system have been since suggested.

The annexed description and figure of Polmaise Heating are copied from the *Gardeners' Chronicle* for Feb. 2, 1846. "Let the

outer shaded lines A A (in fig. 41) represent the walls of a span-roofed hothouse, and B those of a hot chamber, the sides and roof of which it will be well to line with some non-conducting material ; the second shaded lines within A represent the walls of a bark bed. The portion of the floor marked C C, beneath the bark bed and extending towards the hot chamber in the direction of the dotted lines, is to be laid hollow, and its supports so arranged as to allow of free atmospheric communication beneath it. Between the wall of the bark bed (extending round its three sides), and the lines D D D D, is an opening through which the air of the house may have free passage into the space beneath. The arrows indicate the direction of the atmospheric currents passing beneath the floor and the wall of the house into the hot air chamber at E E, and here a small portion of the air is divided from the rest, as shown at F, where there are two dampers, No. 1 acting horizontally, and No. 2 vertically. By means of No. 2 a perfect command is obtained over the quantity of air supplied to the fire, and borne away by the ceaseless currents flowing onwards from beneath the floor of the house. The water-trough O is to be furnished with a screen, extending in front and over the hot air opening, so that the escape of the latter into the house will not fully take place till it has passed over a considerable portion of the surface of the water in the trough." Notwithstanding the improvements made by Mr. Meek, who adopted the system and followed it up with the utmost enthusiasm, it has never gained ground in practice, and indeed it may be said to have fallen into disuse.





POLYA'NTHUS.—See PRI'MULA.

POLY'GALA.—*Polygaleæ*.—Milk-wort.—Very handsome greenhouse shrubs, natives of the Cape of Good Hope, which should be grown in a compost of two-thirds peat, and one-third of very sandy loam, or equal parts of peat and sand, with one-third of vegetable mould, may be used; the pots should be well drained, and the plants frequently watered. When it is wished to raise young plants, the tips of the shoots should be taken off about three inches long, and struck in sand under a bell-glass. All cuttings of the shrubby Polygalas are very apt to damp off, and therefore the glasses should be frequently taken off and wiped. *P. cordata*, *P. myrtifolia*, *P. Dalmaisiana*, and *P. speciosa*, are all very fine species. The flowers of the latter are the largest of the genus, and those of *P. Dalmaisiana* are of a rich and brilliant violet. There are other kinds of Polygala, natives of Europe, which are herbaceous perennials; and others which are natives of North America, some of which are annuals and some perennials. All the herbaceous Polygalas are hardy dwarf plants, very suitable for rock-work; and they may be grown in any common soil, though they prefer peat or very sandy loam. Some of the kinds of Polygala are now included in the genus *Muraltia*, the type of which is *P. Heisteria*; and others in the genus *Mindia*, the type of which is *P. spinosa*.

POLYGO'N'UM.—*Smilacææ*, or *Asphodellææ*.—Solomon's Seal.—Hardy perennial plants which require no other care than planting in any common garden soil. They will thrive either in exposed situations, or under the shade of trees, but the flowers are generally largest

when the plants are grown in the shade. They are sometimes included in *Convallaria*.

POLYGO'NUM.—*Polygoneæ*.—This is a very extensive genus and embraces a great many very different plants; some of which are British weeds, and others stove plants from the East Indies or New South Wales. Some of the commonest kinds in British gardens are the Buckwheat (*Polygonum Fagopyrum*), the Garden Persicaria (*P. Persicaria*), and the Water-pepper (*P. Hydropiper*), the beautiful pink flowers of which are so ornamental in the ponds in Kensington Gardens and other places. Plants so various in their nature require of course different kinds of soil and situation; but they will all grow in sandy loam, and are generally of the easiest culture.

POLYPO'DIUM.—*Cryptogamia Filices*.—An extensive genus of very beautiful Ferns, some of which are natives of Britain, and others are exotic. All Ferns should be grown in shady, damp places; and the hardy ones thrive most in a shrubbery under the drip of trees, where few other plants will grow. The exotic kinds should be grown in a stove glazed with green glass; and the atmosphere should be kept damp by water being frequently poured on the floor and flues.

POMADE'RRIIS.—*Rhamnaceæ*.—Australian shrubs with cymes of yellow flowers and generally of woolly leaves, nearly allied to *Ceanothus*. They are very nearly hardy, and may be grown in the open air with a little protection during winter. They should be grown in sandy peat, or in a mixture of peat and loam; and they are propagated by cuttings.

POMEGRANATE.—See PU'NICA.

PONTEDE'RIA.—*Pontederacææ*.—

Stove aquatics, that should be planted in rich loamy soil, and the cistern filled up with water. They are increased by dividing the roots.

POPPY.—See PAPA'VER.

PORCUPINE CACTUS.—See KOHINOCA'CTUS.

PORTUGAL LAUREL.—*Cerasus lusitánica*.—A handsome evergreen shrub, which thrives best in moist shady situations, and which sometimes attains the size of a tree. In Ireland, Portugal Laurels attain an enormous size, the moisture of the climate suiting them admirably.

PORTULA'CA. — *Portulacææ*. — Splendid annual plants with succulent stems, fleshy leaves, and brilliantly coloured flowers. *P. Thelusnii* and *P. Gilliesii* are among the most splendid of the species. They are natives of South America, and require to be raised on a hot-bed; they may be grown in the greenhouse, or planted out in any warm soil, but that which is sandy or gravelly suits them best. In potting, the soil should be mixed with lime rubbish. The *Portulacas* are well adapted for baskets, borders, and rock-work; they withstand drought and strong sun, and are therefore very useful in hot dry seasons.

POTENTILLA.—*Rosacææ*.—A genus of herbaceous plants and one or two shrubs, the greater part of which are ornamental, and some eminently so. They all thrive in any common soil, and are readily increased by division of the plants, or by seeds, which most of them produce in abundance. They also hybridise freely, from which new kinds are frequently raised by florists. The principal shrubby species is *Potentilla fruticosa*, which forms a hardy bush, commonly between two feet and three feet high, and produces abundance of yellow

flowers in July. The most ornamental herbaceous species is *P. Russelliana*, with rich dark scarlet flowers. All the herbaceous species are low, few of them exceeding one foot in height, and the greater part not being above six inches. They are delightful plants for pots or for rock-work, and the whole are so hardy and of such easy culture, that they will bear neglect better than most other inhabitants of the border or the flower-garden.

POTTING.—The subject of potting plants may be considered in two ways; first, with reference to the advantages of that mode of growing plants as compared with growing them in the free soil; and secondly, with reference to the performance of the operation of potting. Plants growing in pots are placed in very unnatural circumstances, from the limit given to the extension of their roots by the small quantity of soil and the confined space of the pot; and by the circumstance of the outside of the pot being constantly exposed to the action of the air on every side. In consequence of these conditions, the roots of plants in pots are alternately scorched and cooled, and dried by the action of the atmosphere; and as, to keep the plants alive, they require to be frequently watered, the soil soon becomes soddened, or soured as it is called by gardeners, and the plant is either checked in its growth, or becomes diseased. Nevertheless, by well-considered treatment, plants may be grown in pots to a high degree of perfection, and some kinds better than in the free soil. For this purpose, two things are more especially requisite; the first is to provide sufficient drainage for the escape of superfluous matter; and the second is to cover the sides of the pot by some medium which

shall prevent the action of the surrounding air in heating or drying the outside of the pot, and consequently the soil and roots within. Every pot, tub, or vessel, in which a plant is grown, contains a hole or holes in the bottom or lower sides; and these are to be prevented from being closed by the soil by a covering of potsherds, shells, or small stones, covered with turfy matter, over which the soil in which the plant is grown is to be placed. To prevent the sides of the pot or vessel in which the plant is grown from being scorched or dried by the heat of the sun, the pot is plunged in soil, or in moss, or some other porous matter, or the pots are placed sufficiently near together to shade one another. Different kinds of plants require different degrees of drainage, and of protection from the sides of the pot. For example, all Orchidaceous plants, succulents, and hair-rooted plants, such as the *Ericaceæ*, require a great deal of drainage; and all plants which require rich moist soil, such as the *Scitamineæ* and many of the most vigorous-growing tropical herbaceous plants, require the sides of the pot to be protected by plunging it in tan, sand, ashes, soil, moss, or some other non-conducting medium, which will not be readily permeable by drought or heat.

With respect to the operation of potting plants, when seedlings or plants newly-rooted by cuttings, layers, or other means are to be potted, a small pot is chosen, either of the least size, or a size somewhat larger, according to the bulk of the plant to be planted, or its known vigour of growth. The hole in the bottom of the pot being covered with one or more potsherds, and with some rough turfy, rooty, or mossy matter, or with coarse gravel,

some soil is put in over it. On this the roots of the young plants are placed and spread out, and soil is placed over them till the pot is filled, as before mentioned under the article *PLANTING*. The soil in the pot is then consolidated by shaking, and lifting up, and setting it down once or twice with a jerk, the soil round the edge of the pot being rendered firm by the thumb, or by a stick, as already mentioned. Plants of larger size, without balls of earth attached to the roots, are planted exactly in the same manner, excepting that the pots chosen are larger in proportion to the size of the plant. Plants which have grown in the free soil during summer, such as *Pelargoniums*, *Fuchsias*, *Myrtles*, and such other plants as are turned out of pots into the open garden in the beginning of summer, and taken up and repotted about the latter end of autumn, are commonly taken up with balls; and when this is the case, the pot chosen must be of a sufficient size to admit of the ball of earth without breaking it. Previously to the taking up of these plants, more especially when they have grown with great vigour, it is found advantageous to cut the roots all round about the same distance from the main stem as the size of the ball was when put into the ground; by which means the plant receives a check before it is taken up, and is prepared to endure the still greater check which it will unavoidably receive when potted. This precaution is more especially requisite for such strong-growing plants as the *Brugmansias*, *Fuchsia fulgens*, *Scarlet Pelargoniums*, *Stocks*, *Wall-flowers*, &c. All plants, after being newly potted, should receive a sufficient quantity of water to moisten the whole of the soil in the pot; and

all of them require to be shaded, to prevent excessive transpiration till they have begun to grow.

Plants in pots which are to be transplanted into other pots with the ball entire require comparatively little care. The new pot should be at least one size larger than the old one out of which the plant is to be taken, and, being properly drained, and some mould put over the drainage, the plant to be changed is turned out of the first pot by turning it upside down, holding the left hand on the surface of the soil in the pot, and with the neck of the plant between the two middle fingers, while the bottom of the pot is held with the right hand, and then the ball is loosened by the edge of the pot being struck against any fixed object, such as the side of a potting-bench, or the handle of a spade stuck in the ground. The ball containing the plant will thus drop out into the left hand, and the potsherds that have come out with it being taken off with the right hand, the ball thus prepared is set in the middle of the prepared pot, and the interstices between the ball and the sides of the new pot are filled in with earth, and made firm by a potting-stick. The pot may then be lifted up with both hands and set down two or three times with a jerk, so as to consolidate the whole. The pot is then to be supplied with water to such an extent as to moisten the whole of the earth which it contains; and it may be set where it is finally to remain without the necessity of shading. This operation is called shifting.

In potting plants, whether in small or in large pots, it is essentially necessary that the inside of the pot should be perfectly clean and dry. If it is not clean, and if

particles of earth are adhering to the sides of the pot, the fresh soil put in when the plant comes to be shifted will so adhere to the matter attached to the sides as to prevent the ball from being turned out without breaking, and tearing asunder the fibrous roots of the plant. When the sides of a pot in which a plant is to be planted, or a ball shifted, are wet, the new soil becomes sodden or soured, and also adheres so firmly to the sides of the pot as not to come out in shifting without breaking, as in the preceding case. The soddening or souring in this latter case appears to proceed from the choking up of the pores of the sides of the pot.

POTSHERDS, or crocks, are pieces of flower-pots, tiles, or bricks broken very small, and used for draining pots where it is required to retain a certain degree of moisture round the roots of the plants. Thus potsherds should be used for hair-rooted plants, such as the Cape and Australian shrubs, and also the North American Rhododendrons and Azaleas; as they require to have their roots kept in an equable state of moisture, which would be destructive to the Cacti and other similar plants. But cinders, when of a large size, are very useful in draining pots for very delicate succulent-rooted plants, as they do not either absorb or retain moisture, which crocks always do. When cinders are sifted, the largest may be reserved for this purpose; and the ashes that fall from them, or any coal too small to burn, will be useful for setting greenhouse plants on during summer, as they will prevent worms from coming out of the ground under them. Unless this precaution be taken, worms will creep through the holes at the bottom of the pots, and do great injury

to the plants, by tearing asunder the tender fibres of the roots in passing through the mould, and particularly in throwing up their casts.

**POTTING-STICK.**—An instrument made of wood, and resembling a paper-knife, but thicker and blunter at the extremity. Its use is to push the earth into the pots when plants are shifted or transplanted, and it prevents the necessity of using the thumb for that purpose, as is generally done by gardeners. Potting-sticks may be made of different sizes according to the size of the pots.

**PRICKLY PRAR.**—See *OPUNTIA*.

**PRIMROSE.**—See *PRIMULA*.

**PRIMULA.**—*Primulaceæ*.—The Primrose. — This genus includes three of the most popular and beautiful of florists' flowers, viz., the Auricula, the Polyanthus, and the Primrose. Of each of these three there are numerous varieties, and much has been written on their culture and management. I shall here endeavour to give a short outline of the treatment of each.

The Auricula (*Primula Auricula*) is a native of the Alps of Switzerland, where its flowers are commonly yellow and very fragrant; it may be gathered in abundance on the road-side on the highest part of the pass of the Simplon, growing with the different Saxifrages, and not far from *Rhododendron hirsutum*. When it was transplanted into gardens is uncertain, but it has been cultivated in Britain since the days of Gerard, in 1596; and in a state of cultivation its flowers are yellow, red, blue, purple, white, and green, and sometimes double, though the only double variety has the flowers yellow. Many elaborate directions have been given for preparing the soil for the Auricula;

and while some writers, as Justice, recommend rotten willow-wood and old cow-dung, others, as Emmer-son, recommend bullock's blood, sugar-baker's scum, and concentrated night-soil. The plants, however, will grow and thrive on any rich loamy soil; for example, in a mixture of leaf-mould, or thoroughly rotten cow-dung and loam. They will even grow very well in heath-soil mixed with loam, and this is the soil in which they are commonly grown in the neighbourhood of Paris. Whatever kind of manure is used for the Auricula, it should be so thoroughly decomposed as to have become a fine mould, and, in this state, it may be mixed with the common soil of gardens in equal parts, with the addition of a fifth or a sixth part of coarse sand if the plants are to be grown in pots. All the choice varieties of Auricula are grown in pots, and kept under cover in glass frames shaded; or placed in a northern exposure during winter and spring, and in the open air in a situation open to the east, or the west during summer after the flowering season is over. During the time they are in flower, they are commonly kept in frames close under the glass, or under hand-glasses, to protect the flowers from the rain; the flowers in all the varieties, and the leaves in some, being more or less covered with a powdery bloom, the preservation of which is a desideratum among choice cultivators. The Auricula is propagated by division of the root, or by cutting off slips which have generally some roots attached, and are put at once into small pots. The season for performing the operation is shortly after the flowers have gone off, or, if they are left on, immediately after the seed has ripened. There are common kinds

of Auricula which are planted in borders or in beds in the open ground ; but, as before observed, all the choicer sorts are grown in pots and kept in pits or frames. The culture requires so much care and nicety, that whoever would excel in it, and possess a good collection, should procure a book especially devoted to the culture of this and other florists' flowers ; for example, Hogg's *Treatise on the Auricula*, or Maddock's *Florists' Directory*. Auriculas, when grown as florists' flowers, have almost innumerable names ; but they may be all divided into three classes, viz., those with green edges, those with grey edges, and those of only one colour, which are called selfs. No Auricula is valued that is what is called pin-eyed, that is, if the style and stigma appear above the anthers.

The Polyanthus (*Primula vulgaris* var. *caulescens*) and the Primrose (*Primula vulgaris* var. *acaulis*) are cultivated in the same soil and in the same manner as the Auricula ; but being much hardier, and also naturally stronger, a larger proportion of loam is used in the soil, and only the more choice sorts are grown in pots. Both Polyanthus and Primroses form most ornamental border flowers in early spring, but only the Polyanthus is what is properly called a florists' flower. The colour of the flower of the Polyanthus is always yellow and brown, and the finest flowers are those that have the segments of the corolla flat, and the circumference marked with a yellow line, the anthers of the stamens being only visible, and not the pistil, the anthers being arranged symmetrically, so as to form what florists call a moss eye. Sometimes the anthers are not seen, but the style and stigma stand up conspicuously

like a large pin, and when this is the case, the flowers are called pin-eyed, and are considered worthless. The double Polyanthus, and the red and white Hose-in-hose Primrose, are two varieties, having double corollas, which may be called botanists' varieties, and are ornamental border flowers, but are not valued by florists. Besides these, however, there are a great many florists' varieties with names, which are cultivated in pots like Auriculas. As these plants vary so much it is interesting to raise them from seed, which may be done in the following manner :—The seeds may be gathered when the capsules are ready to burst in July, and sown immediately in a shady border, or in pots or pans of loamy soil kept moist and shaded. The covering should be very slight, otherwise the seeds will not come up. In fine seasons seeds sown as soon as they are gathered, will produce plants which will flower in the following autumn ; but in general it is necessary to wait till the next spring. When the seedlings have produced two or three leaves, they should be transplanted into rich loamy soil in a shady situation at the distance of a few inches from each other ; and as they come into flower, the good sorts should be marked, and the less admired kinds pulled up and thrown away. When the seed is not sown immediately after being gathered, it may be kept till the following March, and treated as above mentioned. Auricula seed requires exactly the same treatment ; excepting that it is generally sown in pans of soil composed of a mixture of leaf-mould and loam, and the seedlings are transplanted into larger pans, or into single small pots. *P. denticulata*, *P. cortusoides*, and many other species, are

very ornamental low plants, which generally require a loamy soil, and a somewhat moist situation.

The Primrose is very ornamental as a border flower, but it has not sported so much as the Polyanthus, and there are therefore no florists' Primroses. The border or garden varieties, however, which are mostly double, are very showy; among these the double flesh-coloured, double white, double brimstone, double red, double copper, double dark-purple, and double violet, deserve a place in every garden. The single white and the single red, both of which are found wild, are also much admired, and are valuable as coming into bloom in March. Plants may be raised from seed, as directed for the Polyanthus.

*P. sinensis*, the Chinese Primrose, is a very beautiful greenhouse plant, of which there are varieties with pink, with white, with semi-double flowers; and finally, there is the *P. sinensis fimbriata*, the fringed Chinese Primrose, of which there are also many sub-varieties of different colours. All these are particularly valuable, as forming neat little plants and flowering throughout the winter. They are propagated by seeds, which generally come true to the variety; or by cuttings, which must be struck in sand under a bell-glass, and with bottom-heat. They are only biennials; and therefore new plants require to be raised every year. They are generally grown in pots, which should be well drained with potsherds, and filled up with a rich compost of equal parts of loam, peat, or sand, and rotten dung or vegetable mould.

PRINCE'S FEATHER. — *Amarantus hypochondriacus*. — See AMARANTUS.

PRINOS. — *Rhamnaceæ*. — Hardy

North American shrubs, that will grow in any light soil, though they prefer peat, and any situation. They are generally propagated by layers.

PRIVET. — See LIGUSTRUM.

PRONA'YA. — *Pittosporaceæ*. — *P. elegans* is a very pretty little twining plant with purple flowers, a native of the Swan River Settlement. It is easily propagated by cuttings; and, like most other Australian plants, it thrives in a mixture of sand, loam, and peat; but it should be grown in very small pots, and not kept too moist. It is a valuable greenhouse plant, from the great abundance and long duration of its flowers. It looks best trained to a trellis.

PROPS are artificial supports for plants; and they are of various kinds, according to the nature of the plant that is to be supported. Twining plants are supported by single rods, stakes, or poles without branches; plants which climb by tendrils are supported by branched rods; and plants which raise themselves by elongation, or long slender shoots, among other plants, are supported artificially by branched rods, or by being tied to simple rods. All these kinds of plants, when too tender to be supported in the open garden, are trained to walls, which are the universal supports of plants, whether of the hardy and ligneous kinds, or of such as are slender, somewhat delicate, and either naturally climbing, such as *Bignonia capreolata*, — or rambling or trailing, such as different kinds of Roses. Ornamental plants grown in pots are sometimes supported by single rods of wood, or of iron or wire, and sometimes by small frames either of wood or iron. These frames may either be flat and of equal breadth from the surface of the pot up-

wards; or they may be widest at top, which suits most sorts of climbers; or they may be made in the form of cones, pyramids, inverted cones, or balloon-like shapes, at pleasure. A very common form for such plants as *Tropæolum pentaphyllum*, *T. tricolorum*, and *T. brachyceras*, is that of an elongated fan; and another is that of a shield-like figure with the narrow end at the pot. In general, all plants grown in pots should have the support of



FIG. 42.—PROPS FOR CLIMBERS.

a regular or symmetrical shape; and all those grown in beds or borders, such as Sweet Peas, the Common *Tropæolum* (*Nasturtium*), the Scarlet Runner, &c., should have small branchy stakes inserted in the soil in a regular manner, so as never to appear the work of chance or of carelessness, but of art and careful design. Climbing Roses may either be supported by training against walls or trellis-work, or on single

rods, with expanding parasol-like tops of wire-work; or they may be supported on cones or pyramids of rods or poles. The stronger-growing climbing Roses, which attain the height of twenty feet, or thirty feet, or upwards, such as the double Ayrshire Rose, the Rose de Lisle, the Boursault, *R. Grevillii* or the Seven Sisters, Noisettes, &c., may be supported on cones or pyramids, two feet or three feet in diameter at the ground, and rising to the height of twenty feet, formed of the stems of young Fir-trees tied together; tender Roses, on the other hand, such as *R. Banksia*, and the Musk Rose, require to be trained against walls. Props for border-flowers are generally small rods painted green, and made by splitting the laths used by plasterers or by carpenters from deal boards; but they may be straight rods of hazel, or some such wood, with the bark on. The object of using the rods of this kind is to render the props less conspicuous. The principle to be taken as a guide is, that the rod should always be subordinate to the plant to be supported by it, or trained on it. If this principle be kept constantly in view, few glaring errors will be committed either in forming supports for plants in pots, or for plants in the open ground. Hence walls on which plants are to be trained should never be built of bright red brick, or very white stone; or if they are plastered, the colour should always be of a subdued kind. Some plants are trained up rods or cones for the sake of producing flowers; and others, such as Ivy, when trained up an erect rod with an umbrella-like top, for the sake of producing shade. When the object is flowers during the whole extent of the plant, the prop should always be



wider at the base than at the top, in order that the foliage may enjoy the direct influence of the sun and of perpendicular rains during its whole extent; and this may easily be effected by fixing a pole in the ground with short sticks in the top, to which chains, ropes, or wires may be affixed, up which the plants may be trained. When the flowers are chiefly to be produced at the top, and the object of the stem is merely to elevate the top to a considerable distance from the ground, then the latter must spread over the former as much as may be desirable for the sake of effect. In like manner, when the object is shade, or the covering of a summer shelter or bower, the stems may be trained upright and may be shaded to any extent by the head.

Wire frames for training plants in pots are generally painted green, for the same reason as the props. In supporting large flowers, such as Dahlias, or shrubs, such as standard Roses, in the open garden, stakes of cast or wrought iron are frequently used, and the colour they are painted is almost always green, though a dark-brown colour, or some tint nearer that of the bark of rods, say those of the ash or hazel, would undoubtedly be in better taste. Twining plants, such as the *Convolvulus*, are frequently encouraged to twine round cords made fast at the root of the plant at one end, and to a wall, horizontal rail, or some other fixed point or line at the other. Very handsome screens may be formed in this manner, and also very agreeable figures, provided care is taken that the figure shall not be much broader at the summit than it is at the base. An obelisk, a column, a cone, a pyramid, or a cross, in an open airy situation, may be covered so as to produce a

very striking effect. Arcades and covered ways, formed of framework of wood or wire, may be covered with creepers of every description, ligneous or herbaceous; but the beauty of the flowers is only seen externally, and the advantage to the spectator walking beneath is shade alone. When shade and the beauty of the flowers are to be both enjoyed by the spectator in a covered walk, the covering ought to be produced by arches placed at regular distances, so as to admit of the air and light between, by which means the plants will be covered with flowers from the ground to the crown of the arch. The arches may either cross the walk at right angles, or they may cross each other, so that the vertical profile of every two arches would form a cross.

Trees, after they have grown for some years, frequently lean to one side, especially such trees as the Judas tree, the Mulberry, the Pinaster, and even the Laburnum. These require props to set them upright, and the kind requisite for this purpose is a wooden prop forked at the extremity. In like manner, the branches of trees sometimes split, or for other reasons hang down, so as to incommode the path or the surface beneath; and in this case the branches require to be tied together by iron rods.

PROSTANTHERA. — *Labiata*. — *P. Lasianthus* is a half-hardy Australian shrub, with flowers in loose clusters, purple and white, and which has a good effect amongst rock-work. Easily propagated by cuttings, and will grow on any soil, not cold or wet; but requires protection in winter.

PROTEA. — *Protea*. — Singular-looking plants, natives of the Cape of Good Hope, which are very

difficult to cultivate, as their roots are fleshy and very apt to be injured either by a want of water or an excess. They must also have abundance of light and air, and not be crowded with other plants. They should be grown in pots nearly half filled with potsherds, in light turfy loam, mixed with equal parts of fine silver sand, and placed in a greenhouse. Great care must be taken in shifting them when they require larger pots, as their roots are very brittle, and will be found to have entwined themselves among the potsherds, from which it is very difficult to disengage them, and for this reason the drainage should not be disturbed, but transferred entire with the ball of earth to the new pot. These plants are propagated by cuttings taken off at a joint, and planted in separate pots in sand, under a glass, but not plunged in a hotbed; and the glass should be frequently taken off and wiped, as the cuttings are very apt to damp off.

**PROTECTING TRELLISES.** — In some cases where half-hardy plants are grown in the open garden they are trained on trellis-work, with a framework of coarse wood fixed at the base of the trellis, so as to form a kind of moveable pit over it. In this frame sashes are placed to shield the plants during cold weather, and the whole apparatus, except the trellis, is removed in May or June, when the flower-buds have formed. In this way some of the finer kinds of Passion-flower, the Allamandas, and other tender climbing plants may be grown, apparently in the open air.

**PROTECTING.** — As half-hardy plants, trained against a wall, are frequently much injured by what are called perpendicular frosts, a thatched or wooden coping, project-

ing about two feet from the wall, will be found of the most essential service in protecting them. Such a coping, with a sprinkling of straw or dead leaves over the roots, and a hay-band twisted round the trunk of the tree, about a foot from the ground, will be sufficient to protect even tender plants from all ordinary frosts. Standard plants may have straw or dead leaves laid over the roots, or they may have a thatching of straw attached to the trunk of the tree, and sloping off widely at the base. (See **THATCHING.**) Other coverings made of straw or rushes plaited or sewed together, or of




FIG. 43.—WIRE FRAME.

osiers twisted like basket-work, may be used for smaller plants. One of these may be a kind of hurdle to protect plants against a wall, others may be used to put round the stems of young trees, and to cover Tree Pæonies and other tall shrubs, with an opening on the side next the sun, to admit the air and prevent damp; and others are small beehive-like covers for protecting Geraniums or other greenhouse plants in the borders. Sometimes a slight wire frame is used, like that shown in fig. 43, which may be covered with a mat. A frame of this kind is particularly useful for the Tree Pæony. For the modes of protecting trees from the attacks of cattle, see **SINGLE TREES.**

PRUNING ornamental trees and shrubs is seldom practised to much extent; as all that is required is to cut out the dead wood and to prevent the shoots from growing out of shape. To do this effectually, every lady ought to be provided with a pair of pruning-shears (see fig. 44), so contrived as to make




FIG. 44.—PRUNING-SHEARS.

what is called a draw-cut, and thus not to bruise the wood or the bark so as to prevent its uniting again smoothly. The cut should also be made slanting to a bud, so as not to leave a piece of dead wood projecting beyond the young shoot, which has always a very bad effect. Much of the beauty of a flower-garden depends on removing the dead Roses and other flowers as soon as they fade, and also all the dead or broken branches; but this is a point of culture which is very rarely properly attended to. The French instrument called a *sécateur* is only a somewhat larger and stronger pair of pruning-shears.

PRUNUS.—*Rosaceæ*.—The Plum. Though the common plum-tree ranks among fruit-trees, and as such is not entitled to a place in the present work, yet there are many species of *Prunus* which may be considered as

some of our most ornamental shrubs. Among these are *P. cándicans*, with woolly leaves and long clusters of white flowers; *P. Cocomilla*, a native of Italy; *P. maritima*, with white flowers and dark blue fruit; and *P. divaricata*, with white flowers and yellow fruit. There are many other ornamental shrubs which are called *Prunus* in the nurseries, but which botanists now class in the genus *CERASUS*. Among these are the Mahaleb or Perfumed Cherry, formerly called *Prunus Mahaleb*; and the Bird Cherry, which Linnæus called *Prunus Pádus*. All the kinds of *Prunus* are quite hardy, and will grow in any common soil.

PSIDÍUM.—*Myrtáceæ*.—The Guava.—Tropical shrubs, which are generally grown in a stove in England, but one kind of which, Cattley's Guava, will ripen fruit in a greenhouse. In the West Indies the fruit is used for making the well-known Guava jelly. All the kinds should be grown in loam and peat, and they are all propagated by layers.

PSORA'LEA.—*Legumínosæ*.—Shrubby and herbaceous plants, of easy culture, some of which require a greenhouse in England. They grow freely in loam and peat, and are propagated by seeds or cuttings. Most of the species are natives of the Cape of Good Hope.

PTE'LEA.—*Terebintháceæ*.—American shrubs, quite hardy in British gardens, and ornamental for the fine yellow which their leaves take in autumn. They will grow in any garden soil, and they are multiplied by cuttings and layers.

PTE'RIS.—*Filices*.—Brake. A very ornamental kind of Fern. For the culture, see POLYPO'DIUM.

PULMONA'RIA.—*Boraginææ*.—Herbaceous plants with spotted

leaves, and rather ornamental flowers, natives of Europe and America, which will grow in almost any soil and situation.

PU'NICA.—*Granatæceæ* or *Myrtidæceæ*.—The Pomegranate is a very handsome deciduous shrub or low tree, which, in the climate of London, thrives against a conservative wall, and produces fruit which attain their full size, though they but seldom ripen. It also grows in great luxuriance near Bath. The fruit, which is of a globular shape, and retains the calyx, has been admired for its form from the earliest ages, and was one of the most conspicuous ornaments directed to be used in the construction of Solomon's Temple. There is a double-flowered variety, which, during the seventeenth and eighteenth centuries, was the most favourite plant in continental and British orangeries, next to the Orange and the Lemon; and there is also a dwarf double-flowered variety, which when kept in a greenhouse, produces its fine vermilion flowers from August to November. The plant requires a dry loamy soil, a south wall, and an airy situation; and care should be taken in pruning it not to cut out the small lateral twigs or spurs, on which alone the blossoms are produced, which should be left projecting from the wall. It strikes root freely from ripened cuttings and layers, and the yellow and the white-flowered varieties are sometimes grafted on the common kind.

PU'RSIA.—*Rosæceæ*.—A little North American shrub, with small yellow flowers, which is quite hardy, and should be grown in sandy peat. It is propagated by layers.

PYRÆTHRUM.—*Compósitæ*.—Feverfew.—Most of the species are hardy perennials, which only require planting in the open garden and the

usual treatment of perennial plants. According to the last arrangements of botanists, the Chinese *Chrysanthemums* are now included in the genus *Pyræthrum*.

PYROLA.—*Ericæceæ*.—Wintergreen. A pretty little shrub, one species of which, *P. rotundifolia*, is found wild in Sussex.

PY'RUS.—*Rosæceæ*.—The Apple and Pear Trees. The different kinds of Crabs and Pears are very ornamental from their blossoms, independently of the utility of the fruit of some of the species. The ornamental kinds are all low trees, admirably adapted for the lawn or the shrubbery; they are all of easy culture in any common garden soil; and they are propagated by grafting the finer on the more common kinds. To thrive and look well, however, they require an airy situation, and not to be crowded among other trees. Most of the species, and especially the Crabs, are very liable to be attacked by insects in the leafing and flowering seasons; and they should then be carefully watched, and the caterpillars picked off as soon as they are visible. Among the kinds most worthy of notice, are the following: *Pyrus spectabilis*, the Chinese Crab or Garland-flowering Wild Apple, producing the most showy flowers of the whole genus in May, and as hardy as the common Crab or Wild Pear. *P. coronaria*, the Sweet-scented Crab, with large and beautiful pink blossoms, highly fragrant, as is the first. *P. c. angustifolia*, the narrow-leaved sweet-scented Crab, with blossoms as beautiful as the former, and with the leaves sub-evergreen. This, and the two preceding kinds, have the fruit green when ripe, and fragrant, but it is not good to eat. *Pyrus baccata* and *P. prunifolia*, the two kinds of Siberian Crab, have very showy

blossoms, and small red or yellow fruit, useful in cookery. These are the principal ornamental species of the Crab or Apple kind, unless we except one, the Moscow or Transparent Crab, *Pyrus astracínica*, which has fruit nearly as large as a golden Pippin, wax-coloured, and almost transparent when ripe. Though commonly cultivated for its fruit, as useful for the table, it well deserves a place on the lawn as an ornamental plant, from the extraordinary beauty of the Crabs. The more ornamental Pears are the following: *P. amygdaliformis*, which has silvery-white leaves, and fruit shaped like that of the Almond; *P. elæagnifolia*, which has long narrow white leaves like those of the Elæagnus; *P. salicifolia*, with long, narrow, silky leaves like those of the Willow; and *P. nivalis*, which has round leaves of a snowy whiteness. All these species have small green fruit, not good to eat; but the trees are most ornamental from their shape and the singular colour of their foliage. The following kinds of *Pyrus* belong to the section of *A'ria*. *P. torminalis*, the Gripping Wild Service tree, is remarkable for the beautiful form of its leaves, which, however, are unfortunately very apt to be eaten by insects. The buds are large, of a beautiful green, and very ornamental in the winter season. *Pyrus aucuparia*, the Mountain Ash, is a well-known small tree, beautiful both when in flower and in fruit, and worth cultivating for its foliage alone. *Pyrus americana*, the American Mountain Ash, resembles the common sort, but has larger leaves and smaller fruit, though it is of a much deeper red. *Pyrus Sorbus*, the common Service Tree, has foliage like that of the Mountain Ash, but larger; and the fruit resembles that

of the common Pear, but much smaller, and not ornamental though it is eatable.

The following kinds of *Pyrus* are shrubs, and very ornamental, both for their fruit and flowers: *P. arbutifolia*, which has white flowers and black fruit, and the leaves of which become of a beautiful red in autumn; there are six or eight varieties, commonly treated as species: *P. Chamæspilus*, which has large white flowers and red or black fruit; and *P. floribunda*, which grows about four feet high, and sends down weeping branches all round, which are covered with such a profusion of white flowers during the flowering season, that the plants look like a hillock, covered with snow. These last-mentioned shrubby kinds are sometimes called *Arónia*. *Pyrus japonica*, so well known for its beautiful scarlet flowers, is now removed to the genus *Cydonia*. There is a variety with pink and white flowers. All the kinds belonging to the genus *Pyrus* are quite hardy, and will grow freely in any common garden-soil, and they may all be raised from seeds, or grafted on the Wild Crab, or Wild Pear, or on the Hawthorn, which, though belonging to the genus *Cratægus*, is very nearly allied to *Pyrus*.

**QUAKING-GRASS**—See BR'ZA.  
**QUASSIA**.—*Simarubacca*.—Stove shrubs, natives of the East Indies, the bark, wood, and root of which are so intensely bitter, that an extract from the bark of some of the species is used as a substitute for hops in making beer, and also as a poison for flies and aphides. *Q. amara* is very ornamental from its long upright racemes of bright scarlet flowers, the petals of which

are curiously twisted together. The plants flower freely, if allowed plenty of heat. They should be grown in loam, mixed with peat or sand; and they are propagated by cuttings.

QUEEN'S NEEDLEWORK. — *Spiræa salicifolia*. — See SPIRÆA.

QUERCUS. — *Amentacea*, or *Cupulifera*. — The Oak. — The species are chiefly forest trees, but *Q. Ilex*, the evergreen Oak, and some of its varieties, may be treated as shrubs, and are very ornamental on lawns, and in pleasure-grounds. Some of the kinds of the Turkey Oak, *Q. Cerris*, are also very ornamental, particularly *Q. C. Lucombeana*, which grows rapidly and forms a very handsome pyramidal tree. It ought, however, to be purchased in pots, as it produces but few lateral roots, and seldom grows well if it is transplanted from the open ground. The American Oaks are very handsome, particularly for the colours their leaves take in winter. *Q. coccinea* and *Q. rubra* have deeply cut leaves, which become of a beautiful red in autumn; as do the leaves of *Q. palustris*, which are more elegantly shaped than those of any of the other kinds. Some of the dwarf American Bear Oaks, such as *Q. Banisteri* and *Q. ilicifolia*, do not grow above two or three feet high; and they are called Bear Oaks, because in their native countries the bears can eat their acorns, without climbing.

QUINCE. — See CYDONIA.

QUINCUNX. — A mode of planting trees in rows, by which the plants in one row are opposite the spaces in the next; so as to form a succession of diamonds. — See fig. 45, A and B.


But the term quincunx, although frequently used with reference to planting, is nevertheless differently

and imperfectly understood by many persons. Some understand it as a mode of planting, by which five trees are planted, so that one shall be in each corner of a square and one in the centre, where the diagonals cross. Others vaguely suppose that whilst the trees in one row are opposite the spaces in the next, the plantation must be in quincunx. The French authors, however, define the term more precisely to be that arrangement by which all the plants in a plantation are equidistant from each other, consequently their tops are not crowded on one side more than on another, and thus grow equally balanced. This is an advantage, whether the plantation be trees, shrubs, or flowers; and it is surprising that the mode is not more adopted than



FIG. 45. — TREES IN QUINCUNX, A,

nals cross. Others vaguely suppose that whilst the trees in one row are opposite the spaces in the next, the plantation must be in quincunx. The French authors, however, define the term more precisely to be that arrangement by which all the plants in a plantation are equidistant from each other, consequently their tops are not crowded on one side more than on another, and thus grow equally balanced. This is an advantage, whether the plantation be trees, shrubs, or flowers; and it is surprising that the mode is not more adopted than



AND EQUIDISTANT, B.

it is, and also that the principle of the arrangement should not be clearly understood by some who have the important operations of planting to conduct. We shall endeavour to explain it as briefly as

possible, and at the same time clearly enough, we presume, by reference to fig. 45, D.

It is essential that all the plants shall be equidistant. This can only be possible when every three adjoining ones form an equilateral triangle, as *c, e, d*. In order that this may be the case, let the distance between the plants be determined and marked off, say from *a* towards *b*. Take two rods, or measures, each equal to this distance; place the end of one of them at *c*, and that of the other at *d*; bring their other extremities together, and they will meet in the point *e*, forming with the base *cd* an equilateral triangle, of which the perpendicular *ep* must be the distance between the rows *fg, hi, kl*, running parallel to *ab*, whilst the distance between the plants in these rows is equal to *cd*. When the plantation is all marked off, it will be observed that every three trees form an equal-sided triangle; and six, with one in the centre, a hexagon, in which the plants 2, 3, 5, 6, 7 form a quincunx.

**QUISQUALIS.** — *Combretaceæ*. — A stove climber, a native of the East Indies, with singular flowers, and large and handsome leaves. The flowers are shaped something like those of the Jasmine, but with an excessively long tube, and a very small limb, which, when it first expands, is white, but which afterwards becomes pink, getting darker and darker, till it finally becomes of a blood-red. The plant should be grown in loam and peat, and it is propagated by cuttings struck in sand under a hand-glass.

**RAGGED ROBIN.** — See LYCHNIS.

**RAGWORT.** — See OTHONNA; and SENEPIO.

**RAKE.** — A well-known toothed implement for raking the surface of dry ground, or collecting together grass on lawns which have been mown, or weeds on surfaces which have been hoed. There is also what is called the Daisy-rake, in which the teeth or tines are lance-shaped, sharp at the edges, and so close together that when drawn or raked over the surface of a lawn, they collect or cut off the heads or flowers of such plants as the Daisy, Crow-foot, Plantain, &c. The heads of rakes, or that part which contains the teeth or tines, are of different lengths, from six inches to two feet; and the teeth, which are placed at from one inch to two inches apart, are from two inches to four in length. In raking dug soil with a view to render the surface even and fine, and also to collect stones, roots, &c., the handle of the rake should be held close to the middle of the operator, so that the tines may pass through the ground at an angle less than 45°; but when weeds or short grass are to be raked up, or the heads of Daisies to be cut off, the handle of the rake must be held above the middle of the operator, so that the tines may form an angle with the soil above 45°. In the latter case it is desirable that the tines should slide along the surface; but in the former it is necessary that they should penetrate into it throughout nearly their whole length.

**RANUNCULUS.** — *Ranunculaceæ*. — The Ranunculus. — The species may be divided into two kinds — border flowers, and florists' flowers. The latter consists of some hundreds of varieties obtained from the species *Ranunculus asiaticus*, a native of the Levant, with tuberous roots, which is rather too tender to endure the winter in the open air without some kind of protection. The wild

plant grows naturally in Persia, in meadows which are moist during winter and in the growing season, but dry during great part of summer. Hence one of the first requisites in the culture of this flower is a loamy soil kept moist; and as the varieties are all double and in a highly artificial state, the soil requires to be made very rich with leaf-mould, or the mould of hot-bed dung. The common season for planting the Ranunculus is November; the roots may be placed about six inches apart every way, covered with two inches of soil, and protected by straw, mats, or rotten tan, during severe frosts. The plants will come into flower in July, and when the leaves wither, the roots may be taken up, dried in the shade, and preserved in a dry place till they are wanted for replanting. A great many named kinds may be procured in the seed-shops, the most distinct of which are the Turban, or very dark red, the orange, the white, and the fine or cut-leaved. As the plant seeds freely even when semi-double, new sorts without end may be raised from seed, which may be sown in pots or flat pans as soon as it is gathered, and placed in a cold frame. The common mode of propagating the Ranunculus is by separating the offsets from the larger roots.

The common kinds of Ranunculus are British weeds; but there are several border flowers belonging to this family which are well deserving of cultivation, and of which the following are the most remarkable: *R. acutifolius*, the white-flowered Bachelor's Button, an old inhabitant of British gardens, prolific in double white flowers in May and June, and very ornamental; *R. acris flore pleno*, the double-flowered yellow Bachelor's Button, which flowers in

June or July, is also a very desirable plant; as are *R. repens flore pleno*, and *R. bulbosus flore pleno*, both producing fine yellow double flowers in May and June. *R. cortusae-folius* is handsome both for its foliage and flowers; and *R. rutae-folius* is a low plant well adapted for pots or rock-work, producing abundance of pretty white flowers from May to July. *R. plataginicus* is very handsome, with glaucous lanceolate leaves, and white flowers produced in April; and *R. gramineus*, of which there is a double-flowered variety, with many others, are very handsome and desirable species.

**RAPHIOLEPIS.**—*Rosaceæ*.—The Indian Hawthorn. — Very elegant shrubs, natives of China, with white flowers, the centre of which is red; the bark is also reddish; and there is a reddish tinge in the leaves. The species are only half-hardy in England, and they are generally kept in the greenhouse in the open air against a conservative wall.

**REAUMURIA.**—*Ficoideæ*.—A very pretty little shrub, with fleshy leaves and bright purple flowers, very suitable for rock-work. It should be grown in peat and loam, or in heath-mould, in rather a dry situation, as it is very liable to damp off if grown in a moist situation in the shade. It prefers a warm sunny bank, where it flowers abundantly, and is very ornamental.

**RED CEDAR.**—See **JUNIPERUS**.

**RENANTHERA.**—*Orchidaceæ*.—The Chinese Air-plant. — A very handsome genus of the East Indian Orchideous Epiphytes. It is a true parasite, and never flowers well in a pot. It is a climbing plant: but it differs from all other climbers in attaching itself to surrounding objects by its long fleshy roots, which it twines round any post or column



within its reach, as other plants do their tendrils. Though the most glowing accounts had been received of the splendour of the flowers of the *Benanthera* in China, it did not appear likely to realise these descriptions in England; and it was cultivated in this country for above ten years before it formed a single spike of flowers. At last the ingenious expedient was devised of wrapping the long flexible roots round with moss, and keeping this moss constantly moist, and the result was, that the plant grew ten feet long, and produced several spikes, varying from two to three feet in length, of brilliant scarlet flowers. It is now generally grown on pieces of wood with the bark on, hung from the rafters near a column of the stove or orchideous house, round which the long roots are suffered to entwine themselves, care being taken to wrap them in moist moss as they elongate themselves; and it is found that the plant flowers as freely as any other orchideous Epiphyte grown in Britain.

**RESEDA.** — *Resedaceæ*. — There are many species of this genus, most of which are natives of the south of Europe and Egypt; but those best known in England are *Reseda Lutæola*, the Dyer's-weed, which is a British plant; and *R. odorata*, for the culture of which, see **MIGNONETTE**.

**RESERVE-GROUND.** — In every garden, accidents, diseases, and many other causes, occasion blanks or deformities in beds and borders, and the use of a reserve-ground is to contain a number of growing plants that at a moment's notice can be taken up and planted in the place of those which have ceased to be ornamental or desirable. Wherever there is a greenhouse, it can hardly be kept in high order without a pit

or frame in the reserve-ground for striking cuttings and bringing forward plants to supply the place of those which are no longer ornamental in the greenhouse; and particularly for forcing bulbs and bringing forward annuals, such as Balsams, *Schizanthus*, &c., which are exceedingly ornamental when in flower, but without showy foliage at every other season. The reserve-ground therefore, in point of extent, must bear some relation to the extent and the character of the garden which it is intended to supply. The smallest residence should have a few square yards of reserve-ground, including a pit, in an open, airy situation, but concealed from the ornamental parts of the grounds; and residences of twenty or thirty acres in extent will require several pits, and the sixth or fourth part of an acre as reserve-ground. Where there is a walled kitchen-garden, the reserve-ground may very conveniently be placed adjoining the frame or forcing-ground, or form part of it; and in places so small as to have no kitchen-garden, a concealed glade open to the south, with or without a small pit or frame, will still be necessary. The grand points respecting a reserve-ground, which it is desirable to impress on an amateur gardener, are, first, that a reserve-ground, including a pit, however small it may be, is essential to the keeping in high order of every plot of garden-ground, even those in front of street-houses, and of every garden of plants in pots, even those kept on window-sills and in balconies; secondly, that the reserve-ground must be in an open, airy situation, not shaded by trees; thirdly, that the herbaceous plants planted in the open ground in the reserve-garden must be taken up with balls of earth, and replanted

twice a year, and the shrubs once a year; and fourthly, that where there is a choice of soil, that of the reserve-ground should be of a loamy nature, such as will adhere to the roots of the plants, and never of sand, which will drop away from them. Where there is no reserve-ground, there is no possible way by which even a street-garden, or the pots on a window-sill, can be kept always in the highest order, but by having recourse to the commercial gardener.

REST-HARROW.—See ONO'NIS.

RHAMNUS.—*Rhamnaceæ*.—The Buckthorn.—Handsome deciduous and evergreen shrubs; some of which almost attain the size and appearance of small trees, and others are procumbent shrubs only fitted for rock-work. They are all, however, distinguished by a stiff upright manner of growth, and numerous strong thorns, from which they derive their name of Buckthorn. The flowers are generally small and not ornamental, but the berries are very much so; and the evergreen kinds are very valuable in shrubberies, from their hardiness and free habit of growth. The *Alaternus* (*Rhamnus Alaternus*) is particularly valuable, because it bears coal-smoke and the confined air of towns better than most other evergreens.

*Rhamnus catharticus*, the Purg-ing Buckthorn, is a deciduous shrub with large handsome leaves and showy berries. These berries when unripe are used in making a yellow dye, and they are sold for this purpose in the colour shops, under the name of French berries; when ripe, their juice, mixed with alum, forms what is called sap-green; and if they are suffered to hang on the trees till autumn, their juice becomes purple. The Avignon berries,

also used in dyeing yellow, are the fruit of *R. infectorius*, which is a native of France, near Avignon. *R. saxatilis*, the Stone Buckthorn, which is a deciduous recumbent species, is a valuable plant for rock-work, or for clothing rocks or old walls, where it is desirable to give a wild and natural appearance to the scenery; and *R. Erythroxylon*, the Red-wooded Buckthorn, is very ornamental as a tufted bush among rocks near water. *R. Frangula* and *R. latifolius* are low trees. All the species are quite hardy, and will grow in any common garden soil, and in any situation that is tolerably dry; and they are all easily propagated by seeds and layers.

RHE'XIA.—*Melastomaceæ*.—Herbaceous and shrubby plants, natives of America. *R. virginica*, which is the handsomest species, is quite hardy in peat earth, in a moist situation, and it produces its showy pink or rather rose-coloured flowers, with conspicuous yellow stamens, in July and August. The leaves are strongly ribbed, as in all the *Melastomaceæ*, and slightly edged with pink. The shrubby species are more tender than the herbaceous ones, and they are generally kept in a greenhouse.

RHIPSALIS.—*Cactaceæ*.—Very curious succulent plants, which are natives of both the East and West Indies. As the *Opuntias* may be said to be all leaves, and the different kinds of tree *Cereus* all stem, so the *Rhipsalis* may be considered all branches; for the whole plant consists of a series of short round articulated branches, spreading in all directions. The flowers of this genus differ from those of the *Cacti* generally, in being small and not very handsome. They are generally yellow. The species should all be

grown in brick-rubbish and sandy loam, and they should have very little water. The cuttings must be dried by laying them on a shelf for two or three days before they are planted.

**RHODANTHE.**—*Compositæ*.—A beautiful little annual plant, a native of the Swan River, whence its seeds were imported by Captain Mangles, who so well merits the gratitude of every lover of flowers for the numerous beautiful plants which he has been the means of introducing. The *Rhodanthe* is generally treated as a half-hardy annual, being sown on a hotbed in February and planted out in May; but it may be grown to an enormous size by the following treatment. The seed must be sown the first week in April, in a soil composed of three parts of heath-mould and one of loam; and the young plants pricked out the first week in May into small thumb-pots or sixties, filled with a similar soil. In a week's time they should be shifted into pots a size larger; they should then be suffered to remain a fortnight, after which they should be again shifted into larger pots and the blossom-buds pinched off. The shifting may be repeated five or six times, always pinching off the blossom-buds, till the plants have attained a large size and shrubby character, which will generally be about the middle of August, and when they may be permitted to flower. A plant which had been treated in this manner, and which was given to me by Captain Mangles, measured a foot and a half high and four feet in circumference; it had above a thousand blossoms on it expanded at one time, and it continued producing a succession of flowers from August to the middle of November.

**RHODOLA.**—*Crassulææ*.—Rose-root.—There are only two species of this genus, one of which is a British plant, strongly resembling the House-leek, with a thick fleshy root, smelling so much like a Rose as to have given the name to the genus. The flowers are yellow and terminal. The plant is a perennial, and should be grown in a moist situation on rock-work.

**RHODOCHITON.**—*Scrophulariææ*.—*R. volubile*, formerly called *Lophospermum Rhodochiton*, is a Mexican climbing plant, with abundance of very handsome flowers. It was at first kept in the greenhouse, but it is now found to flourish most in the open air, as it will not flower well when its roots are confined. It should be planted in spring, in a pit about two feet square, formed in the open border, and filled with loamy soil, enriched with leaf-mould or rotten manure. As the plant grows, a little leaf-mould may be added from time to time over the roots; and the plant must be trained up a wire-frame, or against a conservative wall. When it has done flowering, it should be cut down to within a few inches of the ground, and covered with tan or saw-dust, and a pot turned over it, the hole in the pot being stopped up to exclude the rain; or, what is better, the plant may be wrapped in moss, and thus protected. The species is propagated by cuttings struck in spring or autumn, or by seeds sown on a hotbed in February and planted out in May. When wanted for a balcony or greenhouse, it may be grown in a pot, all that need be attended to being to grow the plant in good soil, and to allow it plenty of room for its roots.

**RHODODENDRON.**—*Ericiææ*.—The Rose Bay.—Well-known evergreen shrubs and low trees, with

splendid flowers; which are generally grown in sandy peat, kept rather moist. The hardy Rhododendrons are mostly either natives of America, or hybrids raised in this country from them; and hence, the part of the garden in which they are grown is generally called the American ground, and they are classed with Azaleas, Kalmias, and other plants of similar habit of growth. Many kinds of Rhododendron are, however, from the East, and one of these, *R. ponticum*, is quite hardy, and hybridises freely with the American kinds. Of these last, *R. maximum*, in America, attains the height of twelve or fifteen feet, but in England it neither grows nor flowers freely. The leaves are of a pale yellowish green, and they generally look drooping, as though the plant wanted water. It is remarkable, that it was twenty years in England before it produced a single flower. In its native country it is always found growing upon rocks near water; and it would probably thrive in a similar situation in this country. *R. catawbiense* is a hardy American species, which flowers abundantly from June till August. It seldom grows above four feet high, but it forms a healthy-looking bush, perfectly covered over with flowers. The hybrids between this species and the Nepal tree Rhododendron are very handsome. Of the tree Rhododendrons, the old Nepal scarlet, *R. arboreum*, grows about twenty feet high, with immense bunches of dark scarlet flowers, which have a rich velvet-like appearance. The flowers secrete honey in such abundance that it actually drops from the corollas. The leaves are large, and silvery beneath. The large white-blossomed tree Rhododendron, *R. cinnamomum*, has long narrow leaves, much

wrinkled and covered beneath with a coarse shaggy reddish wool. The flowers are generally white, but there is a variety the flowers of which are rose-coloured. *R. campanulatum* and *R. Rollinsoni*, the Ceylon scarlet, are also splendid species; but in 1850, Dr. Joseph Hooker sent home a number of species of the Himalaya Rhododendron which far surpass in size and beauty of flower all that had hitherto been introduced. All the species of Rhododendron brought from the Himalayas are very ornamental, but none are more so than *R. Dalhousiae*, which flowered for the first time in England in March, 1853. The flowers are very large and fragrant; when they open they are green; they then change to yellow, and afterwards become a pure white, which in their native country is tinged with rose-colour before the flowers drop. The species in the Himalayas is a straggling shrub with a red papery bark, and bearing its flowers and leaves only at the extremity of each shoot; and as it grows in moist forests 9000 feet above the level of the sea, it will probably prove hardy in shady moist places. With this may be associated *R. Thompsonii*, found at the same elevation, with flowers nearly as large and of a bright crimson. *R. glaucum* is another Himalayan species which will probably prove hardy in this country. It is a shrub about a foot high, producing a great profusion of bell-shaped pink flowers, which have a resinous smell. *R. niveum*, also from the Himalayas, has large clusters of lilac flowers, and takes its name of *nivea* (snowy) from the whiteness of the under side of the leaves. In addition to these, other Indian Rhododendrons have been introduced—some shrubs of 10 feet or

12 feet high, and others actually Epiphytes growing on the branches of trees in Java and Borneo. Some, as *R. Javanicum*, have bright yellow flowers; others, as *R. ciliatum*, *R. Blanfordiaeflorum*, and *R. Jasminiflorum*, lose the form of the Rhododendron flower; while others, such as the old *R. hirsutum* and *R. ferrugineum*, are dwarf Alpine species, clothing the sides of mountains close to the regions of perpetual snow. The principal dwarf species are *R. chrysanthum*, with yellow flowers; *R. ferrugineum* and *R. hirsutum*, with rose-coloured flowers, and *R. caucasicum*, with purple or white flowers. All these scarcely exceed a foot in height, and some of them are not more than six inches. *R. dauricum* is not a dwarf plant; but it is a low shrub, with Azalea-like flowers of a pale-lilac crimson, which are produced from December till March, and the flowers of the species appear before the leaves, though there is a variety, *R.-d. atrovirens*, that is evergreen. It is very ornamental, and it is valuable from the early season at which it flowers. All the Rhododendrons were at first supposed to have crimson, scarlet, or white flowers, and when one was raised by a cross with a yellow Azalea having yellowish flowers it was very much admired. In 1847, however, the Rhododendrons already alluded to were introduced from Java, with brilliant yellow flowers and fleshy roots; the plants themselves being found growing not in the ground, but on trees, which threw the previously known yellow Rhododendrons quite in the shade.

All the American Rhododendrons are what are called hair-rooted plants; and they are all grown in sandy peat, or in deep sandy loam. They may also be grown even in

stiff clay if it be kept moist; but the worst soil for Rhododendrons is that of a well-manured garden, particularly if the situation be a dry one; as this kind of soil has not tenacity enough to enable it to adhere to the fine hair-like roots of these plants. All the Rhododendrons may be propagated by cuttings of the young shoots taken off while they are in a growing state, by layers, and by seeds. The latter is the most general mode, as the seeds, which are very small and look like saw-dust, are ripened in great abundance in the months of August and September; and the seeds of the American kinds are imported every year in large quantities from America. They are also now propagated by budding in the open air. All the Rhododendrons and Azaleas may be removed at almost any season, and when of almost any size, if taken up with a ball of earth round the roots. The best seasons, however, for removing them are spring and autumn. It may be observed that Rhododendron seed will remain good for several years, though, when practicable, it is best to sow it as soon as it is ripe, as the plants will come up much sooner. Rhododendrons should be grown in a shady, moist situation, and they will all thrive under the drip of trees.

RHODORA.—*Ericaceæ*.—*Rhodora canadensis* is a very pretty little plant, a native of Canada, resembling the dwarf Rhododendrons, excepting that the flowers are much smaller, and the leaves are deciduous. It is quite hardy, and only requires to be grown in peat earth, kept moist. It flowers in the open ground in April; but it may easily be forced by keeping it under glass, and giving it a little heat, so as to flower at Christmas.

**RHUS.**—*Terebinthaceæ*, or *Anacardiaceæ*.—Sumach. — Deciduous shrubs, natives of Europe, Asia, and America, interesting from the beautiful colours which their leaves assume when dying off in autumn. All the kinds are more or less poisonous. *Rhus Cœtinus*, the Virginian Sumach, is called the Periwig Tree both in French and German, from the curious appearance of its seed-vessels, which look like a powdered wig. It is a very ornamental shrub, often growing ten or twelve feet high, and flowering abundantly. It grows best in a dry loam, and it is propagated by layers. *Rhus typhina*, the Stag's-horn Sumach, has received its name from the singular appearance of the young shoots, which are covered with a soft velvet-like down, resembling that of a young stag's horn both in colour and texture. The leaves are imparipinnate, with eight or ten pairs of leaflets, and they die off of a beautiful purplish-red in autumn. The flowers are produced in terminal spikes, and they are succeeded by deep-purplish red woolly fruit. *Rhus glabra*, the Scarlet Sumach, has red flowers, and rich velvet-looking dark-scarlet fruit, which becomes crimson as it ripens. *Rhus vernicifera*, the Varnish or Japan Sumach, is a greenhouse plant in England; but in India and in Japan it is grown in large plantations for its gum, which issues from the tree when wounded, and forms the finest varnish in the world. *Rhus venenata*, the Swamp Sumach, or Poison-wood, has so virulent a sap that it occasions fever and inflammation in those who cut it down. Even touching the plant, or smelling it, will in many cases produce eruptions and swellings all over the body. The plant is not very handsome, but the leaves become of a brilliant red in autumn.

*R. Coriaria*, the Elm-leaved Sumach, and *R. copallina*, the Gum-copal tree, resemble *R. typhina*; and *R. radicans*, the Poison-oak, and *R. Toxicodendron*, the Poison-vine, are poisonous plants, natives of North America, resembling *R. venenata*. All the kinds of *Rhus* are of easy culture in any loamy soil; and they may be all propagated by cuttings or layers. Several of the kinds may have their branches pegged down, and a little earth strewed over them, when they will strike root.

**RIBBON GRASS.**—*Arundo Donax* var. *versicolor*.

**RIBES.**—*Grossulariaceæ*. — The Currant.—The ornamental kinds of *Ribes* which have been introduced into British gardens since the commencement of the present century are now some of our most beautiful shrubs. They are all quite hardy, and will grow, without any trouble being taken with them, in any common garden-soil. The following kinds are those most deserving of cultivation for their flowers:—*Ribes niveum*, the Snowy-flowered Gooseberry, has white pendulous flowers, and dark purple fruit, the flavour of which is agreeable; *R. speciosum*, the Fuchsia-flowered Gooseberry, has scarlet flowers, with very long projecting stamens, somewhat resembling those of the Fuchsia, and the leaves sub-evergreen; *R. spicatum*, the Tree-currant, which forms an erect fastigate-growing shrub, six or eight feet high, with upright spikes of red fruit; *R. multiflorum*, a most beautiful plant, has long drooping racemes of greenish flowers, and large handsome leaves; *R. punctatum*, an evergreen species, has shining leaves and golden yellow flowers, which are succeeded by red fruit; *R. floridum*, the Flowering Black Currant, has loose racemes of

greenish-yellow flowers, and black fruit; *R. cereum*, the Wax-leaved Currant, has leaves which are nearly round, and appear thinly covered with white wax; *R. sanguineum*, the Red-flowered Black Currant, is a beautiful and well-known species, of which there are several varieties; and *R. aureum*, is the Yellow-flowered Black Currant. All these kinds are very beautiful; but the most ornamental are *Ribes sanguineum*, and its varieties or allied species, *R. glutinosum*, with pale-pink flowers, and *R. malvaceum*, with lilac ones, and also the dark-red variety, *R. s. atro-rubens*, of California. There are also several kinds of *R. aureum*, all of which are well deserving of cultivation. All the kinds of *Ribes* are easily propagated by cuttings, or by seeds, which most of the kinds ripen in abundance; and one kind, *Ribes punctatum*, sends up suckers. They are generally quite hardy; and *R. punctatum*, being a native of Chili, succeeds best against a wall.

RICE.—See ORYZA.

RICE-PAPER PLANT.—*Aràlia papyrifera*.—There are now several specimens of this very curious plant at Kew, where one flowered in a damp stove in December, 1855, but did not produce fruit. In its native country, China, it is represented "as being seven feet high, with a circumference of its terminal branches of twenty feet, and throwing out twelve or fourteen panicles three feet long, drooping like magnificent plumes, in regular form, over the dark palmate leaves." The stem is three, or at most four, inches in diameter, forming very little wood, but filled with the most exquisitely white pith, of which the famous rice paper of China is made.

RICHARDIA.—*Aràcea*.—Kunth's

name for *Cállia athiopica*. For the culture, &c., see A'RUM.

RI'CINUS.—*Euphorbiaceæ*.—*Palma Christi*.—The Castor-oil plant, *Ricinus communis*, is a half-hardy annual in this country, worth growing for its splendid leaves and very curious flowers and seed-pods; but in the East Indies it becomes a tree. The oil is expressed from the seeds. When grown in England, the seeds should be sown in a slight hotbed in February, and the young plants removed to the open border in May. It should be grown in light rich soil, well manured with decayed leaves, and in a situation open to the sun.

RICO'TIA.—*Cruciferae*.—A very pretty little annual nearly allied to *Lunària*, which only requires sowing in the open border in April.—See ANNUALS.

RIDGING.—Throwing up ground in ridges, in order to expose it more thoroughly to the action of the weather. This operation is most useful in clayey soils, as the water freezing separates the particles of the clay, and lightens the soil: and it is performed by opening a trench, and throwing up the ground so as to form a kind of hillock sloping on both sides.

ROBI'NIA.—*Leguminosæ*.—Ornamental trees and shrubs, with long drooping racemes of flowers. The common kinds of Robinias are generally called Acacias in gardens; though why this name has been given to them, unless from their pinnate leaves, which resemble those of the true Acacia, it would be difficult to say. The name of Locust, which is applied to the *Robinia Pseud-Acacia* in America, also appears to have no definite meaning, unless it alludes to the leaves, which bear a very slight resemblance to those of the *Ceratonia siliqua*, the

Locust-tree of Holy Writ. The flowers of all the kinds of Robinia are very handsome; but the arborescent species are not handsome trees, from the liability of their branches to be broken off by high winds, which gives them a ragged and untidy appearance; and the wood, notwithstanding all the very extravagant praises of Cobbett, is of very little value. The roots of the Robinia also extend just under the surface; and thus a tree of this genus occupies nearly twice the extent of ground which would be taken up by a tree of the same size of almost any other kind. The shrubby kinds of Robinia are also liable to the same objections: though the long racemes of rose-coloured flowers of the Rose Acacia (*R. hispida*) are so beautiful that no shrubbery should be without it. All the Robinias are quite hardy, and they may be grown in any soil, though they thrive most in a rather rich sandy loam; care should be taken always to plant them in a sheltered situation, as no plants are more injured by high winds. They are propagated by seeds, layers, cuttings, and suckers, which are produced in great abundance. When Robinias are raised from seed, the seeds should be steeped for twenty-four hours in hot water before sowing; as, unless this is done, they will sometimes remain in the soil two years before they germinate. Several plants, formerly considered to belong to Robinia, are now distributed through the genera Caragana, Halimodendron, &c. Of these, the most beautiful are the Caraganas and the Halimodendron, or Salt Tree.

ROCKET.—See *HE'SPERIS*.

ROCK CRESS.—A kind of *A'rabis*.

ROCK ROSE.—See *C'istus*.

ROCK-WORK is a very common

ornament in gardens; and, producing a striking effect, it is introduced more frequently than judiciously. Rock-work may be divided into two kinds: that which is intended to imitate natural rocks, and that which is intended merely as a nidus for rock-plants. Imitations of nature should always consist of large blocks of stone of the same kind, and should, for the most part, be disposed in imitation of some kind of stratification. At the same time, as in many parts of the country large, round, or roundish, or angular blocks of stone are found distributed over the surface, it is not objectionable to collect these together in groups so as to form a feature in scenery, and to insert plants among them. Rock-work, as a mere nidus for plants, should never be attempted on a large scale without the introduction of large blocks of stone and some kind of stratification being adopted; and in this case, as before mentioned, using one kind of stone will produce an effect in accordance with that of nature. On a small scale, however, different kinds of stone may be used, more especially when these are well covered with plants; but even on a small scale, one kind of stone has always a better effect, and will be felt more agreeable to the eye than a mixture of bricks, flints, pieces of granite, freestones, and perhaps marble, shells, fragments of carved stone, and even roots, which are not unfrequently seen in even the best gardens. Rock-work should always be an independent feature. It rarely looks well when piled up against a wall or around the roots of a tree, or in any situation where it is overshadowed by trees; in short, where it does not form the prominent feature in the scene. It looks well near water, and mergin



into it, or in an open, airy garden, where it is surrounded by a gravel-walk; but it does not look so well when rising from turf, without an adjoining walk, or when large shrubs grow up among the stones. Where there are collections of such plants as Saxifrages or other Alpines, or of Cistuses, Heliánthemums, or other mountain shrubs, rock-work is very desirable; and in such cases it may be placed on a lawn, as a feature in a general collection of herbaceous plants or shrubs, arranged according to the Natural System; but rock-work as an ornamental object, or as a nidus for a miscellaneous collection of plants, should always be in an open, airy situation near a pond, or surrounded by a walk. In short, it may be laid down as a general principle, that rock-work should either adjoin gravel or a piece of water; and that it should seldom or never adjoin trees or grass, or walls or buildings.

One of the most common faults in rock-work is the indiscriminate mixture together of all sorts of stones, bricks, shells, fragments of statuary or sculpture, and even roots of trees; which latter objects, though very suitable as receptacles for plants, should always be arranged in masses apart from any intermixture of stones.—See Root-work.

RODRIGUEZIA. — *Orchidaceæ*. — Orchideous Epiphytes, natives of tropical South America. *R. secunda* has beautiful pink flowers, but the other species have generally drooping racemes of greenish-yellow flowers, more graceful than positively beautiful. All the kinds should be grown in moss, and they all succeed better on wood than in pots.—See ORCHIDEOUS EPIPHYTES.

ROELLA. — *Campanulaceæ*. — Cape plants, generally with blue

flowers, which have somewhat of the dazzling glossy hue of Venus's Looking-glass. The shrubby kinds are of low growth, and rather difficult to propagate; but the annual species are of very easy culture, and only require the usual treatment of half-hardy annuals.—See ANNUALS.

ROME'RIA. — *Papaveraceæ*. — The Purple Horned Poppy.—This is a very beautiful flower, but unfortunately, its beauty is so very short-lived that it is difficult to find a perfect flower, as one or two of its petals drop almost as soon as the flower expands. It is quite hardy, and only requires to have its seeds sown in the open border in April.

ROLLING.—Gravel walks cannot be kept in proper order without frequent rolling, and this rolling is most efficacious when the ground is moist below, but the surface dry. On this account the best time for rolling is a fine dry day after two or three days' rain; and when rolling is necessary in continued dry weather, the walk should be previously watered. Turf should also be rolled occasionally, and when moist, to prevent its surface from becoming uneven.

RONDELETIA. — *Rubiaceæ*. — Beautiful stove plants, with white, blue, or reddish flowers, natives of the East and West Indies. *R. odorata*, which is the most common, has terminal corymbs of scarlet flowers greatly resembling those of *Ixora coccinea*. It should be grown in a moist stove, in peat, sand, and loam, the pots being well drained with potsherds and cinders. The flowers are produced in great abundance, and they are very fragrant as well as beautiful. The species with blue flowers, which was called *R. longiflora*, requires similar treatment. It is now called *Hindsia*.

**ROOT-WORK.**—The roots of trees, and especially large roots including the stool or base of the tree after the trunk has been cut down to the ground, may be combined together in various ways, useful, ornamental, or curious, in gardening. Two or three large stools of trees grouped together on a lawn, with mould and plants placed in their interstices, form a striking contrast to the smoothness and high art displayed on the general surface of the lawn. The plants placed among the roots, whether in pots concealed by mosses, stones, or mould, or planted in soil, should never be of indigenous kinds common in the locality; for these might be mistaken for weeds; but of exotic kinds, such as *Geraniums*, *Petunias*, *Maurandias*, &c., or of British or European alpine of small size, neat foliage, and with brilliant flowers. The idea to be kept in view is, that of creating artificial ornaments without much expense; and, therefore, the roots must never appear to have been left where they are by carelessness or accident, but placed by design, and with reference to the composition of which they form a part. In many situations, conglomerations of roots, as a receptacle for plants, are more pleasing than conglomerations of stones, because they display less effort, and seem a more natural and easy way of obtaining a nidus for ornamental plants. Too much effort and expense for attaining any object is never altogether so satisfactory as when the same object is obtained with ease and economy. Hence rustic seats in a pleasure-ground, and rustic vases, or other vessels for containing plants, are more satisfactory than cast-iron seats or marble vases, unless indeed the latter are connected with some building.

Roots may also be combined to-

gether so as to form seats, open or covered huts, grotto-like structures, and grotesque bridges; and one object for which they are particularly suitable is for placing on the margin of pieces of artificial water along with trees, bushes, or plants. A smooth expanse of water, like a smooth lawn, requires shade and roughness to contrast with it, in order to produce a striking effect; and roots at once supply both roughness and shade. In placing them, a part of the root should always be covered by the water, and another part by the soil; and by planting a young tree or bush adjoining the root, a double contrast is produced between the root, which gives the idea of an aged tree long since felled or dead, and the erect young shoot which foretels a future tree. The shadow of the group so formed in the water is a circumstance that redoubles the interest.

Roots may be piled up and connected together by wooden pegs, so as to form arches, arcades, or covered ways, or grottoes, or other structures, for shelter or repose; the interstices being filled in with moss or heath, and the exterior being thatched with heath, or the chips or shavings from hoops, common in counties which abound in coppice-wood, such as *Sussex*. Roots also may be piled up so as to form grotesque fences, which are suitable for certain situations and purposes. A flower-garden in a wood or sequestered glen, surrounded by a fence of this kind, has sometimes a striking effect; and sometimes the area of gravel before the entrance front of a villa is separated from the lawn by an irregular ridge of roots, varied by greenhouse plants, with the pots concealed.

A very common error in the use of roots is that of mixing them

with stones in rock-work, which has been already pointed out.—See **Rock-work**.

**ROSA.** — *Rosaceæ*. — The Rose-tree.—Of all flowers none are more beautiful than Roses; and none better reward the care of the cultivator. Roses are natives of Europe, Asia, Africa, and America, but none have yet been found in Australia. The number of Roses is almost incredible; above a hundred distinct species have been described, and there are above two thousand named varieties to be procured in the nurseries. In this chaos, all that can be done in a work like the present is, to give a slight sketch of the different kinds of Roses grown in British gardens, with a few particulars of the more remarkable species. The best known and most common kind of Rose is the Cabbage or Provence Rose (*Rosa centifolia*). This species is a native of the Eastern Caucasus, whence it was brought at a very early period. There are more than a hundred varieties of it; all very beautiful and very fragrant, and all distinguished by their close cabbage-like form, the curving inwards of their petals, and their slender foot-stalks, which give a peculiarly graceful and drooping appearance to the full-blown flowers. The Moss Roses are all varieties of the Cabbage. All the Cabbage Roses may be grafted standard high on Briars of the common Dog-rose; and they all require a richly-manured soil and an open situation. The French or Provins Rose (*Rosa gallica*) is a compact erect-growing plant with large open flat flowers borne on stiff erect flower-stalks; thus forming as strong a contrast as possible to the Cabbage Rose. This Rose is found wild in France, and it is grown on a large scale near the little

town of Provins, in the department of the Seine-et-Marne, and also at Fontenay-aux-Roses, near Paris, for the purpose of making conserve of roses. There are more than a hundred varieties of this Rose. The French Roses do not require a rich soil, and they are never grown as standards. *Rosa damascena*, or the Perpetual Rose, differs from *R. centifolia*, in the large size of its prickles, the greenness of its bark, its elongated fruit, and its long reflexed sepals. There are above a hundred varieties of these Roses, the most beautiful of which is Lee's Perpetual, or the Rose du Roi. These Roses are very fragrant, and they continue blossoming till November. As the Perpetual Roses are of very luxuriant growth, and as they produce abundance of flowers, they should be grown in very rich soil, and their shoots not cut in. *Rosa indica*, the Chinese or Monthly Rose, is the parent of another large family of Roses, comprising upwards of two hundred varieties and hybrids; the most interesting of these are the Tea-scented Roses, and the Noisettes. The Tea-scented Roses are delicate little plants, with large drooping flowers, and they are supposed to be hybrids between the common and the yellow Chinese Roses; it is generally considered that they are rather tender, and that they should be grown against a south wall in a raised border composed of equal parts of vegetable mould, light loam, and sand; "but we have one against the verandah of our house at Bayswater, grafted on a common Briar, and growing in the ordinary garden soil, which is splendid." Many cultivators take these Roses up in November, and keep the roots in a pot in a greenhouse, or laid in mould in a shed, till spring, when

they may be planted out again in the open garden. The Noisettes are supposed to arise from a hybrid between the Chinese Rose and the Musk Rose, raised by M. Philippe Noisette, at Charleston, in North America. This kind of Rose is very hardy, and a most abundant flowerer, sixty or eighty flowers having been produced in one cluster; it is admirably adapted for standards and for rose-pillars. There are nearly a hundred different kinds of Noisette Roses.

The climbing Roses are of four different kinds: the Ayrshire, the Evergreen, the Cluster-flowered, and the Boursault. The Ayrshire climbing Roses are all varieties of *R. arvensis*, a trailing plant, which, when left on the ground in moist places, will throw out roots at every joint; but they are climbers by elongation, stretching themselves upwards through a mass of hedges and bushes, and covering them with flowers. The branches are in general slender and feeble; and where they have no supports they are apt to become entangled with each other. All the Ayrshire Roses grow vigorously, sometimes making shoots twenty feet long in one season. The Evergreen Rose (*R. sempervirens*) is a native of the south of France, greatly resembling the Ayrshire Rose in its flowers, but differing in its leaves, which are smooth, leathery, and evergreen. The evergreen Roses do not make such vigorous shoots as the Ayrshire Roses, and consequently are not so valuable as climbers; but they are much more so as undergrowth for covering the ground in shrubberies, as they grow and flower freely under the drip of trees. When thus trained, the shoots should be spread over the ground they are intended to cover, and pegged down near a joint, which

will throw out roots, and the plant will thus grow vigorously. A sloping bank covered with these Roses, in front of a breakfast-room window, has a most beautiful effect. They also look well grafted on low standards of the common Dog-rose, as the shoots will descend all round and form a cone or pyramid of Roses. The many or cluster-flowered Rose (*R. multiflora*) is a beautiful plant, bearing large clusters of Roses: sometimes of more than fifty roses in one cluster. More than three thousand roses have been counted on a plant of this species at one time. The Seven Sisters' Rose (*R. m. Grevillei*) is a variety of this species. The Boursault Rose is generally considered by botanists to be another variety of *R. multiflora*, but it differs from that species in several important particulars. It is a hard-wooded durable Rose, producing abundance of flowers, and growing freely; the shoots, which are of a purplish-red, and almost without thorns, being often fifteen feet long in one season. The flowers appear very early, and are remarkable for their reticulated petals. All these Roses may be made to form beautiful objects on a lawn, by training them up parasol-wires, which may be purchased at any ironmonger's, or up a pyramid. The latter may be made either of iron rods and wire, or of three pieces of wood, with holes bored in them at regular distances, through which narrow laths may be passed. It is useful to put a ball and spike on the top of this figure, to prevent birds from settling on it, which they would be very apt to do, and would dirty the flowers and foliage beneath. Climbing Roses may also be trained over trellis-work, or up the trunks of trees; in which last case they should be allowed to climb through

the head of the tree, and to hang down from the branches in wild and graceful festoons. Hybrid Perpetual Roses are useful for the long time they remain in flower; one of them, Madame Laffay, having continued in flower in the year 1843 till the 29th of December.

Musk Roses (*Rosa moschata*) form another family of Roses, though not a numerous one, as there are not above ten or twelve kinds; they have very long slender branches, which, being too weak to support alone their large bunches of flowers, should be trained against a wall. These Roses never require pruning (except to cut out the dead wood), as the flowers are only produced at the extremity of the shoots. The Banksian Roses (*R. Banksiae*) are of two kinds, one with buff flowers, and the other with white; the Macartney Roses (*R. bracteata* and *R. microphylla*) and some others are natives of China, and rather tender in England, requiring to be trained against a wall, and to receive protection in severe winters. They are also very apt to drop their flowers, of which they produce a great quantity, without fully opening them. *R. alpina* (the Alpine Rose), of which there are a great number of varieties, *R. lutescens* (the yellow American Rose), and *R. spinosissima* (the Scotch Rose), of which there are almost innumerable varieties, are hardy, early flowering Roses, that will grow in almost any soil or situation. *R. sulphurea* (the Double-yellow Rose) is however more difficult to manage. This beautiful Rose, which till lately was only known in a double state, has large drooping flowers, shaped like those of the common Cabbage Rose, and is supposed to be a native of Persia. In some situations it grows freely; but in others the flower-

buds burst on one side when only half formed, and the flowers are thus imperfect. It should be grown in an open, airy situation, in a light free soil, and it should have abundance of light and air. It should be well supplied with water during the flowering season, but the ground in which it grows should be so well drained as never to allow the water to remain in a stagnant state about the roots. When trained against a wall, it should have a north or eastern exposure rather than a southern one; and the shoots should never be cut in. This Rose, in fact, does not require any pruning, except what may be necessary to remove the dead wood, or to train the plant into shape; though the latter should be avoided as much as possible, as all wounds on this Rose are apt to produce canker. It is said to flower freely when grafted on the Musk cluster, at eight or ten feet from the ground, or on the common China Rose; but I have never seen the experiment tried. The most beautiful yellow Roses I ever saw were in the neighbourhood of Worcester, where the plant had grown in a border in front of a south-eastern wall, and had been partly trained against it; though for some time before I saw it, probably two or three years, it had evidently been left entirely to nature. A plant supposed to be the single state of this Rose was imported about 1835, by Sir Henry Willich, from Persia, and flowered for the first time in England in the garden of the London Horticultural Society, in the summer of 1840.

There are many other Roses not included in the foregoing enumeration; the best known of which are the White Rose, (*Rosa alba*), with its numerous varieties; the Yellow Austrian Rose (*R. lutea*), which has

the petals scarlet above and yellow beneath ; the Sweet Briar, or Eg-lantine (*R. rubiginosa*), with its very numerous varieties ; the common Dog-rose, or Briar (*R. canina*), which is common in the hedges in England, and its multitude of varieties ; the ever-flowering dark-crimson Chinese Rose (*R. semperflorens*) ; and the Fairy Rose (*R. Lawrenceana*). To these may be added the Isle of Bourbon Roses (*R. Bourboniana*), the origin of which is uncertain, but which are generally supposed to be hybrids between the common China Monthly Rose (*R. indica*) and the Rose à-quatre-saisons (*R. damascena*). The Bourbon Roses are very beautiful ; they are large and rather flat, with rich velvet-like petals, much darker inside the flower than on the outside. They flower in autumn, and they grow best in dry sandy soils, unless they are grafted standard high on the Dog-rose, when they should be manured like other standard Roses.

Among the best roses grown in 1852 may be mentioned the following :—*Hybrid perpetual*.—Duchess of Sutherland, a large handsome flower ; La Reine, a very large flower, but often shaded with lilac—both these were raised in 1843 ; Madame Audot, flowers of a glossy flesh-colour, with the ledges of the petals of a creamy-blush—a very large, full, and finely-formed Rose ; Comte d'Egmont, very large, full, and rich, raised in 1847 ; and Comte de Montalivet, with the flowers shaded violet and red, and very large and double. *Bourbon*.—Paul Joseph, a magnificent Rose, with flowers of a rich purplish-crimson, but which grows best as a dwarf, or as a dwarf-standard ; Madame Souchet, pale-pink, delicately tinted, large, and very handsome ; and Mar-t jeune, very large rich crimson

flowers. *French Roses*.—D'Agues-sau, large dark-crimson flowers ; and Géant des Batailles, velvet-crimson, shaded with purple. *Moss*.—Countess de Noé, brilliant crimson and purple ; and Mauget, bright rose colour, perpetual. *China*.—Madame Brion, very large, and rich rose colour ; Hébé (hybrid), delicate pink. *Noisette*.—Thélaire, white, very double flowers, produced in great abundance ; Solfaterre and Cloth of Gold, yellow flowers ; and Ophiré, flowers of a reddish-copper colour, outer petals rose and fawn ; very fragrant. *Tea Scented*.—Saffrano, flowers pale yellow.

All roses require a rich and free soil, and plenty of pure air. They



FIG. 46.—ROSE CUTTING, READY FOR PLANTING ; THE DOTTED LINE SHOWING THE GROUND.

are not so particular with respect to light, as they will flower beautifully in situations which are shaded, at least during part of the day ; and, in fact, appear to prefer partial shade to constant exposure to the sun. Coal-smoke is very injurious to them. Roses are frequently planted in Rose-gardens or Rosa-

riums, in which each kind of Rose is contrived to fill a separate bed, and these beds are arranged so as to form a regular figure like a geometric flower-garden. Pyramids or pillars of Roses are formed by twining the climbing kinds against frame-work; or they may be trained over arcades, or so as to form baskets. The Rose is generally propagated by budding or grafting the finer kinds on the common Briar, or by layers. Grafting is often practised in June. New varieties are also raised from seed; and the dwarf kinds are propagated by cuttings, most of the leaves of which should be left on (see fig. 46). Roses should be generally planted in autumn; but some of the more tender Chinese and Musk Roses may be planted in spring. A pit should be dug about two feet square every way, and half filled with very rotten manure or vegetable mould mixed with an equal portion of pit-sand; or if the soil be naturally sandy, with equal parts of sand and loam. Every fifth or sixth year the Roses should be taken up, their roots shortened, and replanted in fresh soil, the old soil being removed; and every year, in March, about half a barrowful of rotten manure should be laid on the surface of the ground, round the stem of the tree, and spread out so as to cover the roots; the unpleasant appearance of the manure being concealed by covering it with turf or stones. It must be observed, that the manure given to Rose trees should always be thoroughly decayed, and does best laid on the surface, as when the earth is manured too much and the manure is dug in, it is very apt to make the trees produce more leaves than roses; and the roses have very often a green centre. Damask Roses, Brennus, Madame Hardy,

and Charles Louis, all very fine Roses, are very apt to produce green leaves in the centre of the flower, when manured with undecayed stable manure. The pruning of Roses is a subject on which there are many different opinions, and Roses are generally cut in every year in October or March, so as not to leave more than three or four buds on each shoot. An opinion, however, appears to be gaining ground among gardeners, that this pruning has been carried too far, and that many kinds, particularly all the climbing Roses, ought not to be pruned at all. Roses are so easily forced, that, with very little trouble, they may be had in flower every month in the year. For instance, some Moss Roses may be taken up as soon as they have done flowering, and having been put into pots and pruned, they may be kept in a shady situation in the open air till wanted for forcing. Those that are wanted to blossom at Christmas, should be plunged into a hotbed, or put into a hothouse the 1st of October; those put into the hothouse in November will flower in January and February; and so on; always calculating that the plants will flower about two months after they are placed in the hothouse or frame. During the forcing they should be abundantly supplied with water of the same temperature as the house in which they grow; and the heat they are kept in should never be less than 60° at night. The China Rose may be made to flower all the winter by keeping in a greenhouse at 50°, and having pinched off all its flower-buds in summer and autumn.

The insects that attack Rose trees are very numerous. Perhaps the most troublesome are the Aphides (see A'PHIDS), which cover the tender shoots in summer and autumn. The

caterpillars of several small moths are also very destructive to Rose trees. One of these, which is called a Leaf-miner, lives within the leaf, where it feeds upon the pulpy matter, leaving traces of its course by a number of pale yellow zig-zag lines, which are occasioned by the skin of the leaf withering when deprived of the pulpy matter which supported it. The perfect insect is called the Red-headed Moth (*Microsetia ruficapitella*); and it is so small, that even with its wings expanded it does not measure more than a quarter of an inch. Another very destructive insect is the maggot or grub of one of the saw-flies. The perfect insect, which is a beautiful creature, with transparent wings, lays its eggs in a flower-bud; and in this the grub is hatched, eating its way out and destroying the petals that it passes through. Other insects are a kind of leaf-rollers, not exactly like those that infest the oak, but a species of the genus *Lýda* (belonging to the *Tenthredinidæ*), which construct a portable case, in which they enfold themselves, of pieces of leaves, which they cut out and fasten together in a spiral direction. Besides, there is the Rose Moth, a species of *Tortrix*, which fastens the bud, by a number of slender threads, to one of the leaves, which it doubles up like the folds of a fan.

The only sure remedies for all these insects are hand-picking and frequent syringing. Tobacco-water is also used; and this is made by pouring a gallon of boiling water on half a pound of the best shag tobacco, and letting the decoction remain till it is cold. The infected shoots should then be dipped in the tobacco-water, and suffered to remain in it about a minute, and then washed with clean water. If the tobacco-water be suffered to dry on

the plants, it will blacken the young shoots; and the remedy will thus be worse than the disease. Lime-water is also sometimes used, but no more lime should be put into the water than to make it look slightly milky; and the leaves should be washed after it has been suffered to remain on a short time. A strong decoction of quassia is another remedy, and it is better than either lime or tobacco-water, as it does not injure the appearance of the plants. Dipping the shoots in clean water, and laying them on one hand, while a soft brush is gently passed over them with the other, is also found very efficacious.

ROSCOEÆ.—*Scitamineæ*.—Handsome stove-plants, somewhat resembling the Indian Shot. They should be grown in loam, peat, and sand; and they are increased by dividing the root.

ROSE.—See Ro'sa.

ROSE ACACIA.—*Robinia hispida*.—A very handsome shrub with pinnate leaves, and long drooping racemes of rose-coloured flowers. It will grow in any soil, but it should be placed in a sheltered situation, on account of the brittleness of its branches, and their liability to be broken off by high winds.—See ROBINIA.

ROSE BAY.—See RHODODENDRON and NERIUM.

ROSE CAMPION.—*Agrostemma*.—The very pretty flowers known by this English name are included by many botanists in the genus *Lychnis*. Many of the kinds are annuals but the common Rose Campion, *A*; *coronaria*, is a perennial.

ROSEMARY.—*ROSMARINUS*.

ROSE OF HEAVEN.—*Agrostemma* or *Lychnis Cæli Rôsa*.—An ornamental annual from the Levant, quite hardy in British gardens.

ROSE OF JERICO.—*Anastatica*



*hierochuntina*.—A cruciferous annual from the Levant, of no beauty, but curious, from the manner in which its branches curl round the seeds when they are ripe. The end of the shoot containing the seeds thus protected falls off, and is blown by the wind from place to place without discharging the seeds, so long as it is dry; but as soon as the ball reaches a moist place, where the seeds can germinate, the protecting branches relax, and the seeds drop out. There is a species of *Lycopodium* from tropical America, *L. lepidophyllum*, which curls up like the Rose of Jericho, and is often mistaken for it.

ROSE-ROOT.—See RHODIOLA.

ROTATION OF CROPS.—It has been found by a series of experiments, that the same kind of annual plant should never be grown for more than two years in succession in the same ground, without manuring or renewing the soil; as plants exhaust the soil of those salts which are nourishing for them. The ground, however, which thus becomes unfit for one kind of plant, is found to be suitable for another kind quite different; and the making these plants succeed each other in a proper manner is called the rotation of crops. Perennial plants, and trees and shrubs, are not so liable to injury from their exhausting the soil, as they elongate their roots every year, so as to have their spongioles always in fresh soil; but some shrubs, such as Roses, which never have long roots, should either be transplanted every third or fourth year, or have manure laid on the surface of the soil, to supply them with fresh food.

ROT-HEAP.—A heap composed of sand, and such fruit as haws, hollyberries, ash-keys, hornbeam-nuts, and similar seed-vessels, which is

turned over several times in the course of the winter, to promote the decomposition of the exterior covering of the seed. The object is to save room in the nursery, because these seeds, and others, if sown before the flesh or exterior covering is rotted off, will lie dormant in the soil for a year; whereas by rotting it off and sowing the seeds in the spring of the second year after which they are gathered, they come up the following May or June. The rot-heap is kept in what is called the rotting-ground, which may be in any open situation fully exposed to the weather. The heaps may be one or two feet in thickness, and of any convenient width, the object being to produce decay without inducing such an active fermentation as would generate sufficient heat to destroy the vital principle in the seeds.

ROUGH POTTING.—This is a most important improvement in the system of growing plants in pots; and it consists in filling the pot with rough pieces of turf, pieces of charcoal, and stones, so as to allow air to pass freely to the roots. It is well known that plants will neither produce flowers nor fruit without an ample supply of carbonic acid gas, which they obtain from the air.

RUBBISH—such as broken bricks, stones, remains of old walls, &c.—is of great use for laying at the bottom of a flower-bed or border in an open garden in which bulbs are to be grown. A similar bed has also been found very useful for growing Dahlias, as they are very liable to be injured by stagnant moisture.

RUBUS.—*Rosæcea*.—The Bramble.—There are but few ornamental species of this very extensive genus. *R. odoratus*, the flowering Raspberry, with reddish flowers, and *R.*

*nootkdnus*, the Nootka Sound Bramble, with large white flowers, both kinds being sweet-scented, are the most ornamental. To these may be added the double-flowered common Bramble (*R. fruticosus* var. *pomponius*) and *R. spectabilis* the Californian Bramble, with fragrant dark-purple flowers, and dark yellow fruit. All the brambles are very hardy, but very short-lived; their stems dying down every second year, like those of the common Raspberry (*Rubus idæus*). They all send up numerous suckers, by which they are propagated; and they all delight in a moist soil and shaded situation; though they will not thrive exactly under the drip of trees.

RUDBECKIA.—*Compositæ*.—Very showy perennial, biennial, and annual plants, which should be grown in light rich soil. They attain a very large size, and are therefore only suitable to large gardens. They are all hardy, and of the easiest culture of their respective kinds.

RUE.—*RUTA*.

RUELLIA.—*Acanthaceæ*.—Herbaceous plants with pretty tubeshaped blue flowers. Some of the species require a stove, and others a greenhouse; but they should all be grown in light rich soil, and are propagated by cuttings.

RUSCUS.—*Smilacææ*.—The Butcher's Broom.—Very curious evergreen shrubs, most of which bear their flowers and fruit on their leaves. All the species prefer shady situations under the drip of trees, where but few other plants will grow, and they are all readily increased by suckers, which they throw up in abundance. One of the kinds is sometimes called the Alexandrian Laurel.

RUSSELLIA.—*Scrophularinææ*.—*R. juncæa* is a very elegant

stove-plant, with slender rush-like branches, and scarlet tube-like flowers. It should be grown in light rich soil, and abundantly supplied with water while in a growing state. It is propagated by cuttings, struck in heat.

SA'BAL.—*Palmææ*.—The Palmetto, or American Palm.—These Palm-trees, which are natives of tropical America, require a stove in England, and they should be grown in light loamy soil. They are increased by suckers, which they send up freely. They are all of dwarf stature, and grow freely in a somewhat moist heat.

SA'CCHARUM.—*Graminææ*.—The Sugar-cane grows freely in England, if kept in a stove in a very rich loamy soil. It may be increased by suckers; or if a part of the stem be laid in a trench in the tan-pit, or in rich loam, where it has bottom-heat, it will form plants at every joint.

SACRED BEAN OF INDIA.—*NU'LUMBUM SPECIOSUM*.

SAFFRON.—*Orbæus sativus*.—See CROCUS.

SAGE.—See SA'LVIA.

SAGITTA'RIA.—*Alismæææ*.—Water plants, some of which require a stove, others a greenhouse, and others are quite hardy. They should all be grown in loamy soil, with their stems in water; and they are increased by seeds or dividing the roots.

SAGO PALM.—See SA'GUS.

SA'GUS.—*Palmæææ*.—A kind of Palm, from the pith of the stem of which Sago is made. The plants should be grown in sandy loam, and they should be exposed to a strong moist heat. The seeds are produced in a sort of cone, which is of a brilliant shining brown, and very hand-

sage; but the plant has never yet produced seeds in this country.

SAINT AGNES'S FLOWER.—The Snow-Flake.—See *LEUCOJUM*.

SAINT BARNABY'S THISTLE.—*Centaurea solstitialis*.

SAINTFOIN.—See *ONOBRYCHIS*.

SAINT JOHN'S BREAD.—See *CERATONIA*.

SAINT JOHN'S WORT.—See *HYPERICUM*.

SAINT MARTIN'S FLOWER.—*Alstromeria Fls Martini*.

SAINT PETER'S WORT.—The Snow Berry.—See *SYMPHORIA*.

SALICARIA.—See *LYTHRUM*.

SALICORNIA.—*Chenopodiaceæ*. Glasswort.—Succulent British plants, which grow naturally by the seashore. When cultivated, they should be grown in silver-sand, and a little salt laid occasionally on the surface of the soil, so as to be washed in by watering or rain. One of the kinds is sometimes eaten as a culinary vegetable, under the name of Marsh Samphire.

SALISBURYA.—*Amentaceæ*, or *Taxaceæ*.—This very remarkable plant was originally called *Ginkgo biloba*, *Ginkgo* being its name in Japan. Its name has, however, now been altered to the more euphonious one of *Salisbùria adiantifolia*, the leaves resembling in form those of the Maiden-hair Fern, the generic name of which is *Adiantum*. As the *Salisbùria* grows to a very large size, and as there are specimens in the neighbourhood of London above sixty feet high, it would not have been mentioned here, had it not been very ornamental when young. The tree has flowered at Kew and at other places; but it has never borne fruit in England, though it has in France.

SALIX.—*Amentaceæ* or *Salicaceæ*.—The Willow.—A very extensive genus of ligneous plants, varying

in size from the tree Willow, of seventy or eighty feet high, to the creeping half-herbaceous kinds called *S. herbacea*, *S. vacciniifolia*, &c. Of these *S. herbacea* creeps so close to the ground that it forms on the Swiss mountains a kind of turf, not rising more than an inch above the surface of the ground, and yet forming, when closely examined, a complete miniature tree. All the kinds of Willow grow best in moist soil, or near water; and they all grow in such situations very rapidly. The Weeping Willow (*Salix babylonica*) has been known to grow twenty feet high in ten years, and the other species to increase in a similar proportion. All the common Weeping Willows grown in England are female plants, and it is supposed that the kind imported from St. Helena, and called Napoleon's Weeping Willow, is the male plant. Of the tall shrubby kinds of Willow *Salix caprea*, the great round-leaved Sal-low, or Grey Withy, is perhaps the handsomest; and it is the flowering branches of this species that are called Palms in the neighbourhood of London, and are gathered by children on Easter Sunday. The Willow will grow in any soil which is not too dry; and it is propagated by cuttings, which strike root when merely put into the ground, without any other trouble being taken with them.

SALLOW.—A kind of Willow, with roundish shaggy leaves.

SALPIGLOSSIS.—*Solanaceæ* or *Scrophularinæ*.—Very beautiful half-hardy annual plants, natives of Chili. The seeds should be sown in February on a slight hotbed; and the young plants should be planted out in May, or sown in May in the open ground for later flowering. The soil should be loam mixed with

one-third of peat or sand ; and the situation should be sheltered, and partially shaded ; as, if the collar of the plant should be exposed to the burning heat of the sun, so as to become withered, the plant will die off suddenly. It is also very easily killed by the collar being exposed to stagnant moisture. When grown in pots, it should be frequently shifted, always into pots only a little larger than the previous ones, so as to make the plant bushy. It varies very much, according to the soil and situation in which it is grown ; and if kept through the winter in a greenhouse, it will become partially woody, like the Mignonette. There are many different kinds, which are made species by some botanists, but which are now generally allowed to be only varieties. Many gardeners sow the seeds in autumn, and keep the plant in frames all the winter, that they may flower early in spring.

SALT-TREE.—See HALIMODENDRON.

SALT-WORT.—SALSO'LA.

SA'L'VIA.—*Labiatae*.—The Sage.—No one who has only seen the common Sage growing in a kitchen-garden could imagine the splendid flowering plants which belong to the genus *Sálvia*. Some of these, as for example *S. formósa*, are shrubby, and have dark scarlet flowers ; and others, such as *S. pátens*, have their flowers of the richest blue ; others, such as *S. aúrea*, have golden-yellow flower ; others, such as *S. dentáta*, have white flowers ; and in others, such as *S. involucrâta* and *S. purpúrea*, the flowers are purple. Besides these, some of the kinds have violet flowers, and others pink or crimson : and the different kinds of Clary (*S. Horminum*) are not cultivated for their flowers at all, but on account of the points of the shoots,

which are so deeply tinted as to have the appearance of flowers. The plants differ in their habits as much as in their flowers ; some are shrubby, some perennial, some biennial, and some annual ; and some are so tender as to require a stove ; while others must be kept in a frame or greenhouse ; but the greater part are quite hardy in the open air. All the kinds should be grown in a light rich soil ; and they are propagated by cuttings, division of the root, or by seeds, which nearly all the species ripen in great abundance. There are above a hundred and fifty distinct species of *Sálvia*, besides varieties.

SA'MBAC.—The Indian Jasmine.—See JASMINUM.

SAMBU'OUS.—*Caprifoliaceæ*.—The Elder.—The Common Elder, *Sambucus nigra*, is a low tree, seldom, if ever, exceeding twenty feet in height, and generally having the character of a shrub rather than that of a tree. The species is not ornamental, but there is a variety with cut leaves, *S. n. laciniâta*, which is very much so. The most ornamental kind of Elder is, however, *S. racemósa*, with loose panicles of large dark scarlet berries, which look like bunches of small scarlet grapes. All the different kinds of Elder thrive most in rich soil kept moist, and they are propagated by layers, cuttings, and seeds, which ripen freely. They are all quite hardy, and require very little attention from the gardener.

SAND is an important article in the propagation and culture of plants ; and no good garden, whether small or large, ought to be without a stock of it. Sand, relatively to gardening, is of two kinds : pure white silver-sand free from earthy matter and ferruginous particles, which is only found in particular situations,

and common brown or grey sand, which is found in pits either with or without gravel, and on shores of rivers or the sea. The first kind of sand is used for striking Heaths, and other plants difficult to root by cuttings, and also for mixing with peat, for growing the more tender kinds of house plants. This sand is procured in abundance in the neighbourhood of London and Paris, from pits; but throughout the country in general, it is chiefly to be found mixed with peat, and forming what is called heath soil on the surface of heaths or commons. In these situations this sand, from being exposed alternately to the air, the sun, and the action of rain, becomes white by bleaching, and is indispensable to the gardener; but when it exists in heath soil in a sufficient proportion for growing plants, pure sand is only wanted by the gardener for striking cuttings. It is, however, so useful for this purpose, that a quantity of it ought to be procured, and carefully kept in a box where it will not be mixed with other soil, by every person who grows plants in pots.

Common coarse sand is used for striking the commoner kinds of plants either by cuttings or layers; it is also used for placing under bulbs when planting them, and in general for mixing with soil of different kinds, with a view to render it more free and pervious to water. This description of sand may be procured in almost every part of the country; and it is also necessary to guard against pit-sand which is of a rusty brown, and consequently strongly impregnated with iron, and sea-sand, which is necessarily impregnated with salt. By mixing irony sand with quicklime in a state of powder, the iron may be neutralised; but this operation requires a

year or two to effect it, besides the expense of the lime, and the necessity of separating it afterwards by sifting. Saline sand may be rendered fit for use by repeated washings with fresh water; but this expense can only be advisable when no other sand can be procured. In various parts of the country there is a lead-coloured soft sandstone, which when broken, and reduced to a state of powder, forms an excellent sand, both for mixing with soil, and striking cuttings.

SANDAL-WOOD.—See SANTALUM.

SANDERSONIA.—*Liliaceæ*.—This very remarkable and ornamental plant was discovered by John Sanderson, Esq., in 1851, near Port Natal, in South Africa. It has a small tuber, an upright stem, and numerous golden orange bell-shaped flowers bearing more resemblance to the Fritillaries than the lilies. It is about as hardy as *Gladiolus natalensis*. *S. aurantiaca* is the only species yet known.

SANGUINARIA.—*Papaveridææ*.—Puccoon, or Canadian Bloodwort. A very pretty little plant with white ranunculus-shaped flowers. It should be grown in a light sandy soil, and it has a good effect when used to fill one of the beds of a geometric flower-garden. The plants are increased by seed or division of the roots.

SANTALUM.—*Santalidææ*.—Sandal-wood.—Stove plants, natives of the East Indies, and one species from New Holland. The flowers of *S. album*, the true Sandal-wood, are small, and are produced in spikes or racemes; but the great value of the plant consists in the fragrance of the wood, which is so great that it is burned for incense, &c., and is said to be destructive to all noxious insects. The plants should be grown in light sandy loam,

and kept rather dry; but the wood has comparatively very little fragrance in this country.

**SANTOLINA.**—*Compositæ*.—Lavender Cotton.—Evergreen dwarf shrubs, which will grow in any common garden soil, and which are propagated by cuttings.

**SANVITALIA.**—*Compositæ*.—A beautiful little Mexican annual, well adapted from its dwarf stature and compact habit of growth for covering a bed in a geometric flower-garden. The flowers are large in proportion to the size of the plant, and they are of a rich brown and yellow. It is quite hardy, and only requires sowing in March or April in the open border.

**SAPINDUS.**—*Sapindaceæ*.—The Soapberry.—Natives of the East and West Indies, which require a stove in England. They should be grown in loam and peat, and they are propagated by cuttings.

**SAPONARIA.**—*Silenaceæ* or *Caryophyllaceæ*.—Soapwort.—Very beautiful little plants, annual and perennial, greatly resembling some of the kinds of *Lýchnis*. All the kinds of *Saponaria* look very well on rock-work, covering it with a profusion of beautiful little pink flowers. The handsomest kinds are *S. ocymoides* and *S. calabrica*, for the perennials; and *S. Vaccària* and *S. perfoliata*, for the annuals. They will all grow in any common garden soil.

**SA'RACHA.**—*Solanaceæ*.—Annual and perennial plants, natives of Mexico and Peru. *S. viscôsa*, which is the handsomest species, has rather large cream-coloured flowers, beautifully marked in the centre with olive dots, and which are succeeded by large red berries. It may be treated as a half-hardy annual; or the roots, which are numerous, may be taken up and kept

dry during winter, like those of the Marvel of Peru, and other similar plants. When treated as an annual, the seeds should be sown on a slight hotbed in February, and the young plants removed into the open border in May.

**SARRACENIA.**—*Sarraceniaceæ*.

—The American Pitcher-plant, or Side-saddle flower.—Bog-plants, with very curious flowers, and pitcher-shaped leaves. Though natives of Canada, where they flower freely, and are produced in great abundance, they are seldom flowered in England without the aid of artificial heat. They are grown in pots filled with peat and moss, and placed in saucers of water, or in the open air, on the banks of ponds or rivers. When kept in a room, or on the balcony, they should be grown in double pots, the interstice between the two being filled with moss.

**SARSAPARILLA.**—See **SMILAX**.

**SASA'NQUA.**—A kind of *Camélia*, the blossom of which strongly resembles that of the Tea-tree.

**SATY'RIUM.**—*Orchidaceæ*.—Terrestrial orchidaceous plants from the Cape of Good Hope. The leaves are very curious, from the flat manner in which they spread themselves on the surface of the pot; and the flowers, which are generally yellow, are very handsome. They should be grown in very sandy loam or peat; and they are generally kept in a greenhouse. They are very apt to damp off if over-watered.

**SAW-FLY.**—*Tenthredinidæ*.—Beautiful flies with clear wings, which are furnished with a curious instrument like a saw in the lower part of the body, with which they wound the bark to deposit their eggs. These eggs, like those of some other insects, greatly increase in size after they are laid. The grub or maggot is short and thick,

with a black shining head, and when attacked, it can let itself down by a thread. These insects are very destructive to Rose trees, as they destroy the flower buds.

**SAW.**—The more convenient kind for a lady to use for garden purposes




FIG. 47.—BOW-SAW FOR CUTTING OFF BRANCHES OF TREES.

is one called a bow-saw (see fig. 47), made to screw tighter if necessary.

**SAXA-GOTHEÆ.**—*Coniferae*.—A very handsome evergreen tree, from the Andes of Patagonia, and consequently likely to prove hardy in British gardens. The leaves resemble those of the Irish Yew on the upper surface, but are almost white, with a glaucous line below. The tree, in its native country, is about thirty feet high. It is named after Prince Albert's family.

**SAXIFRAGA.**—*Saxifragæ*.—Well-known herbaceous plants, many of which are natives of Britain, with white, yellow, or pink flowers. They are all of the easiest culture, and will grow in any light garden soil,

though they prefer a deep sand. *S. umbrosa* is the London Pride, and *S. granulata*, the common Mountain Saxifrage. All the kinds are handsome, and many of them are well adapted for rock-work.

**SAXIFRAGE.**—See **SAXIFRAGA**.

**SCABIOSA.**—*Dipsacæ*.—The Scabious. — Ornamental perennial and annual plants, mostly natives of Europe and the East Indies, that will grow freely in any common garden soil, and may be increased by seeds.

**SCABIOUS.**—See **SCABIOSA**.

**SCALE INSECT.**—See **COCCUS**.

**SCHERIA.**—*Gesneriæ*.—*S. Mexicana* closely resembles some of the species of *Achimenes*, from which genus it has been separated on account of its funnel-shaped stigma. There are two varieties; one with purple, and the other with light blue flowers.

**SCHINUS.**—*Anacardiæ*, or *Terebinthæ*.—Deciduous shrubs or low trees, natives of Brazil and Peru, nearly allied to *Duvaia*. The flowers of *Schinus Mølle*, the commonest species, are small and of a yellowish-green; but they are succeeded by berries of a beautiful rose-colour and highly polished. The leaves are impari-pinnate and very handsome, and they have the same peculiarity as those of the *Duvaia* (see *DUVAUA*). *S. Mølle* was first considered a stove-plant; it was afterwards transferred to the greenhouse, and it is now found to succeed in the open air. It was introduced in 1597, but it was very scarce till about 1830, when it was first tried in the open ground. It will grow in any common garden soil; and it only requires a slight protection during hard frosts.

**SCHIZANDRA.**—*Menispermæ*.—A climbing or trailing half-hardy shrub, with scarlet flowers, nearly

allied to *Cocculus indicus*.—For the culture, see COCOULUS.

**SCHIZANTHUS.**—*Solanaceæ*, or *Scrophulariaceæ*.—A genus of very beautiful half-hardy annual flowers, which may be either sown in autumn or spring. If wanted to flower in spring, the seed should be sown in August or September, as soon as it is ripe, in light rich mould; and the young plants should be kept in well-drained pots, in a frame or greenhouse, during winter. In February, they should be shifted into larger pots, and this shifting should be repeated every week or fortnight till the plants have formed their flower-buds. Care must be taken in shifting the plants not to injure the roots, as they are very tender and succulent. The soil should be composed of equal parts of vegetable mould and sandy loam, or of loam, peat, and rotten manure from an old hotbed. It has lately been found, however, that *S. retusus* will flower better in a poor dry soil than in a rich one; all the kinds require very little moisture, and if the soil be too rich for them they will produce only leaves instead of flowers. When the seeds are sown in spring, it should be on a hotbed, and the young plants should be removed into the open air in May, when they will flower in autumn. The plants are much larger in the open ground, and the flowers are finer, if the soil be sufficiently rich and light: but care should be taken to plant them in a sheltered situation, or to tie them to stakes, as the stems are very brittle, and very liable to be broken off by high winds. The principal kinds of *Schizanthus* are *S. pinnatus*, with its varieties, all of which have purplish flowers; *S. retusus*, with scarlet and yellow flowers; and *S. Priestii*, with white and yellow flowers. Of these, *S. pinnatus* and

its allied species or variety, *S. pbr-rigens*, are the hardiest.

**SCHIZOPETALON.**—*Cruciferae*.—An annual flower, with curiously cut petals, and a strong tap-root. It is rather difficult to grow, as it does not bear transplanting well, unless when quite young, and it requires a deep free soil for its descending root. It should be sown in spring, and, if possible, where it is to remain.

**SOROTIA.**—*Leguminosæ*.—Cape shrubs, with very showy flowers, which may be kept in a greenhouse during the greater part of the year; but which should be removed to a stove or hotbed frame during winter. They should not, however, be plunged, as bottom-heat does not appear to suit them. They should be grown in peat mixed with a little loam, or in a very sandy loam, the pots being very well drained; and they are propagated by cuttings struck without bottom-heat. Many gardeners keep them in a greenhouse all the year, covering them with a hand-glass and a mat in very severe weather.

**SCHOMBURGKIA.**—*Orchidaceæ*.—Some of the species of this genus are very handsome, and as they are found at a great height above the sea in South America, they will probably prove more hardy than most other orchids in this country.

**SCHUBERTIA.**—*Coniferae*.—See DROUOUS CYPRESS.

**SCILLA.**—*Asphodèleæ*.—The Squill or Wild Hyacinth.—Bulbous-rooted plants, mostly natives of Europe, which send up their beautiful bell-shaped flowers before their leaves. Their flowers resemble those of the Hyacinth, but they are much smaller. *S. sibirica* is, perhaps, the most brilliant blue flower grown in British gardens; and there are other kinds with white or pale pink flowers, well deserving of cultivation. *S.*



*nonscripta*, the Wild Hyacinth, is sometimes called the Blue Bell, and the Hare Bell; but these names are also applied, and apparently with more propriety, to *Campánula rotundifolia*.—See CAMPA'NULA and HYACINTHES. All the kinds of Scilla are quite hardy, but they thrive best in a sandy soil and a somewhat shady situation. They are increased by offsets, and the bulbs may be taken up in autumn if it is thought necessary to remove them; but otherwise they may remain in the ground several years without sustaining any injury.

SCITAMINEÆ.—Hothouse plants with reed-like stems, long broad leaves, and showy flowers, which are usually fragrant.

SCORPION GRASS.—See MYOSOTIS.

SCORPION SENNA.—*Coronilla Emerus*.—See CORONILLA.

SCORPIURUS.—*Legumindæ*.—Caterpillars.—Annals with yellow pea flowers, the seed vessels of which resemble caterpillars. The species are all natives of the south of Europe, and they are all quite hardy in British gardens.

SCORZONE'RA.—*Compósitæ*.—Viper's Grass.—Handsome perennials, with purple, pink, or yellow flowers, quite hardy in British gardens, and growing in any common garden soil.

SCOTCH LABURNUM.—*Cytisus alpinus*.—See CYTISUS.

SCOTTIA.—*Legumindæ*.—An Australian shrub with reddish pea-flowers, quite hardy in British gardens, if grown in sandy peat.

SCREENS differ from sieves in having the wires in parallel lines, and not reticulated; and in being too large to be shaken by the hands. A screen consists of a number of parallel wires fixed in a wooden frame, and supported at the one end by two wooden posts, while the other rests

against the ground; and the earth to be sifted is thrown by spadefuls against the wires, so that while the mould passes through them, the stones and rubbish fall on the side next the gardener. The earth must be well broken with the spade before it is thrown upon the screen, and the operation can only be performed when the weather is dry.

SCROPHULA'RIA.—*Scrophulariæ*.

—Figwort.—Perennial plants, with brownish flowers, mostly natives of Europe, and growing in any common garden soil.

SCUTELLA'RIA.—*Labiata*.—Skull-cap.—Handsome perennial plants, generally with blue flowers, but sometimes having pink, white, or purple flowers, all of which are shaped like those of the Snapdragon. Some of the species are natives of Britain and other parts of Europe, and others of North America and Australia. They grow best in peat or in very sandy loam; and they are all quite hardy in British gardens.

SEA BUCKTHORN.—*Hippophæ rhamnoides*.—See HIPPOPHÆ.

SEA HEATH.—See FRANKENIA.

SEA HOLLY.—*Eryngium Aquifolium*.—An umbelliferous perennial with blue flowers, a native of Spain, which should be grown in very sandy loam.

SEA LAVENDER.—See STATICE.

SEA RAGWORT.—*Cineraria Maritima*.—A half-hardy dwarf shrub with yellow flowers, a native of the south of Europe, which is generally grown in a greenhouse, in a mixture of loam and peat.

SEA-SIDE BALSAM.—*Crôton Eleuteria*. A native of Jamaica. See CROTON.

SEATS for gardens are either open or covered, the latter being in the form of root-houses, huts, pavilions, temples, grottoes, &c., and the

former being either fixed, temporary, or portable. Fixed seats are commonly of stone, either plain stone benches without backs, or stone supporters to wooden benches. Sometimes, also, wooden seats are fixed, as when they are placed round a tree, or when boards are nailed to posts, or when seats are formed in imitation of Mushrooms, as in the grounds at Redleaf. Fixed seats are also sometimes formed of turf. Portable seats are formed of wood, sometimes contrived to have the back of the seat folded down when the seat is not in use, so as to exclude the weather and avoid the dirt of birds which are apt to perch on them. Another kind of portable seat, which is frequently formed of iron, as shown in fig. 48, is readily




FIG. 48.—MOVEABLE GARDEN SEAT.

wheeled from one part of the grounds to another, and the back of which also folds down to protect the seat from the weather. There is a kind of camp stool, which serves as a portable seat, imported from Norway, and sold at the low price of 2s. 6d. or 3s.; and there are also straw seats like half beehives, which are, however, only used in garden huts, or in any situations under cover, because in the open air they would be likely to be soaked with rain.—There are a great variety of rustic seats formed of roots and crooked branches of trees, used both for the open garden and under cover, and there are also seats of cast and wrought iron of great variety

of form. There should always be some kind of analogy between the seat and the scene of which it forms a part; and for this reason rustic seats should be confined to rustic scenery; and the seats for a lawn or highly kept pleasure ground ought to be of comparatively simple and architectural forms, and either of wood or stone, those of wood being frequently painted of a stone-colour and sprinkled over with silver sand before the paint is dry, to give them the appearance of stone. Iron seats, generally speaking, are not sufficiently massive for effect, and the metal conveys the idea of cold in winter and heat in summer.

When seats are placed along a walk, a gravelled recess ought to be formed to receive them; and there ought generally to be a foot-board to keep the feet from the moist ground, whether the seat is on gravel or on a lawn. In a garden where there are several seats, some ought to be in positions exposed to the sun, and others placed in the shade, and none ought to be put down in a situation where the back of the seat is seen by a person approaching it before the front. Indeed the backs of all fixed seats ought to be concealed by shrubs, or by some other means, unless they are circular seats placed round a tree. Seats ought not to be put down where there will be any temptation to the persons sitting on them to strain their eyes to the right or left, nor where the boundary of the garden forms a conspicuous object in the view. In general, all seats should be of a stone-colour, as harmonising best with vegetation. Nothing can be more unartistical than seats painted of a pea-green, and placed among the green leaves of living plants.

**SECATEUR**.—A kind of pruning shears, somewhat larger and stronger than those common in English gardens, and principally used in France for pruning peach trees and other kinds of wall-fruit trees.

**SECURIGERA**.—*Legumindæ*.—The Hatchet Vetch. — A hardy annual, with yellow pea-flowers. It requires no other care than sowing in March or April, but as it is very coarse-growing, and requires a great deal of room, it is not suitable for a small garden. This plant was called *Coronilla Securidaca* by Linneus.

**SEDUM**.—*Crassulææ*.—The Stone Crop.—Succulent plants with white, red, or yellow flowers. The genus takes its botanic name of *Sedum* from the Latin verb *sedere*, to sit, because in a wild state it appears to be sitting or crouching on the old walls or rocks which form its habitat; and its English name of Stone Crop alludes to the same habit of growth, as it appears to be growing out of stones, which afford no other crop. The most beautiful species of the genus is decidedly *S. Sieboldii*, but it requires a greenhouse to grow it well. All the species, though quite hardy, should be grown in well-drained pots filled with turfy loam, mixed with lime-rubbish; and they are all admirably adapted for rock-work. They are increased by cuttings or dividing the roots.

**SEEDS**.—The gathering and preservation of seeds is an occupation peculiarly agreeable to persons fond of gardening; partly, no doubt, because it contains so much of future promise, and on the same principle that sowing is universally considered a more exciting operation than reaping. The greater number of seeds of ornamental herbaceous plants are contained in long narrow

Pods called siliques, or silicles, such as those of the Cruciferous plants; or in leguminous pods, such as those of the Sweet Pea; or of capsules, such as those of *Campanula*: but a number of plants produce their seeds naked in tubes, such as the *Scrophularinæ*; on receptacles, such as the *Compositæ*; and some in fruits more or less fleshy, such as the *Fuchsia*. All seeds may be known to be ripe, or nearly so, by the firmness of their texture, and by their changing from a white or greenish colour, to a colour more or less brown. There are, indeed, some seeds which are whitish when ripe, such as the white Lupine, and several of the Sweet Peas; and other seeds that are quite black, such as those of some *Ranunculuses*; but, in general, a brown colour is a characteristic of ripeness. Seeds should be gathered on a dry day, after the sun has had sufficient time to exhale all the moisture which dews or rains may have left on the seed-vessels. In general, the pods, or capsules, should be cut off with a small portion of the stalks attached, and the whole should be spread out, each kind by itself, on papers in an airy room or shed, from which rain and the direct influence of the sun are both excluded. When the seed-vessels are thoroughly dried, they may be put up in papers, without separating the seeds from them, and kept in a dry place, rather airy than close, till wanted for sowing. Seeds preserved in the seed-vessel, no doubt, make comparatively clumsy packages, to seeds from which every description of husk or covering has been separated; but in this clumsy state they are found to keep better than when cleaned. Nevertheless, when they are to be sown the following year, or sent anywhere in a letter,

it is better to take them out of their covering and to render them as clean as possible, by passing them through sieves, with holes sufficiently large to admit the escape of dust, but not of the seeds. Such sieves on a small scale every lady may make for herself, by turning up the edges of a piece of thin pasteboard cut in a circular form, and piercing the bottom with holes with a large pin or darning-needle. When it is determined to separate the seeds from the seed-vessels, instead of putting up the whole together, the vessels, after gathering, may be dried in the sun, when many of the seeds will come out by the expansion of the seed-vessels in the heat, and the remainder can easily be rubbed out. This is the usual practice of nurserymen. For keeping seeds a lady ought to have a small cabinet, which she might form herself of pasteboard, with as many drawers as there are letters in the alphabet; and as her seeds are put up in papers, she can tie the packets of each genus by themselves, and put them in the appropriate drawer. Where so much trouble cannot be taken, a large brown paper bag, or a canvas bag for each letter of the alphabet, may be substituted.

The period during which seeds will retain their vegetative powers differs in different families, genera, and even species. Seeds of the *Ranunculaceæ* and the *Cruciferae* will, in general, retain their vitality for several years, in whatever manner they may be kept, provided the situation be not such as will cause them to germinate. On the other hand, seeds of the *Capsicum* will keep for several years if retained in the berry, but will seldom grow the second year when removed from it. As a safe general guide, to be adopted as a rule, that all

seeds will keep three years, and grow, provided they are retained in the unopened seed-vessel; that most seeds, if maturely ripened, and kept in a dry place in close paper packets, will grow the second year; and that all seeds whatever, whether kept in the seed-vessel or exposed in opened drawers, like those of the seedsmen, will grow the first year after being gathered. Mignonette seed will keep seven years; but that of Stocks and Wallflowers will not remain good more than two years, unless kept in the pod. Sweet Peas and Lupines will, with difficulty, keep two years, while the seeds of Prince's Feather, and of Poppies, will keep several years. Larkspur seed will seldom grow after the second or third year. Notwithstanding the length of time which some seeds will keep, it is generally advisable to sow them as soon after they are ripe as practicable, as fresh seeds always vegetate much sooner than old ones.

*SELAGO.*—*Verbenaceæ.*—*S. distans* is a pretty little greenhouse plant, very easily cultivated, if it is grown in sandy peat, and plenty of water is given to it in hot weather, not only to the roots, but by syringing it overhead.

*SELFHEAL.*—See *PRUNELLA.*

*SEMPERVIVUM.*—*Crassulaceæ.*—*Houseleek.*—Succulent plants, the most beautiful of which are natives of the Canary Islands, and require to be kept in the greenhouse. They should be grown in sandy loam, mixed with lime rubbish, and the pots should be well drained. They require very little water, except when about to flower; and they are propagated by cuttings, which must be laid to dry for some days before they are planted. When potted, they should neither have any water, nor be covered with a glass; but they may be plunged into a bed of

tan or dead leaves. The hardy kinds are very suitable for rock-work, and are increased by suckers from the roots.

SEMEI'NDRA.—*Onagrariæ*.—*S. grandiflora*, the only species known, is a slender shrub about six feet high, with numerous scarlet flowers. It is nearly allied to the Fuchsia, but its flowers are so long and narrow in their divisions, that they look almost like bright scarlet dragon-flies fluttering among the leaves: the plant is a native of Mexico, and first flowered in this country in the summer of 1858.

SENE'CIO.—*Compósitæ*.—A very extensive genus, including many plants which are quite worthless, such as the common British weed called Groundsel (*S. vulgaris*); many showy garden-flowers, such as the Jacobæa, or Purple Ragwort (*S. elegans*); and even some hot-house and greenhouse shrubs. Of these one of the handsomest garden-flowers is the double purple Jacobæa, which is a native of the Cape of Good Hope. It differs from the common British Ragwort (*S. Jacobæa*), the flowers of which are yellow, not only in its flowers, but in its habits of growth. The seeds of the purple Jacobæa should be sown on a slight hotbed, and the young plants removed to the open borders in May; if kept during the winter in a greenhouse they will become shrubby, like Mignonette. The tree groundsel, *S. præcox*, has yellow flowers, and large ivy-shaped leaves. All the species of Senécio like a rather rich loamy soil, kept open by a mixture of sand or peat, and most of them are hardy. There are, however, a few Cape shrubs belonging to the genus, which require a greenhouse. According to the new arrangement of the *Compósitæ* by Professor de Can-

dolle, nearly the whole of the genus *Cineraria* has been incorporated in that of Senécio.—See *CINERARIA*.

SENSITIVE PLANT.—There are several kinds cultivated in hot-houses, but the most interesting are *Mimosa pudica*, which has small white ball-like flowers, and *M. sensitiva*, with pink or lilac flowers, both of which grow about a foot high, and are natives of Brazil. There is also another kind, a floating aquatic plant, with bright yellow double flowers, a native of the tropics, both in the East and West Indies.

SHADDOCK.—See *CITRUS*.

SHADING is necessary to plants after transplanting, to prevent the evaporation from the leaves, which takes place when the plants are exposed to the full heat of the sun, being greater than the roots can supply moisture to support. Besides this, partial shade is necessary to many plants which cannot bear the direct rays of the sun; such, for example, as the Californian annuals—plants which in their native state grow in thick woods, fens, &c. In these cases, however, it is not necessary that the shade should be so great as for newly-transplanted plants. There is a great deal of difference in plants, with regard to their flowers, bearing the direct rays of the sun. Some require solar influence to make them expand, such as all the kinds of *Mesembryanthemum*; while others, such as the Evening Primrose, only unfold their flowers when the sun withdraws its rays. Most of the orchideous Epiphytes, which grow in dense woods, succeed best in hothouses glazed with green glass, which affords them the requisite degree of shade.

SHARP CEDAR.—*Acácia Oxycedrus*.—See *ACACIA*.

SHEEP LAUREL.—See KA'LIMIA.

SHEEP'S SCABIOUS.—JASIO'NE.

SHEPHE'RDIA.—*Elæagnæceæ*.

Beautiful shrubs or low trees, with silvery leaves, which were formerly considered to belong to the genus Hippophae. The silvery appearance of the leaves is produced by their outer surface being of a bluish green, and their lower surface lined with a soft silky down of a snowy whiteness. The plants are natives of North America, and may be grown in peat or in very sandy loam.

SHERA'RDIA.—*Rubiaceæ*.—Field Madder.—Very pretty British weeds, which may be introduced with good effect on rock-work.

SHIFTING is the operation of transferring plants grown in small pots to other pots a little larger; and it is of very great advantage when it is wished to keep plants short and bushy. In shifting, the ball of earth round the roots is not broken, but placed in the centre of the new pot, and the earth filled in round it.—See POTTING.

SINGLE OAK.—*Quercus imbricata*.

SHRUBBY TREFOIL.—*Pisèla trifoliata*.—See PTE'LEA.

SHRUBBY CINQUEFOIL.—*Potentilla fruticosa*.—See POTENTI'LLA.

SHRUBBERY.—A walk bordered by shrubs and trees with some flowers in front, is called a shrubbery. In small villas it generally leads from the house to the kitchen-garden; and sometimes goes round the latter, or is conducted round an open lawn. The object in forming a shrubbery is to produce as great an extent of interesting walk as the nature, extent, and other circumstances of the place will admit. There is then no positive rule for either the length of a shrubbery walk or its direction; and unless a given situation were

to be treated of, only some general directions can be given, or principles laid down, respecting the planting of the shrubs and trees.

If we examine most of the shrubberies in country residences, we shall find that there is a general sameness in the appearance of the trees and shrubs with which they are planted, from one end of the shrubbery to the other. This sameness results from the mode commonly employed of mixing those kinds of trees and shrubs that can be most readily procured indiscriminately together. Some evergreens are distributed throughout the whole, such as a few Hollies, and a few Pines and Firs; Laurels, with a few Roses, and perhaps a few Honeysuckles. The rest is made up of the common mixture planted by contractors or jobbing gardeners on such occasions. The object is merely to produce a plantation which shall have some flowering shrubs in it, and some herbaceous shrubs and Roses. If we examine the progress of such a plantation from the time it has been planted till it has attained the age of twenty or thirty years, we shall find that at the end of four or five years the herbaceous plants will have become choked up, and are either killed or rendered unsightly. In six years the Roses will have ceased to flower freely for want of light and air, and of manuring the soil; and hence they will have become the very reverse of ornamental. In ten years the finer shrubs will have been choked up by the coarser kinds, and in twenty years almost all the shrubs will have vanished, having been destroyed by the trees. There is no way of preventing this result to a shrubbery planted in the usual manner, except by constant thinning; beginning in the third

year and removing all the herbaceous plants that have not sufficient room and air and light to grow and flower freely. The bulbs may be left as long as they will grow; because as they have but little foliage, and that foliage is produced early and soon dies off, they are, under no circumstances, so disagreeable in their appearance as ill-grown common perennials. The Roses should be removed whenever they cease to flower vigorously; and all the other shrubs should be thinned out when their branches begin to interfere with one another. Where the shrubbery is twenty or thirty feet wide, every shrub should be kept separate from every other shrub, so as to be clothed with branches from the ground upwards; or the shrubs should be encouraged to grow in groups of different sizes, each group being kept more or less distinct from every other group. It may be thought that this mode of keeping the single plants, and the groups distinct, will prevent the shrubbery from serving as a screen; but this is a mistake; because though the plants by being placed alternately, will admit the eye of the spectator on the walk to see in among them, which in passing along a walk adds greatly to the variety of its effect, yet this very circumstance will prevent the eye from passing the boundary. Any person may prove this by drawing circles representing the shrubs or groups on paper to a scale; and supposing the strip of plantation to be thirty feet in width, and the circles some of them to be five feet in diameter, and some of them ten feet. The style of planting and thinning so as to keep each plant distinct, and always about to touch but never actually touching those around it, is what Mr. Loudon called the gar-

denesque treatment of shrubberies and plantations; and the style of grouping is called the picturesque mode of planting and management. These remarks may be considered as directions for making the most of a shrubbery already planted in the common manner; and in so far as thinning is considered, they will equally apply to the mode of planting which is now about to be described.

Planting shrubberies so as to produce variety in the aspect of the plantation is to be effected by one mode only, and that is to cause one kind of tree or shrub always to prevail in one place. In extensive shrubberies this will require several plants of the same species or variety to be placed together; but it occasions no additional expense; because, in a common shrubbery at least, the same number of plants of one species would be planted, the only difference being that they would be placed in different parts of the plantation. In a small shrubbery perhaps not more than one or two plants of a species or variety might be required; more especially if the object were to include as extensive a collection in the shrubbery as could conveniently be procured. There are almost a thousand trees and shrubs, exclusive of Roses, in British nurseries, which may be purchased at moderate prices; and all these may be used in a shrubbery which contains no more ground than a single acre. Supposing that only one plant of a kind is planted, and supposing that each genus or natural order is kept by itself, every part of the surface of the plantation will be different from that which precedes or follows it; and the greatest variety which the case admits of will be produced. So many plants planted on one acre

will, however, soon cover the soil ; and therefore in three years after planting, it will be necessary to begin to thin them. The thinning in this case ought to be directed to the removal of the commoner and coarser kinds. The most complete shrubbery that can be imagined is one which should contain all the larger trees distributed along it as a background, with all the smaller trees in front ; next to these should be the larger shrubs, then the smaller shrubs, next the Roses, and finally in the front, apart from the Roses, should be the herbaceous plants ; thus forming a splendid bank of vegetation on level ground. To prevent such an arrangement from becoming monotonous, it is essentially necessary that it should be combined with the natural system of relationship between the kinds ; and this ought to be carried out in the Roses, and in the herbaceous plants, no less than in the shrubs and trees. To solve this problem so as to carry the idea into execution, is one of the nicest points for an amateur landscape gardener to attempt.

All shrubberies whatever, however scientifically they may be planted and thinned out afterwards, will ultimately become old, and entirely lose the character which they had during the first eight or ten years after planting. Hence, in small places, which have been planted a certain number of years, it is impossible to have a shrubbery such as is here described, without removing the large trees and shrubs already existing ; and this must necessarily depend on the taste of the proprietor, and whether a collection of young trees and shrubs, which have a bare and new look, but which will be continually

creasing in beauty and magni-

tude, be preferred to a few full-grown plants which are already in a state of perfection, and which have an air of grandeur and repose.

When a shrubbery is planted, and for some years afterwards, the ground should be kept clear of weeds by hoeing or slight digging ; and the shrubbery should be separated from the walk by a verge of turf or of box. The Irish Ivy, the common English Ivy, and the St. John's Wort (*Hypericum calycinum*), are now used with good effect for edging walks under the shade or drip of trees. When the opposite side of the walk is turf, such as a lawn, then the side next the shrubs must have a verge of turf also ; but where a walk passes through the middle of a shrubbery, box edgings may be used on both sides. In general, however, a grass verge is greatly to be preferred, as being more appropriate to a scene connected with the lawn ; and as not calling up ideas of a kitchen-garden, or of a small flower-garden, where the beds are usually edged with box. Whatever may be the width of the gravel-walk, the grass verge should not be narrower than two feet, because less than that width cannot always be kept in good order ; such as neatly mown, level, and with the margins clipped, but not pared. Besides, a narrow verge has an appearance of meanness, and gives the idea of want of space. As the shrubs spread over the ground, there will soon be scarcely any part of the shrubbery that will not be covered by their lower branches. When these extend their branches towards the verge, and even spread over it, all digging and hoeing becomes unnecessary ; and the verge ought to be encouraged to extend in width under the branches of the plants. This is a point in the



management of shrubberies, which is almost everywhere defective; for the gardener generally continues cutting the inner edge of the verge and digging the ground among the herbaceous plants and the Roses, till he has reduced the verge to about six or eight inches in width next to the walk, this being the only part on which he will suffer any grass to grow; while the Roses and herbaceous plants, which have long ceased to be either healthy or ornamental, are left to display their stunted and naked branches, with the dug earth for a background. The constant digging and stirring of the ground breaks off the branches of the shrubs, and thus an unsightly gap is created, which entirely destroys all the pleasing ideas excited by glades of smooth turf appearing here and there to penetrate among the trees. To produce this latter effect, as the branches of any of the shrubs begin to spread over the verge, all digging and paring ought to be left off, and the grass encouraged to extend itself into the bays and recesses of the plantation. In like manner in a shrubbery with the walks edged with box, the box ought to be removed whenever the branches begin to spread over it, leaving no edging to the walk at all except what is formed by the retiring and advancing of the branches of the shrubs. This will form a walk with what are called picturesque edgings; but if a definite or a gardenesque edging is required, it may be formed of brick or stone. On no account whatever ought any kind of vegetable edging to be kept up which does not grow freely; for it is a maxim in gardening which ought never to be forgotten, that what cannot be grown well, ought not to be grown at all.

SIBERIAN CRAB.—*Pyrus baccata*, and *P. prunifolia*. These trees, though frequently grown in kitchen gardens and orchards for their fruit, deserve admission into ornamental plantations for the beauty of their Crabs when ripe.

SIBERIAN PEA TREE.—A hardy flowering shrub.—See CARAG'NA.

SI'DA.--*Malvaceæ*.—Stove, greenhouse, and hardy plants, natives of the East and West Indies, and North America, with showy white, pink, or yellow flowers, which they produce in great abundance. They are grown in loam and peat, and generally ripen seeds; by which, and by cuttings, they are readily increased.

SIDERO'XYLON.--*Sapdææ*.—Ironwood. — Half-hardy and hardy shrubs, and low trees, natives of America, the East Indies, and the Cape of Good Hope. Some of the species have been removed to Bummelia, and one species, a native of Morocco, which is hardly in British gardens, is now called Argania. All the kinds should be grown in loam and peat; and they have all small white or whitish-green flowers.

SIDE-SADDLEFLOWER.—See SARACENIA.

SIEVES are necessary in gardening to separate the stones and coarser particles from the mould to be used for potting and also for cleaning seeds. Garden sieves for mould should be made with deep wooden rims, but for seeds the wooden rim may be more shallow; in both cases the wires, or *toile métallique*, through which the mould is to pass, should be firmly attached to the rim, the holes or interstices not being more than the fourth of an inch in diameter.

SIFTING is the operation of passing any kind of soil through a sieve or screen to deprive it of its coarser particles; and some gar-

deners sift most of the soil they use for potting. Sifting, however, should be used with caution; as most plants thrive better when the particles of soil are not too fine. Turfy loam, for example, should generally be chopped small with a spade or trowel, and not sifted; and peat should not be deprived of the vegetable fibre in which it abounds. Sifted earth, when of a loamy nature, is very apt to cake together and to become impenetrable to the finer roots of plants.

**SILENE.**—*Sileneæ* or *Caryophyllaceæ*.—The Catchfly.—Well-known annual and perennial plants, many of which are natives of Britain, with flowers something like those of the Pink. They are nearly all quite hardy, and only require the common treatment of their respective kinds. Lobel's Catchfly (*S. Armeria*) is a common garden annual, that requires sowing in the open ground in March or April. *Silene Schäfta* is a very ornamental hardy perennial introduced in 1846. It is a dwarf plant, very suitable for beds, borders, and rock-work, with abundance of bright crimson flowers, which continue from June to October.

**SILK TREE.**—*Acacia Julibrissin*.—See ACAAIA.

**SINGLE TREES AND SINGLE SHRUBS** are the grand sources of variety in a lawn or park, where the surface is flat and without any other resources; and they are also, when judiciously disposed, valuable additions to a surface naturally varied by undulations. The great art in putting down single trees is, to dispose them so as to form groups when seen from a distance, and yet so as to produce variety in every change of position in the spectator when near. The kinds of trees and shrubs may be varied at pleasure, provided some attention be paid to

the prevalence of one general form or character of tree or shrub in one place. For example, if conical trees be distributed equally over the grounds, along with round-headed trees, they will produce great sameness; but if conical trees prevail in one place, round-headed trees in another, and flat-spreading trees in a third, so many distinct characters will be produced. The same may be said as to shrubs. The sure mode of proceeding on right principles is to take the different genera, and allow only the species and varieties of one genus to prevail in one place. Single trees should always be planted in prepared soil raised in heaps a foot or more above the general surface; so that after a year or two, when the earth has settled down, the tree may stand on a little hillock. The trees before planting should be ten feet or twelve feet in height, with trunks three inches or four inches in diameter at the surface of the ground. The shrubs should also be of as large a size as will transplant with ease and a fair prospect of success, and this size will vary according to the kind of shrub. Evergreen trees of the Pine and Fir tribe, and of the Cypress tribe, the beauty of which depends on their spreading branches, should either be planted in a situation where no fence is requisite, or they should be surrounded with iron hurdles or some other light fence placed five or six feet from the stem of the tree, and extended to a greater distance as the lateral branches advance in length; but broad-leaved trees, such as most of the *Exogens*, may be protected by fences placed close to the stem. There are various modes of doing this; fig. 49 shows the mode of protecting by tying thorn branches round the stem, as prac-

tised in the Regent's Park, London, and various other places.



FIG. 49.—PROTECTING BY FAGGOTS.

Fig. 50 shows a mode of protecting trees from sheep by tying laths round them with wire. In the horizontal section, *a* represents the stem of the tree, *b* the wire, and *c* the laths.




FIG. 50.—PROTECTING BY LATHS.

To protect single trees from the wind, various modes have been

adopted; one of the simplest of which consists in driving a stake into the ground much deeper than the roots of the tree, and tying the trunk to it with a hayband, care being taken not to injure the roots in driving in the stake. There is



FIG. 51.—NEWLY-PLANTED TREES.

another mode of fixing a tree, which serves also to protect it; and this consists in driving two pieces of wood into the ground, with their lower extremities spread out, and their upper ones tied to the tree.

In planting single trees, and indeed trees of every kind, the greatest possible care should be taken to place them so high above the surface, as that after they have sunk down, as they will do in a few years, they may still appear to stand on a little hillock, or to grow out of a small mound. If we examine thriving




FIG. 52.—FULL-GROWN TREE.

trees in a natural wood, we shall always find that the collar—that is, the point of junction between the stem and the roots—rises above the general surface, so as to form a little hillock. On the other hand, if we examine trees in artificial

plantations, in which the soil has been deeply trenched, we shall generally find that, though they have been planted at first level with the surface, they will, after a certain number of years, have sunk considerably below the surface; or if care has been taken to keep the ground about them level, by adding fresh soil as the surface sinks, they will appear with their collars completely buried, and their trunks rising out of the soil like so many posts driven into it by art, instead of springing from a wooden base, rising above the soil like trees and shrubs in a natural forest, or on a common. In planting single trees, therefore, hillocks should at first be raised to a height which will for a year or two appear quite unnatural, as shown in fig. 51, in which may be observed a small hollow at the base of the stem for retaining water; but they will soon sink down to the appearance shown in fig. 52.

**SINNINGIA.**—*Generaceæ*.—Stove-plants with large bell-shaped flowers. They should be grown in light rich soil.

**SIPHOCAMPYLOS.**—*Lobeliaceæ*.—A suffruticose plant, with red and green tube-shaped flowers. It is generally kept in the greenhouse, but it is nearly hardy. It should be grown in heath-mould, and it is propagated by cuttings, which should be dried a little before they are planted.

**SIPHONIA.**—*Euphorbiaceæ*.—The American India-rubber tree. —The first elastic gum brought to Europe was the produce of the *Ficus elastica*; and as this plant is a native of the East Indies, the substance was thence called India-rubber. It has since been found that several trees produce it; and the Caoutchouc used for the Macintosh cloaks, &c., is principally produced by the *Siphonia*

*Cakicha*, a native of Guiana. The species requires a stove in England; and it grows freely in peat, loam, and sand. It is propagated by cuttings of the young wood in sand, with a bell-glass and bottom-heat.

**SISTYRINCHIUM.**—*Iridææ*.—Beautiful little plants resembling bulbous plants in their flowers, but with fibrous roots. They are all natives of America, and they should be grown in sandy peat.

**SKIMMIA.**—*Aurantiaceæ*.—A very fragrant shrub, with spikes of small white flowers, and bright red berries; the leaves are evergreen, smooth and shiny, and they are as fragrant as the flowers. *S. japonica*, the only species yet known, was introduced by Mr. Fortune, and first flowered in this country in March, 1853.

**SKULL-CAP.**—See **SCUTELLARIA**.

**SLIPPER-WORT.**—See **CALCEOLARIA**.

**SLUGS.**—See **LIMAX**.

**SMILAX.**—*Smilacææ*.—Evergreen monocotyledonous, dioecious, climbing shrubs, with curiously ribbed leaves, and numerous tendrils, which they twine round every object within their reach. The roots are thick and fleshy, and from them (and particularly those of one species) the drug called sarsaparilla is made. The flowers are small and whitish; and those of the female plants are succeeded by red or black berries. The handsomest species is *S. rubens*, the tendrils of which are of a bright red; and the next is *S. excelsa*, from the large size of its leaves. All the species may be grown in the common garden soil; but they should be planted in a shady situation, and kept rather moist. *S. China* and some other species are rather tender, and require protection from severe frosts.

**SNAILS.**—See **HELIIX**.

**SNAIL-FLOWER.**—*Phaseolus Calacalla*.—A climbing plant, a native of India, with Lilac flowers, nearly allied to the Scarlet-runner.

**SNAKE-GOURD.**—*Trichosanthes anguina*.—A very curious plant, with white flowers, every petal of which appears surrounded with long knotted fringe. The leaves and tendrils resemble those of the common Cucumber; but the fruit is curiously striped, and is so long and narrow as to resemble a snake. Specimens have indeed been grown more than six feet long, and not thicker than the body of a common snake. The plant is an annual, a native of China, and it should be grown in a frame like a common Cucumber or Melon. It is of no use, and only worth cultivating as an object of curiosity.

**SNAKE-WOOD.**—*Ceanothus colubrinus*.

**SNAPDRAGON.**—See **ANTIRRHINUM**.

**SNOWBALL TREE.**—See **VIBURNUM**.

**SNOWBERRY.**—See **SYMPHORICAERUS**.

**SNOWDROP.**—See **GALANTHUS**.

**SNOWDROP TREE.**—See **HALESIA**.

**SNOWFLAKE.**—See **LEUCOJUM**.

**SOAP-BERRY.**—See **SAPINDUS**.

**SOAP-WORT.**—See **SAPONARIA**.

**SOILS** are of two kinds, the surface soils, and the subsoils; the first being what are generally understood by the word soils, and the second being properly designated earths. Soils, according to this definition, consist of the crumbling surface of one of the primitive earths, mixed with decayed animal or vegetable matter, and perhaps with particles of some other earth which may have been washed down by rains, or otherwise accidentally mingled with it. Thus clay is one of the primitive earths; but loam,

which is compounded of the crumbling surface of the clay, mixed with decayed animal and vegetable substances, is a soil. In the like manner, lime is an earth, but chalk is a soil. When several kinds of soil are mixed together, and intermingled with manures, the mixture is called a compost. All soils which contain a considerable portion of sand or peat are called light; and all soils containing sand and clay are called loamy. What is called a light rich soil is generally composed of very sandy loam, mixed with vegetable mould, or the sifted remains of an old hotbed.

**SOLANUM.**—*Solanaceæ*.—The Nightshade.—The flowers of the plants belonging to this extensive genus fall more or less resemble those of the common climbing Nightshade, or Bitter-sweet of the hedges, and indeed those of the Potato, which belongs to this genus. They are all rather pretty, but their foliage is too coarse to be ornamental. *S. campanulatum* is perhaps the handsomest species as regards the flower. *S. Capsicastrum* resembles a miniature Orange tree; it is an evergreen shrub of recent introduction, very ornamental, and much esteemed on account of its richly coloured fruit for the decoration of the greenhouse and conservatory in winter. Some of the species require a stove, others the greenhouse, and others the open air; but they all agree in liking a rich light soil, and they all grow well in a mixture of loam and peat, enriched with vegetable mould.

**SOLDANELLA.**—*Primulaceæ*.—Beautiful little alpine plants, very suitable for rock-work, some with purple, and some with blue flowers. They should be grown in heath-mould, or in peat mixed with very sandy loam; and they are increased

by seeds, or by dividing the root. They are generally grown in small pots, and they should neither have too much nor too little water.

**SOLIDA'GO.**—*Compositæ*.—Golden Rod.—Perennial plants, quite hardy in British gardens, where they flower in autumn. They are too tall for any small garden, and they are only suitable for the back row of a flower-border. They will grow in any common garden soil, and they are increased by dividing the root.

**SO'LLYA.**—*Pittosporææ*.—This beautiful little shrub, though only introduced in 1830, is already as common as the Fuchsia, and it is a favourite everywhere. The leaves are evergreen, and the bright blue bell-shaped flowers, which are produced in tufts near the ends of the branches, are so elegant that no one can see them without admiring them. The plant is a native of New Holland; and it is so nearly hardy, that it will stand in the open air (if trained against a wall, and slightly protected during winter. It is, however, generally grown in pots, in which the only objection to its culture is the circumstance of its having the tips of its shoots frequently covered with aphides, the only cure for which is constant syringing. In the open air it is liable to the attacks of a black insect similar in its nature to the aphid, but still more disagreeable. It should be grown in peat and loam, or in heath-mould, and it is propagated by seeds or cuttings. The fruit, which is a berry full of seeds, ripens freely; but the cuttings are very difficult to strike, and indeed will rarely succeed without bottom-heat. Besides *Sollya heterophylla*, which is the common kind, two or three other kinds have been introduced by Captain Mangles from the Swan River.

**SOLOMON'S SEAL.**—*Polygonatum vulgare* and *P. multiflorum*.—A hardy perennial, which will grow freely in any common garden soil. The English name alludes to the roots, which, when cut through, have the appearance of Hebrew characters.

**SONER'ILLA.**—*Melastomææ*.—*S. margaritacea* has a very singularly marked foliage, of a fine green sprinkled all over with round pure white spots. Flowers numerous; purple. It requires a stove.

**SOPHO'RA.**—*Leguminosæ*.—The common *Sophora japonica* is a large tree which grows freely in the neighbourhood of London, and produces its large bunches of cream-coloured flowers in August and September. The drooping *Sophora*, however, though only considered a variety of this tree, is very distinct. It is a trailing shrub, sending out shoots six feet or eight feet long in a single season; and when it is grafted on a stock of *S. japonica*, ten feet or twelve feet high, these long sweeping shoots, the bark of which is a bright green, have a peculiarly graceful appearance. The *Sophora* will grow in any soil, but a poor one suits it better than a rich one: and its leaves seldom droop even in the driest seasons.

**SOUTHERNWOOD.**—See **ARTEMISIA**.

**SOWING.**—The operation of committing seeds to the soil in flower-gardening, is commonly done in patches: but sometimes flowers are sown broadcast or in drills, and occasionally singly. When annuals are to be grown in borders containing a miscellaneous assemblage of flowers, they are commonly sown in small circular patches, in intervals left on purpose among the perennials, or among the Roses and other low shrubs. Each patch is prepared by digging up a spadeful of the soil

and returning it to its place with the surface downwards; then breaking it finely, and levelling and smoothing the surface; and lastly depressing, or slightly hollowing out a circle from three to six inches in diameter, and from a quarter to half an inch in depth, according to the size of the seeds to be sown. As most seeds germinate best when gently pressed into the soil, a very good mode for amateurs is to take the saucer of a flower-pot, of the diameter of the patch, and gently press down the soil; and then to strew a few seeds on the level surface thus formed. Half-a-dozen seeds will be sufficient, of even the smallest growing plants, if the seeds are good. The next operation is to sprinkle a little fine soil over the seeds, so as to cover them to about the same depth as the seed is thick. After this, the saucer should be again applied, so as to press down the soil and the seeds together; and if there be any danger apprehended from birds or drought, an empty flower-pot should be turned over the patch till the plants come up. The larger seeds of flowers, such as Lupines, Sweet Peas, &c., may be sown three or four in a patch; and some kinds of Lupines, such as *L. Cruckshanksii* and *L. mutabilis*, will not require more than a single seed. In the case of large seeds, and of all the commoner kinds, the use of the saucer for preparing the ground, and of the empty flower-pot as a protection, may be dispensed with.

In sowing broadcast, the bed or space to be covered being stirred up with the spade, and raked fine on the surface, should be gently smoothed with the back of the spade, and the seeds afterwards strewed over it, so as to lie, if the seed be good, at an inch or two apart, or less, if the

plants are to be thinned out or transplanted. The seeds may then be covered by strewing over them some fine mould; and this may be "firmed," as the gardeners term it, by gently beating the ground flat with the spade. For ordinary seeds, raking the surface smooth before sowing, and after sowing, again raking it, will be found sufficient; and the raking should always be light in proportion to the smallness of the seeds. In sowing grass seeds to form a lawn, the ground should be beaten equally firm throughout, to prevent it from sinking unequally afterwards: and after it has been rendered perfectly smooth and even, the seeds should be sown quite thick, and raked in so gently, that the teeth of the rake may not penetrate more than half an inch into the soil.

Sowing in drills, or little furrows drawn by the hoe, is chiefly required for edgings; and as the plants suited to this purpose are small, and also the seeds, great care ought to be taken to distribute them equally, and not to cover them with too much earth.

SPANISH BROOM.—*Spartium junceum*.—See SPARTIUM.

SPARA'XIS.—*Iridææ*.—Beautiful bulbous plants, that will flower vigorously if grown in a well-drained bed in the open air.—For the mode of forming the bed, see I'XIA.

SPARTIUM.—*Legumindææ*.—The Spanish Broom.—A well-known upright shrub, with upright deep-green branches, and very few leaves, which soon drop off. The flowers, which are in terminal racemes, are large, and of a deep yellow. It is a native of Spain and Portugal, and, in short, of the whole of the South of Europe, where it grows in rocky situations, and in dry gravelly soils. In Eng-

land it produces a good effect in a shrubbery, and it will grow vigorously wherever the soil is gravelly or sandy; but it does not thrive in clay, as it has a long tap-root, which it can only send down where the soil is free. It is generally propagated by seeds.

**SPATALA'NTHUS.**—*Irideæ*.—The Ribbon-flower.—A very handsome bulbous plant, requiring the usual treatment of Cape bulbs.—See I'XIA.

**SPEEDWELL.**—See VERO'NICA.

**SPE'RGULA.**—*Carophyllaceæ*.—*S. pilifera* forms a moss-like carpet, of a lively green colour, and is employed as a substitute for grass, often in places where the latter in hot, dry seasons will not grow. Its succeeds in the shade and, on the contrary, on hot sunny banks, provided it is duly watered. It can be introduced in miniature gardens, which ladies may form, with admirable effect. It is easily propagated by division in spring, the smallest fragment forming a spreading tuft in the course of the summer; or it may be sown in pots or pans in the open air, from April to September, and planted out where required. The seeds may be pressed on the surface, or otherwise they should have but the very slightest covering of light fine soil.

**SPHA'GNUM.**—*Cryptogamia*.—A kind of Moss, very useful for the growth of orchids grown on blocks of wood, and for mixing, chopped up, with peat and corks in the case of various species grown in pots.

**SPHE'NO'GYNE.**—*Compositæ*.—Beautiful annual plants, which only require sowing in March or April, in any common garden soil.

**SPIDER O'PHRYS.**—See O'PHRYS.

**SPIDERWORT.**—See TRADESCA'NTIA.

**SPINDLE-TREE.**—See EVO'NYMUS.

**SPIRÆA.**—*Rosææ*.—Hardy

shrubs, generally natives of Siberia, with very pretty flowers. The handsomest kinds are *S. chamaedrifolia*, with spike-like corymbs of white flowers; *S. ulmifolia*, with flat corymbs of white flowers, and large handsome leaves; *S. hypericifolia*, or Italian May; *S. salicifolia*, Bridewort, or Queen's Needle-work, with spikes of pinkish flowers; *S. bella*, a native of Nepaul, with corymbs of beautiful rose-coloured flowers, which it produces in May and June; *S. opulifolia*, the Virginian Guelder Rose, or Nine Bark, a native of North America, with corymbs of rather large white flowers; *S. arizifolia*, a most beautiful species, a native of California, with loose panicles of feathery whitish flowers, which it produces in July and August; and *S. sorbifolia*, with loose panicles of white flowers and pinnate leaves, from Siberia. *S. grandiflora* has white flowers, nearly as large as those of a wild rose. It was introduced in 1854, by Mr. Fortune, from the north of China. *S. callosa* has beautiful corymbs of rose-coloured flowers. All the kinds grow with most luxuriance in moist soil, having a poor and stunted appearance where the soil is dry and gravelly; and they are readily propagated by suckers, which they throw up in great abundance.

**SPIRA'NTHEES.**—*Orchidææ*.—Ladies' Traces.—Mostly tropical plants, which require a moist stove.—See ORCHIDEOUS EPIPHYTES.

**SPLEENWORT.**—*Asplenium*.—Very beautiful Ferns, which differ very much in their appearance, though they are all very handsome. They require, like all other Ferns, to be grown in moist shady places.

**SPO'NDIAS.**—*Terebinthææ*.—The Hog-plum.—West Indian trees, which require a stove in England.



SPRA'GUEA. — *Portulacææ*. — See CALAN'DRINIA.

SPEEKE'LIA. — *Amaryllidæææ*. — The Jacobæa Lily. — A bulbous-rooted plant, with splendid dark scarlet flowers. It is called Jacobæa on account of the brilliant scarlet of its flowers, which the Spaniards in Peru thought resembled the scarlet sword-cases worn by the knights of the order of St. James (Jacobæus).

— For the culture, see AMARYLLIS.

SPURGE. — See EUPHORBIA.

SPURGE LAUREL. — See DA'PHNE.

SQUILL. — See SO'LLA.

SQUIETING CUCUMBER. — See MO-MO'RDICA.

STA'CHYS. — *Labiæææ*. — The Hedge Nettle. — Shrubby and herbaceous plants, natives of Europe and North America, which will grow freely in any light rich soil, and which are increased by cuttings or division of the root.

STAFF-TREE. — See CELA'STRUS.

STAG'S-HORN. — See RHUS.

STANHO'PEA. — *Orchidæææ*. — Beautiful orchideous plants, with large white flowers proceeding from the root. — For the culture, see ORCHIDEOUS EPIPHYTES.

STAPE'LIA. — *Asclepiadæææ*. — Very curious stove-plants, with showy flowers proceeding from the root, which smell so much like carrion, that flesh-flies have been known to lay their eggs upon them. As these plants are very succulent, they are apt to drop off if they are grown in rich soil, or too much watered. They succeed best in sandy loam mixed with lime rubbish, and they are propagated by cuttings, which should be laid on a shelf for two or three days to shrivel before they are planted. The plants from which the cuttings are taken should be kept quite dry for some time afterwards, as they are apt to rot from the wound. All the Stapélias are

natives of the Cape of Good Hope.

STAPHYLE'A. — *Celastrinæææ*. — The Bladder Nut. — Hardy shrubs, natives of England and North America, that will grow freely in any common garden soil. The flowers are white; and the seed, which is brown, is produced in a large inflated capsule or bladder. The seeds, when bored, are used in Catholic countries for rosaries.

STAR OF BETHLEHEM. — See ORNITHO'GALUM. — In the midland counties the large yellow *Hypêricum* is called the Star of Bethlehem.

STARWORT. — One of the English names for the A'STER.

STA'TICE. — *Plumbaginæææ*. — Sea Lavender. — Singular plants, the foot-stalks of the flowers of which are coloured so as to resemble flowers, while the real flowers are the white part at the extremity of the purple. This is very conspicuous in *S. arboresca*, a native of the Canaries, which is quite shrubby. This splendid plant should have plenty of room for its roots: and thus when there is not a conservatory for it to be planted in, it does better in the open border, with a slight protection during winter, than in a pot in a greenhouse. The soil in which it is grown should be half sandy loam and half vegetable mould. It is extremely difficult to raise young plants by cuttings; and though nurserymen contrive to make layers, it is so difficult an operation, as to be scarcely practicable by an amateur. The common kinds of *Statice* are generally increased by seeds, or by dividing the roots; and they should be allowed plenty of space, as they are easily killed when crowded by other plants. *Statice Dickensiana*, has bright rose-coloured flowers which remain a great length of time uninjured after the flower is cut, like the different species of *Helichrysum* or Everlasting. The spe-

cies is a native of the Cape of Good Hope, whence it was introduced in 1844. In Great Britain, it is a greenhouse plant. *Státice Portuacis*, *S. imbricatá*, and *S. frutescens*, are very handsome species, all of which have been introduced since 1845.

STELLA'RIA. — *Caryophyllææ*. — Stitchwort. — Very pretty plants, with white flowers, many of which are natives of Britain. They are all quite hardy, but they grow best in sandy soil. The dwarf kinds are very suitable for rock-work. They are propagated by seeds, which they ripen freely, or by division of the roots.

STENA'CTIS. — *Compositæ*. — *S. speciosa* is a very showy perennial, with large and very handsome flowers. It is a native of California, and will grow in any common garden soil. It is increased by seed, or by dividing the roots.

STENOCH'LUS. — *Myoporinææ*. — Australian shrubs, with scarlet flowers, which should be grown in sandy peat.

STENOME'SSON. — *Amaryllidæææ*. — Bulbous plants, natives of Mexico. *S. Hartwegii* has very pretty orange-coloured flowers.

STEPHANO'TIS. — *Asclepiadæææ*. — *S. floribunda* is a stove climber, with very dark-green, leathery leaves curiously bent at the tip, and large umbels of delightfully fragrant white flowers, which continue for a considerable time. It is propagated by cuttings, and should be grown in peat and loam.

STENOULIA. — *Byttneriæææ*. — Stove shrubs and low trees from the East and West Indies, with greenish or whitish flowers. They should be grown in peat and loam, and they are propagated by cuttings of the ripe wood, not deprived of their leaves, which should be struck in sand, under a bell-glass with bottom-heat.

STE'VIA. — *Compositæ*. — Mexican perennials, with tufts of very pretty white or pinkish flowers, which should be grown in sandy peat, and which require a little protection during winter. *S. Eupatoriá* is a very pretty plant for filling a bed in a geometric flower-garden, from its compact habit of growth, and the abundance of its flowers.

STI'PA. — *Graminæææ*. — *Stipa pennata*, the Feather-grass, is an extremely elegant plant which grows freely in light rich soil, and is increased by seed, or by division of the root.

STIRRING THE SOIL is an operation of considerable importance in the case of all plants in a high state of culture, and especially of young plants. When soil is loosened to the depth of even two or three inches, it admits the air and the rain beneath the surface, and both in this manner convey their temperature to the soil, as well as their nutritive qualities to the roots. It is also remarkable that though soil, when loosened, is advantageous in communicating a warmer temperature and moisture to what is below by admitting the air and the rain, yet that in the heat of summer, plants growing in a soil the surface of which is kept loose, suffer less either from excess of heat or the want of rain than plants in a soil which is kept firm. This will also apply to a certain extent to plants in pots, though stirring the soil is of far less importance to them than to plants in the open ground; as the heat of the surrounding atmosphere, whether it be advantageous or injurious, penetrates readily through the sides of the pots, and the superfluous moisture is exhaled in the same manner. In stirring the soil among plants in the open ground, it must, however, be always

remembered that the soil is full of roots, and therefore that the stirring must not be carried to more than a few inches in depth. It should also be performed with a fork rather than a spade, in order that none of the roots may be cut. The soil should never be stirred, except when it is in a dry state, and when rain is not expected; because, should the soil be in a wet state when it is moved, or should rain occur immediately afterwards, it will defeat the end in view, viz., that of forming a porous surface layer, readily permeable by air and water.

STICHWORT.—See SPELLA'RIA.

STOCK.—See MATTHI'OLA.

STOKESIA.—*Compositæ*.—One of the handsomest plants which can be grown in the flower beds of a garden; from its large bluish lilac flowers. It bears considerable resemblance to a China Aster, but is much handsomer. It is a native of South Carolina, whence it was introduced nearly a hundred years ago, but it is very little known.

STONE-CROP.—See SED'UM.

STOOL.—A tree or shrub which




FIG. 53.—A STOOL, WITH SEVERAL OF THE SHOOTS LAYERED.

has its branches pressed down to make layers.—See fig. 53.

STORAX.—See STY'RAX.

STOVE.—The name given the

plant-houses used for keeping tropical plants.—See HOTHOUSES.

STRAMO'NIUM.—*Solanaceæ*.—The Thorn Apple.—Large showy plants, conspicuous alike for their leaves, flowers, and fruit. They grow best in chalk or a calcareous loam; and they are so completely hardy in Britain, and grow so freely from seed, that the common kind has become naturalised, and is frequently found growing wild. When these plants are grown in gardens, they should be allowed plenty of room, as their principal beauty is the wide-spreading and luxuriant character of their foliage.

STRANVESIA.—*Rosaceæ*.—The new name for *Cratægus glauca*, an evergreen tree, a native of Nepal, with glaucous leaves, woolly beneath, and white flowers. It appears to be hardy, or very nearly so, and it is very handsome. It is generally propagated by grafting on the common Hawthorn.

STRAWBERRY BLITE.—See BLITUM.

STRAWBERRY TREE.—See A'R-BUTUS.

STRELI'TZIA.—*Musaceæ*.—Magnificent plants with large long leaves, and very large and singular-looking orange and purple flowers. They are generally grown in a stove, but they will flower in a greenhouse or room if kept sufficiently moist. They should be grown in light sandy loam. They are very difficult to propagate, but they sometimes send up suckers, and sometimes ripen seeds.

STREPTANTHERA.—*Iridææ*.—Cape bulbs with very showy flowers; which may be grown either in pots, or in beds in the open air.—For the culture see I'XIA.

STREPTOCAR'PUS.—*Gesneriææ*.—Very handsome perennial plants from South Africa, which require a stove in England; but which, when

properly treated, produce their beautiful and elegant pale purple flowers in great abundance. The genus is nearly allied to *Gloxinia*, but it has twisted seed-pods. *S. Saundersii* has a single broad roundish leaf, which lies flat on the surface of the soil and sends up from its centre a single upright flower stem, bearing flowers of a pale delicate blue. No moss is required, as in some cases, to cover the soil in the pot, for the one leaf which the plant produces does that effectually. It should be grown in equal parts of peat, loam, and sand; and it is increased by seeds, which it ripens freely.

**STUARTIA.**—*Ternstroemiaceæ*.—A North American shrub or low tree, with large white flowers, nearly allied to *Malachodendron*. It will grow in any common garden-soil that is tolerably light, and it flowers freely. It is propagated by layers or cuttings.

—See *MALACHODENDRON*.

**STYLIDIUM.**—*Stylidaceæ*.—Australian shrubs and perennials, generally kept in a greenhouse, with small pinkish or purple flowers, the stamens of which are irritable, and move when touched. All the species should be grown in sandy peat, or heath-mould; and the perennials are propagated by seeds or division of the root, and the shrubby species by cuttings.

**STYLOPHORUM.**—*Papaveraceæ*.—A native of the woods in the western part of the United States of North America; beautiful golden yellow flowers and glaucous leaves.

**STYPHELIA.**—*Epacridaceæ*.—*S. tubiflora* is a very elegant little plant, a native of the south-east of Australia. It requires only the usual treatment of the *Epacris* tribe.

**STYRAX.**—*Styracineæ*.—*Storax*.—Ornamental shrubs, with white

flowers, natives of Europe and North America, which grow best in sandy peat or heath-mould, and flower freely. They are propagated by layers.

**SUCCORY.**—*Cichorium Pitybus* is a British plant, with brilliant blue flowers, which grows freely in sandy soils, and which may be grown with the greatest ease in gardens.

**SUCCULENT PLANTS** are those which have both their stems and leaves provided with so few stomata, as to be able to retain a great portion of the moisture which is evaporated by other plants. These plants are generally natives of sandy deserts, where for half the year they are entirely destitute of water, and where their capability of retaining moisture is necessary to keep them alive. When grown in Europe, they are well adapted for sitting-rooms, as they are capable of bearing a greater degree of dryness in the air than most other plants; but they are very liable to be injured by too much water, as in the cloudy atmosphere of England their stomata are not sufficiently numerous to enable them to throw it off, and it rots them, or, as gardeners express it, they damp off. All succulent plants, when grown in pots, should have abundant drainage, and should never be suffered to stand with water in the saucer; and the soil in which they are grown should be mixed with sand or lime-rubbish to keep it open, and in a state fit for their roots to penetrate through it.

**SUFFRUTICOSE PLANTS** are those which are shrubby at the base, but herbaceous in the upper part of the stem; such as the common Wall-flower, the Brompton or Queen Stock, *Iberis sempervirens*, &c.

**SUGAR-CANE.**—See *SACCHARUM*.

**SUMACH.**—See *RHUS*.

**SUMMER CYPRESS.**—See *KOCHIA*.

SUNDEW.—See DR'OSERA.

SUNFLOWER.—See HELIA'NTHUS.

SUNROSE.—See HELIA'Nthemum.

SUTHERLANDIA.—*Legumindæ*.

—A pea-flowered shrub, with scarlet flowers, formerly called *Colutea frutescens*; a native of the Cape of Good Hope, which is half-hardy in British gardens, and which should be grown in sandy loam.

SWAINSONIA.—*Legumindæ*.—Pea-flowered shrubs, natives of Australia, with purplish flowers, which should be kept in a greenhouse, and grown in heath-mould.—See AUSTRALIAN SHRUBS.

SWALLOW-WORT.—See ASCLEPIAS, and CHELIDONIUM.

SWEET BAY.—See LAURUS.

SWEET BRIAR.—See ROSA.

SWEET GALE.—See MYRTICA.

SWEET MARJORAM.—See ORIGANUM.

SWEET PEA.—See LATHYRUS.

SWEET POTATO.—*Batatas edulis*.

—A tuberous-rooted plant formerly considered to belong to *Convolvulus*, then to *Ipomœa*, but now separated from both. It is a native of South America, where it is called *Batatas*; and it requires a stove in England.

SWEET SOP, or Custard Apple.—See ANONA.

SWEET SULTAN.—See AMERBOLA and CENTAUREA.

SWEET WILLIAM.—*Diânthus barbatus*.—This plant is quite hardy in British gardens. The flowers are produced in large clusters, each separate flower resembling a small Chinese Pink, except in the calycine scales or bracts, which are very long and sharply pointed. Some of the varieties are very beautiful, particularly those with deep rose-coloured flowers, and one the flowers of which are white, spotted with pale pink. The finest varieties I ever saw of this plant were in Scotland, at Milton-Lockhart, on the Clyde, where the Sweet Williams

were so beautiful as almost to deserve to take rank as florists' flowers. Some of the varieties are more fragrant than others. The Sweet William, though a perennial, is not a long-lived plant, particularly in London or any other large town, or if the soil be very moist or very dry; and it seldom flowers well after the second year. The plant does best when treated as a biennial.

SYMPHORICARPOS.—*Caprifoliaceæ*.—St. Peter's Wort.—Bushy, deciduous shrubs, which grow so freely in any common garden soil, and send up so many suckers, that when once planted it is difficult to eradicate them. The flowers of *S. glomerata* are produced in clusters, and the berries are small and reddish. *S. racemosa*, the Snowberry, has pinkish flowers, which are disposed in such loose racemes as to appear almost solitary, and which are succeeded by large white berries which are very ornamental. There is another species, *S. occidentalis*, with very large leaves and drooping racemes of flowers, which has not yet been introduced. *S. microphyllus* is a Mexican species, with very small leaves, pink flowers, and pink berries. All the kinds are natives of North America. *S. racemosa* is sometimes grafted on *Lonicera Xylbsteum*, to avoid the inconvenience of its numerous suckers.

SYNGENESIOUS PLANTS.—Plants belonging to the 19th class of the Linnæan system, and the natural order *Compositæ*.

SYRINGA.—*Oleino*.—The Lilac.—Well-known deciduous shrubs, with purplish or white flowers, natives of Europe and the colder parts of Asia, and valuable in British shrubberies for the early appearance of their leaves in spring, and for the beauty and fragrance of their flowers. There are several species and varieties,

varying principally in the colour of the flowers. They are all quite hardy in British gardens, and they will grow in any common soil. They are propagated by layers, and by suckers which they produce in great abundance.

**TABERNÆMONTANA.**—*Apocynææ*.—Trees and shrubs from the East and West Indies, which require a stove in England. They have generally white fragrant flowers, resembling those of the common Jasmine, but are many times larger. They should be grown in loam and peat; and they are propagated by cuttings, which require a moist heat to make them strike.

**TACAMAHAC.**—The Indian name for the Balsam Poplar; a species that should be cultivated in ornamental plantations for the beautiful yellowish green of its leaves, which appear very early in spring.

**TASCO NIA.**—*Passiflorææ*.—Half-hardy climbing plants, with golden, ball-like fruit, nearly allied to the Passion Flower. They are sometimes kept in a stove, but they will both grow and flower freely in greenhouse-heat. *T. ignea*, and *T. manicata*, have scarlet flowers; *T. mollissima*, rose-coloured; and *T. Van-Volxemii*, bright crimson. They should be grown in sandy loam and peat, and they are propagated by cuttings.

**TAGE TES.**—*Compositæ*.—The French and African Marigolds. Well-known half-hardy annuals, with showy flowers that have a very disagreeable smell. The seeds are generally sown on a slight hotbed, and the young plants are planted out in May.

**TALAU'MA.**—*Magnoliææ*.—Low trees and shrubs from Java and other parts of the East Indies, with

very fragrant white flowers, nearly allied to the Magnolias. The plants should be grown in loam and peat if kept in the stove, and they may be propagated by layers and cuttings; but by inarching them on *Magnolia purpurea*, they may be brought to flower in a conservatory or a greenhouse.

**TALINUM.**—See **CALANDRI'NIA**.

**TALLIES** for plants are of various kinds, according as the plant is large or small, grown in the open air or under a glass, and according as the object is of a permanent or a temporary nature. Tallies for trees, as in the case of an Arboretum, which is to endure for many years, are formed of iron, stone, or brick; those for herbaceous plants, of iron or wood; and those for plants in pots kept in houses, of porcelain, wood, lead, zinc, and sometimes, though rarely, of iron. Tallies for plants kept in nurseries in pots, are commonly of wood, on which a little white paint is rubbed with the finger, and the name written with a black-lead pencil; those for plants taken up and packed to be sent to a distance, are commonly of parchment, with the name written in ink; but nursery labels are formed of wood and tied to trees, or of pieces of lead stamped with numbers. The object in every case connected with the nursery business is simply to identify the species or variety; but in the case of private gardens, it is not only to do this, but to produce an object that shall not be unsightly in a garden. For this latter purpose, porcelain tallies (fig. 54), which are formed of various sizes and shapes, are best for pots; and tallies of cast-iron, with panels for tablets containing the names to be covered with glass (fig. 55), are the most efficient for plants in the open ground. Where it is not desired to display the name,

the simplest and least expensive mode is to mark a number on a wood tally or stick, and this may be done either by notching the stick with a knife, which is the common practice among



FIG. 54.—PORCELAIN TALLY FOR POTS.

gardeners, or by cutting a portion of it smooth, rubbing it with a little white lead (white paint), and writing the number while it is yet moist with a black-lead pencil. Of all the different modes which have hitherto been devised of naming or numbering plants in gardens (and they amount, perhaps, to hundreds), the mode by




FIG. 55.—CAST-IRON OR ZINC TALLY FOR THE OPEN GROUND.

a stick, white lead, and a black-lead pencil, is perhaps the best for private gardens; and it is, undoubtedly, by far the cheapest. But a great improvement on this simple plan, and

which may be effected very easily, is to paint the tallies with white paint; and when dry, write on them with a quill pen and common ink, or with Indian ink; let them be thoroughly dry, and then give them a coat of varnish. This mode has the advantage that the tallies can be painted in any convenient spare time and laid aside till wanted; for with ink they can be written upon when dry, whereas the black-lead pencil must only be used whilst the paint is wet. When varnished, the ink-written names will appear clear and legible for several years; the pencil scarcely one. In numbering or naming plants in a garden, where good taste ought to preside, it must always be recollected that the means ought to be kept subordinate to the end, and that the names of plants should in no private garden be more conspicuous than the plants themselves.

**TALLOW TREE.**—*Stillingia sebifera*.—A stove plant, which should be grown in peat and loam. It belongs to Euphorbiaceæ.

**TAMARIND TREE.**—See TAMARINDUS.

**TAMARINDUS.**—*Leguminosæ*.—The Tamarind Tree.—There are two kinds of Tamarinds; *T. indica*, a native of the East Indies, with yellow flowers striped with red, and *T. occidentalis*, a native of the West Indies, the flowers of which are white. Both kinds, however, very rarely flower in this country, probably because the trees have not sufficient room for their roots. The plants may be raised from seeds of preserved Tamarinds sown in a hotbed; and they are worth growing for their handsome foliage. They require a strong heat and a rich soil, and they should be supplied with plenty of water. The soil should be composed of equal parts of fresh turfy loam and vegetable mould or rotten

dung, with a little sand or peat, and these ingredients should be well mixed together before the compost is used. Young plants may also be raised from cuttings, which strike freely in sand with the help of bottom-heat.

**TAMARIX.** — *Tamariscinæe*. — The Tamarisk. — Tall shrubs, mostly natives of Europe, which are sub-evergreen, and useful in withstanding the sea-breeze. A great many species are enumerated in books; but only two are common in British gardens. These are *Tamarix gallica*, the French Tamarisk; and *T. germanica* L. (*Myricaria germanica* Desv.), the German Tamarisk. The French Tamarisk is by far the handsomest, and as it will thrive close to the sea-shore, and produces its long terminal spikes of pinkish flowers in autumn, when people generally visit the coast, it is a most valuable shrub for the gardens of marine towns. It should be grown in a deep sandy soil, and it is propagated by cuttings taken off in autumn.

**TAMUS.** — *Dioscoriææ*, or *Tamææ*. — The Black Bryony. — See **BRYONY**. — The Black Bryony belongs to the same natural order as the Yam. For the Elephant's-foot, which was formerly considered to belong to the genus *Tamus*, see **TESTUDINARIA**.

**TAN.** — The bark of oak or of other trees, after it has been used by tanners. When it is received by gardeners from the tan-pits, it is generally wet and without heat; but after it has been laid in a ridge in an open shed for two or three weeks, and turned over two or three times, it becomes drier and begins to ferment, when heat is evolved in a greater or less degree according to the size of the mass. In this state it is fit to be introduced into pits or beds in hot-houses for the purpose of supplying

bottom-heat. For ordinary purposes the bed or layer of tan need not be thicker than eighteen inches or two feet, but when a very powerful heat is required, double that thickness is desirable. The pots in which the plants are contained, when large, should at first not be plunged more than half their depth in the tan; or, even, in some cases, they should be set on its surface. But after the first violent heat has subsided, they may be plunged to the brim. When the heap begins to cool, in consequence of the fermentation diminishing, the tan may be turned over, and the pots replunged, adding a little fresh tan, if necessary, to keep the pit to the proper degree of fullness. When the heat subsides a second time, the tan may be again turned, and a large portion of fresh material added; and the third time the old tan may be sifted in turning, and afterwards mixed with new. To prolong the heat in tan by diminishing the intensity of the fermentation, common salt is sometimes added; and to increase the fermentation, yeast, though rather an expensive material, is sometimes mixed with it. The heat of the tan-bed should generally exceed the heat of the atmosphere of the house by from 3° to 10°, according to circumstances; and it should seldom be lower than 60°, or higher than 75° or 80°. In general, a tan-pit or bed requires to be turned three or four times a year; and if salt is sprinkled over it each time, the fermentation will be so far retarded that the bed will retain its heat for a twelvemonth. For the purpose of growing Pine Apples, or large hothouse plants, oak or other leaves, or even dung, may be substituted for tan; but for the purpose of striking cuttings, tan is greatly preferable, because the heat produced is not accompanied with so much moisture, and hence the cuttings



are not liable to be damped off. In situations where tan or leaves cannot be procured, sawdust is an excellent substitute, and even the husks of oats. Sawdust is an excellent medium for striking Epacridæ and the Cape Heaths; the heat being more gentle and regular than with most other fermenting substances. When tan has lost the greater part of its heat, it then forms an excellent medium for striking fleshy-leaved plants, such as Bromelia, which require rather a dry heat, and a medium which undergoes the least possible change in respect to moisture. It may also be used as a substitute for peat, if mixed with an equal quantity of sand, and will be very useful for growing Rhododendrons and other peat-earth plants. Recently, cocoa-nut fibre, or refuse, has been substituted for tan in many cases; it answers well as a plunging medium and for striking cuttings, and it is free from the disagreeable smell resulting from fermenting tan.

**TANACETUM.**—*Compositæ*.—The Tansy. Herbaceous plants, which are quite hardy in any common garden soil, and which are increased by dividing the roots.

**TANGIER PEA.**—*Lathyrus tingitanus*.—See **LA'THYRUS**.

**TANSY.**—See **TANACETUM**.

**TAXODIUM.**—*Conifera*.—See **DECIDUOUS CYPRESS**.

**TAXUS.**—*Conifera*.—The Yew. —The common Yew is too large a tree to be noticed here; but the Irish Yew, from its erect form and broad leaves, makes a very handsome plant, which, from the slowness of its growth, may for a long time be almost considered a shrub. There are also some Japan and Chinese species (some of which are now included in the genus *Podocarpus*), which are very ornamental. They will all grow in any garden soil, and are raised from seeds.

**TEA-TREE.**—See **THEA**. The Duke of Argyle's Tea-Tree, *Lycium barbarum*, is often called the Tea-tree in gardens from mistake. See **LYCIUM**.

**TECOMA.**—*Bignoniaceæ*.—The Trumpet Flower. —All the species which now compose the genus *Tecoma* were formerly well known under the name of *Bignonia*, particularly *T. radicans*, the common Trumpet-flower, which is quite hardy in British gardens, and *T. grandiflora*, which is nearly so. Some of the species require a greenhouse, and some a stove; but they all grow freely in a rich, light, loamy soil, and they are all propagated by cuttings of the roots.

**TELOPEA.**—*Proteaceæ*.—The Warratah. —The brilliant scarlet flowers of this plant, which are conspicuous even at a great distance, are said to have been one cause why the coast of New South Wales was distinguished by its first visitors as Botany Bay, in allusion to the great accession to botany likely to be derived from a country where the plants appeared so different to those of Europe. The flower of the Warratah may be compared to a gigantic head of clover; of the most intense and brilliant scarlet; but it is not common in England, probably because it is a very difficult plant to manage. The first point to be attended to is to have the pot in which it is grown thoroughly well drained; and the next to allow it abundance of light and air. It is generally kept in a stove in England; but it succeeds better in a greenhouse, at least during the summer months; as it is very apt to become covered with insects if it is kept all the year in a hothouse. It is propagated by cuttings, or suckers which it throws up in abundance; and it should be grown in heath-mould, mixed with white sand and a little loam. It should be regularly

watered in the flowering season ; but it may be kept almost dry during the winter months.

TENO'RIA. — *Umbelliferae*. — The shrubby species of Hare's Bar. — See BUPLEURUM.

TENTHRE'DO. — See SAW-FLY.

TEPHRI'TIS. — A kind of leaf-mining insect, which attacks celery and chrysanthemums ; the perfect insect is a fly which has a very peculiar sideling motion in flying, quite different to most other flies. From the small size of these flies, it is extremely difficult to catch them by hand, and Mr. Westwood suggests hanging lines of string covered with birdlime over the rows of celery. The grubs may also be crushed by the hand in their passage through the leaf without destroying the leaf, and if this be done in the beginning of the summer, the destruction of one grub at that period will prevent the production of a numerous progeny.

TESTUDINA'RIA. — *Dioscoriadae*. — Elephant's-foot, or Hottentot Bread. — A very singular plant, with an enormous scaly root above ground, from which issues a slender stem, with small flowers. The plant is a native of the Cape, from which country the roots are frequently received. It should have a season of complete repose, without any water being given to it when it is not in a growing state, and it should be grown in a mixture of equal parts of turfy loam, peat, and sand ; the large scaly root being placed on the surface of the soil, and not buried in it. The earth in the pot should be then watered and kept moist till the fibrous roots begin to appear, after which less water should be given till the slender stem appears, when the soil in the pot should be watered regularly and abundantly ; but no water should ever be poured

on the scaly root. The flowers are diœcious, and have never yet produced seed in England. The substance of the scaly root is farinaceous, and it is said to be used by the Hottentots as food. The plant has never been propagated in England ; all the plants grown in this country having been received in the state of dry roots from the Cape.

THA'LIA. — *Cannæ*. — *T. dealbata* is an aquatic plant, a native of South Carolina, with very curious black and white fragrant flowers. It is about as hardy as *Calla æthiopica*, and requires the same treatment. See A'RUM.

THALI'OTRUM. — *Ranunculaceæ*. — Meadow Rue. — Perennial plants, natives of Europe and North America, which are quite hardy in British gardens. *T. aquilegifolium* and its varieties are very showy border-flowers ; and *T. alpinum*, and some other dwarf species, are elegant plants for rockwork. They all grow freely in any common garden soil.



FIG. 56. — PROTECTING HALF-HARDY TREES BY THATCHING.

THATCHING is sometimes applied as a protection to half-hardy trees in

the open ground. Many half-hardy trees and shrubs may be protected from any danger from frost by laying straw over the roots and collar of the stem, and then thatching it, as shown in fig. 56.

THE'A.—*Ternstræmiaceæ*.—Evergreen half-hardy shrubs, natives of China, and nearly allied to the Camellia, from which indeed they differ only slightly in the capsule. They are only half-hardy in British gardens. *Thea Bohlea*, indeed, requires protection every winter; but *T. viridis* will live in the open air with very slight protection (such as laying straw, &c., over the roots) in severe frosts. The flowers of both kinds resemble those of small single white Camellias; and they are cultivated more for the curiosity which most persons feel to see the plants producing tea, than from any real beauty they possess.

THEOBRO'MA.—*Byttneriaceæ*.—The Cacao-Nut Tree.—The tree from the nuts of which Cocoa and Chocolate are prepared comes very appropriately after the Tea-Tree. There are three species, all natives of South America, with brownish flowers; all of which require a stove in England, and should be grown in light rich soil.

THEOPHRA'STA.—*Apocýneæ*.—Stove-plants with very handsome leaves and white flowers. They are grown in loam and peat, and they are propagated by cuttings.

THERMOMETER.—No amateur should attempt to grow plants in a greenhouse or stove, or even in a hotbed, without being provided with a thermometer to regulate the degree of heat. A very ingenious one, with a long tube for plunging into the ground, has been contrived for ascertaining the heat of a hotbed or tan-pit.

THERMO'PSIS.—*Leguminosæ*.—

Herbaceous plants, generally with yellow flowers, natives of Europe and North America, which should be grown in very rich soil, but which are quite hardy in the open air in Britain. There is one kind, *T. borbortus*, a native of the Himalaya, introduced in 1855, which has large dark purple flowers, mixed with bright red and streaked with green. It is a perennial, and appears quite hardy in British gardens. There is one ligneous species, *Thermopsis luburnifolia* D. Don. (*Anagyris indica* Wal.), but it is now generally called *Piptanthus nepalensis*. (See PIPTA'NTHUS.) None of the species belonging to this genus will thrive unless grown in a very rich mould.

THI'BANDIA.—*Vacciniaceæ*.—*T. pulcherrima* and *T. macrantha* are beautiful shrubs from the north and north-east of India, bearing their flowers on the two years' old wood; those of *T. pulcherrima* are ochreous-red, veined with deeper red; those of *T. macrantha* are yellow and bright carmine. They will succeed in a cool greenhouse. Sandy loam and peat, well drained.

THISTLE.—See CA'RDUS.

THOMA'SIA.—*Byttneriaceæ*.—Pretty little Australian shrubs, formerly called *Lasiopetalum*. They should be grown in sandy peat, and kept in a greenhouse.

THORN APPLE.—See DATU'RA and STRAMO'NIUM.

THRIFT.—*Statice Arméria* Lin.; *Arméria vulgaris* Willd.—See ARMÉRIA.

THRIPS.—Very small flies, not above a line in length, and which seem rather to leap than to fly away when it is attempted to catch them; throwing up the lower part of their bodies at the same time, as though they curled themselves up to take a spring. They are very destructive,

and attack both leaves and petals, causing both to curl up, and afterwards to turn yellow and drop off. The larvæ are nearly as large as the perfect insect, and of a pale yellow; and the insect itself is first yellowish, but afterwards becomes black. As soon as the ravages of these little creatures are perceived, the plants they have attacked should be well and frequently syringed, and exposed as much as possible to the free air; hand-picking in their case being of little avail, from the very small size of the insects and their extraordinary activity.

THROATWORT. — See TRACHELIUM.

THU'JA. — *Coniferae*. — The Arbor Vitæ. — There are two kinds of Arbor Vitæ common in British gardens, the American (*Thuja occidentalis*), and the Chinese (*T. orientalis*), both having several varieties. The American species is an open-growing tree, with horizontal branches; and in America, where it is called the White Cedar, it grows in swamps. The Chinese Arbor Vitæ, on the contrary, is a close-growing tree, with upright branches, and should be grown in a dry soil. Both are quite hardy in the climate of London, and both are propagated by layers and cuttings; the former taking two years to root, and the latter being very difficult to strike. Besides these there are several other species, most of which require a greenhouse or protection during winter. The principal of these are *Thuja pèndula* and *T. articulata* Desf. (*Callitris quadrivalvis* Vent.); the latter species, which is a native of Mount Atlas, in Barbary, producing the gum Sandarach, and being the celebrated Spanish wood *Alerce*, which is so hard that it is said to resist fire, and of which the cathedral of Cordova was built. It

is also supposed to have been the sandal-wood of the ancients.

THUNBERGIA. — *Acanthaceæ*. —

The beautiful climbing plants generally known by this name differ very much in the colour of their flowers, though very little in their shape. Some botanists divide them into three genera. *T. Hawtayneana*, with dark purplish flowers, they call Meyenia; and of *T. coccinea*, with three other nearly-allied species, they have formed the genus *Hexacéntris*; while they leave *T. grandiflora*, with dark blue flowers, *T. fragrans*, the flowers of which are white and sweet scented, *T. aurantiaca*, with orange flowers, and *T. alata*, with buff flowers, with its white-flowered variety, in the genus *Thunbergia*. *T. alata* and *T. aurantiaca*, which is probably only a darker-coloured variety, are the most common of these kinds, and they may be grown either as stove or greenhouse climbers, or as half-hardy annuals. *T. alata* is a native of the East Indies, and when treated as either a greenhouse or a stove plant it is very apt to be covered with the red spider (see A'CARUS); but these insects seldom appear upon it when it is grown in the open air. *T. laurifolia* is a very handsome species, with large blue flowers; and *T. Harrisii* is a most splendid species, with blue and yellow flowers. When treated as an annual, the seeds should be sown in January on a slight hotbed, or in a sheltered situation in the open ground. The best soil for them is equal parts of peat and silver sand, to which a little vegetable mould may be added. The soil should be kept moist, but it should be well drained, as the plants will perish if either kept too dry or suffered to have their roots in stagnant water. When planted in the open air where

they are finally to remain, the long shoots should be pegged down at the joints all over the bed; and thus treated they will send up innumerable flower-stalks, so as to make the whole bed appear a mass of flowers. *T. aurantiaca* may be treated in the same manner; but *T. a. albiflora* is rather more tender, and appears generally to succeed better in a greenhouse than in the open air. When these plants are grown in a stove, and beset with the red spider, the only way to destroy it is to syringe them with water heated to 120°. The other species of *Thunbergia* are always kept in the stove, and I believe have never been treated as annuals, though most of them seed freely. They are grown in loam and peat, and are propagated by cuttings.

THYME.—See THYMUS.

THYMUS.—*Labiatae*.—The Thyme.—Fragrant dwarf shrubs, very suitable for rock-work. *T. grandiflorus* is perhaps the most ornamental. They should be grown in light rich soil, and are increased by dividing the root.

THYSACANTHUS.—*Acanthaceae*.—*T. Schomburgkianus* is a very beautiful stove plant, with graceful slender thyrses of pendant long tubular scarlet flowers. The central stem should be trained upright, leaving the side branches to take their natural direction; but after flowering they must be spurred in closely. Turfy loam, peat, and sand.

THYSANOTUS.—*Asphodelaceae*.—Australian plants, with very singularly fringed flowers. The flowers expand about eight o'clock in the morning, and they close at two, never remaining unclosed longer than six hours. They are grown in a greenhouse or stove, in sandy loam or peat.

TIGER FLOWER.—See TIGRIDIA.

TIGRIDIA.—*Irideae*.—The Tiger Flower.—The commonest species of this splendid bulb was formerly called *Ferraria Tigridia*, but it is now changed to *Tigridia pavonia*; there is a variety called *T. p. ledna*, and a second species called *T. conchiflora*. They are all extremely handsome, producing abundance of their magnificent flowers in the open ground, which, however, are very short-lived, seldom remaining expanded more than a few hours. The plants are natives of Mexico, and the bulbs may be suffered to remain in the ground all the year, if they can be kept dry; there being more danger of their being destroyed by wet than frost. The best mode of treating them is perhaps that recommended for the *Ixia*.—See *Ixia*.

TILE-ROOT.—See GEISSORHIZA.

TILLANDSIA.—*Bromeliaceae*.—Very curious stove-plants, most of which are parasitical, and may be treated like the stove *Orchidaceae*.—(See ORCHIDEOUS EPIPHYTES.) The others may be potted in a mixture of peat and loam, and propagated by suckers. They have all showy flowers, which they produce abundantly.

TOAD-FLAX.—See LINA'RIA.

TOBACCO.—See NICOTIA'NA.

TO'LPIS.—See HAWKEWEED.

TONQUIN BEAN.—*Dipterix odorata* Schreb. (*Barysma Tongo* Gert.)—A leguminous plant, of no beauty in its flowers, which are purple, but cultivated for its bean-like seeds, which are remarkably fragrant. It is a native of Guiana, where it is a tall tree; and it requires a stove in England, where it may be grown in a compost of peat and loam.

TOOTHACHE-TREE.—See XANTHOXYLUM.

TOPIARY.—The art of cutting yews and other trees into curious

shapes, by putting a wire framework over them, and then clipping the trees into the desired form. This art was practised to such an extent in ancient Rome, that the word for topiarist was used as synonymous with that for gardener.

TORE'NIA. — *Scrophulariæ*. — Australian plants, with pretty flowers, which require to be kept in a greenhouse, and grown in sandy loam. One species is a half-hardy annual, which may be raised on a hotbed, and planted out in May.

TORMENTI'LLA. — *Rosææ*. — British plants, with yellow flowers, which, though weeds, look very well on rock-work. The double-flowered variety of *T. erecta* is very ornamental.

TORREYA. — *Conifera*. — A very handsome evergreen tree, a native of Florida, in North America, nearly allied to the yew, and forming a link between that tree and the Hemlock spruce.

TO'RTULA. — *Cryptogamia Musci*. — Wall Moss. — A kind of moss, very useful in making moss-houses, from the brightness and variety of its colours; some of the species being of a dark blue-green, others of a rich yellowish green, others of a very pale pea-green, and one of a rich dark brown. They are all common in Britain.

TOUCH-ME-NOT. — See IMPA'TIENS.

TOURNEFO'RTIA. — *Boraginææ*. — Hothouse and greenhouse shrubs, and hardy and half-hardy perennials, natives of South America. *T. Messerschmidia* is a greenhouse shrub, with very fragrant flowers, but which have no beauty. They are all free-growing plants in sandy loam, and they are propagated by cuttings.

TRACHE'LIIUM. — *Campanulæææ*. — Throatwort. — The most common

species, *T. cæruleum*, is a half-hardy biennial, which requires to be raised on a hotbed, kept in a frame during winter, and planted out in spring, where it is to flower, in rich mould.

TRACHYME'NE. — *Umbellifera*. — Australian shrubs, requiring a greenhouse. For the beautiful annual species, *T. cærulea*, see DIDY'SOUS.

TRADESCA'NTIA. — *Commelinæææ*. — Spiderwort. — Handsome herbaceous plants, the common kinds of which only require planting in the open ground, and in any common garden soil. There are, however, several hothouse plants belonging to the genus, and two or three Mexican or South American annuals. *T. virginica* is a good herbaceous border plant, with flowers of a fine blue from May till October. *T. discolor* is an ornamentally foliaged stove plant, leaves green above and purple beneath. Rich light soil, with little water during winter.

TRAGOPO'GON. — *Compositæ*. — Goat's Beard. — Ornamental biennial plants, natives of Europe, which only require to receive the common treatment of similar plants, and to be grown in any garden soil. Of the British species, the most remarkable are *T. pratensis*, the popular name of which is Go-to-bed-at-noon, from the flowers closing in the middle of the day, and which has large yellow flowers, and a very curious feathery head of seeds; and *T. porrifolius*, the common Salsafy, which has purple flowers, and the roots of which are occasionally dressed as a vegetable.

TRAGOPY'RUM. — *Polygonæææ*. — Goat's Wheat. — Ornamental shrubby plants, with pink flowers, natives of Europe and America, which should be grown in very sandy loam, or heath-mould.

TRAINING is an important opera-

tion, whether it be applied to nailing trees against a wall, or to training




FIG. 57.—MODES OF TRAINING ROSES, &c. TO FORM PYRAMIDS.

herbaceous plants over an iron or




FIG. 58.—MODE OF TRAINING PLANTS IN POTS.

wooden frame-work. Climbing roses may be trained as pyramids, by

fixing a pole with three legs, or three poles in the ground, and suspending hoops from them, as shown in fig. 57, and this mode of training may be applied to various other plants. Plants in pots may be trained by fixing a number of sticks or pins of iron, with hooks attached (a), in the earth in the pot, and resting hoops on them, as shown in fig. 58.

TRA'PA. — *Hydrocharideæ*. — Water Caltrops. — Aquatic plants, natives of Europe and the East Indies, with white flowers and very curious nuts, which, when cooked, resemble in taste those of the chestnut, and are equally wholesome. The rhizoma should be planted, or the seeds sown, in loamy soil at the bottom of the water in which the plant is to grow.

TRAVELLER'S JOY. — *Clématis Vitalba*.

TREE CARNATION. — *Dianthus arboræus* is, in its wild state, probably only the common Carnation which has been trained against a wall, (and, by being kept continually growing, has been forced to take the character of a tree. It should be planted in calcareous loam, against an east or west wall, and carefully trained, giving it a little protection in case of severe frosts.

TREE MALLOW. — *Lavatera*. — Besides the common annual species of *Lavatera*, there are nine or ten species which are shrubby, and one of which, *L. phænicea*, a native of the Canary Isles, is a tree ten feet high. *L. maritima* is the commonest kind; and this is a native of Spain and the South of France; it will thrive in the open air in England, if slightly protected during severe frosts. *L. triloba*, *L. subovata*, and *L. africana*, have all the same degree of hardiness, and they will all live and flower

in British gardens, if about the same care be bestowed on them as is usually given to the Tree Pæony. *L. O'bia*, with reddish flowers, *L. Pseudo-O'bia*, with pale purple flowers, *L. unguiculata*, and *L. hispida*, are all shrubby species, which require a greenhouse, and should be grown in loam and peat.

TREFOIL.—See TRIFO'LIUM.

TREVIR'ANA. — *Scrophularinæ*. — The plant commonly called *T. coccinea*, or *Cyrtilla pulchella*, is now included in the genus *Achimenes*. It is a dwarf shrub with bright scarlet flowers, which it produces in September; and it should be kept either in a stove or in a warm greenhouse, the heat of which is between 60 and 70 degrees. It should be grown in a compost formed of equal parts of loam, peat, and sand, enriched with rotten cowdung or vegetable mould, and it should be well and frequently syringed with warm water, to keep it clear of insects. When it is much infested with them, it will be advisable to heat the water to 120 degrees. It is propagated by dividing the roots in February, taking care not to bruise them; or by cuttings off the points of the shoots taken off in August; and in both cases the plants are much improved by frequently shifting them as the pots fill with roots, and always into pots only a little larger than those in which the plants were growing. Thus treated, the plants will become compact little bushes, and will flower abundantly. For the other species of the genus, see *ACHIMENES*.

TRICHOSA'NTHE'S. — *Cucurbitaceæ*. — See SNAKE GOURD.

TRIFO'LIUM. — *Leguminosæ*. — The Clover or Trefoil.—Those who are accustomed to consider the Trefoil as only the common clover of the meadows, will probably be sur-

prised to find that there are nearly a hundred and fifty species, all more or less ornamental. Some of these are perennials and some annuals; and the colour of their flowers varies from dark crimson, and sometimes scarlet, to purple on the one hand, and to white, cream-colour, and pale yellow on the other.

TRI'LLIUM. — *Melanthaceæ*. — Tuberous-rooted plants, generally with dark brown or reddish flowers, which have a remarkably rich and velvet-like appearance. They are all natives of North America, and they should all be grown in shady places, in sand peat kept moist. Thus treated they will flower freely, and their flowers will have a very rich and singular effect.

TRIPTI'LION. — *Compositæ*. — Chilian annuals, which are hardy in Britain, and worth growing for their curious feathery seeds.

TRISTA'NIA. — *Myrtaceæ*. — Australian shrubs, nearly allied to *Melaleuca*; which require a greenhouse in England. They should be grown in sandy peat, and they are propagated by cuttings.

TRITO'NIA. — *Iridææ*. — Bulbous plants, with splendid flowers, which will thrive in the open ground for many years without taking up, if grown in a dry sandy soil, or protected from rain during winter. — See I'XIA.

TRO'LLIUS. — *Ranunculaceæ*. — The Globe Flower is a British plant, frequently grown in gardens, but on which cultivation appears to have had no effect. There are some exotic species.

TROPÆ'OLUM. — *Tropæolaceæ*. — The Garden Nasturtium. — The well-known annual plants called the Nasturtium are common in every garden, and only require sowing with the other hardy annuals in spring; they may be suffered to sow



themselves in autumn. There were formerly only two kinds of the annual Tropæolums, *T. majus* and *T. minus*, but since 1830, several varieties have been raised. One, with very dark flowers, is called *T. m. atrosanguineum*, and another, with dark stripes, is *T. m. venustum*. The young shoots of these plants are succulent, and taste like the common land cress, the botanical name of which is *Nasturtium*, and hence they have received their popular name. Besides the hardy annual kinds, there are several half-hardy species, most of which are kept in the greenhouse. The best known of these is *Tropæolum tricolorum*, with red, black, and yellow flowers, which has tuberous roots, and such very weak and slender stems, that it is found necessary always to train them over a wire frame, as they are quite unable to support themselves. In *Paxton's Magazine of Botany* it is stated, that the tuber of the root should not be buried, but only placed on the surface of the soil, so that the fibrous roots may penetrate it. This, it is said, will enlarge the bulb or tuber in "a truly astonishing manner," and though the plants will not appear healthy the first season, they will afterwards become extremely vigorous. He also recommends using double pots for these plants, and filling up the interstices with river sand, which should always be kept moist. *T. brachyceras* may be treated in the same manner; and it would probably succeed with *T. tuberosum*, a species which it is very difficult to throw into flower under ordinary treatment. *T. peregrinum* or *canariensis*, as it is sometimes called, the Canary Bird flower, was formerly considered a greenhouse plant, but it is now found much better to treat it as a half-hardy annual, raising

the seeds on a hotbed and planting them out in May, near some trellis-work, or other support, which the plant will soon cover, in the most graceful manner, producing thousands of its elegant fringe-like pale-yellow flowers.

Several new species of Tropæolum were introduced from 1840 to 1848 inclusive, and some few have been introduced since that period. An account having been given of a beautiful blue Tropæolum having been seen in Chili, collectors were sent by different persons to obtain it, and in consequence a great number of Tropæolum tubers were sent to England in the hope of one of them being the desired species. At last the Blue Tropæolum, *T. azureum*, was obtained, and it flowered beautifully in Messrs. Veitch's nursery at Exeter, in the autumn of 1842. There are two plants, which appear to be different varieties: the one having dark blue flowers with a white centre, and the other being all pale blue. The habit of both plants is that of *T. brachyceras*, with tuberous roots; and they are natives of Chili, like most of the other perennial species. Among the other tubers imported have been found several other species equally deserving of cultivation. The principal of these are *T. edule*, with bright orange and green flowers, and twining stems; and *T. polyphyllum*, with orange flowers that do not open fully, having a green calyx and a long spur, and leaves cut into eight or ten lobes. *T. Moritzianum* is a splendid species, with scarlet and yellow flowers that are deeply fringed. It is a native of Trinidad, but it is said to grow best in the open air during summer. It is nearly allied to *T. tuberosum*, and like that species it is very difficult to flower. The choicer kinds

of tuberous *Tropæolum* may be propagated by grafting them on tubers of the commoner kinds, in the way already directed for grafting the *Pæony* and the *Dahlia*. For the culture of *Tropæolum pentaphyllum*, see *CHYMOCAEPUS*.

TRUE SERVICE.—*Pyrus Sôrbus*, or *Sôrbus domestica*.

TRUMPET FLOWER.—See *BIAÑO'NIA* and *TE'COMA*.

TUBER.—Tubers closely resemble in their nature what are called solid bulbs or corms, and appear to be reservoirs of nourishment which have been laid up by nature for the support of the infant plant. Some tubers have numerous buds in different parts of their substance, like the potato, and others have only buds in the upper part, like the *Dahlia* and *Ranunculus*.

TUBEROSE.—See *POLYA'NTHUS*.

TULIP.—See *TULIPA*.

TULIPA.—*Tulipacææ*.—The Tulip.—The greater part of the Tulips grown in gardens are varieties of one species, *Tulipa Gesneriâna*, a native of the Levant; but there are several other distinct species. One of the most beautiful of these is the wild French Tulip, *T. sylvestris*, which is most elegantly shaped, of a beautiful yellow, and very fragrant, and which is occasionally found wild in England. *T. ôculus solis* is an Italian species, and *T. præcox*, Van Thol's Tulip, is a dwarf plant, that flowers very early in the season, generally in March or April. Besides these there are twelve other species, quite distinct. The garden varieties of *T. Gesneriâna* are divided into four classes, the first containing the Bizarres, which have a yellow ground shaded with dark-brownish red or purple, and which are subdivided into the flaked, in which the dark colour is in a broad stripe or band, rising from the

bottom of the petal; and the feathered, in which the dark colour forms a marginal edging to the petals, descending into them in various little delicate feathery veins. The second class contains the Byblemens, which are white, shaded with violet or dark purple, and which are also subdivided into flaked and feathered. The third class are called Roses, and they have white grounds, shaded with Rose colour or Cherry red, and they also are divided into flaked and feathered; and the fourth class are the Selfs, which are white or yellow without any dark colour. Besides these there are what are called breeders, which are of a dingy crimson, and which are seedling Tulips before they have shown any variety of colour; parrot Tulips, which are supposed to be a variety of *T. sylvestris*; and double Tulips, which are not valued by florists at all. All seedling Tulips, when they first flower, are what are called breeders, and of a dull uniform colour; and to make them break, that is, to produce the brilliant and distinct colours which constitute the beauty of a florist's flower, a variety of expedients are resorted to. At one time they are grown in poor soil, and only allowed water enough to keep them living; and then they are suddenly transported to the richest soil, abounding in food and moisture; and sometimes they are sent into the country twenty or thirty miles from the place where they were grown, to try the effect of change of air. Seedling tulips are generally five years before they flower. In addition to the kinds already enumerated, the French have what they call Baguettes, which are very tall-stemmed Tulips, the flowers of which are white, striped with dark-brownish red; Baguettes

Rigauds, which resemble the others, but have shorter stems and larger flowers; and Flamands, which have a white ground and broad dark red stripes. The Dutch have also a kind which they call the Incomparable Verport, which is white, feathered with bright-shining brown. All florists' Tulips ought to have cup-shaped flowers, round at the base; the ground colour inside the flower ought to be quite clear and bright in the centre; and all the marks ought to appear sharply cut and distinct.

The culture of the Tulip as a florist's flower requires constant attention. A bed about four feet wide, and of any convenient length, should be dug out to the depth of two feet, and in it a stratum of fresh turfy loam should be laid, and on this there should be a layer of rotten cow-dung and on that a layer of loam mixed with an equal quantity of sand. The surface of the bed should be slightly raised in the middle, and the tallest Tulips should be planted along it; the lower-growing ones being ranged on each side, so as to make the flowers form a gentle curve to the sides of the bed. The Tulips should be seven inches apart every way; and should be planted two or three inches deep; and the bed should be protected by half-hoops placed over it at regular distances, over which mats should be strained; the covering being so contrived as to be removed or opened at pleasure. When the Tulips are nearly arrived at their full height, the hoops and mats should be removed, and a path being made round the bed, a canvas awning, supported on a wooden frame, should be substituted. When the plants have done flowering, the leaves should be suffered to remain on till they turn brown, in order that they may assist in perfecting the new bulb,

which is formed every year in lieu of the old one, which gradually wastes away. The bulb is tunicated, that is, it consists of several coats or tunics laid over one another (see fig. 59). When the leaves are



FIG. 59.—TULIP BULB.

withered, the bulbs are taken up and laid on shelves to dry; after which the leaves, if any remain on, are removed, and the fibrous roots, which will have withered up, are rubbed off, and the bulbs are put into a box, divided into compartments, so as to keep the named sorts apart till the season for re-planting, which is the last week in October or the first in November. A fresh bed should be made for Tulips every year, or the soil of the old bed should be changed; as the exudations from Tulips poison the ground for other plants of the same kind, though they are suitable for other crops. The usual rotation in Holland is, Tulips, Polyanthus, Narcissus, Crocuses, and Hyacinths.

TULIP-TREE. — See *LIBIODENDRON*.

**TU'NA.**—One of the kinds of Prickly Pear or Indian Fig.—See **OPUNTIA**.

**TU'PA.**—*Lobeliaceæ*.—The new name for the large upright-growing kinds of Lobelia, with scarlet flowers.

**TUPELO-TREE.**—*Nýssa sylvática*.

**TURMERIC.**—*Curcúma*.—Scitamineous plants with very showy flowers, natives of the East Indies, which require a stove in England. They should be grown in light rich earth, and they are propagated by offsets.

**TURPENTINE-TREE.**—*Pistácia Terebínthus*.—It must be observed, however, that common turpentine is procured from the different trees of the Pine and Fir tribe.

**TUSSILA'GO.**—*Compósita*.—The Colt's-Foot or Butter Bur.—Some of the species are pretty and worth cultivating, particularly *T. frágans*. They will all grow in any garden soil; but are very troublesome to keep within bounds, from the immense number of suckers that they send up from their roots.

**TUTSAN.**—See **ANDROSÆMUM** and **HYPERICUM**.

**TY'PHA.**—*Týphina*.—Cat's-Tail Rush.—Aquatic plants, suitable for growing on the borders of ponds, and made pieces of water, to hide the boundary.

**U'LEX.**—*Legumindæ*.—The

Furze.—An erect evergreen shrub, with yellow flowers, which are produced nearly all the year. The double-blossomed Furze is very handsome, and makes a beautiful hedge. When it is employed for this purpose, a bank of earth should be raised three or four feet high, and wider at the bottom than at the top, and the cuttings should be planted in a drill along the ridge. The soil should be somewhat sandy, and

if there be plenty of room the plants should be left to nature, to hang down loosely over the bank, and they should never be pruned, except to cut out the dead wood. *U. nána* grows generally on very poor gravelly soils, and seldom exceeds two feet in height; while *U. europæa*, the common kind, in favourable situations, will grow ten feet high. *U. stricta*, the Irish Furze, has no spines, and it grows straight upright to the height of eight or ten feet. It requires a moist rich soil; and it is propagated by cuttings like the double-blossomed kind, as it has never yet been known to ripen seeds. All the other kinds are propagated by seeds, which they ripen in great abundance.

**UL'MUS.**—*Ulmæceæ*.—The Elm.—The Weeping Elm is a very ornamental tree for pleasure-grounds.

**UMBILI'CUS.**—*Crassulæceæ*.—The new name for some of the kinds of Navelwort.—See **COTYLEDON**.

**UMBRELLA TREE.**—*Magnolia tri-pétala*.—See **MAGNOLIA**.

**UNDERGROWTH.**—As nothing can look worse than naked ground under trees and shrubs, it is useful to know what plants will grow under the shade of trees. The best mode of concealing the ground is to cover it with ivy or laurel pegged down. Evergreen climbing roses may also be pegged down, or Azaleas and Rhododendrons. These last plants make beautiful undergrowth, as may be seen at Bagshot Park, High Clere, Claremont, and other places. The Aucuba, nearly all the Mahonias, and the different kinds of Periwinkle, are all plants well adapted for undergrowth.

**URE'DO.**—*Cryptogamia*.—A kind of rust often found on the leaves of rose trees and other plants.—See **MILDEW**.

**U'SNEA.**—*Cryptogamia*.—A kind

of lichen that hangs down like a beard from the branches of old trees, particularly Oaks, and has a very picturesque appearance.

UVULA'RIA. — *Melanthaceæ*. — Perennial hardy plants with pale yellow flowers, natives of North America, which should be grown in a compost of peat and loam.

VACCINIUM. — *Ericaceæ*. — The

Whortle Berry. — Dwarf shrubs, with pretty drooping heath-like flowers and rather showy fruit; found wild generally on commons in Europe and North America. *V. Myrtillus*, the common Bilberry, is the commonest species in England, and there is a variety with white berries in Germany. The Cranberry, *V. Oxycoccus* Lin., is now called *Oxycoccus Palustris*.

VALERIAN. — See VALERIA'NA.

VALERIA'NA. — *Valeriaceæ*. — Perennial plants, mostly natives of Europe, which will grow in any common soil. The dwarf species are very suitable for rock-work.

VALLISNERIA. — *Hydrocharidææ*. — Water plants, which succeed best in a greenhouse, and which should be planted in a layer of loam at the bottom of the cistern in which they are to be grown. The male and female flowers are on different plants; and the latter rise on long spiral stalks, which gradually uncoil above the surface of the water, while the former are produced at the bottom. Before, however, the anthers burst to discharge the pollen, the male flowers detach themselves from their stalks and rise up to the surface, on which they float like little white bubbles. After the pollen has been distributed over the stigmas, the male flowers wither, and the spiral stalk of the female coils up again, so as to draw the

seed-vessel under the water, that it may ripen at the bottom and burst when just in the proper place to deposit its seeds. Nothing can be more beautiful than the whole arrangement; and nothing can show more strikingly the admirable manner in which the economy of nature is carried on.

VALONIA OAK. — *Quercus Egilops*. — The acorns are enveloped in a curious leafy cup; and the tree, which is generally of a small size, is very handsome. — See QUE'ROUS.

VA'NDA. — *Orchidææ*. — A beautiful Epiphyte, which is made the type of a section from the great number that are nearly allied to it. It should be grown on the branch of a tree. — See ORCHIDEOUS EPIPHYTES.

VA'NILLA. — *Orchidææ*. — A creeping parasite, common in tropical climates, which throws out roots at every joint, that penetrate into the bark of the trees on which the plant grows. When grown in an orchideous house these plants are frequently fixed in a crevice in the damp wall, whence they spread out in different directions, catching hold of every object within their reach. When thus treated, and kept in a strong moist heat, the plants will flower; but unless objects are near for their roots to attach themselves to, the plants will never be strong and healthy. The native Vanilla is used for putting into chocolate.

VASCULA'RES are plants, the leaves and stems of which contain spiral vessels, in opposition to Cellulâres or plants which are composed only of cellular tissue. All the flowering plants belong to the Vasculâres; but the mosses, fungi, and lichens, are Cellulâres.

VASES in pleasure-grounds have often a very good effect, particularly on the terrace of an Italian villa.

Wherever they are introduced, however, they should always stand on a plinth, broader than the circular base, as nothing can have a more unartistical effect than to see a vase resting on the bare ground.

**VEGETABLE IVORY.**—This curious substance is the albumen of the seed of a plant called *Phytéléphas*, a native of the Gallipagos Islands, and South America. The seed is so hard that its albumen is cut into thimbles, and various articles for the work-table, and indeed is applied to nearly the same uses as ivory.—See *PHYTÉLEPHAS*.

**VELLA.** — *Cruciferae*. — The shrubby Creas Rocket.—*V. Pseudocytisus* is one of the few Cruciferous shrubs. It is evergreen, and only grows two or three feet high, with glaucous leaves and bright yellow flowers, which appear in April and May. It is a native of Spain, and it was formerly considered a greenhouse plant in England, but it is now found to be hardy. It grows best in calcareous loam, but it will thrive in any garden soil; and it is very suitable for rock-work. It is propagated by cuttings of the young wood planted in sand under a glass.

**VENUS'S COMB.**—*Scandix Pecten*.—A British weed.

**VENUS'S FLY-TRAP.**—See *DIOMEA*.

**VENUS'S LOOKING-GLASS.**—See *CAMPANULA*.

**VERBA'SCUM.**—*Solanaceae*.—The Mullein, or Flannel Plant.—Showy herbaceous plants, generally with yellow flowers, and most of which are natives of Britain. The greater number of the species are biennials, and require the usual treatment of such plants (See *BIENNIALS*); but *V. phæniceum*, one of the handsomest species, is a perennial. They will all grow in any common garden soil, though they prefer one which

is somewhat loamy; and they are increased by seeds, or by dividing the root.

**VERBENA.**—*Verbenaceae*.—Verbain.—Only a few years ago the Verbenas were scarcely known in flower-gardens, except by *V. Aubletia*, with pinkish flowers, and *V. Lamberti*, with purple ones, neither of which possessed much beauty. In 1827, the beautiful *Verbena Melindres*, or, as it is sometimes called *V. chamædrifolia*, was introduced from Buenos Ayres, and it directly became a favourite, though for some years it was kept carefully in the greenhouse, and considered difficult to manage. Since that time, however, numerous other species have been introduced, and as they are found to hybridise freely, and to ripen abundance of seed, innumerable hybrids and varieties have been raised. They are all found to root freely from layers, and to strike as freely from cuttings, and to thrive during summer in the open air. They will all grow in any light soil, though they thrive best in peat or heath-mould; and when once planted they require no other care but occasional watering, and they spread rapidly, producing abundance of flowers. They have thus become general everywhere; and it is now rare to see a garden or a balcony without them. The kinds principally cultivated are the following: *V. Melindres*, the common scarlet Verbena, the colour of which is the most brilliant scarlet. It is, however, the most tender kind of Verbena, and when planted in the open air it is generally killed by the first frost, if not protected. It is a prostrate plant, and should be pegged down over the bed it is intended to cover, when it will throw out roots at every joint. Its varieties, *V. M. latifolia*, and *V.*

*M. splendens*, which are probably hybrids between *V. Melindres* and *V. Tweediana*, are much more hardy than the species, and they are naturally more upright-growing, though when pegged down they throw out roots at every joint in the same manner. *V. ignea* and *V. atrosanguinea* are of a still more intense and yet brilliant scarlet than *V. Melindres*, but the former of these is difficult to keep through the winter. *V. Tweediana* is an upright-growing plant with crimson flowers, and it is very hardy. *V. Netlisti* is an upright-growing sweet-scented sort; as is also *V. tenerioides*, and between the latter and *V. incisa* numerous varieties have likewise been raised. The lemon-scented plant, *Verbena triphylla*, is now called *Aloysia citriodora*.—See ALOR'SIA.

VERONICA.—*Scrophulariæ*.—Speedwell.—Many of these kinds are pretty perennial and annual plants, generally with blue flowers, natives of Britain, and other parts of Europe. All these are of the easiest culture, as they will grow well in any common garden soil that is tolerably light and at the same time moist; and they are propagated by seeds, and by division of the root. Many of these plants are very suitable for rock-work. Within the last few years, several very ornamental shrubby species, growing from three feet to six feet high, have been introduced; and of these the most ornamental are, *V. salicifolia* or *V. Lindleyi*, and *V. speciosa*, both natives of New Zealand. *V. formosa* is a native of Van Diemen's Land, and, notwithstanding its name, is very inferior in beauty to the New Zealand kinds. It is the same as the *V. diosmæfolia* of some nurseries.

VERVAIN.—See VERBENA.

VESICARIA.—*Crucifera*.—Herbaceous plants, mostly with yellow flowers, natives of Europe and America, that should be grown in sandy loam, and which are propagated by seeds or division of the root.

VETCH.—See VICIA.

VIBURNUM.—*Caprifoliaceæ*.—The Viburnum. — Ornamental shrubs, generally with terminal corymbs of white flowers. One of the best known of these, the Laurustinus, *V. Tinus*, is an evergreen bush, with white flowers that are rose-coloured in the bud, and dark-blue berries; and it is very valuable in town-gardens, as it flowers from December till March. It is a native of the south of Europe and the north of Africa. There is a variety with shining leaves and larger cymes of flowers, but it is rather more tender than the common kind. When the Laurustinus is grown near a dwelling-house, care should be taken in spring, when the leaves drop, to have them swept away every day, as they have an extremely disagreeable smell when they are decaying, and are said to be very unwholesome. The tree Viburnum (*V. Lentago*) is a native of North America, and it forms a very hardy and handsome low tree in British gardens. It is also valuable for the great abundance of its berries, which are a favourite food with birds. The Wayfaring Tree, or Wild Guelder Rose (*V. Lantana*), is another interesting small tree; and *V. cotinifolium* is a beautiful species from Nepal. *V. odoratissimum*, *plicatum*, and *macrocephalum*, are natives of China, the former of which well deserves cultivation on account of its fragrance, and the latter for the large size of its flowers. The most interesting kind of Viburnum grown in small gardens is, however, the Guelder Rose, or Snowball Tree *V.*

*Opulus*. This is a deciduous shrub, a native of Europe and part of Asia, which is always found in a wild state in swampy thickets. In a wild state its principal beauty lies in its bright red berries; but in a state of cultivation its heads of flowers become so compact, of such a snowy whiteness, as amply to justify its popular name of the Snowball Tree. All the *Viburnums* are hardy in British gardens; and they will all grow freely in any common soil. They are generally propagated by layers, but cuttings will strike freely if kept moist and in a shady situation. When transplanted, the evergreen species should be removed in October or November, as they have few fibrous roots, and are very apt to be killed by a continuance of dry weather if they are transplanted in spring.

**VICIA.** — *Leguminosæ*. — The Vetch. The ornamental species are generally pretty climbing plants, with purplish flowers, natives of Europe. Some of the kinds, however, have white, some pink, others blue, and others pale-yellow flowers. All the kinds grow freely in any garden soil, though they thrive most when the soil is deep and sandy; and they are propagated by seeds or division of the roots.

**VICTORIA REGIA.** — *Nymphaeaceæ*. — A splendid aquatic plant, a native of South America, the leaves of which have been known to be six feet in diameter, and the flowers two feet in diameter. It is most nearly allied to the Eastern Water Lilies. It was named in honour of her Majesty.

**VIOLAS.** — *Iridææ*. — The Peacock Iris. — These beautiful flowers are better known under their old names of *Iris pæonia* and *Moræa*, than under their present almost unpronounceable appel-

lation. They are very nearly hardy, and may be grown in the open border if treated as the common kinds of *IRIS*; but as the bulbs are very small and delicate, it is, perhaps, safer to grow them in pots, in equal parts of peat, vegetable-mould, and sand, and to keep them dry, or to take them out of the pots when they have done flowering till the planting or growing season returns the following year.

**VINCA.** — *Apocynææ*. — The Periwinkle. — There are two species common in British gardens, both of which are creeping or trailing evergreen shrubs, which will grow freely under the shade of trees. They both prefer a soft moist soil, which they can easily penetrate with their long creeping roots. *V. major* is the common species, and *V. minor* only differs in the flowers being smaller, and the whole plant more delicate. The Periwinkle is generally propagated by its runners, which strike root from every joint, like those of the strawberry, and which only want dividing from the parent to become plants. When it is wished to make the Periwinkle produce seeds, the plants should be grown in a pot, and all the lateral shoots cut off.

**VINE.** — The common Vine (*Vitis vinifera*) may often be introduced with very good effect in ornamental garden scenery, for covering a bower or verandah, or training round the window of a breakfast-room. Nothing can, indeed, be more beautiful than a Vine in the last-mentioned situation, forming a framework, as it were, to the garden beyond; and with its beautiful leaves looking almost transparent in the morning sun. A Vine also looks very well when suffered to grow naturally among the tall trees of a lawn or shrubbery, as it hangs



itself from branch to branch in a manner more graceful than any art can hope to imitate. Vines thus treated would have a very good effect in the grounds of an Italian villa. The three American species, *V. Labrusca*, or the Wild Vine, *V. Vulpina*, or the Fox Grape, and *V. riparia*, or the sweet-scented Vine, the flowers of which smell like Mignonette, are all very suitable for growing in the open air, from their extreme hardiness. All Vines like a very rich and somewhat moist soil, and thrive best when their roots can get access to a drain, sewer, or muddy pond.

**VIO'LA.**—*Violæææ.*—Beautiful perennial dwarf plants, natives of Europe and North America, and growing generally on the moist shady banks in woods. There are nearly 150 kinds grown in British gardens, but the most common are, *V. odorata* (see VIOLET), and *V. tricolor* (see HEART'S-EASE). The Fan-leaved Violet (*V. flabellifolia*), and the Hollow-leaved Violet (*V. cuculata*), are both American species, with large and handsome flowers. All the species should be grown in peat and loam kept moist, and they all thrive best in a shady situation.

**VIOLET.**—The common sweet-scented Violet (*V. odorata*) is a British plant, which grows in woods or on and under banks. The white Violets are found generally in calcareous soils; and the sweetest I ever smelt were, I think, those I have gathered growing among the limestone rocks in the woods of Dudley Castle. In garden culture, however, what are called the Neapolitan and Russian Violets are the most useful, as they flower during the winter months; and of these the Neapolitan are the sweetest. These delightful Violets, which flower from October to April or

May, should be grown in pots or boxes, where they can be covered with a hand-glass in cases of severe frost. They should be propagated by runners taken off in May, and removed to prepared beds in the open garden, the soil of which should be composed of equal parts of heath-mould, leaf-mould, and strong yellow loam, but no dung. The plants should be a foot apart every way, and kept clear of runners. They should be freely watered during the summer months; but in August they should be suffered to become rather dry, to give them a season of rest. About the middle of September they should be removed to the place where they are to flower, and this should be so contrived as to allow them to have a bottom-heat of 70° or 75°. The best mode of effecting this is to make a hotbed, the surface of which is brought to within ten inches of the lights. The plants should be taken up with balls of earth attached, and the space between them filled in with yellow loam, rotten dung, vegetable mould, and heath-mould. After planting they should be well and frequently watered during two days with warm water, and then again about a month afterwards. With these exceptions, the plants are kept dry till February. During severe weather the hotbed must be covered with mats, &c., admitting dry air when practicable. The surface of the bed should be covered with coarse river sand to keep off the slugs. Another mode is to take off the runners in May, and to plant them at once in the pots or boxes in which they are to flower. These pots or boxes should be well drained by having a layer of potsherds of considerable thickness at the bottom; and they should be filled up with a compost

made of two-fourths of vegetable mould, one of loam, and one of silver sand. They should be covered with a hand-glass during heavy rains, or in frosty weather; and if the frost is very severe, a mat should be put over the glass. When the pots or boxes are introduced into a sitting-room, they should be watered twice a day, but once will be sufficient if the plants are grown in the open air. It must be observed that plants in a sitting-room, where a constant fire is kept, are generally in an equal degree of heat to a hothouse at 65°; only the air of the living-room is much drier than that of the stove, and, to counteract this, additional watering is required. The common Violets only require planting on a sloping bank in a shady place, in a peaty soil, where they will have moisture, but where their roots will not be exposed to the effects of stagnant water.

VIPER'S BUGLOSS.—See ECHINUM.

VIPER'S GRASS.—See SCORZONERA.

VIRGILIA. — *Leguminosæ*. — A very handsome low tree, a native of North America, with drooping racemes of white flowers, resembling in form those of the Laburnum. It grows freely in any sandy soil.

VIRGINIAN CREEPER.—See AMPPELOPSIS.

VIRGINIAN POKE.—See PHYTOLOCA.

VIRGIN'S BOWER.—*Clematis Vitalicella*.

VISCUM. — *Loranthææ*. — The Mistletoe.—This curious parasite can hardly be called ornamental, though it may sometimes be introduced with effect to give an air of antiquity to newly-planted pleasure-grounds. It grows best on old cankered apple-trees, but it may be made to take root on even a young

tree, by pressing a berry in a crack in the bark, and then tying oiled paper over it. As, however, the male and female flowers of the Mistletoe are on separate plants, the berries are not always fertile. It is a vulgar error to suppose that the Mistletoe grows generally on the oak, as it is extremely rare on that tree in England; it is found most commonly on the apple, and next on the hawthorn; it is also found on the lime, the sycamore, the willow, the poplar, and the ash; occasionally on the cherry, and sometimes, though rarely, on pines and firs. When the seeds begin to grow, they send out first one or two roots, which ascend for a short time, and then turn back to the bark, on which they fix themselves, like the suckers of an insect. The other end afterwards detaches itself from the tree, and becomes leaves and shoots. The roots of the Mistletoe descend between the bark and the young wood, and no intimate union takes place between the old wood of the parasite and its supporter. This is plainly shown in a piece of an old thorn, given to me by H. L. Long, Esq., of Hampton Lodge, to which a Mistletoe of very large dimensions was attached. The wood of the Mistletoe is of a very fine pale yellowish tinge, and it is as hard and of as fine a grain as box, which it greatly resembles, while that of the thorn is dark brown.

VITEX. — *Verbenææ*. — The Chaste Tree.—The principal species are *V. Agnus Castus*, which is a dwarf shrub, with whitish flowers, which will grow in any common soil, and will generally stand out in British gardens, though it is sometimes killed by a severe winter; and *V. incisa*, which has pretty palmate leaves and purple flowers, but it is so long before it puts out its leaves

in spring, and looks so much as though it were dead before its leaves expand, that it is often thrown aside as worthless when it is in perfect vigour; it is generally kept in a greenhouse, and grows in peat and loam. Besides these, there are several hothouse species, natives of the East Indies, which are not worth cultivating.

VITIS.—*Ampelidææ*.—See VINE.

VOLKAME'RIA. — *Verbenæææ*.— Nearly all the plants formerly included in this genus have been removed to *CLERODEN'DRUM*, and it now contains only two species, one a stove shrub with white flowers, from the West Indies; and the other a half-hardy tree, with purple flowers, from Nepal.

WACHENDO'RFIA. — *Hæmodoræææ*.—Bulbous and tuberous-rooted plants with large panicles of very showy flowers, which are generally yellow. These plants have rhizomas or under-ground stems, in the scales of which, in some of the species, little bulbs form, which, if removed and planted, become distinct plants. These are the bulbous kinds. The others have the same kind of rhizoma or fleshy under-ground stem, but no bulbs form in it. All the kinds are nearly hardy, and they will thrive in the open ground, provided the situation be tolerably dry, without its being necessary to take up their roots during winter.

WAHLENBE'RGIA. — *Campanulæææ*.—Perennial and annual plants, formerly considered as belonging to *Campanula*, and of which *Campanula grandiflora* is the type. They should all be grown in sandy loam, and they are propagated by seeds, or by division of the roots.

WALKS may be considered with

reference to their direction, their construction, and their management. In a small garden, the direction of the main walks should generally be governed by the boundary lines; and hence, in a plot of ground which is square or oblong, the walks should be straight and rectangular; the object in such a case being to produce the beauties of regularity and symmetry. On the other hand, when the boundaries of a garden are irregular, the surrounding walk may be irregular also; the object in this irregularity being to create a variety by contrast in the direction. When a garden bounded by straight lines is so large as to contain an acre or two, and the whole of the interior is to be laid out as a pleasure-ground, then the walks may be varied in direction; the boundary being concealed by trees and shrubs, or by artificial undulations of the soil. In general, it may be laid down as a principle, that all walks should be straight when there is no obvious reason why they should be otherwise; and hence, in the case of all winding walks, if there is not a natural and apparently unavoidable reason for their deviating from the straight line, an artificial reason ought to be created. This may always be done, even on a flat surface, by the position of trees and shrubs; or when there is the slightest inclination to inequality of surface, the same sufficient reason may be created by heightening these inequalities. When a winding walk bends to the right, the trees and shrubs ought to be chiefly conspicuous on the left side, and on the contrary; and the same rule is applicable to the natural or artificial inequalities. When a walk is made perfectly straight, the surface of the ground ought to be perfectly even for some feet in

width on each side of the walk, excepting in some few cases, such as a straight terrace walk along a regular uniform slope, in which case the ground on one side of a walk will rise regularly, and on the other side will fall regularly. All straight walks should lead to some conspicuous object at the further end of the walk, and facing it, so as to appear to belong to it; and this object should be seen the moment the walk is entered upon. Hence every straight walk should have an object at each end, such as a seat, an alcove, an archway, a gate, a door, a statue, a fountain, &c. A winding walk, on the contrary, requires no object at the further end to allure the spectator; because every turn has the effect of an object by exciting his curiosity and inducing him to advance to see what is beyond. Where one walk abuts upon or joins another at a nearly right angle, it becomes subject to the same laws as a straight walk; and opposite to the abutting point or place of junction there ought to be a seat, a statue, or some other object, partly to form a termination to the abutting or joining walk, and partly to serve as an obvious reason why the one walk joins to the other at that point rather than elsewhere. At the same time other reasons for the junction at that point may exist or may be created; for example, the surface of the ground may be favourable, or trees and shrubs may be planted so as to render it apparently impossible to join anywhere else. It has been said, that in laying out winding walks nature should be imitated, and the tracks of sheep in pastures, or of wild animals on commons, have been held up as examples:—

—“The milkmaid’s careless step  
Has, through yon pasture green, from  
stile to stile,  
Imprest a kindred curve; the scudding  
hare  
Draws to her dew-sprent seat, o’er  
thymy heaths,  
A path as gently waving.”—

But to imitate such walks would be to copy vulgar nature; and therefore art refines on these lines by rendering them more definite and elegant: in short, by exhibiting in them a choice of form or line for its own sake; because, of the various lines or parts of lines found in accidental footpaths, or in the tracks of hares, some must be more agreeable to the eye than others, and it is only these agreeable parts which are to be imitated and combined in garden scenery. All this is founded on the recognition of a principle which is, or ought to be, the foundation of all the fine arts; viz., that nature is to be imitated, not to be copied. To copy nature exactly as she appears before us is the province of common art, and may be pleasing to many minds; but to minds of culture and refinement, nature requires to be copied in such a manner or in such a medium as to show art. If this were not the case, and if we were to copy footpaths exactly, then we should, of course, not gravel them, or define them by regular edges. Hence, when one walk joins another, the angles of junction should never be rounded off in that extreme degree which is found in public roads: where, in turning out of one path into another, an obtuse or rounded angle seldom fails to be found. The appearance of such an angle in garden scenery, whether in carriage-roads or foot-walks, destroys all allusion to high art: and hence, in all gardens containing winding walks which are much frequented,

the junctions of these walks with others should be protected by trees and shrubs, or by vases or other architectural objects, in such a manner as to render this rounding of the angles of junction impossible.

The construction of walks, more especially on soils which are not naturally dry, and on surfaces which are not level or nearly so, requires considerable skill. The inclination of the walk from one point to another should be so arranged as to carry off the surface-water from rain or melting snows along the edges of the walks, and the underground water by drains beneath the surface. On even surfaces, though not level, this is attended with little difficulty; and one drain under the centre of the walk, or on one side of it, will suffice for a considerable length, without any branch drains to carry off the water which accumulates; but where the surface rises and falls alternately it is not only necessary to have a drain under the walk throughout its whole length, but a branch drain to some natural outlet is essential at every change of surface. These drains are not only intended to carry off the underground water, but also that which collects on the surface and finds its way to the sides; and for this purpose there are small cross drains formed at certain distances, which communicate from the sides to the centre, and these side drains communicate with the surface by a small upright tube or well, covered by an iron grating, or by a flagstone pierced with holes, to admit the water. Sometimes the main drain, instead of being formed under the centre of the walk, is made at one side, and sometimes, in the case of walks through a lawn, the drain is made under the turf; but in this

case, as in the other, the small cross drains communicate with it, and are furnished with gratings on a level with the surface of the sides of the walk. In general these gratings are placed close to the edge of the walk, more especially when it passes through dug ground edged with box, or where there is little ground to spare; but when it passes through a lawn, the gratings are best placed in small recesses in the turf at the sides. In the case of dry soils with a porous subsoil of gravel, sand, or rock, drains may be dispensed with altogether; and in those parts of the country where the kind of gravel used does not bind so as to form a sufficiently smooth and compact surface to prevent the water from sinking into it, the side gratings may be dispensed with. In walks on very uneven surfaces, such as where they are conducted up and down declivities, considerable care in the construction is required, in order to prevent the gravel from being washed away during heavy rains or the thawing of snow. Two things are requisite for this purpose: very complete drainage, with gratings on both sides, not more than two or three yards apart, and having the surface of the walk raised much higher in the middle than usual, so as to throw the water immediately to the sides, and never to admit of a current in the direction of the walk; the next requisite is, a much coarser gravel than usual, in consequence of which the water of rain or snow cannot wash away the sandy particles. The most effective mode, however, is to wash the gravel quite clean, so as to leave no particle smaller than a large gooseberry, or larger than a small apple, and to mix the whole with Roman cement. Were it not for the dis-

agreeable dark colour of asphalt, walks on steep declivities laid with this material would be preferable to any others, as being by far the most durable.

In the operation of forming walks, the first step, after the line has been marked out, is to take the levels of the surface, so as to determine the degree of inclination necessary for carrying off the water, and also what quantity of soil will have to be removed on each side of the walk, so as to reduce the whole to a uniform surface. The next step is to mark out the width of the walk, after which the soil is to be excavated. The depth of the excavation will depend on the nature of the subsoil. If that is dry and absorbent, such as gravel or rock, then the depth need not be more than a foot or eighteen inches; but if the subsoil is retentive, such as clay or loam, then the depth, at least in the centre of the walk, should be between eighteen inches and two feet, and it should be at least one foot in depth at the sides. The drain may be made in the centre, that being the deepest part; and this being done, the excavation is to be filled up to within nine inches of the surface with small stones, broken brickbats, and such-like materials, which are to be well beaten down with a rammer. On this surface a layer, three inches in thickness, of coarse gravel should be laid and well rammed down; then the remaining six inches should be filled in with the best gravel, which should not be rammed, but rolled, after being raked to an even surface. If the walk is to be edged with box, that should be planted immediately before laying on the three-inch stratum of coarse gravel; but if it is to be edged with turf, the most convenient time for laying

it down is before putting on the upper stratum of six inches.—See *BUXUS* and *EDGEINGS*.

The management of walks consists in keeping them clean by the removal of all extraneous matters from the surface, including weeds; and in preventing worms from working in them and throwing up casts. Leaves and other extraneous matters are removed by sweeping; but weeds must be hoed or pulled up, or killed by salt, which is the cheapest and most effectual mode, for the impure agricultural salt can be had for less than 30s. a ton, and this quantity will keep clear a large extent of walks. But care must be taken that salt does not come in contact with the tops or roots of edgings such as box, &c. Every time a walk is hoed, it ought to be raked and rolled; and to preserve the surface quite smooth and firm, it ought always to be rolled as soon after rainy weather as the surface has become dry. To renew the surface of walks, they may be turned over once a year in spring; but this is only advisable in the case of fine-coloured gravels, such as that of Kensington, in order to present a fresh surface; for, with reference to the smoothness, firmness, and easy keeping of the walk, turning over the gravel is injurious rather than otherwise.—See *GRAVEL*.

*WALL CRESS*.—See *A'RABIS*.

*WALLFLOWER*.—Common as this flower is, it well deserves great pains to be taken in its cultivation, as its principal beauty is displayed at a season when there are few hardy plants in flower; the *Crocuses*, *Hyacinths*, and *Narcissi*, are just over, or beginning to decay, and the annuals have not yet begun to expand their blossoms. In April and May the brilliant yellow and dark orange of the Wallflowers give

a peculiar brilliancy and liveliness to gardens, which without them would present a naked and dull appearance. The common Wallflower (*Cheiranthus Cheiri*) is generally called a biennial, and it does not flower till the second year after sowing. It will, however, frequently live three or four years in favourable situations. There are ten or twelve varieties; some with rich dark reddish-brown flowers, called the Bloody Wallflowers, and others of a light yellow, with nearly all the intermediate shades. There is also one with dark purple flowers, and another with purple and pale yellow flowers, the first of which has variegated leaves. The dark and double flowered kinds should be grown in very rich soil, but not freshly manured. The remains of Celery trenches used the previous year, or part of the ground under an old hotbed, will suit these flowers exceedingly well; taking care to mix a little sand with the soil, if it be at all loamy, in order to lighten it. As the varieties can never be depended upon for coming true from seed, the best way to preserve any that are very rich in colour, or very double, is to make cuttings of them in May. These cuttings should be from shoots of the current year, and they should be about three inches long. They should be cut off carefully, and the end should be cut smooth at a joint with a sharp knife. The leaves should then be cut off close to the stem, for about half the length of the cuttings; and they should be put into pots filled with sandy loam and vegetable mould, about four inches apart, and three in a pot. They should be sprinkled with water three times a day, till they have taken root, which will be known by their beginning to grow. In many cases, the cuttings are

merely put into the open garden; choosing a shady place, and mixing a little sand with the mould, when the ground is dug over, before planting them. *C. mutabilis* is a half-shrubby evergreen, with dark purple, yellow, and lilac flowers, and it requires a light rich soil. *C. alpinus* is a dwarf plant, with small yellow flowers, and is well adapted for rock-work. The Stocks, which were formerly considered to belong to this genus, are now removed to *Matthiola*. Both Stocks and Wallflowers are frequently called Gilliflowers, said to be a corruption of *grosfée*, or perhaps of *jolies fleurs*.

WALLS for gardens are either used as boundary fences, and at the same time for the purpose of training plants on, or they are erected in gardens for the latter purpose only. They may be formed of different materials, according to those that are most abundant in any given locality; but the best of all walls for garden purposes are those which are built of brick. Stone walls are durable and good; but the stones being much larger than bricks, the joints between them are too far apart for the purpose of neat training. Mud or earth walls, when properly built, with a coping sufficient to throw off the rain on every side, are dry, warm, and very congenial to plants, but from the fragile nature of the mud, they are not well adapted for training on. These two last kinds of walls should, therefore, be covered with wire or wooden trellis-work, to which the plants may be tied. Walls made of boards are very good, where they are not required to be high; and where the boards are soaked with tar, or coated over with pitch, and placed on a footing of brickwork, stone, or oak plank, they will last many

years. Shelters, as substitutes for walls, are formed of panels of reeds covered with trellis-work ; or sometimes in Russia with wicker-work, the interstices being caulked with moss ; and both these kinds of substitutes for walls last a number of years, when protected from perpendicular rains by copings which project at least a foot on every side, and when placed on footings which secure them from the damp of the soil. Walls have also been formed for training on, by inserting large slates or thin flag-stones, such as the Caithness pavement, either in the soil (in which case the walls are not above four or five feet in height), or in frames of timber or iron, in which case they may be of any height required. Such walls are always covered with trellis-work, to which the trees or plants are attached. The most generally applicable kind of walls, however, and those which are by far the best for garden purposes, are, as before observed, those formed of brick. When the wall is not intended to be more than four or five feet in height, it need not exceed nine inches in thickness ; and the thickness of fourteen inches will admit of fifteen feet in height or more, the wall in both cases being built without piers, which are great impediments to good training. With piers, the height with any given thickness may be increased one-fourth. In no case, however, ought garden walls, or indeed division or fence walls of any kind which have not a load to support perpendicularly, or a pressure to resist on one side, to be built with piers. The same object may always be obtained by building the walls hollow ; each side being of the thickness of four inches, and the two sides being joined together by cross partitions of four-inch work.

An excellent garden wall may thus be raised to the height of twelve or fourteen feet, with the same quantity of bricks that would raise a nine-inch wall to that height, with the addition only of the bricks necessary to form cross partitions at every three or four feet. The width of the wall may either be fourteen or eighteen inches, the vacuity in the former case being five inches, and in the latter nine inches. Where it is desired to save the expense of a coping, the sides of the wall may be gradually contracted towards the top, so as to finish with a coping of bricks set on edge crosswise ; but no wall intended for fruit-trees or for tender-flowering shrubs should ever be built without a protecting coping, because the rains run down the face of the wall, and render it moist and cold at those seasons when dryness and heat are most wanting, viz., in spring, when the buds are bursting, and in autumn, when the young wood is ripening. The same moisture, and its alternation with dryness, rots the mortar in the joints of the bricks, and greatly injures and disfigures the face of the wall. When, therefore, walls are built without projecting copings, the exterior joints ought invariably to be pointed with stucco, as in France and Italy, or with Roman cement. Walls of nine inches in thickness, and even four-inch walls if built in a winding or zigzag direction, may be carried to a considerable height without either having piers or being built hollow ; and such walls answer perfectly for the interior of gardens. Hollow walls of every description may also be built at less expense by placing the bricks on edge instead of being laid flat ; and not only garden walls, but those of cottages and farm buildings may be



constructed in this manner. Lengthened details on this subject will be found in Mr. Loudon's *ENCYCLOPEDIA OF COTTAGE, FARM, AND VILLA ARCHITECTURE*, and in his *VILLA GARDENER*.

For further particulars respecting the use of walls in ornamental gardens, see *CONSERVATIVE WALL*.

**WARRATAH.**—See *TELO'PEA*.—There is also a Warratah Camellia; so called because its bright crimson colour resembles that of the true Warratah plant or *Telòpea* of Botany Bay.

**WATER**, in gardening, may be considered with reference to its use in vegetable culture, and to its effect in landscape. When water is too abundant in any soil, it is to be removed by surface or underground draining; and the rain, or thawing snow which produces water on the surface, is to be conveyed away by similar means. (See *WALKS*.) Water, as an element of culture, is next in importance to soil, for plants can no more subsist without the one than without the other. All plants in a highly artificial state, even in a moist climate like that of Britain, require water occasionally; for extraordinary excitement by means of soil, or manure, or artificial temperature, will be ineffective unless seconded by water. For all ordinary purposes, it is sufficient to pour the water on the surface of the ground; but if the operation of watering were carried to the full extent of which it is susceptible, it would be supplied subterraneously by underground drains, as is sometimes done in fen lands, and not unfrequently in reclaimed bogs, both in Great Britain and Ireland. Where the soil of a garden is to be made the most of, there should be a substratum of gravel or small stones, with drains or small tunnels, or

perforated tubes of earthenware at regular distances, communicating with a supply of water a few feet above the surface of the soil, by which water might be admitted at pleasure, so as to irrigate the whole of the under strata, and to supply moisture to the roots of the plants altogether, independently of what they might receive either artificially or naturally from the surface. This would be of great advantage in dry soils, not only to crops of herbaceous vegetables, and to the plants of flower-gardens, but to fruit-trees, forest-trees, and useful or ornamental shrubs. It would be more especially useful, in the case of orchards, to set the blossoms in spring, and to swell off the fruit in autumn. It would produce astonishing effects in the case of fruit-trees planted against walls, and on vines planted on prepared borders, and on peach-trees in a state of forcing. The only objection to this mode of applying water is the expense.

Water, considered with reference to its quality, should be without the admixture of extraneous mineral substances, such as acids or alkalies; and it should be of the same temperature as the soil, or higher rather than lower. In order that it should be of the same temperature as the soil, it is necessary to expose it to the action of the atmosphere in ponds or basins, before using, and even when taking the water from such ponds or basins the surface-stratum of the water ought always to be taken, by dipping in the watering-pot in such a manner as that only the surface of the water should run into it. In the application of water to plants, the most general mode is to pour it at their roots; but in doing this it is not necessary that the water should touch the stems or the collar

of the plant. On the contrary, the stems of tender plants, and even the soil for an inch or two all round them, are better kept dry ; because the moisture on the collar is apt to create decay. The fibres which absorb the moisture and convey it to the leaves of the plants, are always extended to some distance from the stem ; and hence it follows that a plant may be moistened immediately round the stem without rendering it any service, but, on the contrary, incurring the risk of rotting it ; while if watered at some distance from the stem, it may be nourished in reality, and yet have the appearance of being perfectly dry.

For certain kinds of plants, such as the *Hydrangea* and the *Balsam*, *Cock's-combs*, *Chrysanthemums*, and others which are of vigorous growth, water may be mixed with manure, such as concentrated stable-dung, recent sheep's-dung, or any other description of animal manure which is soluble in water. For some plants, such as heaths and most of the hair-rooted shrubs and herbs, this liquid manure is found to be injurious ; but for many others, applied when they are in a growing state, it is found greatly to increase their vigour.

Water, as an element of landscape scenery, is exhibited in small gardens either in ponds or basins, of regular geometrical or architectural forms ; or in ponds or small lakes of irregular forms, in imitation of the shape seen in natural landscape. In general, all geometrical or architectural basins of water ought to have their margins of masonry, or at least of stones placed so as to imitate a rocky margin. The reason is, that by these means the artificial character is heightened, and also a colour is introduced between the surrounding grass, vegetation, gravel,

or dug ground, which harmonises the water with the land. Artificial shapes of this kind should never be of great diameter, because in that case the artificial character is comparatively lost, and the idea of nature occurs to the spectator. When round or square, they should not be of greater diameter than the house or building to which they belong ; but a better effect would be produced by their being smaller, as is shown in the architectural basins of Italy, and the tanks of Persia and India. When of oblong forms, they may be of any length, provided they are never of any great breadth ; because in this case they never can be seen in such a manner as to obliterate the idea of high art, the stone margins being always in part, at least, near the eye.

Water in imitation of nature should be in ponds or basins of irregular shape ; but always so contrived as to display one main feature or breadth of water. A pond, however large it may be, if equally broken throughout by islands, or by projections from the shores, can have no pictorial beauty, because it is without effect, and does not form a whole. The general extent and outline of a piece of water being fixed on, the interior of the pond or lake is to be treated entirely as a lawn. If small, it will require no islands ; but if so large as to require some, they must be distributed towards the sides, so as to vary the outline and to harmonise the pond with the surrounding scenery, and yet to preserve one broad expanse of water exactly in the same manner as, in varying a lawn with shrubs and flowers, landscape-gardeners preserve one broad expanse of turf. The margin of pieces of water in imitation of nature should be a refined imita-

tion of what is seen in natural lakes. The turf should never exactly touch the water, because the green of the one and the blue of the other do not harmonise. In nature, the harmony is provided for by the water sinking lower at one time than it does at others; which leaves a dark line of soil even in the most unfavourable cases, and a narrow line of bright gravel or sand in cases best deserving imitation. As substitutes for gravel, stones may be introduced here and there; and grouped either with plants on the shore or with aquatics, and the shades and reflection of these will produce a degree of intricacy and force of effect which will complete the beauty of the scene.

In the placing of water, whether in imitation of nature or in the creation of artificial character, regard should always be had to the surrounding scenery. Water in landscape attracts the eye more powerfully than any other material, and therefore it should never be placed near a boundary, or near any object to which it is not desirable to attract attention. Water in imitation of nature should also be placed in what is in reality or in appearance the lowest part of the grounds; but, this rule does not apply to water in highly artificial forms.

WATER CALTROPS.—See TRA'PA.

WATER FLANNEL.—A very curious substance, resembling a kind of grey cloth, about a quarter of an inch thick, which is occasionally thrown by rivers upon the meadows they overflow. When examined by a microscope, this cloth will be found to consist of a great number of plants of *Conferva crispa* or *capillaris* (which has the property of entwining its curling stems together, so as to form large beds),

coated over with carbonate of lime. The stems of the *Conferva* are so closely woven together, and the interstices are so completely filled up by the starchy seeds of the plant and the chalky covering that is spread over them, as to form a sufficiently compact mass to make into articles of clothing; and it is said that waistcoats have actually been made of it.

WATERING POTS are generally formed of tinned-iron, painted; but a cheaper kind, nearly as durable, is formed of zinc, which requires no paint. Watering pots are of different sizes, and in every garden having plants in pots there ought to be three sizes: large, for the open garden; smaller, for plants in pots under the hand; and yet smaller, and with a long tube or spout, for pots on a shelf, or at a distance from the operator.

WATERING.—See WATER.

WATER-LEAF.—See HYDRO-  
PHYLLUM.

WATER LILY.—See NYMPHÆA  
and NELU'MBIUM.

WATER PLANTS are those which must have their roots and a portion of the stalk submerged in water, in contradistinction to marsh plants, which only need to have their roots constantly kept moist. Most water-plants require to be planted, or to have their seeds sown, in a layer of soil at the bottom of the cistern or aquarium in which they are grown, if they are tender plants; or in the soil at the bottom of a pond or other piece of water, in the open ground, if they are hardy. Most water-plants have their leaves and flowers always above the surface of the water; and others raise themselves above the water in the day, when their flowers are expanded, and sink below it at night, when their flowers are closed up,

so as not to be injured by the water. To enable them to do this, if the water should be deep, the stems are sometimes unnaturally elongated, and consequently they become weak and unable to flower or perfect their seeds properly. To avoid the inconvenience of this, a framework is sometimes fixed in the margin of the pond to hold the pot in which the plant grows, and to keep it at a proper depth in the water. When plants are placed in the beds of rivers, a stone should be laid on the roots to keep them in their proper place, and to prevent them from being washed away by the stream.

WATER PLANTAIN.—*Alisma*.—British marsh plants.

WATER REED.—*Arundo Donax*.—See ARUNDO.

WATER STARWORT.—*Callitriche aquatica*.

WATER SOLDIER.—*Stratites aloides*.—This curious British plant, when rooted in the mud at the bottom of ponds or other pieces of still water, sends out long runners, which rise to the surface, and there protrude roots. Then detaching themselves from the parent plant, they float about till they have blossomed and perfected their seeds; after which they sink down to the bottom, where, fixing themselves in the mud, they ripen their seeds, which sow themselves, and thus give birth to new plants, which send out fresh runners, to rise to the surface the following summer. When this plant is to be grown in pleasure-grounds or cisterns, it is only necessary to throw some plants of it into the water to which they are to be transferred, at the time they are floating about in their detached state; and at the proper season they will sink and take root in the mud at the bottom. These

plants are worth growing, on account of the curious manner in which they illustrate the beautiful economy of nature.

WATER VIOLET.—*Hottonia palustris*.—See HOTTONIA.

WATER YAM.—See OUVIRA'NDRA.

WATSONIA.—*Iridææ*.—Bulbous plants, very nearly allied to *Gladiolus*; and which require exactly the same culture as plants of that genus.—See GLADIOLUS.

WAX TREE.—*Ligustrum lucidum*.—See LIGUSTRUM.

WAYFARING TREE.—See VIBURNUM.

WEIGELA.—*Caprifoliæææ*.—Very beautiful shrubs, natives of China, introduced in 1845, allied to the Fly Honeysuckle, but much more ornamental. *W. rosea*, is a half-hardy shrub, with a profusion of beautiful rose-coloured flowers. *W. rosea alba* has pale green leaves and snow-white blossoms; it was introduced in 1863 from Japan.

WELLINGTONIA.—*Coniferaæææ*.—A great interest has been excited respecting this tree, on account of the specimen exhibited in London, in 1856 and 1857, of a portion of its bark formed into a room. The tree in its native country, California, is about three hundred feet high, and thirty-two feet in circumference at four feet from the ground. The cones are very small; and the whole tree has not at all the appearance of the ordinary pines and firs, the foliage (which is something like *Thuja*) spreading less in the lower branches than at the head of the tree.

WHEELBARROW.—A wheelbarrow is a necessary appendage to every garden; and one intended for the use of a lady ought to be made as light as possible, and the handles curved so as to require very little stooping. The wheel also

ought to be made broad, to prevent it from injuring the walk. In addition to the wheelbarrow, there may be a hand-barrow, consisting of a square basket with two long poles, so as to be carried between two persons; the use of this being to hold the haulm of Sweet Peas, the long stalks of perennial plants, clippings of Box, dead flowers, &c., &c., which are not heavy, but which take up a great deal of room. These waste articles should be carried to the reserve ground, where they should be laid in a heap to rot for manure. A great part of the beauty of a flower-garden depends on removing withered flowers and all unsightly objects as soon as is possible without injuring the plants to which they belong.

WHITE BEAM TREE. — *Pyrus A'ria*. — See PY'RUS.

WHITE CEDAR. — *Cupressus thyoides*.

WHITLA'VIA. — *Hydrophyllaceæ*. — *W. grandiflora*. — A very pretty and quite hardy annual from California, with purple tube-shaped flowers.

WHITLOW-GRASS. — See DRA'BA.

WHORTLE-BERRY. — See VAOCI'NIUM.

WILD BUGLOSS. — *Lycopsis*. — British and American annual plants, some of which are pretty, and which will grow in any common soil.

WILD LIQUORICE. — *A'brus precatarius*. — A climbing leguminous plant, with pale-purple flowers, and very beautiful red and black seeds; a native of the West Indies. The root tastes like liquorice. In England the plant should be grown in sandy peat, and it requires a stove. The seeds are used for making necklaces.

WILD OLIVE. — Several plants are known by this name; but the one most commonly so called is the

Elmágnus. Three other plants, called the Wild Olive, are the Rhús Cótinus, the common Daphne, and Nýssa sylvática, or the Tupelo Tree. Notelæa is also sometimes known by the same name.

WILD SERVICE. — *Pyrus torminalis*. — See PY'RUS.

WILD THYME. — *Thymus Segrillum*.

WILLOW. — See SA'LIX. — Besides the botanical divisions of the genus Salix, which are very numerous, Willows are divided into three or four distinct kinds; viz., the Willows which include all the trees, and generally all that have smooth shining leaves; the Osiers, which are the shrubby species with long pliant shoots; and the Sallows, which have thick, shaggy leaves. The wood of the tree kinds is white, and, being very soft and elastic, it is used for making bats for cricket-players, wooden mallets, and other purposes, where wood is required that will bear a heavy blow without splitting; the Osiers are used for basket-work; and the Withies, which are a diminutive kind of Osier, for tying up bundles. All the Willows grow best in moist marshy land; and they are all propagated by cuttings, which strike with the greatest facility.

WILLOW-HERB. — See ÉPILO'BIVM.

WILLOW-OAK. — *Quercus Phellos*. — An American Oak, with very narrow Willow-like leaves.

WINDOW-PLANT. — See OUVIRA'NDRA.

WINGED PEA. — *Lathyrus alatus*. — See LATHY'RUS.

WINTER ACONITE. — See ERA'NTHIS.

WINTER BERRY. — See PRINOS.

WINTER CHERRY. — See PHY'SALIS.

WINTER CRESS. — *Barbarea vulgaris*. — A cruciferous plant, with

handsome yellow flowers. A double-flowered variety of the common Winter Cress is called the Yellow Rocket.

WINTER GREEN.—See PYROLA.

WIREWORM.—The *ver blanc* of the French.

WISTA'RIA. — *Legumindæ*. — Climbing shrubs with drooping racemes of beautiful purple or lilac fragrant flowers, which in shape greatly resemble those of the Laburnum. The commonest kinds are *W. sinensis* and *W. frutescens*, but some other species have been lately introduced by Dr. Sieboldt from Japan. For some particulars respecting *W. sinensis*, see GLYCINE; and to these may be added that, in the summer of 1840, the plant in the London Horticultural Society's Garden had more than ninethousand racemes, containing in all about 675,000 separate flowers. *W. frutescens* is a much smaller plant, with closer racemes of flowers, which are small and of a dark purple. It is a native of North America. Both plants require a rich soil, and to be frequently watered in dry weather.

WITCH HAZEL.—See HAMAME'LIS

WITHT.—Those kinds of shrubby Willows which have long flexible shoots.

WOAD.—See ISA'TIS.

WOLF'S BANE.—See ACONIT'UM.

WOODBINE.—See CAPRIFOLIUM.

WOOD-LOUSE.—*Oniscus asellus*. —These creatures are exceedingly destructive, particularly to succulent plants and Dahlias. They belong to the Crustacea, and possess the power, when alarmed, of curling themselves up like a hedgehog, so as to resemble a little ball-like shell. They are fond of creeping into any dark places, and are frequently caught by laying small flower-pots sideways with hay in them, near the plants which have been attacked.

They will also creep into reeds, or the hollow stalks of Rhubarb, and all these traps are used to prevent their ravages on Dahlias. Very frequently small flower-pots, with dry moss stuffed in their bottoms, may be seen inverted on the stakes which support Dahlias or other plants, solely to serve as a trap for these creatures. Wood-lice were formerly supposed to be useful in medicine, but, like many remedies that were formerly popular, they are now no longer esteemed. When young they are white, and in this state they are frequently found in great numbers in the ant-hills, living with the ants in perfect harmony; they are then very small, and if examined closely, they will be found to have one segment of the body and one pair of legs less than when full grown. This circumstance, combined with the difference of colour, has led many persons to fancy the creatures found in the ant-hills to be different from common wood-lice, though, in fact, they are exactly the same.

WOODROOF.—See ASPERULA.

WOOD SAGE.—*Teucrium Scordonia*.—One of the British kinds of Germander.

WOOD'SIA. — *Filices*. — A very beautiful kind of British Fern, with very delicate leaves. One species is a native of Brazil.

WOOD SORREL.—See O'XALIS.

WOODWA'RDIA. — *Filices*. — Exotic Ferns, natives of North America and Madeira.

WORMS. — The common earth-worm (*Lumbricus terrestris*) is a most destructive creature in flower-pots. It has been ascertained that worms swallow earthy matter, and that after having deprived it of its nourishing properties, they eject the remainder in the form of what are called worm-casts, and which in-

stinct teaches them to throw out of their burrows, to the surface, that they may not be in danger of swallowing it again. To find fresh earth, the worm is continually incited to penetrate the ground in different directions; while, after each repast, it is induced to return to the surface to eject its cast; and thus ground inhabited by worms is sure to be thoroughly perforated and pulverised. In a field, this has a good effect, as it lightens the soil, and renders it pervious to the air and rain; but in a pot, every passage of the worm tears asunder the roots of the plant, which are pressed close together from the smallness of the space in which they are confined, and thus it does a serious injury. The common earthworm moves by bristles, with which the rings of its body are furnished, and which enable it to move either backwards or forwards at pleasure; and it emits a slimy substance which facilitates its passage through the earth; this slimy matter adheres to leaves and other substances, which the worm drags after it along the surface of the ground, but which, as it cannot take them through its passages, they being only large enough to admit its own body, it leaves at the mouth of the hole, where it disappears. When a worm is cut in two it is generally believed that both parts will become perfect worms; but, in fact, only the part which contains the head possesses the power of throwing out a new tail; and the part containing the tail cannot form a new head. Worms are produced from eggs; and they are always most abundant in rich humid soil. When the casts are seen on the surface of the earth in a pot, no time should be lost in turning out the earth on the hand, and picking out the worms. The

roots torn asunder should then be thrown away, and the plant re-potted in fresh earth.

WORMWOOD.—See ARTEMISIA.

WOUNDWORT.—*Anthyllis vulneraria*.—A British plant, only found in chalky soils.

WRACK GRASS.—See ZOSTERA.

WRIGHTIA.—*Apocynæ*.—Hot-house trees, natives of the East Indies, which were formerly considered to belong to the genus Nerium. One of the species, *W. coccinea*, has splendid flowers; it should be grown in sand and peat. The other kinds have white flowers.

XANTHORRHIZA.—*Ranunculaceæ*.—Yellow-root.—An American shrub, with very neat dark-purple flowers, which are produced early in spring, and handsome leaves. It will grow in any common garden soil, and it is increased by suckers from the roots.

XANTHOXYLUM.—*Rutaceæ*, or *Terebinthaceæ*.—The Toothache-tree.—Trees and shrubs, most of which require a stove in England, and should be grown in a sandy loam. *X. fraxineum*, the Prickly Ash, is an American shrub, the bark of which is aromatic, and is considered very efficacious in rheumatism. It is hardy in British gardens, and will grow in common soil. *X. nitidum*, which has strong thorns on the mid-ribs of its leaves, is used as a hedge plant in China.

XERANTHEMUM.—*Compositæ*.—Purple Everlasting Flower.—Very beautiful annual flowers, which may either be sown in the open ground in April, or raised on a hot-bed, and planted out in May; the only advantage by the latter plan being that the plants flower earlier. They are very beautiful, and well-deserving of a place in every flower-garden.

**XEROPHYLLUM.**—*Melanthaceæ*.

—Singular plants with long, narrow leaves, and spikes of pretty white flowers. The species are natives of North America, and quite hardy in British gardens, where they should be grown in peat and loam. *X. gramineum* is a peculiarly desirable species, from its loose and elegant spikes of small star-like white flowers.

**XIMENE'SIA.**—*Compositæ*.—Annual and perennial plants, natives of Mexico, with yellow flowers, which will grow in any common garden soil. There are two biennial species, which should be kept in a frame during winter, and transplanted to the open border in spring.

**XYLOBIUM.**—*Orchidaceæ*.—Brazilian parasites, growing on trees, and requiring a stove in England.—For their culture, see ORCHIDEOUS EPIPHYTES.

**XYLOPHYLLA.**—*Euphorbiaceæ*.—Very curious shrubs, which produce their flowers on the margins of their leaves. They are mostly natives of Jamaica, and require a stove in England. The flowers are generally greenish, but those of *X. montana*, the Sea-Side Laurel, are of a bright yellow. They are generally grown in sandy peat.

**XYLOSTEUM.**—The Fly Honey-suckle.—See LONI'CERA.

**YAM.**—*Dioscorea*.—Herbaceous plants, natives of the tropics, generally with greenish-white flowers, the tuberous roots of which are eaten as a substitute for Potatoes. The stems of most of the species are weak, and cannot support themselves.

**YARROW.**—*Achillea Millefolium*.

**YELLOW RATTLE.**—*Rhinanthus major*.—A British plant, which is

very ornamental, from its yellow labiate flowers having each a bright dark eye.

**YELLOW ROOT.**—See XANTHORRIZA.

**YELLOW SULTAN.**—See AMBERBO'A.

**YELLOW VETCHLING.**—*Lathyrus Aphaca*.—A British climbing Vetch, with yellow flowers, only found in sandy soils.

**YELLOW WORT.**—*Chlora perfoliata*.—A British annual, with glaucous leaves and yellow flowers. It is always found in a wild state in chalky soils, and it will seldom grow in gardens unless the soil be chalky, or of a calcareous loam.

**YEW TREE.**—See TA'XUS.

**YUCCA.**—*Liliaceæ*, or *Tulipaceæ*.—Adam's Needle.—Evergreen plants with leaves like the Aloe, and sometimes a stem, or rather trunk, like a Palm-tree. Some of the species have been known to have a trunk twenty feet high, sending up, every year, five or six immense flower-stems, each six or eight feet high. In ordinary cases, however, the trunk is rarely more than two or three feet high, though the flower-



FIG. 60.—YUCCA DRACO'NIS.

stem frequently measures five or six feet. The flowers are bell-shaped, and generally white. The



commonest kinds in British gardens are *Y. gloriosa*, *Y. dracœnis*, and *Y. flamentosa*. All these are natives of North America, and are quite hardy in Britain; they have all white flowers, and they are Aloe-like shrubs, presenting the general appearance shown in fig. 60, which was taken from a plant of *Y. dracœnis*. *Y. albifolia*, on the contrary, always forms a palm-like tree, from twelve to twenty feet high; it is rather more tender, and its flowers are purplish on the outside and white within. All the kinds prefer a deep sandy soil, and are propagated by suckers. They will all grow close to the sea-side, and are therefore very suitable for the grounds of marine villas. They also produce a good effect in vases, on the terrace garden of an Italian villa, as they form an excellent substitute for the Agaves, so common in Italy, but which are too tender for the open air in England.

**Z.**—Several botanical names beginning with X are occasionally spelt with Z.

**ZAMIA.**—*Cycadaceæ*.—Very curious Palm-like plants, with short tubercle-like stems, and long frond-like leaves, which are stiff and leathery, and stand erect round the stem. The remains of the foot-stalks of the old leaves form a scaly kind of bark to the stem. The flowers are dioecious; and the fruit is an oblong, erect, scaly nut, which is hard and bony. The species are mostly natives of the Cape of Good Hope, but some are found in the West Indies; and one, *Z. spiralis*, in New South Wales. The plants should be grown in very sandy loam, and they are generally propagated by off-sets. They are very tenacious of life, and when the centre of the stem is rot-

ten, the scale, if planted, will generally send up leaves, and become a separate plant.

**ZANTHOXYLUM.**—See **XANTHOXYLUM**.

**ZAUSCHNE'RIA.**—*Onagræaceæ*.—A very singular plant, having bright scarlet flowers, which bear a considerable resemblance to those of a Fuchsia. The plant is a hardy perennial, a native of California, whence it was introduced by Mr. Hartweg in 1847.

**ZE'A.**—*Gramineæ*.—The Indian Corn.—An annual plant, a native of America. The plant is very ornamental, and the male blossoms are particularly elegant. It should be grown in rich mould, and should be sown very early in spring; or it may be raised on a hotbed, and transplanted into the open ground in May.

**ZEBRA PLANT.**—*Calathea zebrina*.—Cane-like plants, with red and yellow, purple and yellow, or white flowers; natives of Brazil, which require a stove in England, and which should be grown in sandy peat.

**ZEDOARY.**—*Curcuma Zedoaria*.

**ZENO'BIA.**—*Ericaceæ*.—The new name given by the late Professor Don to a species of *Andrœmeda*.

**ZEPHYRANTHES.**—*Amaryllidaceæ*.—Cape bulbs, with very elegant flowers. Nearly all of the species are quite hardy, and only require planting like the Crocus, in a warm border, in a somewhat sandy soil, without wanting any further care, except occasionally taking them up every third or fourth year, to remove the offsets.

**Zi'CHYA.**—*Leguminosæ*.—Baron Hügel's new name for some of the kinds of *KENNEDYA*.

**Zi'NGIBER.**—*Scitamineæ*.—The Ginger.—Stove plants, with small flowers, which are produced in a

very curious spathe, and a fleshy rhizoma, or under-ground root. One of the species is the common Ginger.

ZINNIA.—*Compositæ*.—Beautiful annual flowers, natives of Mexico, which should be raised on a hot-bed, and planted out in May. See HALF-HARDY ANNUALS, pp. 19, 20.

ZIZYPHUS.—*Rhamnaceæ*.—Half-hardy shrubs, some of which are frequently grown in British gardens.—See JUJUBE TREE, and PALIUREUS.

ZOSTERA.—*Fluviales*.—Wrack-grass, or Grass-wrack.—A marine plant, common in salt-water ditches.

The leaves, when dry, are tough and flexible; and they have been lately used for filling beds and cushions.

ZYGOPETALUM.—*Orchidaceæ*.—Showy orchideous plants, which in their native state are found growing on the branches of trees, and which should be grown on wood in the stove.—For their culture, see ORCHIDEOUS EPIPHYTES.

ZYGOPHYLLUM.—*Rutaceæ*, or *Zygophylleæ*.—The Bean Caper.—Greenhouse and hardy perennials, which will grow in any common garden soil, that is somewhat loamy. They are propagated by cuttings.

## Monthly Calendar

OF

### WORK TO BE DONE IN THE FLOWER-GARDEN.

---

#### JANUARY.

THE gravel walks should be occasionally rolled, particularly after slight rain ; and after a thaw, heavy rain, or melting snow, care should be taken to open the drains, and keep them clear of rubbish and withered leaves, which are very apt to choke them up. Snow should never be suffered to lie on the walks of small gardens, as it is apt to render them soft ; and gutters or drains should be provided on each side, particularly on sloping ground, to prevent the heavy rains from ploughing up the walks, and washing away the gravel. If the season should be wet and rather mild, weeds will begin to appear on the gravel walks, when they should be instantly destroyed either by hand-picking, or watering with a strong solution of salt and water. If the weather should be mild and dry, air may be given to the greenhouse ; and to half-hardy plants kept in pits, or planted in the open ground and covered during winter. The latter kind of plants are very apt to damp off, if kept too close in mild weather. Honeysuckles, Clematisses, and other deciduous climbing plants, may be pruned if the weather be open ; and the dead wood should be cut out of flowering trees and shrubs. Snails and slugs may be destroyed in this month, as they will begin to move if the weather be mild ; and the easiest way of killing them is to throw them into a cistern or other very large vessel of water, where they will be soon drowned ; but if the vessel is small, they will creep out.

#### FEBRUARY.

IN this month the borders are dug over and manured ; the best general manure being the remains of an old hotbed, or of celery trenches from the kitchen garden. Beds are prepared for Anemones and Ranunculuses, and the tubers planted. Hotbeds are prepared for the tender annuals, and the climbing kinds should be sown ; of these the most beautiful are *Ipomœa rubro-cœrulea*, the beautiful blue *Ipomœa* ; *Tropæolum peregrinum*, the Canary-bird flower ; *Rhodochiton volubile*, sometimes called

*Lophospermum Rhodochiton* ; *Lophospermum scandens*, and *erubescens* ; *Cobaea scandens* ; and *Maurandya Barclayana*. *Eccremocarpus* or *Calam-pelis scabra* may also be raised from seed, and will flower the first year, but it will live two or three years, and sometimes longer. Most or all of the others will also live more than one year, if protected from frost. Some of the most showy hardy annuals should be sown in pots for early flowering. Towards the end of the month, shift Carnations and Ficoetes into the pots in which they are intended to bloom. Greenhouse plants are now generally shifted. The gravel walks require the same attention as in January, the snails and slugs should be killed, and the eggs of insects looked for and destroyed. The deciduous Roses may be pruned and manured ; and the old plants may be taken up and replanted, to prevent them from producing too much wood. Composts are also now prepared in the reserve ground. The turf is swept, and the whole garden put in order for spring.

### MARCH.

DAHLIAS are potted, and placed in a cold frame or pit. Stocks and China Asters are sown on a slight hotbed. *Lobelia gracilis* and *L. bicolor*, *Phlox Drummöndii*, *Gaillardia bicolor*, *Thunbergia alata*, *Anagallis Monelli* and *Phillipsii*, the Petunias, and other half-hardy annuals, should also be sown on a slight hotbed at the beginning of this month, and *Primula sinensis* for autumn flowering, if not sown with the climbing annuals in February ; and Balsams, Cock'scombs, and other tender annuals, may be sown on a warm hotbed. The gravel walks are now raked over, and fresh gravel added ; and the edges are trimmed with a verge-cutter where the walls are bordered with grass. The turf is mowed ; and any places that may be burnt up or worn bare are repaired by patches of fresh turf. Dahlia seeds are sown on hotbeds. Pots of Hyacinths and Tulips, that were planted in October, are plunged into the borders ; and the scarlet Lobelias are potted, and placed in a gentle hotbed. The tree Pæony should be covered at night during this month and the next, to protect it from spring frosts.

### APRIL.

THE gravel walks are rolled, and the box edgings trimmed. The borders are forked over and raked for sowing the seeds of annuals, which is best done in this month, though it is sometimes deferred till May. The evergreen Honeysuckles and Jasmines, and the evergreen Roses, are now pruned and trained. Cuttings of Verbenas, Salvias, Petunias, Mimulures, Fuchsias, Calceolarias, and Heartseases, may be planted on a slight hotbed, to make handsome plants for turning out into the open borders in June. The seeds of Hollyhocks, Brompton Stocks, Wall-flowers, and other biennials, may be sown, and the Californian annuals sown in autumn may be removed to beds to receive them ; and many of the more hardy bedding plants are now planted out.

## MAY.

IN this month a second sowing is made of the hardy annuals for autumn flowering ; and the half-hardy annuals are transplanted into the open ground, sheltering them for a day or two by turning a flower-pot over them. There is great advantage in getting out these plants as early as possible. The greenhouse plants standing in the open ground, which were protected during winter, are now uncovered. The *Lobelias*, *Verbenas*, *Salvias*, *Petunias*, and other half-hardy plants that were in pots, are now planted out ; the hardy annuals sown in March and April are thinned out, and transplanted ; and the stems of the *Phloxes* and other coarse-growing herbaceous plants are cut in, taking away about a third part ; as, when they are suffered to have too much herbage, it weakens the flowers. The gravel walks must now be carefully attended to, sweeping and rolling them frequently, and the turf must be mowed once a-week. Pots of *Ixias* and other summer-flowering bulbs are now plunged in the borders ; and also *Gladioluses*, which are now deservedly becoming much more cultivated than formerly.

## JUNE.

THE *Dahlias* are planted out in this month in beds, the plants being four or five feet apart every way. The cuttings of greenhouse plants, which were intended for planting out, are now removed to the open ground ; and the *Pelargoniums*, *Heliotropes*, and other greenhouse plants, and the more tender annuals and bedding plants are now planted out. The *Aphides* now begin to appear on the *Rose* trees, and they should be destroyed by dipping the tips of the shoots into clear water, and shaking them gently in the water. All the insects may be thus removed without disfiguring the tree. A brown grub (the larva of a kind of saw-fly) now appears in the *Rose* buds, and it should be removed by hand-picking. Many good flower-gardeners prefer cutting their box-edgings in this month, just when the plants have nearly completed their annual shoots, as they afterwards push out a few leaves ; and thus the edging does not show the mark of the knife, which it does when cut later.

## JULY.

THE withered *Roses* and other flowers should be cut off as soon as they fade, as nothing disfigures a flower-garden more than dead flowers. Some of the herbaceous plants that have done flowering should be cut down, and the pots of summer bulbs should be removed to give place to *Pelargoniums*, German and Russian Stocks, &c., which will continue in flower till October. Cuttings of *Verbenas* are planted under hand-glasses for potting in September, for plants to supply cuttings for propagation, so as to have young stocks well advanced before winter. *Calceolarias* are sown in pans, which are kept in a cool pit. The annual plants from the May sowing are now thinned out. Cuttings of greenhouse plants are also put in the open border under hand-glasses. *Pelargoniums* that are nearly

past flowering should be exposed to sun and air previously to their being cut back ; and previously to cutting, the soil in the pots should be kept dry ; and when the wounds are dried and commencing to heal over, give the plants a little water, and keep them warmer than before till they break into fresh shoots. Pyramids and pillars of Roses should now be trained carefully, and tied in so as to present a mass of bloom. The turf should be mown every week, and the broad-leaved grasses, and other wild plants, such as Daisies, should be removed, where their appearance is objected to.

#### AUGUST.

THE flower-borders must be frequently weeded during this month, great care being taken to prevent the weeds from ripening their seed. The vacant places made by plants that have flowered, and have had their stalks cut down, may be now generally supplied by greenhouse plants, such as *Mesembryanthemums*, &c. ; or by pots of *Thunbergia alata*, *Schizanthus retusus*, hybrid *Calceolarias*, &c., which have been prepared purposely for filling up blanks. A number of German Stocks and Asters, which have been provided in pots, may now be planted among the Pinks which have done flowering, and they will produce an excellent effect. The Evergreens in the shrubberies may be pruned so as to prevent them from touching each other ; but large branches should not be cut off ; such should be prevented by timely pruning when in a young state ; but if this has been neglected, and it becomes absolutely necessary that large branches must be shortened in considerably, it should not be done all at once, but by degrees ; and those seeds that are ripe may be gathered. The bulbs of Crown Imperials and Lilies are planted. The gravel walks should be frequently rolled and swept, and the turf regularly mown every week to render the grass fine. The dead flowers should also be constantly taken off as fast as they appear.

#### SEPTEMBER.

THE operations of August are continued, with the addition of beginning to take up the greenhouse plants towards the close of the month. Some are left in the ground all the winter, coverings being made for them of various kinds. The seeds of the Californian annuals are sown on some waste ground to stand the winter, whence they may be removed in spring to beds properly prepared for them. The half-hardy plants which are still in flower are lightly covered with furze branches, or worsted netting at night, when frost is apprehended ; sticks being placed to support the netting over the plants. Some gardeners do not cut their box-edgings till this month, when they clip them with shears ; but this is a bad practice, as the leaves which have been injured by the shears retain the marks till the following May ; and weak plants are frequently killed, or the lower part of their stalks rendered bare.

#### OCTOBER.

BULBS of Hyacinths, &c., are planted in pots. Anemones are also

planted in beds. The dead leaves of trees and shrubs are swept up and laid in heaps to decay for vegetable mould. The Dahlias which have been killed by the frost have their tubers taken up and laid to dry; after which they are packed up in boxes, or laid in saw-dust or malt-dust, to preserve them from the frost. The remainder of the greenhouse plants are taken in; or if any are left out, they are covered carefully at night from the frost. The gravel walks are swept and rolled occasionally, and the gutters and drains should be all opened and cleared. The turf should be swept, but it need not now be mowed oftener than once a fortnight or three weeks.


#### NOVEMBER.

THE Dahlias, if not all killed by frost the preceding month, should now have their stems cut down to the ground previously to taking up the roots; and the greenhouse plants being all removed, the ground should be dug over, having previously received a good dressing of vegetable mould and rotten dung. The half-hardy plants are now closely covered up with furze, or baskets of wicker-work; over which mats are thrown in severe frosts, and straw, dead leaves, or moss are put over the roots of those plants which are only a little tender. In the greenhouse the principal points to be attended to are to keep the plants as dry as possible, in order to give them a season of rest, and to remove all the decayed leaves as soon as they appear. Air should also be admitted freely, whenever the weather is sufficiently dry. It must be observed, that exotic plants are as frequently killed by damp as cold; no means therefore should be omitted of keeping the air of a greenhouse as dry as possible during winter. The turf is mowed once during this month, if the weather should be open; and the gravel walks seldom require any attention.

#### DECEMBER.

If the weather should be open, the flower-beds planted in summer with Stocks, Verbenas, &c., should be dug two spades deep, and dressed with strong stable manure. In the greenhouse and pits, it may be observed, that thick coverings of mats save a good deal of fire-heat; and that care should be taken to ventilate, by the admission of dry air, wherever it is practicable.

If the grass should continue growing, the turf may be mown once during this month. The dead leaves should be kept in a heap, and frequently turned over, watering if the weather should be dry, to hasten their decay; if thus treated, and sifted, they will make fine vegetable mould for the ensuing summer. The refuse wood from trees, and dead shrubs, &c., should be burnt for charcoal whenever there is an opportunity, and the charcoal kept in a dry place for use. The pots which are not in use should be washed and wiped dry, and then laid one in another on their sides, but they should never be put one within another when they stand erect, as the weight is almost sure to break the lower pot.





## APPENDIX.

SINCE publishing the first edition of this Work, it has been suggested to me that it might be very greatly improved by the addition of some plans of flower-gardens, accompanied by lists of plants of various kinds. Acting upon this suggestion, I have added to my Work this Appendix, in which I shall give four plans of flower-gardens, designed by Mr. Loudon himself, and published by him in the "Gardener's Magazine" shortly before his death, with lists of plants for each, arranged by practical gardeners. I shall then give a few examples of rock-work, with lists of rock-plants, and plants for an Aquarium; and I shall add to these a few other lists of plants adapted for different purposes.

### FLOWER-GARDENS.

*Fig. 61* is the working-plan of a geometrical flower-garden, which is intended to have gravel-walks between the beds. The beds themselves are all numbered, for the convenience of planting, and they are drawn to a scale which is given below the plan. The following list, will keep the beds full of flowers from June till October:—

- |   |  |
|---|--|
| 1. Verbena, Purple King.  | over the sides; and Oenothera macrocarpa, pale yellow, in the bed. |
| 2. Lobelia lutea, yellow.   | 14. Petunia, Laura, purple.  |
| 3. Salvia patens, with S. chamædryoides, dark blue, round the sides; and Sanvitalia procumbens, a dwarf annual with yellow flowers, in the bottom, to cover the ground. | 15. Verbena, Géant des Batailles, crimson.                         |
| 4. Bouvardia triphylla, scarlet.  | 16. Heliotropium peruvianum, violet.                               |
| 5. Tournefortia heliotropioides, pale blue.   | 17. Pelargonium, Helen Lindsay, rose scarlet.                      |
| 6. Verbena, Le Grand Boule de Neige, white.   | 18. Pelargonium, Tom Thumb, brilliant scarlet.                     |
| 7. Campanula carpatica, dark blue.  | 19. Calceolaria rugosa, yellow.                                    |
| 8. Verbena, Lady Middleton, pale lilac.   | 20. Lobelia speciosa, dark blue.                                   |
| 9. Same as No. 3.   | 21. Nierembergia filicaulis, French white.                         |
| 10. Pentstemon gentianoides coccineus, scarlet.   | 22. Verbena Tweediana superba, dark crimson.                       |
| 11. Verbena, Rival King, purple.  | 23. Heliotropium Voltaireanum, dark purple.                        |
| 12. Lotus jacobæus luteus, yellow.  | 24. Crucianella stylosa, pale rose.                                |
| 13. Diplacus glutinosus, orange yellow, in the vase, with Lobelia Erinus, blue, to droop  | 25. Pelargonium Manglesii, variegated white.                       |
|   | 26. Pelargonium zonale, Frogmore, scarlet.                         |

27. *Calceolària*, Cloth of Gold, yellow.
28. *Anagallis cœrùlea grandiflora*, dark blue.
29. *Nierembèrgia calycina*, white.
30. *Verbena*, General Simpson, crimson.
31. *Petùnia*, Princess Helena, blush.
32. *Verbena*, Ne plus ultra, pale pink.
33. *Pelargonium*, variegated ivy-leaved white.
34. *Agératum mexicanum*, pale blue, to be pegged down.
35. *Petùnia*, Laura, purple.
36. *Anagallis Monélli major*, dark blue.
37. *Lobelia*, Speciosa Paxtoni major, pale blue.
38. *Pelargonium*, Punch, scarlet.
39. *Agératum grandiflorum*, pale blue.
40. *Petùnia*, Laura, purple.
41. *Anagallis Phillipsii*, dark blue.
42. *Lobelia*, Speciosa Paxtoni major, pale blue.
43. *Pelargonium*, the Shrubland, scarlet.
44. *Pelargonium*, Comte de Morny, rose scarlet.
45. *Heliotropium*, Reine des Héliotropes, violet.
46. *Verbena teucrioides*, white.
47. *Petùnia*, purple.
48. *Nierembèrgia intermedia*, purple.
49. *Sanvitalia procumbens*, yellow.
50. *Sálvia pátens*, &c., the same as No. 3.
51. *Campánula Barrelièri*, pale blue.
52. *Verbena*, Ne plus ultra, pale pink.
53. *Pentstemon*, Lord Clyde, scarlet.
54. *Verbena*, Purple King.




FIG. 61. — FLOWER-GARDEN ON GRAVEL.

- |   |   |
|---|---|
| 55. Calceolària, Cloth of Gold, yellow. | 58. Verbena teucroides, white and pink. |
| 56. Same as No. 3.                      | 59. Bouvardia splendens, scarlet.       |
| 57. Campánula gargánica, blue.          | 60. Same as No. 13.                     |

Should these beds be thought too small, Nos. 1 and 2, 6 and 7, &c., may be joined together, so as to reduce the number of beds to thirty-eight, which may be planted according to the following lists, furnished by Mr. Ayres, according as the garden may be wished to display its greatest beauty in spring, summer, or autumn. It will be observed that the first list consists chiefly of bulbs and low-growing herbaceous plants, which flower from January to the middle of May; the list for summer consists of hardy annuals and biennials, which should be brought forward ready to transplant the moment the bulbs have done flowering and are removed; and the list for autumn consists chiefly of greenhouse plants, such as Pelargoniums, Verbenas, Lobelias, &c. Standard Rose-trees may be planted in the central beds.

### I. List for Spring.

- |  |  |
|--|--|
| 1. Blue Crocuses. Pale lilac.                      | 20. Anemones. Pale blue.                           |
| 2. Anemones. Pale blue.                            | 21. Hyacintha. Dark purple.                        |
| 3. Anemones. White.                                | 22. Alyssum saxatile. Yellow.                      |
| 4. Alyssum saxatile. Yellow.                       | 23. Crocuses. Pale lilac.                          |
| 5. Hyacinths. Dark purple.                         | 24. Anemones. White.                               |
| 6. Ranunculuses, Turban. Scarlet.                  | 25. Ranunculuses, Turban. Scarlet.                 |
| 7. Crocuses. Yellow.                               | 26. Crocuses. Yellow.                              |
| 8. Heartsease. Variegated.                         | 27. Heartsease. Variegated.                        |
| 9. Tulips, mixed, common. Various colours.         | 28. Tulips, mixed, common. Red, yellow, and white. |
| 10. Tulips, Royal Standard. Various colours.       | 29. Tulips, Gold Standard. Red and yellow.         |
| 11. Hyacinths. White.                              | 30. Hyacinths. White.                              |
| 12. Tulips. Yellow.                                | 31. Tulips. Yellow.                                |
| 13. Hyacinths. Blue.                               | 32. Hyacinths. Blue.                               |
| 14. Tulips, Duc Van Thol. Scarlet, and Yellow.     | 33. Hyacinths. Red.                                |
| 15. Hyacinths. Red.                                | 34. Tulips, Duc Van Thol. Scarlet and yellow.      |
| 16. Crocuses. Purple.                              | 35. Tulips, mixed, common. Red, yellow, and white. |
| 17. Heartsease. Variegated.                        | 36. Heartsease. Variegated.                        |
| 18. Tulips, mixed, common. Red, yellow, and white. | 37. Crocuses. Purple.                              |
| 19. Ranunculuses, Turban. White.                   | 38. Ranunculuses, Turban. White.                   |

### II. List for Summer.

- |                                     |  |
|-------------------------------------|--|
| 1. Clintònia pulchella. Blue.       | 7. Leptosiphon densiflorus. Pale purple. |
| 2. Clàrkia pulchella alba. White.   | 8. Godetia Lindleyana. Rose and white.   |
| 3. Godetia bifrons. Pink and white. | 9. Erýsimum Perowskianum. Orange.        |
| 4. Yellow Wallflower. Yellow.       | 10. Nolana atriplicifolia. Blue.         |
| 5. Nemòphila insignis. Bright blue. |  |
| 6. Nemòphila atomaria. White.       |  |

- |   |  |
|---|--|
| 11. <i>Collinsia</i> bicolor. Lilac and white.      | 28. <i>Leptosiphon androsæus</i> . Lilac.              |
| 12. <i>Gilia</i> tricolor alba. White.              | 27. <i>Godetia</i> rosea alba. Rose and white.         |
| 13. <i>Gilia</i> tricolor. White and purple.        | 28. <i>Erysimum</i> Perowskianum. Orange.              |
| 14. <i>Nemophila insignis</i> . Blue.               | 29. <i>Nemophila insignis grandiflora</i> . Pale blue. |
| 15. <i>Clarkia pulchella</i> . Rose.                | 30. <i>Collinsia</i> bicolor. Lilac and white.         |
| 16. <i>Collinsia grandiflora</i> . Purple and blue. | 31. <i>Gilia</i> tricolor alba. White.                 |
| 17. <i>Schizopetalon Walkeri</i> . White.           | 32. <i>Gilia</i> tricolor. White and purple.           |
| 18. <i>Clarkia elegans</i> . Lilac.                 | 33. <i>Clarkia pulchella</i> . Rose.                   |
| 19. <i>Godetia rubicunda</i> . Purple.              | 34. <i>Nolana prostrata</i> . Blue.                    |
| 20. <i>Clarkia pulchella alba</i> . White.          | 35. <i>Iberis umbellatus</i> . Purple.                 |
| 21. <i>Nemophila insignis</i> . Bright blue.        | 36. <i>Schizopetalon Walkeri</i> . White.              |
| 22. Yellow Wallflower. Yellow.                      | 37. <i>Collinsia grandiflora</i> . Purple.             |
| 23. <i>Clintonia pulchella</i> . Blue.              | 38. <i>Godetia Romanzovii</i> . Purple.                |
| 24. <i>Godetia rubicunda</i> . Purple.              |  |
| 25. <i>Nemophila atomaria</i> . White.              |  |

### III. List for Autumn.

- |  |  |
|--|--|
| 1. Verbena, The Colonel. Scarlet.              | 20. Verbena, Ne plus ultra. Pale rose.             |
| 2. Crucianella stylösa. Flesh colour.          | 21. Anagallis Monelli. Blue.                       |
| 3. Verbena teucrioides carnea. Flesh colour.   | 22. Pelargonium, Manglesii. Variegated.            |
| 4. Pelargonium, Alma. Variegated.              | 23. Verbena ignea. Scarlet.                        |
| 5. Lobelia speciosa. Crystal Palace var. Blue. | 24. Verbena teucrioides carnea. Pale flesh colour. |
| 6. Lobelia, Paxtoni major. Pale blue.          | 25. Campanula carpatica. Blue.                     |
| 7. Verbena, Purple King.                       | 26. Verbena, André. Pale purple.                   |
| 8. Pelargonium, Tom Thumb. Scarlet.            | 27. Pelargonium, Scarlet Perfection. Scarlet.      |
| 9. Calceolaria rugosa. Yellow.                 | 28. Calceolaria integrifolia. Yellow.              |
| 10. Lobelia axillaris. Pale blue.              | 29. Anagallis Phillipsii. Blue.                    |
| 11. Petunia phœnicea. Purple.                  | 30. Petunia, Lady Peel. Purple.                    |
| 12. Verbena, Ne plus ultra. Rose.              | 31. Verbena, Lord Raglan. Rose.                    |
| 13. Verbena, White Lady. White.                | 32. Verbena, Mont Blanc. White.                    |
| 14. Petunia hybrida. Purple.                   | 33. Senecio elegans pleno. Purple.                 |
| 15. Heliotropium corymbosum. Pale purple.      | 34. Heliotropium peruvianum. Pale purple.          |
| 16. Nierembergia filicaulis. Lilac.            | 35. Cnothera macrocarpa. Yellow.                   |
| 17. Verbena, Fire Ball. Scarlet.               | 36. Verbena, Lady Victoria Scott. Scarlet.         |
| 18. Cnothera Drummondii. Yellow.               | 37. Nierembergia intermedia. Purple.               |
| 19. Verbena, André. Pale purple.               | 38. Tournefortia heliotropioides. Pale purple.     |

The plan for a flower-garden, fig. 62, occupies the same space as the design, fig. 61; and both may be surrounded by a low wire fence, only 20 inches high, for the sake of excluding rabbits. The beds are supposed to be on turf, and there is a basin with a fountain in the centre compartment (a 30) and a vase on a pedestal in the centres of the two others (29). The following lists show various modes of planting this garden:—

*Lists of Plants for the Flower Garden, fig. 62, by Mr. Ayres.*

*I. List for Spring.*

1. Hepática triloba, double. Dark-blue.
2. A'rabis álvida. White.
3. Crocuses, yellow Dutch. Yellow.
4. Hepática triloba, double. Dark-red.
5. Hepática triloba, double. White.
6. Crocuses, Cloth of Gold. Yellow and Brown.
7. A'rabis rósea. Red.
8. Omphalòdes vérna. Blue.
9. Anemòne nemoròsa. White.
10. Prímula vulgàris, double. Lilac.
11. Prímula aurícula, border varieties. Various colours.
12. Anemonea, double. Various colours.
13. Ranunculusea. Various colours.
14. Hyacinths. Various colours.
15. Hyacinths. Various colours.




FIG. 62.—FLOWER-GARDEN ON GRASS.

- |  |  |
|--|--|
| 16. <i>Ranunculuses</i> , double. Various colours.               | 22. <i>Phlox subulata</i> . Red.                 |
| 17. <i>Anemones</i> , double. Various colours.                   | 23. <i>Arabis alpina</i> . White.                |
| 18. <i>Primula auricula</i> , border varieties. Various colours. | 24. <i>Primula vulgaris</i> , double. White.     |
| 19. <i>Pulmonaria virginica</i> . Blue and purple.               | 25. <i>Hepatica triloba</i> , double. Dark red.  |
| 20. <i>Dodecatheon Meadia</i> . Lilac.                           | 26. <i>Crocuses</i> , yellow Dutch. Yellow.      |
| 21. <i>Omphalodes verna</i> . Blue.                              | 27. <i>Primula vulgaris</i> , double. Red.       |
|  | 28. <i>Hepatica triloba</i> , double. Dark blue. |

## II. List of Annuals for Summer.

- |  |   |
|--|---|
| 1. <i>Nemophila atomaria</i> . White.                | 15. <i>Lupinus nanus</i> . Purple and blue.     |
| 2. <i>Collinsia grandiflora</i> . Purple.            | 16. <i>ibëris coronaria</i> . White.            |
| 3. <i>Gilia tricolor</i> . White.                    | 17. <i>ibëris umbellata</i> . Purple.           |
| 4. <i>Nemophila insignis</i> . Blue.                 | 18. <i>Clintonia pulchella</i> . Blue.          |
| 5. <i>Nolana atriplicifolia</i> . Blue.              | 19. <i>Clarkia elegans</i> . Lilac.             |
| 6. <i>Leptosiphon androsaceus</i> . Lilac and white. | 20. <i>Godetia rosea alba</i> . Rose and white. |
| 7. <i>Nolana prostrata</i> . Violet.                 | 21. <i>Erysimum Perowskianum</i> . Orange.      |
| 8. <i>Clintonia pulchella</i> . Blue.                | 22. <i>Leptosiphon densiflorus</i> . Purple.    |
| 9. <i>Collinsia bicolor</i> . Lilac and white.       | 23. <i>Nolana prostrata</i> . Violet.           |
| 10. <i>Clarkia pulchella</i> . Rose.                 | 24. <i>Nemophila phacelioides</i> . Lilac.      |
| 11. <i>Eschscholtzia crœcea</i> . Orange.            | 25. <i>Nemophila insignis</i> . Blue.           |
| 12. <i>Godetia bifrons</i> . Purple.                 | 26. <i>Gilia tricolor alba</i> . White.         |
| 13. <i>Clarkia pulchella alba</i> . White.           | 27. <i>Collinsia grandiflora</i> . Purple.      |
| 14. <i>Eutoca viscida</i> . Blue.                    | 28. <i>Nemophila atomaria</i> . White.          |

## List of half-hardy Plants for Autumn.

- |   |   |
|---|---|
| 1. <i>Verbena ignea</i> . Dark scarlet.         | 16. <i>Senecio elegans pleno</i> . Purple.        |
| 2. <i>Pelargonium</i> , ivy-leaved. Variegated. | 17. <i>Calceolaria integrifolia</i> . Yellow.     |
| 3. <i>Verbena Hendersoni</i> . Purple.          | 18. <i>Lotus jacobæus</i> . Black.                |
| 4. <i>Lobelia ramosa</i> . Blue.                | 19. <i>Nierembergia gracilis</i> . Lilac.         |
| 5. <i>Oenothera macrocarpa</i> . Yellow.        | 20. <i>Verbena teucrioides</i> . White.           |
| 6. <i>Verbena purpurea</i> . Purple.            | 21. <i>Verbena Melindres latifolia</i> . Scarlet. |
| 7. <i>Pelargonium Manglesi</i> . Varieties.     | 22. <i>Petunia nictaginiflora</i> . White.        |
| 8. <i>Verbena</i> , Lord Leigh. Scarlet.        | 23. <i>Verbena Purple King</i> . Purple.          |
| 9. <i>Verbena</i> , White Lady. White.          | 24. <i>Oenothera Drummondii</i> . Yellow.         |
| 10. <i>Verbena Drummondii</i> . Lilac.          | 25. <i>Anagallis cœrulea grandiflora</i> . Blue.  |
| 11. <i>Lotus jacobæus</i> . Blackish.           | 26. <i>Nierembergia intermedia</i> . Pale yellow. |
| 12. <i>Calceolaria rugosa</i> . Yellow.         | 27. <i>Pelargonium</i> , variegated. White.       |
| 13. <i>Petunia hybrida</i> . Purple.            | 28. <i>Verbena Melindres</i> . Scarlet.           |
| 14. <i>Pelargonium</i> . Frogmore scarlet.      |   |
| 15. <i>Pelargonium</i> , Punch. Scarlet.        |   |

*List of Plants for planting the Flower-Garden, fig. 62. By Mr. Pringle.*

- |  |  |
|--|--|
| 1. Snowdrops as an edging; the body of the bed of Moss Roses, dwarf. | 16. <i>Collinsia grandiflora</i> . Dahlias.                      |
| 2. Hepática. Petunias, var.  | 17. <i>Gilia tricolor</i> . Dahlias.                             |
| 3. Hepática. <i>Heliotropium peruvianum</i> .                        | 18. <i>Primula cortusoides</i> , <i>Sálvia patens</i> .          |
| 4. Double Primrose. Provence Roses, dwarf.                           | 19. Scilla, or Hyacinths. Select herbaceous plants.              |
| 5. Double Primrose. Scotch Roses.                                    | 20. Scilla, or other bulbs. Select herbaceous plants.            |
| 6. Crocuses. <i>Calceolària</i> , var.                               | 21. Snowdrops. Hybrid China Roses, dwarf.                        |
| 7. Crocuses. Verbèna, var.   | 22. <i>Sanguinària canadensis</i> . Geranium, var.               |
| 8. Snowdrops. Perpetual Roses, dwarf.                                | 23. <i>Adonis vernalis</i> . Scarlet Geraniums.                  |
| 9. Narcissus. Select herbaceous plants.                              | 24. <i>Auricula</i> , var. China Roses, dwarf.                   |
| 10. Narcissus, or other Bulbs. Select herbaceous plants.             | 25. <i>Polyanthus</i> , var. Tea-scented Roses, dwarf.           |
| 11. <i>Gentiana acaulis</i> . <i>Sálvia fulgens</i> .                | 26. <i>Scilla bifolia</i> . <i>Senecio elegans flore-pleno</i> . |
| 12. <i>Nemophila insignis</i> . Dahlias.                             | 27. <i>Erythronium Dens Canis</i> . <i>Lòtus jacobæus</i> .      |
| 13. <i>Lasthènia californica</i> . Dahlias.                          | 28. Snowdrops. Noisette Roses, dwarf.                            |
| 14. Dwarf Larkspur. Fuchsias.  |  |
| 15. <i>Cladanthus arbutus</i> . Fuchsias.                            |  |

According to this plan, the centres of the two extreme figures may contain fancy baskets or vases for greenhouse plants in summer; and the centre, *a*, may be a basin and fountain, if there is water at command; if not, Azaleas and other American plants, mixed with select standard Roses. If the beds Nos. 2, 3, 6, 7, 22, 23, 25, and 27, were planted with American plants, the garden might then be kept at much less annual expense of plants and labour.

*List of Plants for planting the Flower-Garden, fig. 62. By Mr. James Call, Foreman in Duncombe Park Gardens.*

- |  |   |
|--|---|
| 1. <i>Lobelia fulgens</i> , and <i>Lupinus nanus</i> .                   | 9. Herbaceous plants.   |
| 2. <i>Mimulus</i> of dwarf varieties.                                    | 10. Herbaceous plants.  |
| 3. Heartsease of varieties.  | 11. Scarlet geraniums, and Verbena Tweediana.                       |
| 4. Verbena Drummondii, and V. Melindres.                                 | 12. <i>Crassula coccinea</i> , and <i>Salpiglossis picta</i> .      |
| 5. Petunias of varieties, and <i>Anagallis Monelli</i> .                 | 13. <i>Sálvia patens</i> , and German Stocks.                       |
| 6. <i>Eschscholtzia californica</i> , and <i>Anagallis grandiflora</i> . | 14. Fuchsias of varieties, and <i>Antirrhinum caryophylloides</i> . |
| 7. <i>Alonsoa Warszwiczi</i> and <i>Clarkia pulchella</i> .              | 15. Dahlias of varieties, and German Asters.                        |
| 8. <i>Calceolarias</i> of varieties, and <i>Collinsia bicolor</i> .      | 16. <i>Sálvia coccinea</i> , and Dwarf Rocket Larkspur.             |

17. *Hydrangeas*, & *Aster Amé-  
lus*.
18. *Pentstemon  
gentianoides*,  
*P. fruticosa*  
and *Nemophila  
insignis*.
19. Herbaceous  
plants.
20. Herbaceous  
plants.
21. *Heliotropium  
peruvianum*  
and *Collomia  
coccinea*.
22. *Oenothera  
Drummondii*,  
and *Nemophila  
atomaria*.
23. *Antirrhinum  
Vivid & Eutoca  
viscida*.
24. *Verbena Tweed-  
ieana elegans*,  
and *V. Sabina*.
25. *Potentillas* of  
varieties, and  
*Schizanthus  
pinnatus*.
26. *Heartsease* of  
varieties.
27. *Verbena incisa*,  
and *V. Melin-  
dres*.
28. *Lobelia propin-  
qua*, & *Convól-  
vulus minor*.

*Fig. 63* is a de-  
sign for a small  
American garden,  
which may be plant-  
ed with *Azaleas* at  
*a* and *g*, *Kalmias* *b*  
and *f*, and *Rhodo-  
dendrons* *c* and *e*.  
The central bed, *d*,  
being planted with  
*Magnolias*.




FIG. 63.—AMERICAN GARDEN.



*Fig. 64* is a design for a garden, to contain a select collection of Dahlias and Hollyhocks.

The beds at *a a* embrace small basins of water; and, in order to contrast with the others, may be planted with a collection of Hollyhocks.

The beds marked *b b* may be planted with evergreen shrubs, in order to prevent the whole garden from being seen at once when entering. — There may also be a few plants of Junipers, or other dark evergreens, sprinkled down the middle of the garden from *b* to *b*, in order to form a background to the Dahlias and Hollyhocks: for this garden, like *fig. 63*, is one of those, the beauties of which are to be seen in succession, and not at a single glance, as in the design *fig. 62*. The Dahlia beds are so disposed as that every variety may be seen from the walk. The width of the beds is 3 feet, which will admit of two rows, the plants of one row alternating with those in the other. The whole of the space planted with Dah-




FIG. 64.—DAHLIA AND HOLLYHOCK GARDEN.

lias should be dug out to the depth of 2 feet, and a layer of brickbats, &c., placed at the bottom of the bed, which should then be filled with rich light soil. The Hollyhocks should also have a bed dug out for them, and filled with rich soil. Both plants grow better for having a layer of manure on the surface of the soil, while they are forming their flower-buds.

## GENERAL OBSERVATIONS ON FLOWER-GARDENS.

THE foregoing plans will give a general idea of the usual method of planting flower-gardens ; and, of course, the designs and the plants may be varied at pleasure. The principal points to be attended to, in order to make the beds of a flower-garden look well, are the size of the plants and their colours.

*With regard to the size*, no plant should be much higher than the others, and those that would grow taller should be pegged down. The usual rule is, that no plant should exceed six inches in height in a bed eighteen inches wide ; and that the plants may increase about six inches in height for every foot the beds increase in width. The plants should not be too near ; or they will be drawn up in height instead of spreading laterally ; and when this is the case, they never flower well, but become bare of both leaves and flowers towards the root. If plants should be in this state, the only remedy is taking up and replanting wider apart ; but it is generally best to use new plants, as the old ones which have been drawn up will generally have weakened themselves too much ever to do well.

*The management of the colours* of plants in flower-beds is a point of some difficulty ; but it is also reducible to rules. Every colour is said to contain within itself the germ of another colour, which, if mixed with it, would make black, or dingy white ; and these two colours harmonise better together than either would do with any other colour. It is well known that every ray of light may be divided into seven colours, which may be seen in a rainbow or in a prism ; and of these colours three are primitive or simple, and four compound. Now, it is found that every simple colour harmonises best with a compound colour ; and thus, that the secondary colour of red, which is a simple colour, is green, which is a compound colour ; that of yellow, is violet or purple ; and that of blue, orange. It is found, also, that no primitive colour harmonises well with a compound colour composed from it. Thus, red does not look well with purple, which is composed of red and blue ; but it looks very well with green, which is composed of blue and yellow. It is true that in plants green is so common, as to come in contact with every other colour ; but we shall also find that there are so many shades of green, as to render the hue of the leaves in harmony with every varied tint that may be found in the flowers. Green is also the most agreeable of all colours to the eye. It may be further observed, with regard to colours, that certain colours, such as red, yellow, and orange, are what are called warm ; and that others, such as blue, lilac, and sea-green, are what are called cold : also, that where the walks in a flower-garden are of gravel, cold colours ought to predominate in the flowers in the beds ; and where the walks are of grass, warm colours ought to predominate among the flowers.

*The usual way to try the effect of a new mode of forming and planting a regular flower-garden* is, to make a plan of the intended design on paper ; and then, after colouring the walks green or reddish, according as it may be wished to have them of grass or gravel, to tint the beds according to the colours of the flowers to be planted on them ; or, what is better, to put coloured wafers on the beds, as these will admit of being removed and shifted about at pleasure, till a proper effect has been pro-

duced. As soon as the colours for the different beds have been chosen, plants may be selected of the colours required, and brought forward in a reserve garden, till the beds are ready to receive them.

*When a flower-garden is to be laid out*, the ground is first dug over, raked, and made perfectly smooth. The plan traced on the paper is then transferred to the ground, generally in the following manner: The paper containing the plan is covered with regular squares, like the paper containing plans of the Berlin worsted work: the ground to be laid out is covered with similar squares, formed by sticking wooden pegs in the ground at regular distances, and fastening strings from peg to peg, till the whole ground is covered with a kind of lattice-work of string. Each string is then chalked and made to thrill by pulling it up about half-way between the pegs with a sudden jerk, and letting it go again; this transfers the chalk from the string to the ground, which thus becomes marked all over with white lines, forming regular squares. The squares on the ground should be of the same number as those on the paper, but larger; the usual proportion is, every square inch on the paper is represented by a square foot on the ground. The pattern is then traced with a sharp-pointed stick, the proportion in each square being copied. Sometimes, when the pattern is simple, it is traced on the ground simply by chalked string stretched from peg to peg—the pegs being stuck into the ground at regular distances, which have been previously measured, having been enlarged from the plan traced on paper according to a regular scale, in the same way as the squares were directed to be enlarged, according to the previous plan. If a circle is to be traced, it is done by getting a piece of string the length of the diameter of the circle, with a piece of stick tied to each end. One stick is then driven into the ground in the centre of the circle, and a line is traced with the stick at the other extremity of the line, which is drawn out quite tight. An oval is made by tracing two circles, the outer line of one of which just touches the centre of each other; short lines are afterwards made at the top and bottom, and the central lines are obliterated. A square only requires a peg at each corner, with a chalked string drawn from peg to peg; and an oblong, or long square, is made by joining two common squares and taking off the corners if required.

When the beds are traced out, the walks must be laid with either turf or gravel, and very great care must be taken to keep them exactly within bounds; very great care must also be taken to keep the beds of precisely the proper form, as the least disproportion is seen in a moment in a regular figure, and has a very bad effect. The plants should also be constantly attended to, so as to let them cover the beds entirely, and not project in the least beyond the outline; for, however beautiful wildness and irregularity may be in some situations, in a regular flower-garden they can only give the idea of carelessness and neglect.

---

#### ROCK-WORK.

It has been already stated in this work, that there are two kinds of rock-work, viz., that which is intended to imitate natural scenery (see



FIG. 65.—RUSTIC BRIDGE AMONG ROCK-WORK.



FIG. 66.—ARCH OF ROCK-WORK.

fig. 65), and that which is intended to serve merely as a receptacle for plants (see fig. 66); sometimes with the last kind of rock-work is combined an aquarium (see fig. 67). The first of these does not require any particular care in planting, except that the rocks should not be overshadowed by tall trees; but the second and third kinds need skilful planting, as their beauty depends principally on the plants they contain. The principal point to be attended to in selecting plants for rock-work is to choose those that do not grow too fast, and yet flower profusely; as the great difficulty is to keep each plant within its proper bounds, and yet to have the whole a mass of flowers.

#### *List of Plants for Rock-Work.*

The following plants are very suitable for rock-work, to flower from February to May:—*White.* The wood Anemone; *Anemone montana*; the white Hepatica; *A'rabis alpina*, and *A. alba*; the white and Scotch Crocuses (*Crœus biflorus*); Lily of the Valley (*Convallaria majalis*); *Iberis sempervirens*, and *I. gibraltarica*; Christmas Rose (*Hellêborus niger*); Snowdrops; the white double Primrose; and *Sanguinaria canadensis*. *Blue.* *Anemone apennina*; *Crœus vernus*; the blue Hepati-




FIG. 67.—ROCK-WORK ROUND A POND.

ca; *Iris pumila*; Grape Hyacinth; *Scilla præcox*, *S. verna*, and *S. sibirica*; and *Gentiana acutis*. *Yellow.* The Winter Aconite; *Adonis vernalis*; *Alyssum saxatile*; *Crœus sulphureus* and *C. luteus*, and the Cloth of Gold Crocus (*C. susianus*); *Iris lutescens*; *Narcissus minor*, and *N. Bulboëdium*; *Draba aizoides*; the common Primrose; and the Cow-

slip. *Purple.* *Aubriëtia deltoidea*; *A. purpurea*; *Erinus alpinus*; the dog's tooth Violet; the common Violet; the double lilac Primrose; Chinese Primrose; *Saxifraga oppositifolia*; *Soldanella alpina*; *Verbena Lamberti*, and *V. Arraniæna*, &c. *Red.* *Silene rubella*; *Lýchnis alpina*; Pink Hepática; double red Primrose; and *Cineraria cruenta*, though this last must be kept in the house during winter, and only planted out after its flower-buds have formed. Various kinds of Heaths, and some of the Cape bulbs may be brought forward under glass, and planted out when about to flower in a similar manner. For the summer months the following flowers may be used: *White.* *ibëris Tenoreana*; *Alýssum calycinum*; *Arabis bellidifolia*, and *A. petraea*; *Actæa racemosa*; *Achillea Clavennæ*; White dwarf *Campánula*; *Valeriana montana*; *Cardamine asarifolia*; *Potentilla rupëstris*; and *Stëvia Eupatoria*. *Blue.* *Aquilegia alpina*; *Campánula rotundifolia*, *C. garganica*, and *C. pulla*, *Viola cucullata*; *Aster alpinus*; *Lupinus nanus*; *Periwinkle*; *Lobelia gracilis*; *L. cærulea*, and *L. unidentata*; and the Calathian Violet; *Sedum Sieboldii*. *Yellow.* *Gazania speciosa*; Moneywort; *Lasthënia californica*; *Bartonia aurea*; yellow Musk plant (*Mimulus moschatus*); Hoop Petticoat *Narcissus*; and *Allium Moly*; *Potentilla aurea*; *Tritonia uvaria*. *Purple.* Wild Geraniums of various kinds; several kinds of *Phlox*; dwarf Asters; and dwarf Stocks. *Red.* *Anemone japonica*; *Dianthus deltoides*, and *D. barbatus*; *Lýchnis læta*; Pink-flowered Cistuses, and *Helianthemums*; *Phlox Drummöndii*; *Rhodiola rosea*; *Saponaria ocymoides*, and *S. calabrica*; *Saxifraga sarmentosa*; *Linnaea borealis*; *Erodium alpinum*; *Selene Schäfta*; and several dwarf Pinks; *Antirrhinum majus*, and many other flowers of various colours, but which may be very appropriately introduced, including several foliage plants of different colours, such as the *Stipa pennata*, *Cerastium tomentosum*, and the Pampas grass. This list will serve to give an idea of the kind of flowers which are suitable. Many others will occur to every one fond of a garden. When an aquarium is added to the rock-work, as in *fig. 67*, it will be necessary to place a few aquatic plants in the water, and a few marsh plants round the borders of the pond, for which purpose I have subjoined the following list of suitable plants, some of which are quite hardy, and may remain in the water all the year, and others will require protection during winter.

#### *List of Aquatic and Marsh Plants.*

Two of the handsomest aquatics I know are *Aponogëton angustifolium*, and *A. distachyon*; they have both white flowers tinged with pink, and black anthers, which give them a very lively appearance. *A. distachyon* is much the larger plant of the two. They are both tolerably hardy, but require protection during winter. *Pontedëria cordata* has arrow-shaped erect leaves, and an upright spike of dark purple flowers. It is a native of North America, and is quite hardy in England. *Bütomus umbellatus*, the flowering rush, with its head of pink flowers, and *Acorus Calamus*, the sweet-scented water-reed, are tall showy plants, as is *Cyperus longus*, which last bears some resemblance to the *Papyrus* of the Nile. For smaller plants, may be mentioned the little Frog-bit, *Hydrocharis morsus-ranae*, with its pure white flowers; *Hottönia palustris*, the water violet, with its pretty pink flowers; *Calla palustris*, the water dragon; *Caltha*

*palustris*, the marsh marigold ; *Nymphaea alba*, the common water-lily ; *Stratiotes aloides*, the fresh-water soldier ; *Sagittaria sagittifolia*, the Chinese arrow-head, with its white and green flowers ; *Pinguicula lusitanica* ; *Samolus Valerandi* ; *Villarsia nymphaoides*, the yellow-fringed buck-bean ; *Comarum palustre* ; and *Nuphar advena*. The beautiful little *Polygonum amphibium*, the rose-coloured water-pepper, with its dark pink flowers, of which there is so much in the large piece of water opposite the palace in Kensington Gardens, is quite hardy ; as is *Menyanthes trifoliata*, the common buck-bean. These are all common ; but *Thalia dealbata*, a curious black-and-white plant, and *Trapa natans*, the water caltrops, also curious, are more rare.

For the plants not aquatics, but which will thrive when they have their pots plunged in water, are the white Arum (*Calla aethiopica*), the tall scarlet Lobelias, and all the kinds of Mimulus. As a companion to the little Musk plant, I may recommend the *Myosotis palustris*, the true Forget-me-not, and *Houstonia cærulea*, a pretty little plant, with very pale, star-like flowers.

The following bulbs will also grow and flower splendidly with their pots half plunged in water :—*Crinum capense*, the white-striped, and purple Cape Crinums ; *Amaryllis speciosa*, sometimes called *Hippeastrum purpureum*, and sometimes *Vallota purpurea*, with dark crimson, lily-like flowers ; *Pancratium mexicanum* ; and *Calostemma purpurea*, *C. lutea*, and *C. alba*. All these are half-hardy bulbs, and require protection during winter.

### SUNDRIES.

Under this head I propose to give a few lists of plants suitable for particular purposes, which I think it may be useful for amateur gardeners to know, in order to be able to select what may be required for any particular purpose. Thus I have given lists of roses to aid the amateur to select from the long catalogues proffered by nurserymen. There are many plants which may be planted in pots, and brought forward in a hot-house, or by plunging in a hot-bed, so as to flower much earlier than in their natural season ; while other plants may be killed by similar treatment. It is therefore useful to know what plants will bear to be unnaturally stimulated with heat ; and I have given a list of those usually forced by the London nurserymen, so as to flower in February, March, and April. As many kinds of Cape Heaths are very ornamental in their flowers in winter, I have subjoined a list of those that flower about Christmas ; and I have added other lists of different kinds which have been suggested to me, in the hope of rendering this little book as useful as possible.

### LISTS OF ROSES.

**SUMMER ROSES.**—Common and crested cabbage, common and crested Moss, Luxembourg. *Damask.*—Madame Hardy, Madame Zöetmans. *Alba.*—Sophie de Marcilly.—*French or Gallica.*—Boula de Nanteuil, Kean, Ohl, Transon Goubault, Blancheffleur.—*Hybrid Chinese, Bourbon and Noisette.*—Brennus, Charles Lawson, Chénédolé, Coupe d'Hébé, Madame Boll, Madame Plantier, Paul Ricaut, William Jesse.

**AUTUMN ROSES.**—*Hybrid Perpetuals*. Auguste Mie, Baronne Prevost, Madame C. Crapelet, Caroline de Sansal, Catherine Guillot, Charles Lefebvre, Comtesse de Chabillant, General Jacqueminot, Duchess of Sutherland, Géant des Batailles, John Hopper, Jules Margottin, La Reine, Lord Macaulay, Lord Raglan, Madame Rivers, Madame Alfred de Rougemont, Maurice Bernardin, Olivier Delhomme, Prince Camille de Rohan, Pierre Notting, Sénateur Vaisse, Turenne, Victor Verdier, Madame Freeman, Mademoiselle Bonnaire, Le Rhone, Louise Odier, William Jesse.

*Bourbon*.—Prince Albert, Sir Joseph Paxton, Souvenir de Malmaison, Souchet.

*Noisette*.—America, Desprez à fleurs Jaunes, Celine Forestier, Dean Hardy, Isabella Gray, Lamarek, Ophirie, Solfatare, Triomphe de Bennes.

*China*.—Cramoisie Supérieure, Fabvier, Marjolin du Luxembourg. Mrs. Bosanquet.

*Tea*.—Bougere, Devoniensis, Gloire de Dijon, Madame Willermoz, Moiret, Niphetos, Souvenir d'Elise Vardon, Souvenir d'un Ami, Safrano, Vicomtesse de Cazes.

*Yellow Roses*.—Persian yellow, Harrisoni.

**HARDY CLIMBING, RUNNING, OR TRAILING ROSES.**—*Boursault*.—Amides, Gracilis,

*Ayrshire, and Hybrid ditto*.—Bennet's Seedling, Dundee Rambler, Ruga, Splendens.

*Alba*.—Félicité.

The following are suitable for pillar roses in a conservatory:—Brennus, Charles Lawson, Coupe d'Hébé, Gloire de Dijon, Paul's Vivid, Chéné-dolé, Madame Louise Carique, Souvenir de Malmaison, Sir Joseph Paxton, Cloth of Gold, Solfatare, and Fortune's Double Yellow China, which will grow to cover a large extent, flowering abundantly early in spring, and again late in autumn.

#### *Ornamental flowering Shrubs,*

Weiglée rose, all the Mahonias, or Ash Berberries, Ceanóthus azuréus, and other kinds, Viburnum, various kinds, Spiræa aërifolia, S. bélla, the Judas tree, Rose Acacia, and several kinds of Escallonia, Azéleas, Rhododéndrons, Kálmias, Pávia macrostýcha, Double-blossomed red, and Double-blossomed white Chinese Peaches, Ribes aëreum, sanguineum, &c., Persian lilacs, Dáphne Mezereum, Deutzia grácilis, &c.

#### *Shrubs Flowering in Winter,*

Gárrya elliptica, Chimonáanthus frágans, Laurustinus, Forsýthia viridíssima.

#### *Perennial Plants flowering in Winter.*

Tussilágo frágans, Christmas Rose, Chrysanthemums, Dielytra spectábilis, Violets, Duc Van Thol Tulips, Scilla præcox, Mopsídium acáule.

#### *List of Plants suitable for early Forcing.*

The common and Persian Lilacs, the Jasmine, Deutzia scabra, Lily of



the Valley, Roses, *Abutilon striatum*, *Cinerarias*, *Kalmias*, *Azaleas*, Chinese *Primroses*, *Acacia armata*, *Heliotrope*, *Hydrangea*, *Calla ethiopica*, *Cinerarias*, Lemon-scented *Verbena*, *Hyacinths*, *Van Thol Tulips*, *Camellias*, *Sweet Peas*, and *Mignonette*. *Pelargoniums*, and dwarf *Dahlias*, are also generally brought forward in heat for flowering earlier than the ordinary time.

*List of Winter-flowering Heaths which blossom about Christmas.*

*Erica hyemalis*, *E. Archeriana*, *E. óllula*, *E. vestita*, and *E. imbricata*, all with pink or red flowers ; *E. grandinosa*, *E. Bowieana*, *E. Lamberti-ana*, and *E. cáffa*, the flowers of which are white, and those of the last species fragrant ; *E. Sebana lutea*, with yellow shining flowers ; and *E. Massoni*, with orange and green flowers.

*Plants for Glass Cases.*

Ferns of various kinds, viz., the dwarf species of *Asplénium*, *Aspidium*, *Adiantum* (Maiden hair), *Polypodium*, *Pteris* (the Brake), and *Trichomanes* ; *Lycopodium* (the Club Moss), various species ; *Oxalis acetosella* (the Wood Sorrel), *Anemone nemorosa* (the Wood Anemone), *Verónica alpina*, the Bird's-nest *Neottia*, or *Ladies' traces*, *Dentaria bulbifera*, *Paris quadrifolia*, *Crocuses*, *Hyacinths*, and various kinds of bulbs.

*Plants suitable for pegging down in Beds.*

Nearly all the *Verbenas* ; the dwarf *Dahlias* ; the evergreen and all the trailing *Roses* ; most of the *Petunias* ; the *Periwinkles* ; some of the *Lobelias* ; *Cistus purpureus*, and other kinds of *Cistus* and *Heliánthemum* ; *Crucianella stylosa* ; *Rhododéndron hirsutum* ; *Fuchsia globosa* ; several kinds of *Vaccinium* ; *Gaultheria Shallon* ; *Clématis montana*, and some other kinds of *Clématis* ; and generally all kinds of trailing plants.

*Plants for Baskets, to hang down.*

*Maurándya Barclayana*, *Lophospermum scandens*, *L. erubescens*, *L. Hendersoni*, and *L. spectabilis*, *Recremocarpus scaber*, *Tropæolum peregrinum* (the Canary-bird flower), *Cobæa scandens*, and *C. scandens variegata* ; *Convólulus* of various kinds, *Moneywort*, *Nolana atriplicifolia* and *prostrata*, *Campanula garganica* and other kinds, *Lobelia erinoides*, *L. sellidifolia*, *L. gracilis*, and other kinds ; *Marianthus cæruleo-punctatus* ; *Thunbergia alata*, *T. a. alba*, and *T. aurantiaca* ; *Verbena Melindres*, and other kinds ; *Petunia nyctaginiflora*, and some other kinds ; *Iberis sempervirens*, and *I. Tenoreana* ; and various kinds of roses.

RIBBON GARDENING.

Of late years a mode of arranging plants in flower gardening, so as to form stripes or bands of different shades of colour, and called ribbon gardening, has become very fashionable ; and when the colours are well contrasted it has an excellent effect. For this purpose the following list

will prove useful to select from :—*Amaránthus melanchólicus* rùber; *Agathæa celéstis argétea* variegàta; *A'rabis álvida* variegàta; *A'triplex horténsis* rùber; *Centàurea argétea*, *C. Ragusina*, *C. candidíssima*, and *C. gymnocárpa*; *Cinerària marítima*; *Cerástium tomentòsum*, *C. Biebersteinii*; *Còleus Verscháfelti*, *C. Blúmei*, *C. nígricans*, *C. marmoràta*; *Farfúgium grànde*; *Gnaphálum lanàtum*; *Lobélia speciòsa*, *L. Paxtoniàna*; *Lonicera àureo-reticulàta*; *Malcòlmia marítima*; *Pelargonium*, variegated gold and silver leaved; *Perilla nankinénsis*; *Tropæolums*; *Verbenas*; *Vínca májor* variegàta.

#### SUBTROPICAL GARDEN.

Several kinds of ornamental foliaged plants have lately been turned out of pots in summer and planted in well-drained soil in situations sheltered from cold winds, and generally on slopes, natural or artificial, facing the south, so that the sun's rays may have a more powerful effect in rendering the soil warmer for the roots of the plants than if these had been planted on level ground. Moreover, superfluous moisture can readily pass down the slopes. It is essentially necessary that no stagnant moisture should remain about the roots; and the soil should be rich, light and porous. In this way the following, mostly subtropical, plants have been successfully grown in summer, at which season, from the grandeur of their foliage, they offer a magnificent appearance. *Aràlia papyrifera*, *A. Siebòldi*; *Arundinària falcàta*; *Arúndo dònax*, *A. dònax* variegàta; *Calàdium esculéntum*, *C. odòrum*, and others; *Cannas*; *Cinerària platanifolia*; *Ferdinándia éminens*; *Gúnnera scàbra*; *Montagnea heracleifolia*; *Pánicum palmifolium*; *Phórmium tènax*; *Ricinus sanguíneus*, and others; *Solànum argentéum*, and others; *Wigandia caracasàna*.

#### MODES OF PROTECTING.

As many persons having small gardens are at a loss for a place in which to keep their half-hardy plants during winter, I have thought it may be




Fig. 68.

useful to give a short description of the most simple contrivance I know, for effecting the desired purpose. It is to have a frame made of wood (which can be put together by any common carpenter), erected against

the wall of a stable, or in any convenient place, where it will be out of sight. — When the frame is erected, a wall of manure should be formed, as shown in

*fig. 68* ; or if manure cannot be readily obtained, turf, or stones, or bricks lined with straw or hay will do. Within this wall the pots may be placed as closely as possible ; and where manure can be obtained easily, a little may be laid on the earth in each pot. Some Russian matting, old carpet, tarpaulin, or baize, may then be nailed over the top and sides of the frame, and a piece left loose to hang down in front like a curtain. When the weather is very severe, an additional covering of matting, or old blankets may be thrown over the frame ; but the curtain in front should be thrown up to admit the air, whenever the weather is sufficiently mild ; and the mat in front should be kept fastened up, and an oil-cloth thrown over the frame in continued rains, lest the plants should damp off.

Where there are tree *Pæonies* or other plants in the open ground, which require a slight protection from spring frosts, nothing can be better than wicker-work coverings, like that shown at *c* in *fig. 69*. The




Fig. 69.

evergreen *Magnolias*, the Australian *Acacias*, and similar half-hardy trees, and the more delicate kinds of pines and firs, may be protected in the same manner ; while the smaller half-hardy shrubs, such as the *Cistuses* and *Helianthemums*, may be protected by the smaller coverings shown at *d* and *e* ; and plants against a conservative wall, such as China Roses for early flowering, may be protected by the coverings shown at *a* and *b*. These coverings may be made of plaited rushes, sewed together ; and making them will afford excellent employment for poor women and children in autumn.

## CONCLUSION.

The above observations may be rather considered as hints to amateur florists, than as directions for the management of a flower-garden ; but they will be useful to those who take an interest in the subject ; and to those who do not, no directions, however ample they may be, will be of any avail. No one, in fact, can ever make a good gardener, who has not a sincere love for plants ; and I cannot conclude better than by adding, in the words of Ray, who wrote on flower-gardens about two hundred years ago :—

“The love of such a master will keep each tender plant alive his care

and skill have collected ; for never was any art or excellence liked or loved by the ignorant ; it is knowledge that begets affection, and affection increaseth knowledge. Love was the inventor, and is still the maintainer of every noble science. It is chiefly that which hath made my flowers and trees to flourish, though planted in a barren desert, and hath brought me to the knowledge I now have in plants and planting ; for, indeed, it is impossible for any man to have any considerable collection of noble plants to prosper unless he love them ; for neither the goodness of the soil, nor the advantage of the situation, will do it without the master's affection : it is that which animates and renders them strong and vigorous ; without which they will languish and decay through neglect, and soon cease to do him service."

THE END.

APR 16 1915

# WORKS ON BOTANY AND GARDENING.

---

*In Two Vols., royal 8vo, price 3l.,*

**NATURE-PRINTED BRITISH FERNS**, being  
Figures and Descriptions of the Species and Varieties of Ferns found  
in the United Kingdom. By THOMAS MOORE, F.L.S. The  
Figures Nature-Printed by HENRY BRADBURY.

---

*In One Volume, 8vo, cloth, price 36s., with upwards of 500 Illustrations,*

**THE VEGETABLE KINGDOM**; or, **THE STRUCTURE**,  
CLASSIFICATION, AND USES OF PLANTS. By DR. LINDLEY. Illus-  
trated upon the Natural System.

---

*In One Volume, 8vo, cloth, with numerous Illustrations, price 12s.,*

**THE ELEMENTS OF BOTANY**, Structural and  
Physiological. With a Glossary of Technical Terms. By DR.  
LINDLEY.

*\*\* The Glossary may be had separately, price 5s.*

---

*In One Volume, 8vo, cloth, price 7s. 6d.,*

**MEDICAL AND OECONOMICAL BOTANY.** By  
DR. LINDLEY.

---

*In One Volume, 8vo, half-bound, with 400 Illustrations, price 5s. 6d.,*

**SCHOOL BOTANY**; or, **THE RUDIMENTS OF BO-  
TANICAL SCIENCE.** By DR. LINDLEY.